

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDERS"

Sealed item rates tender are hereby invited by the Executive Engineer, Ghumarwin Division, HP-PWD. Ghumarwin for the following works from the registered contractors of appropriate class enlisted in HP-PWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act. 1968. The important date of tender are as under:-

Date of application 0811/2021
Date of sale of tender. 09/11/2021


The tender shall be received up to 11:00A.M. on 10/11/2021 and will be opened on the same day at 11:30 A.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment as shown below (Non-refundable) during the working hours on 9/11/2021.

The Earnest money in the shape of National Saving Certificate/Deposit at call/ Time Deposit /Account/ in any of the Post-Office /Nationalized Bank in H.P. duly pledged in favour of Executive Engineer, Ghumarwin Division, HP-PWD, Ghumarwin must accompany with each application. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The XEN reserve the right to accept or reject the tenders without assigning any reason.

| S No. | Name of work | Estimated cost | Earnest Money | Cost of for | Time limit |
|-------|--|----------------|---------------|-------------|-------------|
| 1 | C/o rain shelter on Bhager Auhar road Km 0/0 to 3/330 (SH:-C/o Rain shelter at RD 1/950 at Daryana) | Rs.356005/- | Rs.7200/- | Rs.350/- | Three Month |
| 2 | C/o electrical panel room shed for oxygen plant at CHC Ghumarwin for 200 PSA (Deposit work) | Rs.117268/- | Rs.2400/- | Rs.350/- | One Month |
| 3 | M/T on Mohara Khil Dalote Kuhadre road (SH:-P/L M/T in km 0/0 to 0/550 & 2/600 to 2/790) | Rs.499090/- | Rs.10000/- | Rs.350/- | Two Month |
| 4 | C/o Awari to Peherwin Km 0/0 to 1/500 (SH:-C/o interlocking Concrete block pavement 1/0 to 1/30) | Rs.477897/- | Rs.9200/- | Rs.350/- | Two Month |
| 5 | C/o L/R in H/basti Balh Bard No. 13 GP Taroun (SH:-C/O CC pavement at RD 0/125 to 0/225) | Rs.169764/- | Rs.3400/- | Rs.350/- | Two Month |
| 6 | R/R on Bhager Panol Suhna road Km 0/0 to 7/0 (SH:-C/o R/wall at RD 0/565 to 0/584 and 0/586 to 0/600) | Rs.199736/- | Rs.2000/- | Rs.350/- | Three Month |
| 7 | C/o L/R from Samolhal to Chhadolvia Pickle Factory Km 0/0 to 2/460 (SH:-C/o RCC slab culvert 3.00 span a/w W/wall both side at RD 0/510) | Rs.433419/- | Rs.8700/- | Rs.350/- | Two Month |
| 8 | Removal of black spot on L/R from Kothi to Baddu Km 0/0 to 2/285 (SH:-C/o R/wall in wire crate at RD 2/170 to 2/190 & 2/202.50 to 2/209) | Rs.492334/- | Rs.10000/- | Rs.350/- | Two Month |

Terms and conditions

- I. The XEN reserve the right to accept or reject the tenders without assigning any reason.
- II. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
- III. The contractors should have executed two similar type of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within last five years.
- IV. The list of similar type of work executed & work done performance certificate issued by the concerned Executive Engineer/GST/EPF No should be accompanied with application.
- V. Earnest money should be accompanied with application. Application without earnest money will not be entertained.
- VI. **CERTIFICATE**
Certified that the tenders have been invited in exigencies/emergency of work.


Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT


No.PW/GHD/CB/Tender/2021-

Copy along with Notice Inviting Tender list is forwarded to:-

1. The Engineer-in-Chief HPPWD Shimla-2
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineer, 10th Circle, HPPWD Bilaspur
4. The Executive Engineer (IT) O/O Engineer-in-Chief HPPWD Shimla-2 eeict-pwd-shi[at]hp[dot]gov.in a/w schedule of quantity to download on the department portal.
5. Drawing Branch
6. Account Branch

Dated:-

29/10/2021


Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

Schedule of Quantity

Estimated Cost:- Rs. 3,56,005.00
 Earnest Money:- Rs. 7,200.00
 Time :- Three Month

Name of Work:- Construction of Rain Shelter on Bhager Auhar road km 0/0 to 3/330 (SH:- Construction of Rain Shelter at RD 1/950 at Daryana)

| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|---------|--|----------|-----------------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | Excavation in foundation, trenches etc., in all classification of soil such as pick work, jumper work, blasting work, soft rock and hard rock including chiselling wedging and any other mixed variety of soil in dry or saturated conditions up to any depth and lift including pumping and bailing out water where required including stacking the serviceable and un-serviceable material separately as directed and then returning the stacked soil in fifteen centimeters layers when required into plinth and sides of foundation etcetra consolidating each deposited layer by ramming and watering and then disposing of all surplus un-serviceable excavated earth as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 30.16 | Per cubic metre | | | |
| 2 | Providing and laying cement concrete 1:4:8 (One cement : four sand : eight graded stone aggregate 40mm (forty millimeter) nominal size and curing complete excluding cost of centering and stirring in foundation and plinth mechanically mixed and vibrated as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 9.87 | Per cubic metre | | | |
| 3 | Providing and laying cement concrete for plain / reinforced concrete in open foundations complete as per technical specifications clauses 802.803, 1202 and 1203 1:2:4 (one cement :two sand:four crushed stone aggregate) PCC Grade M-20 (twenty) as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 10.70 | Per cubic metre | | | |
| 4 | Brick work using 2nd class common burnt clay building bricks in foundation and plinth in cement mortar 1:6 (one cement: six sand) as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 5.17 | Per cubic metre | | | |
| 5 | Excavation in earth work and filling in 15 cm (fifteen centimetre) layers in foundation and plinths including ramming, watering and consolidating upto any lead Pick Work as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 8.99 | Per cubic metre | | | |
| 6 | Stone soling properly hand packed filling interstices with spalls and consolidation to the required level including spreadly binning material as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 3.85 | Per cubic metre | | | |
| 7 | Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In beams joists channels, angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 25.19 | Per quintel | | | |

| | | | | | | |
|----------------|--|-------|-------------------|--|--|--|
| 8 | Providing and fixing 10mm (ten millimetre) thick anti skid water proof stain and impact resistant heavy duty vetrified tiles NITCO or equivalent 600x600x10mm (six hundred into six hundred into ten millimetre) manufactured of approved shade and colour in flooring treads of steps and landing laid over 12mm (twelve millimetre) thick cement mortar 1:3 (one cement : three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 38.33 | Per square metre | | | |
| 9 | Providing and fixing 0.60 mm (point sixty millimeter), thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (twenty) microns over 5 (five) microns primer coating to back coat of polyester of 5 (five) microns over 5 (five) microns primer coating including fixing with prepainted iron J of L hooks, bolts and nuts 6 mm (six millimeter), dia meter with prepainted limpet and rubber washers complete with all accessories as required including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 35.52 | Per square metre | | | |
| 10 | Providing and fixing ridges or hips 60cm (Sixty centimeters) over all with 0.60mm (Zero point sixty millimetre) thick prepainted steel sheets in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester organic coating 20 (Twenty) microns over 5 (Five) microns primer coating plus back coat of polyester of 5 (Five) micron over 5 (Five) microns primer coating including fixing with prepainted iron J or L hooks bolts and nuts 6mm (Six millimeters) diameter and prepainted GI limpet & Bitumen washers complete with all accessories as required as per the the direction of Engineer in Charge including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 36.13 | Per running metre | | | |
| 11 | Painting two coats (excluding priming cost on new steel and other metal surfaces eith enamel paint brushin to give an even shade including cleaning the surface of all dirt,dust and other foregin matters Enamel paint other than white as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 64.48 | Per square meter | | | |
| Total:- | | | | | | |

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

Schedule of Quantity


Estimated Cost:- Rs. 1,17,268.00
 Earnest Money:- Rs. 2,400.00
 Time :- One Month

Name of Work:- Construction of Electrical Panel room shed for Oxygen Plant at CHC Ghumarwin for 200 PSA.

| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|---------|---|----------|-------------------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | Demolition below G.L. Upto any depth and disposal of unserviceable materials within any lead. Un-reinforced cement concrete upto 15 cm (Fifteen centimetre) thickness including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 0.50 | Per cubic metre | | | |
| 2 | Providing and laying cement concrete work 1:2:4 (one cement:two sand:four graded stone aggregate 20 mm (twenty millimetre) nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. (1) Foundation footings base of columns and the like and mass concrete. | 2.25 | Per cubic metre | | | |
| 3 | Steel work in built-up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 675.40 | Per kilogram | | | |
| 4 | Providing and fixing pressed steel doors frames manufactured from commercial mild steel sheet of 1.25mm (one point two five millimetre) thickness including hinges, joints, lock jamb, bead and if required, angle threshold of mild steel angle of section 50X25 mm (fifty into twenty five millimetre) or base ties of 1.25 mm (one point two five millimetre) pressed mild steel welded or rigidly fixed together by mechanical means, adjustable lugs with split and tails to each jamb including steel butt hinges 2.5 mm (two point five millimetre) thick with guards, lock strike plate and shock absorber as specified and applying a coat of approved steel primer after pretreatment of the surface PROFILE-B including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 5.18 | Per running metre | | | |
| 5 | Providing and fixing flush door shutters decorative type core of block board construction with frames of first class hard wood and well matched first class indian teak plyveneering with vertical grains or cross bends and face veneering on both faces of shutter. 35mm (thirty five millimetre) thick including black enamelled M.S. butt hinges including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 2.44 | Per square metre | | | |
| 6 | Providing and fixing anodized aluminium sliding door bolt anodized colour and shade with bolts and nuts screws etc. as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. complete. 300x16mm (three hundred into sixteen millimetre). | 1.00 | Each | | | |

| | | | | | | |
|----|---|-------|-------------------|--|--|--|
| 7 | Providing and fixing aluminum tower bolts (berrel type) with screws etc. Complete 250x10mm. (Two hundred fifty into ten millimetre.) as per HP-PWD Specification including entire carriage of materials upto all leads and lifts. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 2.00 | Each | | | |
| 8 | Providing and fixing aluminium handles anodized transparent or dyed to required colour & shade with necessary screws etc. complete including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. (i) 125 mm. (one hundred twenty five millimetre) | 2.00 | Each | | | |
| 9 | Providing and fixing 0.60 mm (point sixty millimetre). thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (twenty) microns over 5 (five) microns primer coating to back coat of plyster of 5 (five) microns over 5 (five) microns primer coating including fixing with prepainted iron J of L hooks, bolts and nuts 6 mm (six millimetre). dia meter with prepainted limpet and rubber washers complete with all accessories as required including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 29.24 | Per square metre | | | |
| 10 | Providing and fixing ridges or hips 60cm (Sixty centimeters) over all with 0.60mm (Zero point sixty millimetre) thick prepainted steel sheets in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester organic coating 20 (Twenty) microns over 5 (Five) microns primer coating plus back coat of polyester of 5 (Five) micron over 5 (Five) microns primer coating including fixing with prepainted iron J or L hooks bolts and nuts 6mm (Six millimeters) diameter and prepainted GI limpet & Bitumen washers complete with all accessories as required as per the direction of Engineer in Charge including carriage of materials within all leads, lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 4.25 | Per running metre | | | |
| 11 | Providing and fixing expanded metal 20x6mm. (twenty into six millimetre) strands 2.50mm (two point five zero millimetre) wide and 1.25 mm (one point two five millimetre) thick for windows etc. including 60x20 mm (sixty into twenty millimetre) heading of 2nd class indian teak wood including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 8.71 | Per square metre | | | |
| 12 | Painting two coats (excluding priming coat) on new wood and wood based surfaces, with readymixed paint, brushing to give an even shade including cleaning of all dirt, dust and other foreign matter sand papering and stopping with white paint as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 74.52 | Per square metre | | | |
| 13 | Providing and fixing on wall face PVC (D-Plast) rain water pipes of working pressure not less than 4.5 kg/sqm including filling the joints with approved adhesive complete. 100mm (one hundred millimetre) dia pipes including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 38.45 | Per running metre | | | |

| | | | | | | |
|----------------|--|------|------|--|--|--|
| 14 | Providing and fixing on wall face PVC (D-plast) accessories for rain water pipes including fitting the joints with approved adhesive complete 150 mm. (one hundred fifty millimeter) dia plain bends including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 6.00 | Each | | | |
| 15 | Providing fixing M.S holder bat clamps of approved design to C.I of S.C.I pipes embedded in and including cement concrete blocks 10x10x10 cm. Ten into ten into ten centimeter) of 1:2:4 (one cement : two sand : four graded/ crushed stone aggregate 20 mm (twenty millimetre) nominal size and cost of cutting holes and making good the hundred mm dia meter for C.I. pipe including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 6.00 | Each | | | |
| 16 | Constructing chamber 600millimeters x 450millimeters x 600millimeters (six hundred into four hundred fifty into six hundred millimetre) inside size for water meter complete with C.I.double flap surface box 400millimeters x 200millimeters x 200millimeters (four hundred into two hundred into two hundred millimetre) (inside) with locking arrangement and RCC top slab 1:2:4 mix (one cement : two sand : four graded stone aggregate) 20millimeters (twenty millimetre) nominalsize 100millimeters (one hundred millimetre) thick foundation concrete 1:5:10 (one cement : five sand : ten graded stone aggregate) 40millimeters (forty millimetre) nominal size and inside plastering with cement mortar 1:3 (one cement:three sand) finished with a floating coat of neat cement including curing complete.with 200millimeters (two hundred millimetre) thick walls of brick Masonry in cement mortar 1:5 (one cement:five sand), including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge.The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 2.00 | Each | | | |
| Total:- | | | | | | |


Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

Schedule of Quantity

Estimated Cost:-Rs 499090/-
Earnest Money:- Rs. 10000 /-
Time:- Two month

Name of Work:- Metalling and Tarring on Mihara Khil Dalote Kqhadre Lohat road km 0/0 to 5/0 (SH:- Providing and Laying Tarring in km 0/0 to 0/550 and 2/600 to 2/790).

| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|----------------|---|----------|-------------------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spreading primer at the rate of 0.70- 1.0 kg per square metre (Zero point seven zero to one point zero kilogram) as per table 500.1(a) of MORD technical specification 2014, by mechanical means as per technical specification clause 502 of MORD technical specification 2014, as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 2369.85 | Per Square metre. | | | |
| 2 | Providing and applying tack coat with bitumen emulsion(RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg (Zero point two five to zero point three zero kilogram) per Square metre as per table 500.2 of MORD technical specification 2014, on the prepared bitumenous surface cleaned with hydraulic broom as per technical specification clause 503. of MORD technical specification 2014, as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 2369.85 | Per Square metre. | | | |
| 3 | Providing laying and rolling of open graded premix carpet of 20mm(Twenty millimeter) thickness composed of 13.2mm to 5.6mm (thirteen point two to five point six millimetre) aggregate either using penetration grade bitumen V-G-10 (viscosity grade-ten) to required line grade and level to serve as wearing course on a previously prepared base including mixing in a suitable plant, laying and rolling with three wheel 80-100 KN(eighty to hundred KN) static roller capacity, finished to required level and grades to be followed by seal coat of either type-B as per technical specification clause 508 by mechanical means using bitumen V-G-10(viscosity grade-ten) as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 2369.85 | Per Square metre. | | | |
| 4 | Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels grade and cross fall using Type-B as per Technical specification 510 by mechanical means using bitumen V-G-10 (Viscosity grade ten) having bitumen @6.8 Kg (six point eight kilogram) premix with 0.06 cum (zero point zero six cubic meter) of fine aggregate 10 sqm (ten square metre) as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 2369.85 | Per Square metre. | | | |
| Total:- | | | | | | |


Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin


Schedule of Quantity

Estimated Cost:- Rs. 4,77,897.00
Earnest Money:- Rs. 9,600.00

Time :- Two Month

Name of Work:- Construction of Awari to Pehrwin km 0/0 to 1/500 (SH:- Construction of interlocking concrete block pavement 1/100 to 1/300)

| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|----------------|--|----------|------------------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | Granular sub-base/base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408. Using naturally occurring gravel as per Technical Specification Clause 502 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 50.25 | Per cubic metre | | | |
| 2 | Providing and Laying concrete 1:4:8 (one cement : four sand : eight crushed stone aggregate) (40mm forty millimetre) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 30.50 | Per cubic metre | | | |
| 3 | Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm (eighty millimetre) as per drawings and Technical Specification Clause 1504 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 610.00 | Per square metre | | | |
| 4 | Providing and laying cement concrete for plain / reinforced concrete in open foundations complete as per technical specifications clauses 802,803, 1202 and 1203 1:2:4 (one cement :two sand:four crushed stone aggregate) PCC Grade M-20 (twenty) as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 7.50 | Per cubic metre | | | |
| Total:- | | | | | | |


 Executive Engineer
 Chumarwin Division
 HPPWD Chumarwin

Schedule of Quantity

Estimated Cost:- Rs. 1,69,764.00
Earnest Money:- Rs. 3,400.00

Name of Work:- Construction of link road in H/Basti Balh Bard No. 5 Gram Panchayat Traun (SH:- Construction of C.C. Pavement at RD 0/125 to 0/225)
Time :- Two Month

| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|----------------|--|----------|-----------------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per Technical Specification Clause 405. By Manual Means as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 7.80 | Per cubic metre | | | |
| 2 | Providing and laying mechanically mixed and vibrated cement concrete for plain/reinforced concrete in open foundations for all type of structure complete of plain cement concrete grade M-10(M-Ten) nominal mix 1:3:6(One cement: Three sand: Six graded crushed stone aggregate) 20mm(Twenty millimetre size) in or under water and curing complete including pumping of bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work as per drawing and M.O.R.D. technical specification clause 802,803,1202 and 1203 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 29.19 | Per cubic metre | | | |
| 3 | Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 R.C.C. grade M 25 (twenty five) 1:1/1/2:3 (one cement : one and half sand : three crushed stone aggregate) as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 19.50 | Per cubic metre | | | |
| Total:- | | | | | | |


 Executive Engineer
 Ghumanwin Division
 H.P.P.W.D Ghumanwin

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs.199736/-ONLY.

EARNEST MONELY:- Rs 2000 Only.

TIME ALLOWED:- TWO MONTH.

NAME OF WORK:- R/R on Bhager Panol Sunhani road km 0/0 to 7/0 (SH:- C/O RWall at RD.0/565 to 0/584 and 0/586 to 0/600)

| Sl.No | Sub-Head and item of work. | Quantity | rates in | | Unit | Amount. |
|--------|---|----------|----------|--------|-----------------|---------|
| | | | Figures | Words. | | |
| 1 | Earth work is excavation for structures as per drawings and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50 metres dressing of sides and bottom and back filling in trenches with excavated suitable materials (i) upto 3 metre depth MORD specification page NO.126 Sr.No.1.1 MORD specification 300 including carriage of material within all leads and lifts as directed by the Engineer-in-charge. GST, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same | 30.17 | | | Per cubic metre | |
| 2 | Providing and cement concrete 1:5:10 (One cement:Five sand:Ten graded stone aggregate of form work for plain/reinforced concrete in retaining walls, breast walls, as per drawing and H.P.W.D., specification including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government. | 88.94 | | | Per cubic metre | |
| 3 | Providing weep holes in brickmasonry/stone masonry/plain reinforced and concrete abutment wing wall RWall BWall with 100mm dia (Hundred millimetre) PVC pipe and complete providing and technical specification clause 614,709,12043.7. including carriage of material within all leads and lifts as directed by the Engineer-in-charge. GST, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same | 47.00 | | | Each | |
| TOTAL= | | | | | | |

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

Schedule of Quantity

Estimated Cost:- Rs. 4,33,419.00
Earnest Money:- Rs. 8,700.00

Time :- Two Month

Name of Work:- Construction of link road Samlohla to Chadol via Pickle factory km 0/0 to 2/460(SH:- C/o RCC slab culvert 3.00 mtr. Span at RD 2/621) (under SCSP).

| Sr. No. | Description Item | Quantity | Unit | Rates | | Amount |
|---------|---|----------|-----------------|-----------|----------|--------|
| | | | | In figure | In words | |
| 1 | Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lift. dressing of sides and bottom and back filling in trenches with excavated suitable material as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 59.25 | Per cubic metre | | | |
| 2 | Providing and Laying concrete 1:4:8 (one cement : four sand : eight crushed stone aggregate) 25m (twenty five metre) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 8.71 | Per cubic metre | | | |
| 3 | Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 P.C.C grade M 15 Nominal mix (1:2.5:5) (one cement : two and half sand : five crushed stone aggregate) as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 73.08 | Per cubic metre | | | |
| 4 | Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 R.C.C M 25 1:1.5:3 (one cement : one and half sand : three crushed stone aggregate) Upto 5m height as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 9.60 | Per cubic metre | | | |
| 5 | Providing and laying and Supplying, fitting and placing HYSD bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.254 | Per Tonne | | | |
| 6 | Providing weep holes in brick masonry / stone masonry / plain reinforced concrete abutment wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614,709,1204.3.7 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 19.00 | Each | | | |
| 7 | Back filling behind abutment, wing walls return wall complete as per drawings and technical specification clause 1204.3.8 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 18.94 | Per cubic metre | | | |

| | | | | | | | |
|----------------|---|------|-------------------|--|--|--|--|
| 8 | Providing and laying cement concrete wearing course M 30 grade including reinforcement complete as per drawing and technical specifications Clauses 800 and 1206.3 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.71 | Per cubic metre | | | | |
| 9 | Construction of R.C.C. railing of M 25 grade in cast-in-situ with 20 mm (twenty millimetre) nominal size aggregate, true to line and grade, tolerance of vertical railing post not to exceed 1 in 500, centre-to-centre spacing between vertical posts not to exceed 2000 mm (two thousand millimetre) as per drawing and technical specifications Clauses 800, 900 and 1208.3 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 8.00 | Per running metre | | | | |
| 10 | Drainage spouts complete as per drawing and technical specifications Clause 1209 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 2.25 | Per running metre | | | | |
| Total:- | | | | | | | |


 Executive Engineer
 Chumarwin Division
 HPPWD Chumarwin

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs.492337/-ONLY.

EARNEST MONELLY:- Rs 10000/-Only.

TIME ALLOWED:- Two MONTH.

NAME OF WORK:-Removal of Black Spots on link road from Kothi to Baddu km 0/0 to 2/285 (SH:-C/O R/Wall in Wire crate at RD. 2/170 to 2/190 & 2/202.50 to 2/209)

| Sr.No | Surf Head and item of work. | Quantity | rates in | | Unit | Amount. |
|--------|---|----------|----------|--------|-----------------|---------|
| | | | Figures | Words. | | |
| 1 | Earth work is excavation for structures as per drawings and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50 metres dressing of sides and bottom and back filling in trenches with excavated suitable materials (i) upto 3 metre depth MORR specification page NO.126Sr.No.11.1 MORR specification 300 riage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government. | 169.34 | | | Per cubic metre | |
| 2 | Providing and laying of boulder apron in wire crate with 4mm. Dia G-1 wire conforming of I.S. 280 & I.S 4826 in 100mmx100mm mesh woron diagonally including 10% extra for laps and joints laid with stone boulder weighing not less 25kg. each as per drawing & technical specification clause riage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government. | 289.91 | | | Per cubic metre | |
| 3 | Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government. | 99.38 | | | Per cubic metre | |
| TOTAL= | | | | | | |

Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin