

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PW-MDI(Padhar)E-Tender-NIT/2022-23- 2437-39

Dated:- 24 ^S/₂₂

To

The Executive Engineer (IT Cell),
Nirman Bhawan ,Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,


Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.


Executive Engineer,
Mandi Division No.I,
HP. PWD at Padhar

Copy forwarded the Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and further necessary action please.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., **at Padhar** on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before **03.06.2022 up to 12:00 Noon** and the same shall be opened on the same day **at 12:30 P.M.** in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on **01.06.2022 upto 01:00 P.M.**

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., **at Padhar** reserves the right to accept or reject the tenders. The tender shall remain valid for 90 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.

Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Construction of Community Health Centre building at Kataula District Mandi (H.P.) (SH:- Earth work in excavation for Toe wall and R/wall & providing and laying formwork, PCC 1:4:8 in Toe wall below boundary wall and back side with steps at valley side).	4,99,677/-	10,000/-	350/-	One month
2	Construction of Community Health Centre building at Kataula District Mandi (H.P.) (SH:- Providing and laying formwork, PCC 1:4:8 in R/wall front side near porch, PCC 1:3:6 in steps back side and autoclaved aerated cement block masonry in pillars and panel at valley side).	4,00,478/-	8,000/-	350/-	One month
3	Construction of Community Health Centre building at Kataula District Mandi (H.P.) (SH:- Providing Plastering, Plinth protection, weep holes etcetra in Retaining wall at valley side).	1,07,498/-	2,200/-	350/-	One month
4	Annual repair and maintenance of PWD Rest House at Prasher Distt. Mandi (H.P.) (SH:- Providing water supply, sanitary installations and other minor repair works etcetra).	3,03,784/-	6,100/-	350/-	One month
5	Annual repair and maintenance of PWD Rest House at Prasher Distt. Mandi (H.P.) (SH:- Providing and laying wooden flooring).	4,83,188/-	9,700/-	350/-	One month
6	Annual repair and maintenance of PWD Rest House at Prasher Distt. Mandi (H.P.) (SH:- Providing and fixing wooden flooring and PVC Pannel ceiling).	4,98,780/-	10,000/-	350/-	One month
7	Annual repair and maintenance of PWD Rest House at Prasher Distt. Mandi (H.P.) (SH:- Providing and fixing wood work).	3,82,975/-	7,700/-	350/-	One month
8	Annual repair and maintenance of PWD Rest House at Prasher Distt. Mandi (H.P.) (SH:- Providing and fixing PVC vetrified tiles 300x300x10mm and Duro stone vetrified tiles 600x600x8mm etcetra).	4,75,370/-	9,500/-	350/-	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The intending Contractors are requested to see the site of the work before submitting the tender.
5. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.
6. The offer of the tender shall remain valid upto 90 days after the opening of tender.
7. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% to (-) 30% of the amount put to tender, otherwise the tender will be cancelled and recalled.
8. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.



Executive Engineer,
Mandi Division No. I,
HPPWD., at Padhar Distt. Mandi (H.P.)
on behalf of Governor of Himachal Pradesh

Schedule of Quantity

Estimated Cost:- 499677.00
 Earnest Money:- 10000.00
 Time:- One month.

Name of work:- Construction of Community Health Centre building at Kataula District Mandi (H.P.)
Sub Head:- Earth work in excavation for Toe wall and RWWall & providing and laying formwork, PCC 1:4:8 in Toe wall below boundary wall and back side with steps at valley side.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for all kinds of soil by mechanical means/manual means in foundation trenches or drains over areas upto any depth and width including dressing of sides and ramming of bottoms upto any lift including getting out the excavated soil and disposal of excavated earth complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	59.12 Cum.			Per cubic metre	
2	Providing and laying in position cement concrete 1:4:8 (one cement: four sand : eight graded stone aggregate 40mm (forty millimetre) nominal size of specified grade excluding the cost of centering and shuttering -All works up to plinth level including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	73.50 Cum.			Per cubic metre	
3	Providing centering and shuttering including strutting,propping etcetra and removal of form for Retaining walls,return walls, walls (any thickness) including attached pillars, buttresses, plinth and string courses fillets, kerbs and steps etcetra complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	215.36 Sqm			Per square metre	
					Total:-	


 Executive Engineer,
 Mandi Division No.1,
 H.P.W.D. at Padhar

Schedule of Quantity

Estimated Cost:- 400478.00
 Earnest Money:- 8000.00
 Time:- One month.

Name of work:- Construction of Community Health Centre building at Kataula District Mandi (H.P.)

Sub Head:- Providing and laying formwork, PCC 1:4:8 in R/wall front side near porch, PCC 1:3:6 in steps back side and autoclaved aerated cement block masonry in pillars and panel at valley side.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and laying in position cement concrete 1:4:8 (one cement: four sand : eight graded stone aggregate 40mm (forty millimetre) nominal size of specified grade excluding the cost of centering and shuttering -All works up to plinth level including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	37.81 Cum.			Per cubic metre	
2	Providing and laying in position cement concrete 1:3:6 (one cement: three sand : six graded stone aggregate 20mm (twenty millimetre) nominal size of specified grade excluding the cost of centering and shuttering -All works up to plinth level including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	14.18 Cum.			Per cubic metre	
3	Providing and laying autoclaved aerated cement blocks masonry with 230mm(two hundred thirty millimetre) thick AAC blocks in super structure above plinth level up to floor V (five) level with RCC band at sill level and lintel level with approved block laying polymer modified adhesive mortar (The payment of RCC band and reinforcement shall be made for seperately) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	16.15 Cum.			Per cubic metre	
4	Providing centering and shuttering including strutting,propping etcetra and removal of form for Retaining walls,return walls, walls (any thickness) including attached pillars, buttresses, plinth and string courses filets, kerbs and steps etcetra complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	47.49 Sqm			Per square metre	
				Total:-		


 Executive Engineer,
 Mandi Division No.1,
 H.P.PWD. at Padhar.

Schedule of Quantity

Estimated Cost:- 107498.00
 Earnest Money:- 2200.00
 Time:- One month.

Name of work:- Construction of Community Health Centre building at Kataula District Mandi (H.P.)
Sub Head:- Providing Plastering, Plinth protection, weep holes etcetra in Retaining wall at valley side.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	15 mm (fifteen millimetre) cement plaster on rough side of single or half brick wall of mix 1:6 (one cement: six coarse sand) complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.	141.01 Sqm.			Per square metre	
2	Finishing walls on new work (two or more coats applied @ (at the rate of) 3.84 kg/10 sqm (three point eighty four kilogram per ten square metre) with water proofing cement paint of required shade complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.	141.01 Sqm.			Per square metre	
3	Making plinth protection 50mm (fifty millimetre) thick of cement concrete 1:3:6 (one cement : three coarse sand (zone - III) : six graded stone aggregate 20 mm (twenty millimetre) nominal size) over 75mm (seventy five millimetre) thick bed of dry brick ballast 40 mm (forty millimetre) nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & finishing.	17.67 Sqm.			Per square metre	
4	Providing and laying in position specified grade of reinforced cement concrete 1:2:4 (one cement: two sand : four graded stone aggregate 20mm (twenty millimetre) nominal size excluding the cost of centering and shuttering, finishing and reinforcement- All work up to plinth level in foundation, footing, bases of columns and the like and mass concrete including carriage of materials within all leads and lifts	0.60 Cum.			Per cubic metre	
5	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	12.00 No.			Each	
6	Stone filling behind abutment retaining walls etcetra complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	31.15 Cum.			Per cubic metre	
				Total:-		


 Executive Engineer,
 Mandi Division No.1,
 H.P.W.D. at Padhan

Schedule of Quantity

Estimated Cost:- 303784.00
 Earnest Money:- 6100.00
 Time:- One month.

Name of work:- Annual repair and maintenance of PWD Rest House at Prasher Distt. Mandi (HP).
Sub Head:- Providing water supply , sanitary installations and other minor repair works etcetra.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and fixing ALI- 85001 Pillar Cock (Jaquar) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	16.00 Nos.			Each	
2	Providing and fixing KUP -35037 PM Bib Cock with wall Flange (Jaquar) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	18.00 Nos.			Each	
3	Providing and fixing OHS-1989 Overhead Shower 110mm dia (one hundred ten diameter) Round Shape single Flow (ABS Body Chrome Plated with Gray Face plate) with Rubit Cleaning System SHA-479L300S Shower Arm 20mm dia (twenty millimetre diameter) and 300mm (three hundred millimetre) Long Round Shape with 90° (ninety degree) bend for Wall Mounted showers with stainless steel Flange Jaquar including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	5.00 Nos.			Each	
4	P/F ACN-113 in Soap Dish Holder of superior quality (Jaquar) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	6.00 Nos.			Each	
5	Providing and fixing 100 mm (one hundred millimetre) sand cast Iron grating for gully trap including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	6.00 Nos.			Each	
6	Providing and fixing 110mm (one hundred ten millimetre) diameter single socketed pipe, on wall face unplasticised Rigid PVC rain water pipes conforming to IS:13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10mm (ten millimetre) gap thermal expansion including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	150.00 Rmt			Per Running metre	
7	Providing and fixing G.I Pipes complete with G.I fittings and clamps, including making good the walls etcetra concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the walls including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	150.00 Rmt			Per Running metre	
8	Providing and fixing ACN-1153 S (Jaquar) Toilet Roll Holder with Stainless Steel Flap of Superior quality including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	6.00 Nos.			Each	
9	Providing and fixing 450mm (four hundred fifty millimetre) long CAN -1111BNM Single Towel Rail (Jaquar) of Superior quality including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	6.00 Nos.			Each	
10	Providing and fixing LYS-WHT-38801 Wall Hung Basin with Fixing Accessories (Jaquar) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	6.00 Nos.			Each	

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
11	P/F ACN-1121 N (Jaquar) Towel Ring Square with Round Flange of Superior quality including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	6.00 Nos.	.		Each	
12	Providing and fixing 8mm (eight millimetre) diameter C.P./S.S. Jet with flexible tube upto 1 (one) metre long with S.S triangular plate to European type W.C. of quality and make as approved including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	6.00 Nos.			Each	
				Total:-		


 Executive Engineer,
 Mandi Division No.1,
 P.P. PWD. at Padhar.

Schedule of Quantity

Estimated Cost:- 483188.00
 Earnest Money:- 9700.00
 Time:- One month.

Name of work:- Annual repair and maintenance of PWD Rest House at Prasher Distt. Mandi (HP).

Sub Head:- Providing and laying wooden flooring.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and fixing wooden laminate flooring made in superior water resistant high density hard wood fiber board make action tesa with all accessories including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	176.52 Sqm			Per square metre	
				Total:-		


 Executive Engineer,
 Mandi Division No.1,
 HP.PWD. at Padhar.

Schedule of Quantity

Estimated Cost:- 498780.00
 Earnest Money:- 10000.00
 Time:- One month.

Name of work:- Annual repair and maintenance of PWD Rest House at Prasher Distt. Mandi (HP).

Sub Head:- Providing and fixing wooden flooring and PVC Pannel ceiling.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and fixing PVC pannel ceiling including ceiling section chanel of superior quality including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	163.55 Sqm.			Per square metre	
2	Providing and fixing wooden laminate flooring made in superior water resistant high density hard wood fiber board make action tesa with all accessories including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	84.50 Sqm.			Per square metre	
				Total:-		


 Executive Engineer,
 Mandi Division No.1,
 HP.PWD. at Padharan

Schedule of Quantity

Estimated Cost:- 382975.00
 Earnest Money:- 7700.00
 Time:- One month.

Name of work:- Annual repair and maintenance of PWD Rest House at Prasher Distt. Mandi (HP).

Sub Head:- Providing and fixing wood work.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and fixing 12mm (twelve millimetre) thick Pre-laminated Particle board with decorative lamination on both side Grade, 1 Type 11 IS: 14842 marked including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	22.64 Sqm.			Per square metre	
2	Providing and fixing 40mm (forty millimetre) thick 2nd (second) class deodar wood in frames of door and window cleastory, window and other frames and fixed in position including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.29 Cum.			Per cubic metre	
3	Providing and fixing 40mm (forty millimetre) thick 2nd (second) class deodar wood panelled glazed or panelled and glazed shutters for door windos and clerestory windows Including black enamelled iron bott hinges with necessary screws including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	11.73 Sqm.			Per square metre	
4	Providing and fixing 40mm (forty millimeter) thick second class deodar wood wire gauge shutters using galvanized MS wire gauge of IS gauge designation 85g (Eighty five) gauge with wire of diameter 0.56mm (zero point five six millimeter) for doors, windows and clerestorey windows including bright finished black enamelled iron hinges with necessary screws including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	11.73 Sqm.			Per square metre	
5	Providing and fixing viterous China (CERA)EWC(P) single peace seat with UF soft close seat cover, hinges including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	5.00 Nos.			Each	
6	Providing and fixing ALI-85053 Angular Stop Cock with Wall Flange (jaquar) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	40.00 Nos.			Each	
	Total:-					


 Executive Engineer,
 Mandi Division No.1,
 HP.PWD. at Padhar

Schedule of Quantity

Estimated Cost:- 475370.00
Earnest Money:- 9500.00
Time:- One month.

Name of work:- Annual repair and maintenance of PWD Rest House at Prasher Distt. Mandi (HP).
Sub Head:- Providing and fixing PVC vetrified tiles 300x300x10mm and Duro stone vetrified tiles 600x600x8mm etcetra.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etcetra complete and stacking upto any lead of area 3 (three) square metre and below complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	2.00 Nos.			Each	
2	Dismantling tile work for thickness of tiles above 25 mm and up to 40 mm in floors and roofs laid in cement mortar including stacking material complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	206.61 Sqm.			Per square metre	
3	Providing concrete for plain reinforced concrete gradeM-10 (ten) nominal mix 1:3:6(One cement: three sand :six graded stone aggregate 20mm (twenty millimetre) nominal size) in open foundation complete as per drawing and technical specifications clause 802.803,1202 and 1203 curing complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	12.91 Cum.			Per cubic metre	
4	Providing and laying Duro stone vetrified tiles 300mmx300mmx8mm (three hundred millimetre into three hundred millimetre into eight millimetre) in grey/coloured of required shade in skirting risers of steps and dados on 12mm (twelve millimetre) thick cement mortar 1:3(one cement :three sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	23.78 Sqm.			Per square metre	
5	Providing and laying ceramic tiles 300x300mmx10mm (three hundred millimetre into three hundred millimetre into ten millimetre) in grey/coloured or of approved shade in flooring, treads of steps and landing laid on a bed of 12mm (twelve millimetre) thick cement mortar 1:3 (one cement :three sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	45.36 Sqm.			Per square metre	
6	Providing and laying Duro stone vetrified tiles 600mmx600mmx8mm (six hundred millimetre into six hundred millimetre into eight millimetre) manufactured of approved shade and colour in flooring ,treads of steps and landings laid over 12mm (twelve millimetre) thick cement mortar 1:3 (one cement :three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	124.16 Sqm.			Per square metre	
				Total:-		


 Executive Engineer,
 Mandi Division No.1,
 S.P.P.W.D. at Padhar