



Office of
Executive Engineer B&R Division HP.PWD. Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on **16/05/2023 up to 11:30 A.M.** and will be opened on the same day at **(12:00 noon)** in the presence of intending contractors. The tender application will be received in this office on **12/05/2023 up to 10.00 A.M. to 12:30 P.M.** and tender form can be had from this office on **15/05/2023 from 2.00 P.M. to 5.00 Pm.** The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.


	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Construction of Govt. Degree College Lad-Bharol District Mandi (H.P.) (Sub Head:- Providing and fixing Fire Extinguisher ISI mark).	Rs. 3,22,000/-	Rs. 6,400/-	Rs. 350/-	Class "D"	One month
2	Restoration of damages due to OFC on various road under Joginder Nagar Sub Division HPPWD., Joginder Nagar (Sub Head:- Supplying and stacking of hard fuel wood for patch work).	Rs. 1,57,500/-	Rs. 3,200/-	Rs. 350/-	Class "D"	Three months
3	Construction of link road to Village Bheru Km. 0/0 to 0/800 (Sub Head:- Providing and laying wearing G-II & cement concrete pavement at Km. 0/300 to 0/400).	Rs. 3,20,277/-	Rs. 6,400/-	Rs. 350/-	Class "D"	Three months
4	Restoration of damages due to OFC on various road under Lad-Bharol Sub Division HPPWD., Lad-Bharol (Sub Head:- Supplying and stacking of hard fuel wood for patch work).	Rs. 1,57,500/-	Rs. 3,200/-	Rs. 350/-	Class "D"	Three months
5	Construction of Administrative (Combined office) building at Joginder Nagar District Mandi (H.P.) (Sub Head:- Providing and fixing Fire Extinguisher ISI mark).	Rs. 3,22,000/-	Rs. 6,400/-	Rs. 350/-	Class "D"	One month
6	Construction of link road from Kurati Shel Nallah to Connect with village Joun Km. 0/0 to 2/300 (Sub Head :- Constriction of 900 mm dia RCC hume pipe culvert at Km. 0/950).	Rs. 2,43,642/-	Rs. 4,900/-	Rs. 350/-	Class "D"	Three months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.

5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.


Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.

District Mandi (HP) on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-I/NIT/Press/2021-22-1476-1525 Dated:- 24-6-2023

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Notice Board.
9. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.

3

SCHEDULE OF QUANTITY


Name of Work : Construction of link road to Village Bhero km 0/00 to 0/800

(S.H. : Providing and laying of Wearing G-II & Cement Concrete pavement at km 0/300 to 0/400)

Estimate Cost: 3,20,277
Earnest Money: 6,400
Time Limit : Three Mo

AMOUNT
Rs. P

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 KN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstics of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	23.63	Per cubic metre			
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	39.38	Per Cubic metre			
Total						


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

(4)

Schedule of Quantity

Estimated Cost:- 157500.00
Earnest Money:- 3200.00
Time:- Three months

Name of work:- Restoration of damages due to OFC on various road under Lad Bharol sub division HPPWD Lad Bharol.
Sub Head:- Supplying and stacking of hard fuel wood for patch work.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking at site of work dry hard fuel wood, the fuel wood shall be dry and have a minimum girth of nine inch but not exceeding one feet six inch including entire carriage of materials within all lead lifts and proper stacking at site as per the direction of Engineer-in-Charge including carriage of material with in all leads lifts complete in all respect. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	210.00			Per quintal	
Total:-						

~~Executive Engineer,~~
B&R Division, HP. PWD.,
Joginder Nagar.

5

Schedule of Quantity

Name of work:- Construction of Administrative (Combined office) building at Joginder Nagar District Mandi (H.P.) (SH:- Providing and fixing Fire Extinguisher ISI m

Estimated Cost:- 322000.00
Earnest Money:- 6400.00
Time:- One Month

Sr. No.	Description of Item	Qty.	Rate		Unit	Ar
			In Figure	In Words		
1	Providing and fixing Powder Fire Extinguisher (stored pressure type) 9 (Nine) Kilogramme capacity duly ISI marked confirming to ISI : 15683:2006, with IS 14609, ISI marked ABC powder complete with squeeze grip release valve, discharge pipe locking arrangement, pressure gauge, operation manual, bracket with two screw and sleeve with in all leads, lifts and carriage of materials as per direction of Engineer-In-Charge . The rate is included all taxes levy by the Govt. excluding GST.	40.00			Each	
					Total:-	

Executive Engineer,
B&R Division HP.PWD.,
Joginder Nagar.

ount

rk).

SCHEDULE OF QUANTITY

566 NO 6

Name of Work : Construction of Kurati Sheel Nallah to Connect with Village Jounn Km 0/00 to 2/300
(Sub Head:- Construction of 900mm dia Hume Pipe Culvert alongwith both side wing wall at km 1/900)

Estimate Cost: 2,43,642.00
Earnest Money: 4,900.00
Time Limit : Three Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	51.75	Per cubic metre			
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentials.The rate is inclusive all taxes levy by the government time to time excluding GST.	2.99	Per cubic metre			
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentials.The rate is inclusive all taxes levy by the government time to time excluding GST.	9.58	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
4	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	19.87	Per cubic metre			
5	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification. Rubble stone laid in cement mortar 1:5 (one cement : five sand) complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	0.49	Per cubic metre			
6	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	6.69	Per cubic metre			
7	Providing and laying 900mm (nine hundred millimetre) diametre reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	7.50	Per running metre			
8	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diametre) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	6.00	Each			
Total						

 Executive Engineer

B & R Division HP.P.W.D,
Joginder Nagar