

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

No.PW-MDI(Padhar)E-Tender-NIT/2023-24- 3607-9

Dated: 1-7-2023

To


The Executive Engineer (IT Cell),  
Nirman Bhawan, Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,


Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16<sup>th</sup> July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

**DA:- Notice Inviting Tender.**

  
Executive Engineer,  
Mandi Division No.I,  
HP. PWD. at Padhar

Copy forwarded the Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and further necessary action please.

  
Executive Engineer,  
Mandi Division No.I,  
HP. PWD. at Padhar



**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**\*NOTICE INVITING TENDER\***

Sealed percentage rate tender on form No. 6&8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 13.07.2023 up to 12:00 Noon and the same shall be opened on the same day at 12:30 P.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 12.07.2023 upto 1:00 P.M.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.

| Sr. No. | Name of work.  | Estimated Cost (in Rs.) | Earnest Money (in Rs.) | Cost of Tender Form (in Rs.) | Time       |
|---------|--|-------------------------|------------------------|------------------------------|------------|
| 1       | Construction of Ropa Khad Harizen Basti Ropru to Nasloh road Km 0/0 to 3/500 under SCSP (SH:- Construction of 900mm dia metre RCC Hume pipe culvert along with wing walls at RD 3/005 & 3/195) | 4,95,504/-              | 9,900/-                | 350/-                        | Six months |
| 2       | Construction of Ropa to Kathog road Km 0/0 to 5/400. (SH:- Construction of P.C.C. retaining wall at R.D. 0/450 to 0/460).  | 4,39,968/-              | 8,800/-                | 350/-                        | One month  |
| 3       | Construction of Ropa to Kathog road Km 0/0 to 5/400. (SH:- Construction of P.C.C. retaining wall at R.D. 2/460 to 2/470).  | 2,10,335/-              | 4,200/-                | 350/-                        | One month  |
| 4       | Construction of Ropa to Kathog road Km 0/0 to 5/400. (SH:- Construction of P.C.C. retaining wall at R.D. 0/460 to 0/470).  | 4,41,320/-              | 8,800/-                | 350/-                        | One month  |
| 5       | Construction of Ropa to Kathog road Km 0/0 to 5/400. (SH:- Construction of P.C.C. retaining wall at R.D. 2/470 to 2/479).  | 1,89,182/-              | 3,800/-                | 350/-                        | One month  |
| 6       | Construction of Ropa to Kathog road Km 0/0 to 5/400. (SH:- Construction of wire crated Breast wall at R.D. 4/570 to 4/585).  | 1,40,038/-              | 2,800/-                | 350/-                        | One month  |
| 7       | Restoration of rain damages on Tikkar Sarni road Km 0/0 to 3/720. (SH:- Construction of wire crated Breast wall at RD 1/405 to 1/419)  | 1,18,012/-              | 2,400/-                | 350/-                        | One month  |



**1. Certified that tender of above works are being called of emergent nature in exigency of public interest.**

**TERMS AND CONDITIONS:-**

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.



5. The intending Contractors are requested to see the site of the work before submitting the tender.
6. The offer of the tender shall remain valid upto 75 days after the opening of tender.
7. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
8. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.

  
Executive Engineer,  
Mandi Division No. 1,  
HPPWD., at Padhar Distt. Mandi (H.P.)  
on behalf of  Governor of Himachal Pradesh



**PERCENTAGE RATE BILL OF QUANTITY**

Estimated Cost Rs:- 495504.00  
 Earnest Money Rs:- 9900.00  
 Time :- Six months

Tender Inviting Authority: Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.

Name of work:- Construction of Ropa Khad Harizen Basti Ropru to Nasloh road Km. 0/0 to 3/500 under SCSP. (Sub Head:- Construction of 900mm diameter RCC hume pipe culvert along with wing walls at RD. 3/005 & 3/195).  
 Contract No.:


Name of Bidder/Bidding Firm/ Company:

**SCHEDULE OF WORKS**

| Sr. No. | Item Description  | Quantity | Units             | Estimated Rate Rs. P. | TOTAL AMOUNT with all Taxes excluding GST in Rs. P. | TOTAL AMOUNT with all Taxes excluding GST in words.              |
|---------|---|----------|-------------------|-----------------------|---|--|
| 1       | 2   | 3        | 4                 | 5                     | 6   | 7  |
| 1       | Excavation in soil in hilly area by manual means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.   | 7.89     | Per cubic metre   | 218.28                | 1722.00   | Rupees Seven Hundred Twenty Two Only                             |
| 2       | Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.   | 82.31    | Per cubic metre   | 485.28                | 39943.00  | Rupees Thirty Nine Thousand Forty Three Only                     |
| 3       | Providing and laying concrete Mechanically mixed and vibrated mix 1:6:12 (one cement: six sand: twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.  | 3.36     | Per cubic metre   | 4561.64               | 15327.00  | Rupees Fifteen Thousand Three Hundred Twenty Seven Only          |
| 4       | Providing and laying concrete mechanically mixed and vibrated mix 1:4:8 (one cement: four sand: eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts or as per the entire satisfaction and direction of Engineer-in-Charge.  | 48.22    | Per cubic metre   | 5025.43               | 242326.00   | Rupees Two Lakh Forty Two Thousand Three Hundred Twenty Six Only |
| 5       | Providing concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement : three sand : twelve graded, crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.   | 19.18    | Per cubic metre   | 5951.41               | 114148.00   | Rupees One Lakh Fourteen Thousand One Hundred Forty Eight Only   |
| 6       | Providing and laying reinforced cement concrete 900mm (Nine hundred millimetre) diameter pipe NP2 as per design for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) but excluding excavations, protection works, back filling, concrete and masonry works in head walls and parapets as per drawings and technical specifications for Rural roads clause 1101 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge. | 14.00    | Per running metre | 3561.22               | 49857.00  | Rupees Forty Nine Thousand Eight Hundred Fifty Seven Only        |
| 7       | Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1303. Rubble stone laid in cement mortar 1:3 (one cement : three sand) ( Excavation for preparation of bed and cement concrete bedding to be measured and paid for separately) including curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.   | 0.98     | Per cubic metre   | 5275.43               | 5170.00   | Rupees Five Thousand One Hundred Seventy Only                    |



| Sr. No.                     | Item Description   | Quantity  | Units           | Estimated Rate Rs. P. | TOTAL AMOUNT with all Taxes excluding GST in Rs. P. | TOTAL AMOUNT with all Taxes excluding GST in words.    |
|-----------------------------|--|---|-----------------|-----------------------|---|--|
| 1                           |  | 3   | 4               | 5                     | 6   | 7  |
| 8                           | Providing weep hole in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge. | 24.00   | Each            | 284.42                | 6826.00   | Rupees Six Thousand Eight Hundred Twenty Six Only      |
| 9                           | Back filling behind abutment wing wall and return wall complete as per drawing and technical specifications clause 1206.3 with Granular material complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.   | 13.38   | Per cubic metre | 1508.63               | 20185.00  | Rupees Twenty Thousand One Hundred Eighty Five Only    |
| <b>Total in Figure</b>      |  |   |                 |                       | <b>495504.00</b>                                    | <b>Rupees Four Lakh Ninety Five Thousand Four Only</b> |
| <b>Quoted Rate in Words</b> |  | <b>Rupees Four Lakh Ninety Five Thousand Five Hundred Four Only</b> |                 |                       |   |  |

  
 Executive Engineer,  
 Mandi Division No. 1,  
 HP.PWD. at Padhar.



PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 439968.00

Earnest Money Rs:- 8800.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of work :- Construction of Ropa to Kathog road Km. 0/0 to 5/400. (Sub Head:- Construction of P.C.C. retaining wall at R.D. 0/450 to 0/460.)

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

| Sr. No.                  | Description of items.   | Quantity | Units           | Estimate Rate Rs. P. | TOTAL AMOUNT with all taxes excluding GST in words.                        | TOTAL AMOUNT with all taxes excluding GST in Rs. P. |
|--------------------------|---|----------|-----------------|----------------------|--|---|
| 1                        | Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.                       | 36.85    | Per cubic metre | 485.30               | Rupees Seventeen Thousand Eight Hundred Eighty Three Only                  | 17883.00  |
| 2                        | Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.  | 72.22    | Per cubic metre | 5497.70              | Rupees Three Lakh Ninety Seven Thousand Forty Four Only                    | 397044.00   |
| 3                        | Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.   | 14.55    | Per cubic metre | 1560.10              | Rupees Twenty Two Thousand Six Hundred Ninety Nine Only                    | 22699.00  |
| 4                        | Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge. | 8.00     | Each            | 292.80               | Rupees Two Thousand Three Hundred Forty Two Only                           | 2342.00   |
| <b>Total in figure :</b> |   |          |                 |                      |  | <b>439968.00</b>                                    |
| <b>Total in Words :</b>  |   |          |                 |                      | <b>Rupees Four Lakh Thirty Nine Thousand Nine Hundred Sixty Eight Only</b> |   |

  
 Executive Engineer,  
 Mandi Division No.1,  
 HP. PWD. at Padhar.




PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 210335.00  
 Earnest Money Rs:- 4200.00  
 Time One month

**Tender Inviting Authority :** Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.  
**Name of work :-** Construction of Ropa to Kathog road Km. 0/0 to 5/400. (Sub Head:- Construction of P.C.C. retaining wall at R.D. 2/460 to 2/470.)  
**Contract No. :**  
**Bidder Name :**

SCHEDULE OF WORKS

| Sr. No.                  | Description of items.   | Quantity | Units           | Estimate Rate Rs. P. | TOTAL AMOUNT with all taxes excluding GST in Rs. P. | TOTAL AMOUNT with all taxes excluding GST in words.                |
|--------------------------|---|----------|-----------------|----------------------|---|--|
| 1                        | Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.                       | 20.75    | Per cubic metre | 485.30               | 10070.00  | Rupees Ten Thousand Seventy Only                                   |
| 2                        | Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.  | 35.32    | Per cubic metre | 5497.70              | 194179.00   | Rupees One Lakh Ninety Four Thousand One Hundred Seventy Nine Only |
| 3                        | Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.   | 2.40     | Per cubic metre | 1560.10              | 3744.00   | Rupees Three Thousand Seven Hundred Forty Four Only                |
| 4                        | Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge. | 8.00     | Each            | 292.80               | 2342.00   | Rupees Two Thousand Three Hundred Forty Two Only                   |
| <b>Total in figure :</b> |   |          |                 |                      | <b>210335.00</b>                                    | <b>Rupees Two Lakh Ten Thousand Three Hundred Thirty Five Only</b> |
| <b>Total in Words :</b>  |   |          |                 |                      |   | <b>Rupees Two Lakh Ten Thousand Three Hundred Thirty Five Only</b> |

  
 Executive Engineer,  
 Mandi Division No.I,  
 HP. PWD. at Padhar.



PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 441320.00  
Earnest Money Rs:- 8800.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of work :- Construction of Ropa to Kathog road Km. 0/0 to 5/400. (Sub Head:- Construction of P.C.C. retaining wall at R.D. 0/460 to 0/470.)


Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Description of items.

| Sr. No.                  | Description of items.   | Quantity | Units           | Estimate Rate Rs. P. | TOTAL AMOUNT with all taxes excluding GST in words.     | TOTAL AMOUNT with all taxes excluding GST in Rs. P.                  |
|--------------------------|---|----------|-----------------|----------------------|---|--|
| 1                        | Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.                       | 32.40    | Per cubic metre | 485.30               | Rupees Fifteen Thousand Seven Hundred Twenty Four Only  | 15724.00   |
| 2                        | Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.  | 72.22    | Per cubic metre | 5497.70              | Rupees Three Lakh Ninety Seven Thousand Forty Four Only | 397044.00  |
| 3                        | Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.   | 16.80    | Per cubic metre | 1560.10              | Rupees Twenty Six Thousand Two Hundred Ten Only         | 26210.00   |
| 4                        | Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge. | 8.00     | Each            | 292.80               | Rupees Two Thousand Three Hundred Forty Two Only        | 2342.00  |
| <b>Total in figure :</b> |   |          |                 |                      |   | <b>441320.00</b>   |
| <b>Total in Words :</b>  |   |          |                 |                      |   | <b>Rupees Four Lakh Forty One Thousand Three Hundred Twenty Only</b> |

  
 Executive Engineer,  
 Mandi Division No.I,  
 HP. PWD. at Padhar.



PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 189182.00


Earnest Money Rs:- 3800.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.  
Name of work :- Construction of Ropa to Kathog road Km. 0/0 to 5/400. (Sub Head:- Construction of P.C.C. retaining wall at R.D. 2/470 to 2/479.)

Contract No. :  
Bidder Name :

| SCHEDULE OF WORKS        |   |          |                 |                      |   |   |
|--------------------------|---|----------|-----------------|----------------------|---|---|
| Sr. No.                  | Description of items.   | Quantity | Units           | Estimate Rate Rs. P. | TOTAL AMOUNT with all taxes excluding GST in Rs. P. | TOTAL AMOUNT with all taxes excluding GST in words.                     |
| 1                        | Earth work in excavation for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.                                      | 19.66    | Per cubic metre | 485.30               | 9541.00   | Rupees Nine Thousand Five Hundred Forty One Only                        |
| 2                        | Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.  | 31.78    | Per cubic metre | 5497.70              | 174717.00   | Rupees One Lakh Seventy Four Thousand Seven Hundred Seventeen Only      |
| 3                        | Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.   | 2.03     | Per cubic metre | 1560.10              | 3167.00   | Rupees Three Thousand One Hundred Sixty Seven Only                      |
| 4                        | Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge. | 6.00     | Each            | 292.80               | 1757.00   | Rupees One Thousand Seven Hundred Fifty Seven Only                      |
| <b>Total in figure :</b> |   |          |                 |                      | <b>189182.00</b>                                    | <b>Rupees One Lakh Eighty Nine Thousand One Hundred Eighty Two Only</b> |
| <b>Total in Words :</b>  |   |          |                 |                      |   | <b>Rupees One Lakh Eighty Nine Thousand One Hundred Eighty Two Only</b> |

  
Executive Engineer,  
Mandi Division No.1,  
HP. PWD. at Padhar.



PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 140038.00

Earnest Money Rs:- 2800.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.  
Name of work :- Construction of Ropa to Kathog road Km. 0/0 to 5/400. (Sub Head:- Construction of Wire crated Breast wall at R.D. 4/570 to 4/585.)  
Contract No. :  
Bidder Name :

| SCHEDULE OF WORKS |  |  |                 |                      |  |   |
|-------------------|--|--|-----------------|----------------------|--|---|
| Sr. No.           | Description of items.  | Quantity   | Units           | Estimate Rate Rs. P. | TOTAL AMOUNT with all taxes excluding GST in words.  | TOTAL AMOUNT with all taxes excluding GST in Rs. P. |
| 1                 | Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.  | 63.82  | Per cubic metre | 485.30               | Rupees Thirty Thousand Nine Hundred Seventy Two Only | 30972.00  |
| 2                 | Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge. | 46.88  | Per cubic metre | 2326.50              | Rupees One Lakh Nine Thousand Sixty Six Only         | 109066.00   |
| Total in figure : |  | Rupees One Lakh Forty Thousand                   |                 | Thirty Eight Only    | 140038.00  | Rupees One Lakh Forty Thousand Thirty Eight Only    |
| Total in Words :  |  | Rupees One Lakh Forty Thousand Thirty Eight Only |                 |                      |  |   |

  
Executive Engineer,  
Mandi Division No.1,  
SHP. PWD. at Padhar.



PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 118012.00  
Earnest Money Rs:- 2400.00  
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.


Name of work :- Restoration of rain damages on Tikkar Sarni road Km. 0/0 to 3/720. (Sub Head:- Construction of Wire crated Breast wall at R.D. 1/405 to 1/419.)

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

| Sr. No.                  | Description of items.  | Quantity | Units           | Estimate Rate Rs. P. | TOTAL AMOUNT with all taxes excluding GST in Rs. P. | TOTAL AMOUNT with all taxes excluding GST in words. |
|--------------------------|--|----------|-----------------|----------------------|---|---|
| 1                        | Earth work in excavation for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.   | 33.39    | Per cubic metre | 485.30               | 16204.00  | Rupees Sixteen Thousand Two Hundred Four Only       |
| 2                        | Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diametre G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge. | 43.76    | Per cubic metre | 2326.50              | 101808.00   | Rupees One Lakh Thousand Eight Hundred Eight Only   |
| <b>Total in figure :</b> |  |          |                 |                      | 118012.00   | Rupees One Lakh Eighteen Thousand Twelve Only       |
| <b>Total in Words :</b>  |  |          |                 |                      |   | Rupees One Lakh Eighteen Thousand Twelve Only       |

  
Executive Engineer,  
Mandi Division No.1,  
HP. PWD. at Padhar.