

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-MDI(Padhar)E-Tender-NIT/2023-24- 6300-02 Dated:- 18/8/2023

To


The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,


Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

Copy forwarded the Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and further necessary action please.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed percentage rate tender on form No. 6&8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 29.08.2023 up to 12:00 Noon and the same shall be opened on the same day at 12:30 P.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 28.08.2023 upto 1:00 P.M.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.


Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Construction of Ropa Khad Harizen Basti Ropru to Nasloh road Km 0/0 to 3/500 under SCSP (SH:- Construction of 900mm dia metre RCC Hume pipe culvert along with wings walls at R.D. 3/195)	2,48,715.00	5,000/-	350/-	Three months
2	Construction of Ropa Khad Harizen Basti Ropru to Nasloh road Km 0/0 to 3/500 under SCSP (SH:- Construction of 900mm dia metre RCC Hume pipe culvert along with wings walls at R.D. 3/005)	2,47,099.52	5,000/-	350/-	Three months
3	Restoration of rain damages on Shegli Prasher road Km 0/0 to 22/510. (SH:- Construction of retaining wall at RD 13/545 to 13/558)	3,98,282.00	8,000/-	350/-	One month
4	Restoration of rain damages on Shegli Prasher road Km 0/0 to 22/510. (SH:- Construction of retaining wall at RD 0/518 to 0/526)	3,67,799.00	7,400/-	350/-	One month
5	Restoration of rain damages on Shegli Prasher road Km 0/0 to 22/510. (SH:- Construction of retaining wall at RD 0/510 to 0/518)	3,67,799.00	7,400/-	350/-	One month
6	Restoration of rain damages on Neri Navlay road Km 0/0 to 3/0. (SH:- Construction of retaining wall at RD 0/825 to 0/835)	3,60,031.84	7,200/-	350/-	One month
7	Restoration of rain damages on Neri Navlay road Km 0/0 to 3/0. (SH:- Construction of retaining wall at RD 2/900 to 2/910)	4,33,526.58	8,700/-	350/-	One month
8	Restoration of rain damages on Neri Navlay road Km 0/0 to 3/0. (SH:- Construction of retaining wall at RD 2/910 to 2/915)	2,17,302.09	4,300/-	350/-	One month
9	Restoration of damages caused due to laying of O.F.C. by Indian Army N.F.S. on Kamand Neri road Km 0/0 to 6/0. (SH:- Construction of retaining wall at RD 2/950 to 2/960)	2,24,922.12	4,500/-	350/-	One month
10	Restoration of damages caused due to laying of O.F.C. by Indian Army N.F.S. on Kamand Neri road Km 0/0 to 6/0. (SH:- Construction of retaining wall at RD 3/540 to 3/550)	2,92,088.88	5,800/-	350/-	One month

11	Restoration of damages caused due to laying of O.F.C. by Indian Army N.F.S. on Kamand Neri road Km 0/0 to 6/0. (SH:- Construction of retaining wall at RD 4/075 to 4/088)	4,30,002.54	8,600/-	350/-	One month
12	Restoration of damages caused due to laying of O.F.C. by Indian Army N.F.S. on Kamand Neri road Km 0/0 to 6/0. (SH:- Construction of retaining wall at RD 1/810 to 1/820)	2,30,460.76	4,600/-	350/-	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.
5. The intending Contractors are requested to see the site of the work before submitting the tender.
6. The offer of the tender shall remain valid upto 75 days after the opening of tender.
7. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
8. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


 Executive Engineer,
 Mandi Division No. I,
 HPPWD., at Padhar Distt. Mandi (H.P.)
 on behalf of Governor of Himachal Pradesh

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost 248715.00

Earnest Money Rs:- 5000.00

Time :- Three months

Tender Inviting Authority: Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.

Name of work:- Construction of Ropa Khad Harizen Basti Ropru to Nasloh road Km. 0/0 to 3/500 under SCSP. (Sub Head:- Construction of 900mm diameter RCC hume pipe culvert along with wing walls at R.D. 3/195).


Contract No.:

Name of Bidder/Bidding Firm/ Company:

SCHEDULE OF WORKS

Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1		3	4	5	6	7
1	Excavation in soil in hilly area by manual means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	4.07	Per cubic metre	218.28	888.40	Rupees Eight Hundred Forty Only
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	42.77	Per cubic metre	485.28	20755.43	Rupees Thousand Hundred and Paise Fifty Three Only
3	Providing and laying concrete Mechanically mixed and vibrated mix 1:6:12 (one cement: six sand: twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	1.68	Per cubic metre	4651.64	7814.76	Rupees Thousand Hundred and Paise Seventy Six Only
4	Providing and laying concrete mechanically mixed and vibrated mix 1:4:8 (one cement: four sand: eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts or as per the entire satisfaction and direction of Engineer-in-Charge.	24.11	Per cubic metre	5025.43	121163.12	Rupees One Lakh Twenty One Thousand One Hundred Sixty Three and Paise Twelve Only
5	Providing concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement : three sand : twelve graded,crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.59	Per cubic metre	5951.41	57074.02	Rupees Fifty Seven Thousand Seven Hundred and Paise Two Only
6	Providing and laying reinforced cement concrete 900mm (Nine hundred millimetre) diameter pipe NP2 as per design for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) but excluding excavations, protection works, back filling, concrete and masonry works in head walls and parapets as per drawings and technical specifications for Rural roads clause 1101 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7.00	Per running metre	3561.22	24928.54	Rupees Twenty Four Thousand Nine Hundred Twenty Eight and Paise Fifty Four Only

Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
7	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1303. Rubble stone laid in cement mortar 1:3 (one cement : three sand) (Excavation for preparation of bed and cement concrete bedding to be measured and paid for separately) including curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	0.49	Per cubic metre	5275.43	2584.96	Rupees Two Thousand Five Hundred Eighty Four and Paise Ninety Six Only
8	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	12.00	Each	284.42	3413.04	Rupees Thousand Four Hundred Thirteen and Paise Four Only
9	Back filling behind abutment wing wall and return wall complete as per drawing and technical specifications clause 1206.3 with Granular material complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	6.69	Per cubic metre	1508.63	10092.73	Rupees Ten Thousand Ninety Two and Paise Seventy Three Only
Total in Figure					248715.00	Rupees Two Lakh Forty Eight Thousand Seven Hundred Fifteen Only
Quoted Rate in Words						Rupees Two Lakh Forty Eight Thousand Seven Hundred Fifteen Only


 Executive Engineer,
 Mandi Division No. 1,
 S.H.P.P.W.D. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 247099.52
Earnest Money Rs:- 5000.00

Time :- Three months


Tender Inviting Authority: Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.

Name of work:- Construction of Ropa Khad Harizen Basti Ropru to Naslosh road Km. 0/0 to 3/500 under SCSP. (Sub Head:- Construction of 900mm diametre RCC hume pipe culvert along with wing walls at R.D. 3/005).

SCHEDULE OF WORKS						
Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	Excavation in soil in hilly area by manual means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	3	Per cubic metre	5	840.38	Rupees Eight Hundred Forty and Paise Thirty Eight Only
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	39.54	Per cubic metre	485.28	19187.97	Rupees Nineteen Thousand One Hundred Eighty Seven and Paise Ninety Seven Only
3	Providing and laying concrete Mechanically mixed and vibrated mix 1:6:12 (one cement: six sand: twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	1.68	Per cubic metre	4651.64	7814.76	Rupees Thousand Eight Hundred Fourteen and Paise Seventy Six Only
4	Providing and laying concrete mechanically mixed and vibrated mix 1:4:8 (one cement: four sand: eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts or as per the entire satisfaction and direction of Engineer-in-Charge.	24.11	Per cubic metre	5025.43	121163.12	Rupees One Lakh Twenty One Thousand One Hundred Sixty Three and Paise Twelve Only
5	Providing concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement: three sand : twelve graded, crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.59	Per cubic metre	5951.41	57074.02	Rupees Fifty Seven Thousand Seventy Four and Paise Two Only
6	Providing and laying reinforced cement concrete 900mm (Nine hundred millimetre) diameter pipe NP2 as per design for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) but excluding excavations, protection works, back filling, concrete and masonry works in head walls and parapets as per drawings and technical specifications for Rural roads clause 1101 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7.00	Per running metre	3561.22	24928.54	Rupees Twenty Four Thousand Hundred Twenty Eight and Paise Fifty Four Only



Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
7	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1303. Rubble stone laid in cement mortar 1:3 (one cement : three sand) (Excavation for preparation of bed and cement concrete bedding to be measured and paid for seperately) including curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	0.49	Per cubic metre	5275.43	2584.96	Rupees Two Thousand Five Hundred Eighty Four and Paise Ninety Six Only
8	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	12.00	Each	284.42	3413.04	Rupees Thousand Hundred Thirteen and Paise Four Only
9	Back filling behind abutment wing wall and return wall complete as per drawing and technical specifications clause 1206.3 with Granular material complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	6.69	Per cubic metre	1508.63	10092.73	Rupees Ten Thousand Ninety Two and Paise Seventy Three Only
Total in Figure					247099.52	Rupees Two Lakh Forty Seven Thousand Ninety Nine and Paise Fifty Two Only
Quoted Rate in Words						Rupees Two Lakh Forty Seven Thousand Ninety Nine and Paise Fifty Two Only


 Executive Engineer,
 Mandi Division No. 1,
 S.H.P. P.W.D. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 398282.00
Earnest Money Rs:- 8000.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.


Name of work :- Restoration of rain damages on Shegli Prasher road Km. 0/0 to 22/510. (Sub Head:- Construction of retaining wall at R.D. 13/545 to 13/558.)

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	29.97	Per cubic metre	485.30	14544.00	Rupees Fourteen Thousand Five Hundred Forty Four Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	70.49	Per cubic metre	4910.40	346134.00	Rupees Three Lakh Forty Six Thousand One Hundred Thirty Four Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	24.18	Per cubic metre	1508.60	36478.00	Rupees Thirty Six Thousand Four Hundred Seventy Eight Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	4.00	Each	281.60	1126.00	Rupees One Thousand One Hundred Twenty Six Only
Total in figure :					398282.00	Rupees Three Lakh Ninety Eight Thousand Two Hundred Eighty Two Only
Total in Words :						Rupees Three Lakh Ninety Eight Thousand Two Hundred Eighty Two Only


 Executive Engineer,
 Mandi Division No.I,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 367799.00
 Earnest Money Rs:- 7400.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.


Name of work :- Restoration of rain damages on Shegli Prasher road Km. 0/0 to 22/510. (Sub Head:- Construction of retaining wall at R.D. 0/518 to 0/526.)

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	34.76	Per cubic metre	485.30	16869.00	Rupees Sixteen Thousand Eight Hundred Sixty Nine Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	66.51	Per cubic metre	4910.40	326591.00	Rupees Three Lakh Twenty Six Thousand Five Hundred Ninety One Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	14.64	Per cubic metre	1508.60	22086.00	Rupees Twenty Two Thousand Eighty Six Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	8.00	Each	281.60	2253.00	Rupees Two Thousand Two Hundred Fifty Three Only
Total in figure :					367799.00	Rupees Three Lakh Sixty Seven Thousand Seven Hundred Ninety Nine Only
Total in Words :						Rupees Three Lakh Sixty Seven Thousand Seven Hundred Ninety Nine Only


 Executive Engineer,
 Mandi Division No.1,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 367799.00
 Earnest Money Rs:- 7400.00
 Time One month


Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.
Name of work :- Restoration of rain damages on Shegli Prasher road Km. 0/0 to 22/510. (Sub Head:- Construction of retaining wall at R.D. 0/510 to 0/518.)

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	34.76	Per cubic metre	485.30	16869.00	Rupees Sixteen Thousand Eight Hundred Sixty Nine Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	66.51	Per cubic metre	4910.40	326591.00	Rupees Three Lakh Twenty Six Thousand Five Hundred Ninety One Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	14.64	Per cubic metre	1508.60	22086.00	Rupees Twenty Two Thousand Eighty Six Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	8.00	Each	281.60	2253.00	Rupees Two Thousand Two Hundred Fifty Three Only
Total in figure :					367799.00	Rupees Three Lakh Sixty Seven Thousand Seven Hundred Ninety Nine Only
Total in Words :						Rupees Three Lakh Sixty Seven Thousand Seven Hundred Ninety Nine Only


 Executive Engineer,
 Mandi Division No.I,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 360031.84
 Earnest Money Rs:- 7200.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.
Name of work :- Restoration of rain damages on Neri Navlay road Km. 0/0 to 3/0. (Sub Head:- Construction of retaining wall at R.D. 0/825 to 0/835.)

Contract No. :
Bidder Name :

SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	38.60	Per cubic metre	461.00	Rupees Seventeen Thousand Seven Hundred Ninety Four and Paise Sixty Only	17794.60
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	65.55	Per cubic metre	4795.20	Rupees Three Lakh Four Hundred Twenty Five and Paise Thirty Six Only	314325.36
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	14.40	Per cubic metre	1433.20	Rupees Twenty Thousand Six Hundred Thirty Eight and Paise Eight Only	20638.08
4	Providing weep hole in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	27.00	Each	269.40	Rupees Seven Thousand Two Hundred Seventy Three and Paise Eighty Only	7273.80
Total in figure :						360031.84
Total in Words :					Rupees Three Lakh Sixty Thousand Thirty One and Paise Eighty Four Only	


 Executive Engineer,
 Mandi Division No.1,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 433526.58
 Earnest Money Rs:- 8700.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.
 Name of work :- Restoration of rain damages on Neri Navlay road Km. 0/0 to 3/0. (Sub Head:- Construction of retaining wall at R.D. 2/900 to 2/910.)

Contract No. :
 Bidder Name :

SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	58.50	Per cubic metre	461.00	26968.50	Rupees Twenty Six Thousand Nine Hundred Sixty Eight and Paise Fifty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	79.40	Per cubic metre	4795.20	380738.88	Rupees Three Lakh Eighty Thousand Seven Hundred Thirty Eight and Paise Eighty Eight Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Per cubic metre	1433.20	17198.40	Rupees Seventeen Thousand One Hundred Ninety Eight and Paise Forty Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	32.00	Each	269.40	8620.80	Rupees Eight Thousand Six Hundred Twenty and Paise Eighty Only
Total in figure :					433526.58	Rupees Four Lakh Thirty Three Thousand Five Hundred Twenty Six and Paise Fifty Eight Only
Total in Words :						Rupees Four Lakh Thirty Three Thousand Five Hundred Twenty Six and Paise Fifty Eight Only


 Executive Engineer,
 Mandi Division No.1,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 217302.09
 Earnest Money Rs:- 4300.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.

Name of work :- Restoration of rain damages on Neri Navlay road Km. 0/0 to 3/0. (Sub Head:- Construction of retaining wall at R.D. 2/910 to 2/915.)

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	29.25	Per cubic metre	461.00	13484.25	Rupees Thirteen Thousand Four Hundred Eighty Four and Paise Twenty Five Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	39.70	Per cubic metre	4795.20	190369.44	Rupees One Lakh Ninety Thousand Three Hundred Sixty Nine and Paise Forty Four Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	6.00	Per cubic metre	1433.20	8599.20	Rupees Eight Thousand Five Hundred Ninety Nine and Paise Twenty Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	18.00	Each	269.40	4849.20	Rupees Four Thousand Eight Hundred Forty Nine and Paise Twenty Only
Total in figure :					217302.09	Rupees Two Lakh Seventeen Thousand Three Hundred Two and Paise Nine Only
Total in Words :						Rupees Two Lakh Seventeen Thousand Three Hundred Two and Paise Nine Only


 Executive Engineer,
 Mandi Division No.1,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 224922.12
 Earnest Money Rs:- 4500.00
 Time One month

Order Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.
 Name of work :- Restoration of damages caused due to laying of O.F.C. by Indian Army N.F.S. on Kamand Neri road Km. 0/0 to 6/0. (Sub Head:- Construction of retaining wall at R.D. 2/950 to 2/960.)

Contract No. :
 Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	22.40	Per cubic metre	461.00	10326.40	Rupees Ten Thousand Three Hundred Twenty Six and Paise Forty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	40.55	Per cubic metre	4749.30	192584.12	Rupees One Lakh Ninety Two Thousand Five Hundred Eighty Four and Paise Twelve Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Per cubic metre	1433.20	17198.40	Rupees Seventeen Thousand One Hundred Ninety Eight and Paise Forty Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	18.00	Each	267.40	4813.20	Rupees Four Thousand Eight Hundred Thirteen and Paise Twenty Only
Total in figure :					224922.12	Rupees Two Lakh Twenty Four Thousand Nine Hundred Twenty Two and Paise Only
Total in Words :						Rupees Two Lakh Twenty Four Thousand Nine Hundred Twenty Two and Paise Twelve Only


 Executive Engineer,
 Mandi Division No.1,
 HP. PWD. at Padhar.


PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 292088.88
 Earnest Money Rs:- 5800.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.	
Name of work :- Restoration of damages caused due to laying of O.F.C. by Indian Army N.F.S. on Kamand Neri road Km. 0/0 to 6/0. (Sub Head:- Construction of retaining wall at R.D. 3/540 to 3/550.)	
Contract No. :	
Bidder Name :	

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	31.40	Per cubic metre	461.00	14475.40	Rupees Fourteen Thousand Four Hundred Seventy Five and Paise Forty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	52.95	Per cubic metre	4749.30	251475.44	Rupees Two Lakh Fifty One Thousand Four Hundred Seventy Five and Paise Forty Four Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	13.20	Per cubic metre	1433.20	18918.24	Rupees Eighteen Thousand Nine Hundred Eighteen and Paise Twenty Four Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	27.00	Each	267.40	7219.80	Rupees Seven Thousand Two Hundred Nineteen and Paise Eighty Only
Total in figure :					292088.88	Rupees Two Lakh Ninety Two Thousand Eighty Eight and Paise Eighty Eight Only
Total in Words :						Rupees Two Lakh Ninety Two Thousand Eighty Eight and Paise Eighty Eight Only


 Executive Engineer,
 Mandi Division No.1,
 HP. PWD. at Padhar.


PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 430002.54
 Earnest Money Rs:- 8600.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.
 Name of work :- Restoration of damages caused due to laying of O.F.C. by Indian Army N.F.S. on Kamand Neri road Km. 0/0 to 6/0. (Sub Head:- Construction of retaining wall at R.D. 4/075 to 4/088.)
 Contract No. :
 Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	53.88	Per cubic metre	461.00	Rupees Twenty Four Thousand Eight Hundred Thirty Eight and Paise Sixty Eight Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	78.60	Per cubic metre	4749.30	Rupees Three Lakh Seventy Three Thousand Two Hundred Ninety Four and Paise Ninety Eight Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	14.40	Per cubic metre	1433.20	Rupees Twenty Thousand Six Hundred Thirty Eight and Paise Eight Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	42.00	Each	267.40	Rupees Eleven Thousand Two Hundred Thirty and Paise Eighty Only
Total in figure :					430002.54
Total in Words :					Rupees Four Lakh Thirty Thousand Two and Paise Fifty Four Only


 Executive Engineer,
 Mandi Division No.1,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 230460.76
 Earnest Money Rs:- 4600.00
 Time One month


Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.
 Name of work :- Restoration of damages caused due to laying of O.F.C. by Indian Army N.F.S. on Kamand Neri road Km. 0/0 to 6/0. (Sub Head:- Construction of retaining wall at R.D. 1/810 to 1/820.)

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	27.40	Per cubic metre	461.00	12631.40	Rupees Twelve Thousand Six Hundred Thirty One and Paise Forty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	42.40	Per cubic metre	4740.20	200984.48	Rupees Two Lakh Nine Hundred Eighty Four and Paise Forty Eight Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	8.40	Per cubic metre	1433.20	12038.88	Rupees Twelve Thousand Thirty Eight and Paise Eighty Eight Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	18.00	Each	267.00	4806.00	Rupees Four Thousand Eight Hundred Six Only
Total in figure :					230460.76	Rupees Two Lakh Thirty Thousand Four Hundred Sixty and Paise Seventy Six Only
Total in Words :					Rupees Two Lakh Thirty Thousand Four Hundred Sixty and Paise Seventy Six Only	


 Executive Engineer,
 Mandi Division No.1,
 HP. PWD. at Padhar.