



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

"SHORT TERM NOTICE INVITING TENDERS"

Scaled item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before 07/10/2023 up to 11.00 AM. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on 06/10/2023 up to 4.00 P.M and the application for issue of tender form shall be received on 05/10/2023 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	Restoration of rain damages on Nagni to Gharana road Km 0/0 to 10/00. (SH:- C/o R/wall at RD 0/800 to 0/815).	3,82,124/-	7600/-	Two Months	350/-
2	Restoration of rain damages on Bhilla Sargooni to Malander via Kufru road Km 0/0 to 1/0 (SH:- Construction of R/wall at RD 0/010 to 0/022).	4,85,526/-	9700/-	Two Months	350/-
3	Restoration of rain damages on Mangehar Pira road (SH:- Construction of Toe wall & Protection work for Abutment of existing 4.00 mtr span culvert at RD 2/430).	2,06,152/-	4000/-	Two Months	350/-
4	Restoration of rain damages on link road from Danai to Dagera road Km 0/00 to 6/00 (SW:- C/o R/wall in Km 0/150 to 0/170)	4,73,890/-	9500/-	Two Months	350/-
5	Restoration of rain damages on Nagni to Gharana road Km 0/0 to 10/00. (SH:- Improvement / Widening of road at RD 4/100 to 4/135 and C/o B/wall at RD 4/100 to 4/128).	3,67,143/-	7300/-	Two Months	350/-
6	Restoration of rain damages on Santoshi Mata Mandir to Umri via Malander, Garthoon road Km 0/0 to 7/0 (SH:- C/o R/wall with Pusta at RD 6/795 to 6/800).	4,45,838/-	8900/-	Two Months	350/-
7	Restoration of rain damages on Dadh Malan Massal Rajhoon road. (SH:- C/o R/wall at RD 16/690 to 16/701).	3,16,802/-	6300/-	Two Months	350/-
8	Restoration of rain damages Hamirpur Sujampur Thural Maranda road Km. 30/0 to 59/775 (SW:-C/o B/Wall at Rd 30/225 to 30/260)	3,44,912/-	6900/-	Two Months	350/-
9	Restoration of rain damages on link road Darang Block to Madhya Marg Gadiara Jamwal Awadi to Harizan Basti via Forest Hut to Connect NH-20 Km. 0/0 to 3/780 (SW:- C/o B/Wall at Rd 1/150 to 1/170)	1,32,740/-	2600/-	Two Months	350/-
10	Restoration of rain damages on link road to Chider Mahadev road (SW:- C/o R/Wall at Rd 1/405 to 1/421.80)	4,10,747/-	8200/-	Two Months	350/-
11	C/o AE Office building HPPWD Sub Division Bhawarna (SW:- P/L Interlocking paver block & railing).	1,65,068/-	3300/-	Two Month	350/-
12	A/R & M/O AE Office at Dheera Distt. Kangra (HP) (SH:- Repair of AE Office).	1,62,050/-	3200/-	Three Months	350/-
13	A/R & M/O various roads under Dheera Sub-Division (Section Dheera) (SH:- Painting, writing on rain shelter, Boards, Bridges Pedestals, Painting on bridge railing and kilometre stones etc.	2,61,486/-	5200/-	Two Months	350/-
14	A/R & M/O HPPWD Rest house at Khera (SH:- Installation of CCTV Camera's in Rest house Campus)	3,54,220/-	7100/-	Two Months	350/-
15	Restoration of rain damages on Hamirpur Sujampur Thural Maranda road (SH:- Removal of slips & C/o Un-lined drain & Earthen shoulders	4,93,650/-	9900/-	One Month	350/-

E.E.



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

16	Restoration of rain damages on Dadh Malan Massal Rajhoon road(SH:- Cutting in earth work in Km. 18/255 to 18/390 & 19/945 to 20/180)	4,23,321/-	8400/-	One Month	350/-
17	C/o 2 nos bridge (30.00 mtr span each) RCC box girder i/c both side approaches over Soon Khad on Garla Dai Bhawarna via Henja Swargjan road at Rd 0/266 & 1/515 (SW:- Balance work of super structure of RCC Box girder bridge at Rd 0/266).	2,45,733/-	4900/-	Two Months	350/-
18	Restoration of rods damaged due to laying of OFC on Darang Ghanetta Jharet road (C/o R/Wall at Rd 6/630 to 6/675)	3,79,968/-	7600/-	Two Months	350/-
19	Restoration of rain damages on Lahar Thakraim Saddun Bargran road (SW:- C/o Toe wall and P/L 900mm dia Hume pipe at RD 3/840 & C/o Approaches of existing 900mm dia HP culvert at Rd 3/840)	4,44,948/-	8900/-	Two Months	350/-
20	Restoration of rain damages on Panhar Bachwai road (SW:- C/o R/Wall at Rd 0/210 to 0/224)	4,23,411/-	8500/-	Two Months	350/-
21	C/o Raipur Tea Estate to Bhadal Devi Km. 0/0 to 1/00 (SW:- P/L Interlocking concrete block at Rd 0/110 to 0/160)	2,35,821/-	4700/-	Two Months	350/-
22	Restoration of rain damages on Hamipur Sujanpur Thural Maranda road Km 30/0 to 59/775 (SH:- C/o B/wall Pusta in Km 45/550 to 45/564.50)	4,99,026/-	10,000/-	Two Months	350/-

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm have to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.
5. The contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

HIM SUCHANA AVM JAN SAMPARK

Executive Engineer
Bhawarna/Division
HPPWD Bhawarna

(On behalf of Governor of Himachal Pradesh)

No. PWD/BWD/Tender/NIT/2023-24/-

8593-8652

Dated:-

29.09.2023

Copy to following for information and necessary action:-

1. The Principal Secy.(PW) to the Govt. of H.P.Shimla.
2. The Engineer-in-Chief,HPPWD.,Shimla.
3. The Chief Engineer (KZ),HPPWD, Dharamshala.
4. The Director, Information & Publications Department, HP Shimla.
5. The Executive Engineer (IT), Nigam Vihar Shimla. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
7. The Deputy Commissioner, Kangra at Dharamshala.
8. The Sub-Divisional Officer(Civil) Palampur.
9. All the S.E.s/E.E.s under Kangra Zone.
10. All the Assistant Engineers under this Division.
11. The Drawing /Accounts Branch in this office.
12. Notice Board.

Executive Engineer
Bhawarna/Division
HPPWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Nagni to Gharana road Km 0/0 to 10/0

Estimate Cost :- 3,82,124/-


Earnest Money :- 7600/-

(SH:- C/o R/wall in Km 0/800 to 0/815).

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi,	30.15			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	88.20			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	39.00			Each	
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.00			Per Cubic metre	

5	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drains and foundations of other structures or other sources graded and compacted in 200mm (two hundred millimetres) thickness in every layers and compacted with three Wheel Road Roller 80-100 (eighty-hundred) KN static weight roller to meet the requirement of tables 300.1 and 300.2 as per M.O.R.D. technical specification Clause 301 and 1603.5 and as per the entire satisfaction and direction of the Engineer- In -Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Matikana, toll tax, GST or other taxes imposed by the Government.	50.70	Per Cubic metre	
Total :-				


 Executive Engineer
 Bhawaria Division
 HP PWD Bhabarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Bhilla Sargooni to Malander via Kufru road Km 0/0 to 1/0


Estimate Cost :- 4,85,526/-

Earnest Money :- 9700/-

Time Limit :- Two Months

(SH:- Construction of R/wall at RD 0/010 to 0/022).

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wodging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing . removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material) to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	45.36			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, GST or other taxes imposed by the Government.	115.40			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry: stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.00			Each	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Estimate Cost :-2,06,152/-
Earnest Money :-4000/-


Name of Work :-Restoration of rain damages on Mangehar Pira road

(SH:- C/o Toe wall & Protection work of Abutment of existing 4.00 mtr span culvert at RD 2/430).

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	19.39			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	22.95			Per Cubic metre	
3	Supplying, filling, spreading & leveling stone boulders of size range 5 cm to 20 cm, in the required thickness as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.60			Per Cubic metre	
4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water. dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, GST or other taxes imposed by	4.20			Per Cubic metre	

5	<p>Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimeter) nominal size in open foundation in flooring of catchpit as per drawing and M.O.R.D. technical specifications clause 802, 803. 1202 and 1203, including the cost of form work, curing complete and hauling of materials in all kinds of leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.</p>	13.16			Per Cubic metre
Total :-					


 Executive Engineer
 Bhawana Divan
 HP PWD, Bhabarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Danai to Dagera road Km 0/00 to 6/00

Estimate Cost :- 4,73,890/-

Earnest Money :- 9500/-

(SH:- C/o R/wall in Km 0/150 to 0/170).

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including ocrroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	32.40			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana. toll tax, sale tax or other taxes imposed by the Government.	110.00			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone inasonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	39.00			Each	
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana. toll tax. sale tax. GST or other taxes imposed by the Government.	34.80			Per Cubic metre	

5	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drains and foundations of other structures or other sources graded and compacted in 200mm(two hundred millimetres) thickness in every layers and compacted with three Wheel Road Roller 80-100 (eighty-hundred) KN static weight roller to meet the requirement of tables 300.1 and 300.2 as per M.O.R.D. technical specification Clause 301 and 1603.5 and as per the entire satisfaction and direction of the Engineer- In -Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi. royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	77.00			Per Cubic metre	
Total :-						


~~Executive Engineer~~
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Nagni to Gharana road Km 0/0 to 10/0

Estimate Cost :- 3,67,143/-


Earnest Money :- 73000/-

Time Limit :- Two Months

(SH):- Improvement/ Widening of road in Km 4/100 to 4/135 and C/o B/wall at RD 4/100 to 4/128).

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Cutting in earth work having hard rock (where blasting is prohibited) with rock breakers including breaking rock, trimming bottom and side slopes in accordance with requirements of lines, grades and cross-sections as per Technical Specification Clause 302.3.5 by manual/ mechanical means and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of unuseful material for filling in road way, camber, embankments for grade improvement and disposal of all surplus material to required width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its levelling fine dressing and carriage of machineries, materials, tools equipments and safety measures and incidentals necessary to complete the 14.68 cubic metre quantity at the Rate of Rupees 300/- only (Rupees Three hundred only) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	293.56			Per Cubic metre	
2	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	63.84			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D. technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	73.36			Per Cubic metre	

4	<p>Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.</p>	46.00		Each	
Total :-					


 Executive Engineer
 Bhawana Division
 HP PWD Bhawana

Schedule of Quantity

Name of Work :- Restoration of rain damages on Santoshi Mata Mandir to Umri via Malander, Garthoon road Km 0/0 to 7/0 (SH:- C/o R/wall with Pusta at RD 6/795 to 6/800).

Estimate Cost :- Rs. 4,45,838/-
Earnest Money :- Rs. 8900/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	31.55			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax. GST or other taxes imposed by the Government.	109.80			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1205.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	25			Each	
4	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drains and foundations of other structures or other sources graded and compacted in 200mm(two hundred millimetres) thickness in every layers and compacted with three Wheel Road Roller 80-100 (eighty-hundred) KN static weight roller to meet the requirement of tables 300.1 and 300.2 as per M.O.R.D. technical specification Clause 301 and 1603.5 and as per the entire satisfaction and direction of the Engineer-In -Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	43.50			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Dadh Malan Nassal Rajhoon road

Estimate Cost :- 3,16,802/-

Earnest Money :- 6300/-

(SH:- C/o R/wall in Km 16/690 to 16/701).

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.53			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	73.59			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	27.00			Each	
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	20.90			Per Cubic metre	

5	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drains and foundations of other structures or other sources graded and compacted in 200mm(two hundred millimetres) thickness in every layers and compacted with three Wheel Road Roller 80-100 (eighty-hundred) KN static weight roller to meet the requirement of tables 300.1 and 300.2 as per M.O.R.D. technical specification Clause 301 and 1603.5 and as per the entire satisfaction and direction of the Engineer- In -Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	28.60		Per Cubic metre	
Total :-					


 Executive Engineer
 Bhawana Division
 HP PWD Bhatinda

Schedule of Quantity

Name of Work :- Restoration of rain damages Hamirpur Sujjanpur Thural Maranda road Km 30/0 to 59/775
(SW:- C/o B/wall at RD 30/225 to 30/260).

Estimate Cost :- 3,44,912/-
Earnest Money :- 6900/-

Time Limit :- Two Months


S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	49.35			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	83.16			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	33.00			Each	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Link road Darang Block to Madhya Marg Gadiara Jamwal Awadi to Harizan Basti via Forest Hut to Connect NH-20 Km 0/00 to 3/780
 Estimate Cost :- 1,32,740/-
 Earnest Money :- 26000/-
 Time Limit :- Two Months
 (SW:- C/o B/wall at RD 1/150 to 1/170).

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing ; removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	12.00			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1205 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	32.40			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	20.00			Each	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on link road to Chider Mahadev road

Estimate Cost :- 4,10,747/-


Earnest Money :- 8200/-

Time Limit :- Two Months

(SH)- Construction of R/wall at RD 1/405 to 1/421.80

S. No	Description of Item	Quantity	Rate		Amount Rs.
			In figure	In Words	
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	26.88		Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	95.76		Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	42.00		Each	
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.92		Per Cubic metre	

5.	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drains and foundations of other structures or other sources graded and compacted in 200mm(two hundred millimetres) thickness in every layers and compacted with three Wheel Road Roller 80-100 (eighty-hundred) KN static weight roller to meet the requirement of tables 300.1 and 300.2 as per M.O.R.D. technical specification Clause 301 and 1603.5 and as per the entire satisfaction and direction of the Engineer- In -Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	37.80	Per Cubic metre	
Total :-				


 Executive Engineer
 Bhargava Division
 HRPWD Bhargava

Schedule of quantity

Name of Work :- C/o AE Office building HPPWD Sub Division Bhawarna (Sft:- P/L Interlocking paver block & railing).

Estimate Cost :- 1,65,068/-

Earnest Money :- 3300/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm (Eighty millimetre) of approved make having compressive strength of M-50 as per drawings and MORD Technical Specification section 1500 including sand bedding, carriage of material within all leads and lifts, other incidentals. The rate is rate including of octroi, royalty, malkana, tolltax. GST or other taxes imposed by the government.	43.20			Per Square metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimeter) nominal size in open foundation in flooring of catchpit as per drawing and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203, including the cost of form work, curing complete and hauling of materials in all kinds of leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	0.40			Per Cubic metre	
3	Steel work welded in built up sections trusses and frame work including cutting hoisting and fixing in position and applying a primer coat of red lead paint in gratings framed guard bares ladders railings brackets and similar work etc. including carriage of materials within all leads lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.50			Per Quintal	
4	Painting two coats (excluding priming coats) on new steel and other metal surfaces with enamel paint brushing to give and even shade including cleaning the surfaces of all dirt dust and other foreign matter enamel paint other than white. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	50.40			Per Square metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- A/R & M/O AE Office at Dheera Distt. Kangra (HP)

Estimate Cost :- 1,62,050/-

Earnest Money :- 3200/-

Time Limit :- Three Months

(SH:- Repair of AE Office).

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Dismantling W.C. Pan of all sizes including disposal of dismantled materials including malba all complete as per directions of Engineer-in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	2.00			Each	
2	Dismantling of Flushing cistern of all types (C.I./PVC/Virious China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead complete as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana. toll tax, sale tax or other taxes imposed by the Government.	2.00			Each	
3	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead complete as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	52.72			Per Square metre	
4	Second class half brick work using common burnt clay building bricks with hoop iron in cement mortar 1:4 (one cement isto four sand) in super structure as per PWD specification, drawing and design and curing complete including scaffolding. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	3.78			Per Square metre	


5	Providing and laying antiskid vitrified tiles planks of size 1200x 200 (twelve into two hundred) of premium quality of Nitco/ Kajaria/ Somany/ Well/ Johnson as per approved shade and manufacture on wall over 12 mm (twelve millimeters) thick cement mortar 1:3(one cement: three sand)jointed with cement slurry mixed with pigment to match the shade of tiles as required complete as per approved specification, drawing and design including entire . The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals. as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	40.03	Per Square metre
6	Providing and laying 300x300x10 mm (three hundred into three hundred into ten millimeters) thick antiskid ceramic tiles of premium quality of Nitco/ Kajaria/ Somany/ Well/ Johnson as per approved shade and manufacture in flooring over 12 mm (twelve millimeters) thick cement mortar 1:3(one cement: three sand)jointed with cement slurry mixed with pigment to match the shade of tiles as required complete as per approved specification, drawing and design including entire . The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	10.57	Per Square metre
7	Providing and laying 300x300 mm (three hundred into three hundred millimetre) thick antiskid ceramic tiles of premium quality of Nitco/ Kajaria/ Somany/ Well/ Johnson as per approved shade and manufacture in skirting risers of steps and dados over 12 mm (twelve millimeters) thick cement mortar 1:3(one cement: three sand)jointed with cement slurry mixed with pigment to match the shade of tiles as required complete as per approved specification, drawing and design including entire. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals. as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	42.15	Per Square metre
8	In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government. Providing and fixing 5mm (five millimetre) thick glazing with glass pane of Modiguard/ Saint gobin in aluminium for window, ventilator and Doorset, shutters . with PVC / neoprens gaskets complete weight not less then 12.50 Kg/Sqm (Twelve decimal five zero Killogramme per square metre) as per the Architectural Drawings approved specification. (Cost of aluminium snap beeding shall be paid in basic item) including cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	2.70	Per Square metre

9	Wall painting (two coats) with interior emulsion washable paint of approved brand and manufacture for interior grade on undecorated concrete/stone-plastered wall surfaces to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth including applying of putty a required for melling the surface. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	55.05	Per Square metre
10	Painting two coat (excluding priming coat) on previously painted steel and other metal surfaces with enamel paint to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	9.72	Per Square metre
11	Providing and fixing off sizes Curtains made of good quality cloth including stitching & fixing rings etcetra complete for Doors & windows as per the entire satisfaction, direction and approved by Engineer- in-Charge including carriage of materials within all leads and lifts. The rate is including toll tax, GST or other taxes imposed by the Government.	8.00	Each
12	Providing and fixing vitreous china European type W.C. of star sr. No 20087 (S-50) of size 57x35x39 cm (fifty seven into thirty five into thirty nine centimeter) wash down water closet hindware/aguar/cera of star white/ snow white including jet pressure integral P or S trap including jointing the trap with soil pipe in fixture (seat cover/ jet pressure to be paid separtely) including entire carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2.00	Each
13	Providing and fixing vitreous china wash basin De'la No 10010 and size 55x40 cm (fifty five into forty centimeters) Hindware/Cera/Aguar with double hole for pillar trap with C.I. or M.S. brackets including hole in walls and making good the same (under counter basin) including all fitting complete in all respect including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2.00	Each

14	Providing and fixing vitreous china pedestal for wash basin. C.I.R.A make including entire carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2.00	Each
15	Providing and fixing PVC waste pipe for wash basin or sink including necessary fitting and carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2.00	Each
16	Providing and fixing 600mmx450mm (six hundred millimeter into four hundred fifty millimeter) beveled edge mirror of superior glass mounted on 6mm (six millimeter) thick A.C. Sheet or plywood sheet and fixed to wooden plugs with C.P. screws and washers of Atul/Modi Guard/ Golden fish including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2.00	Each
17	Providing and fixing chromium plated brass soap dish of ESS with C.P. brass brackets fixed with cleats with C.P. brass screws, within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2.00	Each
18	Providing and fixing PVC Floor Trap size 110x75 mm (one hundred ten into seventy five millimeters) (SI marked self cleaning design including fixing with approved adhesive cost of cutting and making good the wall) and floor complete within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	3.00	Each
19	Providing and fixing C.P. brass towel ring trapezoidal shape 215mm long, 200mm wide of continental series of Jaguar/Classic of Hindware/Cera complete with C.P. brass brackets fixed to wooden plugs with C.P. brass socket including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2.00	Each

20	Providing and fixing C.P. brass towel rail size 600x20mm (Six hundred into twenty millimetre) of continental series of Jaguar/Classic of Hindware/Cera complete with C.P. brass brackets fixed to wooden plugs with C.P. brass socket including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2.00	Each	
21	Providing and fixing 15 mm nominal outer dia Pipes Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc complete including entire carriage of materials within all leads and lifts and other incidentals. as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	10.00	Per Running metre	
22	Providing and fixing 15mm (Fifteen millimetre) diameters C.P. brass bib tap of continental series of Jaguar/Classic series of Hindware/ Floral series of Cera/ Hindon series of Jal/ Vintage series of Kerovite as per specifications including carriage of material within all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	3.00	Each	
23	Providing and fixing casealed C.P. brass stop cock Continental/Classic series /floral series of Jaguar Hindware/Cera 15mm (fifteen millimetre) dia (Heavey duty makes IS) marked) including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2.00	Each	
24	Providing and fixing 15mm (fifteen millimetre) C.P. Brass Angle valve of Continental Series of Jaguar continess plus series /Hindware / Occan series of Nintage series of Kerovite/ hindon series of Jal/ Cera/ Jal as per specifications with nuts & bolts including carriage of material within all leads, lifts, and other incidentals. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	2.00	Each	

25	Providing and fixing 15mm (fifteen millimetre) C.P. Brass extension nipple of size 15mm x 50mm of Continental Series of Jaguar conness plus series /Hindwave / Ocean series of Nintage series of Kerovite/hindon series of Jal/ Cera/ Jal as per specifications with nuts & bolts including carriage of material within all leads, lifts, and other incidentals. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	4.00			Lach
26	Providing and fixing 150 mm (One hundred fifty millimetre) diametre high pressure P.V.C spigot and socket soil, waste and ventilating pipe of Supreme/Finolex/Prime working pressure not less than 6.0 kg/cm2 (Six kilogram per square centimetre) I.S.I. Marked including fixing with approved adhesive etcetra complete including carriage of material within all leads, lifts and other incidentals. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	15.00			Per Running metre
Total :-					


 Executive Engineer
 Bhanu Arna Division
 HP PWD Bhanu Arna

Schedule of quantity

Name of Work :- A/R & M/O various road under Dheera Sub Division (Section Dheera) (SW:- Painting, Writing on Rain Shelter, Boards, Bridges Pedestals and painting on Bridge railing and Kilometers stone)

Estimate Cost :- 2,61,486/-
Earnest Money :- 5200/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Removing white wash or colour wash by steel wire brushing and/or scrapping sand papering and preparing the wall surfacesmooth including necessary repairs to scratches complete. as per direction of Engineer-in-charge. The rate is including octroi, royalty, Malkana. toll tax, GST or other taxes imposed by the Government.	33.48			Per Square metre	
2	Painting two coats(excluding priming costs) on new steel and other metal surfaces with enamel paint to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	33.48			Per Square metre	
3	Finishing wall with water proofing cement paint of approved brand and manufacture and of required shade on undecorated wall surfaces (Two coats) to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials. The rate is inclusive for carriage of materials within all leads, lifts and other incidentals as per the direction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	495.00			Per Square Metre	
4	Writing letters or figures on any surface with black japan paint (stops,comas,hyphens and the like not to be measured and paid separately) as per the direction of Engineer-in-Charge.					
4.1	Block letters/figures	116000.00			Per letter per centimetre height	
					Total :-	


 Executive Engineer
 Bhawarna Division
 HP PWD Bhabharna

Schedule of Quantity

Name of Work :- AVR & M/O HPPWD Rest house at Khera (SH:- Installation of CCTV Camera's in Rest house campus)

Estimate Cost :- 3,54,220/-

Earnest Money :- 71000/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and fixing Pinetron Bullet IP Camera 4MP (Four Mega Pixel) starlight of good quality complete with all accessories as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.00			Each	
2	Providing and fixing Pinetron 16CH NVR Recording Box of good quality complete with all accessories as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1.00			Each	
3	Providing and fixing Surveillance hard disk of good quality complete with all accessories as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1.00			Each	
4	Providing and fixing POE switch 4 port of good quality complete with all accessories as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.00			Each	
5	Providing and fixing Dlink cat 6 wire Armored complete with all accessories as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	350.00			Per Running Metre	
6	Providing and fixing RJ 45 connector complete with all accessories as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.00			Each	
7	Providing and fixing LED TV 32" (Thirty two inches) complete with all accessories as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1.00			Each	

8	Providing and fixing 4U DVR Rack/ Table complete with all accessories as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1.00			Each
9	Providing and fixing Voltage controller set complete with all accessories as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1.00			Each
10	Providing and fixing PVC pipe complete with all accessories as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1.00			Each
Total :-					


 Executive Engineer
 Bhawana Dhillon
 HP PWD Bhabra

Schedule of Quantity

Name of Work :- Restoration of rain damages on Hamirpur Sujampur Thural Maranda road (SH:- Removal of Slips, C/o un-lined drain & Earthen shoulders).

Estimated Cost :-Rs 4 93,650/-
 Earnest Money :- Rs 99000/-
 Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Removal of Land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within lift upto 1.50 m and lead upto 1000m as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge Rate inclusive toll tax, GST and any other taxes imposed by the government.	225.26			Per Cubic metre	
2	Construction of un lined surface drain of average cross sectional area 0.40 Sqm (zero decimal four zero square metre). In soil to specified lines, grades, level and dimension excavated materials to be used in embankment with a lift upto 3 m (Three metre) and lead of 50m (Fifty metre) (Average lead 25m) as per technical specification clause 307 The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5250.00			Per Running metre	
3	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	5900.00			Per Square metre	
Total :-						



 Executive Engineer
 Bhawarna Division
 HP PWD, Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Dadh Malan Massal Rajboon road (SI):- cutting in earth work in Km 18:255 to 18/390 & 19/945 to 20/180).

Estimate Cost :- Rs. 4,23,321/-
 Earnest Money :- Rs. 84000/-
 Time Limit :- One Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Excavation in Hilly Area in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft Rock, Hard rock, chiselling/wedging out of rocks (where blasting is prohibited) and their intermediate classification of soil setting out true to the required line, grades cutting and trimming of side slopes and level as shown in the drawings and as directed by the Engineer in charge at site according to the technical specification clause 302.1603.1 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts in required width of road and transportation of unuselul material for filling in road way, camber, embankments for grade improvement and disposal of all surplus material to required width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its levelling, fine dressing and carriage of machineries materials, tools equipments and safety measures and incidentals necessary to complete the 136.56 cubic metre quantity at the Rate of Rupees 300/- only (Rupees Three hundred only) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2731.10		Per Cubic metre		
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of quantity

Name of Work :- C/o 2 nos. Bridges (30.00 mtr. span each) RCC box girder i/c both side approaches over Soon khad on Garla Dai Bhawarna via Hlenja Swargjan road at RD 0/266 & I/515 (SH)- Balance work of super structure of RCC Box girder bridge at RD 0/266)

Estimate Cost :- 2,45,733/-

Earnest Money :- 49000/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and laying M-15 grade cement concrete with ordinary portland cement not less than 275 Kg (Two hundred seventy five) Kilogram per cubic metre using stone aggregate 20mm (Twenty millimetre) nominal size and approved quality sand mechanically mixed, vibrated and curing complete in open foundation, levelling course below approach slab as per the Drawings and MORTH Technical Specifications section 1500. 1700 and 2100 including carriage of material with in all leads, lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.04			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete design mix to obtain minimum compressive strength of grade M-30 (M- thirty) using minimum cement contents of 407 Kg (Four hundred seven Kilogram) per cubic metre in approach slab including reinforcement complete with bending, binding, straightening of bars, cost of handling wire and cost of curing and form work complete in all heights / depths as per drawing and MORT&H technical specifications section 1500. 1600. 1700. 2700 and as per the directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.69			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated reinforced cement concrete in super structure as per drawing and MORT&H. technical specification clause 2702 RCC Grade M-30 (M- thirty) designed mix with minimum cement contents of 407 kg. (Four hundred seven) Kilogram per cubic metre with 20mm (Twenty millimetre) nominal size graded crushed stone aggregate and curing complete including cost of form work and reinforcement for reinforced cement concrete work in wearing course complete as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax or other taxes imposed by the Government.	12.26			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of roads damaged due to laying of OFC on Darang Ghanetta Jharet road (C/o R/wall at RD 6/630 to 6/675)

Estimate Cost :- Rs. 3,79,968/-
Earnest Money :- Rs. 7500/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling & wedging out rocks (Where blasting is prohibited) as per drawings and M O R D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	32.85		Per Cubic metre		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M O R D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	90.45		Per Cubic metre		
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	76		Each		
Total :-						


Executive Engineer
Bhawarna Division
 HP PWD Bhawarna


Schedule of Quantity

Restoration of rain damages on Lahar Thakrain Saddun Bargran road (SH:- C/o Toe wall and P/L 900 mm dia Hume pipe at RD 3/840 & C/o Approaches of existing 900 mm dia HP culvert at RD 3/840).

Estimate Cost :- Rs. 4,44,948/-
Earnest Money :- Rs. 8900/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling/wedging out rocks (Where blasting is prohibited) as per drawings and M O R D technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	34.31			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement, three sand, six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.84			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub-structure for all type of structure complete nominal mix 1: 2 ½ :5 (One cement : two point five sand : five graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths in abutments, parapet etcetera and the like including the cost of form work as per drawings and M O R D technical specification section 800, 900 and 1200 as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	12.58			Per Cubic metre	
4	Providing and laying (to level or slope) 900mm dia (Nine hundred millimetre) diameter reinforced cement concrete non pressure pipes IS Class NP-2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, concrete and masonry work in head walls and parapets as per drawing and M O R D technical specifications section 1100 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	2.81			Per Running metre	

5	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement five sand ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D. technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	82.50	
6	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/stone masonry plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical, twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	33	Each
7	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government	24.54	Per Cubic metre
8	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drains and foundations of other structures or other sources graded and compacted in 200mm(two hundred millimetres) thickness in every layers and compacted with three Wheel Road Roller 80-100 (eighty-hundred) KN static weight roller to meet the requirement of tables 300.1 and 300.2 as per M.O.R.D. technical specification Clause 301 and 1603.5 and as per the entire satisfaction and direction of the Engineer-in -Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	40.22	Per Cubic metre
Total :-			


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work : Restoration of rain damages on Panhar Bachwai road (SH:- C/o R/wall at RD 0/210 to 0/224).

Estimate Cost - Rs 4,23,411/-
 Earnest Money - Rs 8500/-
 Time Limit - Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	20.16		Per Cubic metre		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1.5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	98.42		Per Cubic metre		
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V) 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	36		Each		
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in charge including carriage of material within all leads and lifts and other incidental The rate is including octroi royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government	33.74		Per Cubic metre		

5	<p>Consignment of embankment with approved materials deposited at site from road way cutting and excavation from drains and foundations of other structures of other sources graded and compacted in 200mmi two hundred (two metres) thickness in every layers and compacted with three Wheel Road Roller 60 100 (eighty hundred) KN static weight roller to meet the requirement of tables 300 1 and 300.2 as per M O R D technical specification Clause 301 and 1503 5 and as per the entire satisfaction and direction of the Engineer In -Charge including carriage of materials within all leads, lifts, and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.</p>	2394
---	---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	------

Total -


 Executive Engineer
 Bhawana Division
 HP PWD Bhabiana

Schedule of quantity

Name of Work :- C/o Raipur Tea Estate to Bhadal Devi Km 0/00 to 1/00 (S.B:- P/1, Interlocking concrete block at RD 0/110 to 0/160).

Estimate Cost :- 2,35,821/-

Earnest Money :- 47000/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate			Amount Rs.
			In figure	In Words	Unit	
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm (Eighty millimeters) of approved make having compressive strength of M-50 as per drawings and M.O.R.D. Technical Specification section 1500 including sand bedding, carriage of material within all leads and lifts, other incidentals. The rate is rate including of octroi, royalty, Malkana tolltax, GIS) or other taxes imposed by the government.	155.00		Per Square metre		
2	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimeter) nominal size in open foundation in flooring of catchpit as per drawing and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203, including the cost of form work, curing complete and hauling of materials in all kinds of leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.19		Per Cubic metrie		
Total :-						


 Executive Engineer
 Bhawarna Division
 H.P. P.W.D. Bhabhna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Hamirpur Sujampur Thural Maranda road Km 30/0 to 59/775 (SH- C/o B/wall pusta at RD 45/550 to 45/564.50)

Estimate Cost :- Rs. 4,99,026/-
Earnest Money :- Rs. 10,000/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing, removal of slumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	21.32			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement, five sand, ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	129.92			Per Cubic metre	
Total :-						

Executive Engineer
Bhawalna Division
HP PWD Bhawalna