

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

Offline

☎ 01899-240618 292000

Fax No 01899-240618

E-mail- [ee-dal-hp@nic.in](mailto:ee-dal-hp@nic.in)

No. PWD-Dal/TA/Tender /2023-24- **10780-82**

Dated: - **20-02-2024**

To


The Executive Engineer (IT Cell)  
Nigam Bihar Shimla-2

**Subject: - Publishing of Tender Notice.**

**Dear Sir,**


Enclosed please find herewith the tender Notice of work as given in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16<sup>th</sup> July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

**DA/ As above.**

  
Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie.



Copy forwarded to the Superintending Engineer, 7<sup>th</sup> Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

  
Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie



Certificate

Certified that the tenders called vide this office letter No. PWD-/TA/Tender /2023-24:-10780-82 dated 20.02.24 is emergent nature and in Public interest.

  
Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie.  


Certificate

Certified that the tenders called vide this office letter No. PWD-/TA/Tender /2023-24:-10780-82 dated 20.02.24 is emergent nature and in Public interest.

  
Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie.  


**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**"NOTICE INVITING TENDERS"**

Sealed Item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Dalhousie Division, HPPWD, Dalhousie on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

- |   |  |  |
|---|--|--|
| 3 | Date of receipt of application for the tender Form a/w requisite documents:- | 21.02.2024 onward (between 2:00p.m.to 4:30.p.m.) |
| 4 | Date of issued/sale of tender form against Cash payment (non refundable).    | 27.02.2024                                       |

The tender shall be received upto 3:00 PM on 28.02.2024 and will be opened on the same day at 3:30 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Non refundable) during the working hours on 27.02.2024.

The Earnest Money in the shape of National Saving Certificate/FDR of any Bank in HP duly pledged in favour of Executive Engineer, Dalhousie Division, HPPWD, Dalhousie must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1.	Restoration of Rain damage on Brangal Wangal Mandoh road k.m. 0/0 to 39/600 (SH:- C/o PPC retaining wall at R.D. 5/135 to 5/141)	142692/-	3000/-	350/-	Three month	Class-D & C
2.	Restoration of Rain damage on Samah to hadila road K.m.0/0 to 5/510 (SH:-C/o Breast wall in wire crate at R.D. 4/015 to 4/025)	134099/-	3000/-	350/-	Three month	Class-D & C
3	Restoration of Rain damage on lahar to Sangrain road K.m. 0/0 to 5/500 (SH:-Hiring of Excavator cum loaer for removal of slips in K.m. 3/045 to 4/105)	73140/-	1500/-	350/-	Two month	Class-D & C
4	Restoration of Rain damage on Brangal Wangal Mandoh road k.m. 0/0 to 39/600 (SH:- C/o PPC retaining wall at R.D. 2/210 to 2/217)	169102/-	3500/-	350/-	Three month	Class-D & C
5	Restoration of Rain damage on Link road to village Padhrotu K.M. 0/0 to 2/0 SH:- Hiring of Excavator cum loaer for removal of slips in K.m. 0/0 to 0/090	54192/-	1200/-	350/-	Two month	Class-D & C
6	Restoration of Rain damage on Brangal Wangal Mandoh road k.m. 0/0 to 39/600 (SH:- C/o PPC retaining wall at R.D. 0/345 to 0/353)	148913/-	3000/-	350/-	Three month	Class-D & C
7	A/R & M/O to HPPWD 7 <sup>th</sup> Circle & HPPWD Sub Division office Dalhousie (SH:- Wall Painting in Sub Division office Dalhousie and Boundary wall of 7 <sup>th</sup> Circle & French polishing in SE office at Dalhousie)	71442/-	1500/-	350/-	One month	Class-D & C
8	Restoration of Rain damage on Brangal Wangal Mandoh road k.m. 0/0 to 39/600 (SH:- C/o of Retaining wall in PCC putha and wire crate at R.D. 28/810 to 28/825)	410789/-	8500/-	350/-	Three month	Class-D & C
9	A/R & M/O to HPPWD Rest House Manola (SH:- Painting work of Rest House Manola)	101503/-	2500/-	350/-	Two month	Class-D & C
10	Restoration of Rain damage on various roads under Banikhet Sub Division HPPWD Banikhet (SH:-Hiring of Excavator cum loader for removal of slips in various roads)	451500/-	9500/-	350/-	Two month	Class-D & C
11	Restoration of Rain damage on various roads under HPPWD Division Dalhousie (SH:- Supplying and stacking of Calcium Chloride for spraying on snow bounded roads)	73500/-	1500/-	350/-	Three month	Class-D & C

12	Restoration of Rain damage on various roads under Dalhousie Sub Division (SH:-Removal of slips/ snow on Banikhet Dalhousie Khajjar road k.m. 0/0 to 6/400 & 15/600 to 27/0,Dalhousie Jandrigat Chamba via Kohlari road k.m. 0/0 to 11 0/40,Link road to village Ruliyani k.m.0/0 to 3/0 & link road to village Kathlog to Bharera k.m. 0/0 to 2/180)	495600/-	10000/-	350/-	Three month	Class-D & C
13	Restoration of Rain damage on various roads under Dalhousie Sub Division (SH:- Supplying and stacking of WBM-III, and for rectification of various road thereof.)	161865/-	3500/-	350/-	Three month	Class-D & C

1. The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
2. The tender shall be issued to those contractor o who have not more than two works in hand.
3. GST No./Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.
4. Application without all documents will not be entertained.
5. Proxy application will not be entertained.

Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie.

sNo. PWD/TA/Tender /2023-24- 10783-833

Dated: - 20-02-2024

Copy forwarded to the following for information and necessary action please:-

- 1 Engineer-in-Chief, HPPWD, Shimla.
- 2 All the Chief Engineer in HPPWD.
- 3 All SEs/EE in HPPWD.
- 4 All AEs Contractor under this Division.
- 5 Deputy Commissioner, Chamba
- 6 BDO Bhattiyat.
- 7 Sub Divisional Magistrate/Tehsildar Dalhousie.
- 8 Notice Board of this office.

Executive Engineer,  
Dalhousie Division,  
HPPWD, Dalhousie

## Schedule of Qty.

Name of work: -Restoration of Rain damage on Braungal Waungal Maudoh road Km. 0/0 to 39/600 (SH: - Construction of PCC Retaining wall at RD. 5/135 to 5/141).

Estimated Cost: - Rs.142692.00  
 Earnest Money :- Rs. 3000.00  
 Time Limit :- Three Months

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORRD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any head and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	10.02			Per Cubic Metre	
2	Providing and Laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and vibrated in foundation for all type structure complete for all heights / depth including curing and cost of form work complete in all respect as per the drawing and technical specifications clause 802. 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sales tax . GST or any other taxes imposed by the Government.	27.96			Per Cubic Metre	
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORRD technical specification clause 1204.3.8 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	4.68			Per Cubic Metre	
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	12.00			Each	
<b>Total: -</b>						

Executive Engineer  
 Dalhousie Division,  
 H.P.W.D. Dalhousie

## Schedule of Qty.

Estimated Cost: - Rs.	134099.00
Earnest Money :- Rs.	3000.00
Time Limit :-	Three Month

Name of work: -Restoration of rain damage on Samah to Hadila road Km. 0/0 to 5/510 (SIH: - Construction of Breast wall in wire crate at RD. 4/015 to 4/025).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana toll tax sale tax . GST or other taxes imposed by the Government.	25.75			Per Cubic Metre	
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 40 Kg (forty kilogramme) each as per drawing technical specifications Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkhana, toll tax, sales tax, GST or any other taxes imposed by the Government.	46.90			Per Cubic Metre	
<b>Total:-</b>						

  
 Engineer  
 Damousie Division,  
 HPPWD, Tolbousie

## Schedule of Qty.

Estimated Cost: - Rs.	73140.00
Earnest Money :- Rs.	1500.00
Time Limit :-	Two Month


Name of work: - Restoration of rain damage on Lahar to Sangrain road Km. 0/0 to 5/500 (SI:- Hiring of Excavator cum Loader for removal of slips in Km. 3/045 to 4/105).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period / execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	585.68			Per Cubic - Meter	
					<b>Total</b>	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


  
Executive Engineer  
Dahousie Division,  
H.P. and N.H. side

## Schedule of Qty.

Estimated Cost: - Rs.169102.00  
 Earnest Money :- Rs. 3500.00  
 Time Limit :- Three Months

Name of work: - Restoration of Rain damage on Braungal Vangal Mandoh road Km. 0/0 to 39/600 (SH: - Construction of PCC Retaining wall at RD. 2/210 to 2/217).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	15.05			Per Cubic Metre	
2	Providing and Laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and vibrated in foundation for all type structure complete for all highs / depth including curing and cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	32.62			Per Cubic Metre	
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	6.51			Per Cubic Metre	
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	14.00			Each	
<b>Total: -</b>						

  
 Executive Engineer  
 Dalhousie Division,  
 HPPWD, D.O.  
 31P

## Schedule of Qty.

Name of work: - Restoration of rain damage on Link road to village Padhrota Km. 0/0 to 2/0 (SH:- Hiring of Excavator cum Loader for removal of slips in Km. 0/0 to 0/090).


Estimated Cost: - Rs.	54192.00
Earnest Money :- Rs.	1200.00
Time Limit :-	Two Month

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period / execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	433.95			Per Cubic Meter	
					<b>Total</b>	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds

  
**Engineer**  
 Dalhousie Division,  
 H.P. ROAD, DALHOUSIE

# Schedule of Qty.

Estimated Cost: - Rs. 142913.00  
 Earnest Money :- Rs. 3000.00  
 Time Limit :- Three Months

Name of work: - Restoration of Rain damage on Bhangal Wargal Mandoh road Km. 0/0 to 39/600 (SIF: - Construction of P.C.C Retaining wall at R.D. 6/345 to 6/353).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In Fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MOPD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shooting and backing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shooting and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantity of water including cleaning of slush which may arise out during dewatering and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the control, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	14.32			Per Cubic Metre	
2	Providing and laying plain cement concrete 1:2:10 (one cement into five sand into ten graded) crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and vibrated in foundation for all type structure complete for all heights / depth including curing and cost of form work complete in all respect as per the drawing and technical specifications clause 202, 203, 202 and 203 and as per directions of Engineer-in-Charge. The rate including the control, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	28.56			Per Cubic Metre	
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MOPD technical specification clause 1204.3.2 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the control, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	5.76			Per Cubic Metre	
4	Providing Moschobes in brick masonry / stone masonry / plain / reinforced concrete abutment, wing wall, return wall, retaining walls with 150 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing basin complete as per drawing and technical specifications clause 614, 709, 1204.3.7 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the control, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	13.50			Each	
	Total: -					

Engineer  
 Bhangal Wargal Mandoh  
 Mandoh, Mandoh

Estimated Cost: - Rs.71442.00

Earnest Money :- Rs. 1500.00

Time Limit :- One Months

## Schedule of Qty.

Name of work: -A/R & M/O HP PWD 7th Circle & HP PWD Sub-Division Office Dalhousie (SH: - Wall Painting in Sub-Division Office Dalhousie and Boundary wall of 7th Circle & French polishing in SE Office at Dalhousie).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Wall painting two coats with premium acrylic emulsion paint of interior grade, Asian 4 Paints/Nerolac surksha Paints/Berger Paints /Delux Paint having VOC (Volatile Organic Compound) consist less than 50 grams (fifty milli grams)/ liter of approved brand and manufacture, including applying additional coats wherever to achieve even shade and colour as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	419.67			Per Square Metre	
2	Painting one coat on previously painted wood or wood based surface with enamel paint Asian Paints/Nerolac surksha Paints/Berger Paints /Delux Paintto give a even shade including cleaning of all dirt, dust and other foreign matter sand papering and slopping with enamel paint other than white within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax GST or any other taxes imposed by the Government.	142.34			Per Square Metre	
3	Painting one coat (excluding priming coat) on previously painted steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter With Enamel paint other than white as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	141.68			Per Square Metre	
4	Polishing on wood work with French Polishing of approved Brand and manufacture including applying additional coats wherever required to achieve even shade and colour, matter, and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	73.99			Per Square Metre	
	<b>Total: -</b>					

  
Executive Engineer  
Dalhousie Division,  
H.P.W.D. 7th Circle

# Schedule of Qty.

Name of work: - Restoration of Rain damage on Braungal Waugal Mandoh road Km. 0/0 to 39/600 (SH: - Construction of Retaining wall in PCC putha and wire crate at RD. 28/810 to 28/825).

Estimated Cost: - Rs. 410789.00  
 Earnest Money :- Rs. 8500.00  
 Time Limit :- Three Months

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	42.75			Per Cubic Metre	
2	Providing and Laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and vibrated in foundation for all type structure complete for all hights / depth including curing and cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	26.10			Per Cubic Metre	
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	22.28			Per Cubic Metre	
4	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 40 Kg (forty kilograme) each as per drawing technical specifications Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	93.75			Per Cubic Metre	
	<b>Total: -</b>					


Exc. Engineer  
 Dalnoid Division,  
 HOPWAL, Dalnoid

## Schedule of Qty.

Name of work: - A/R & M/O to HP PWD Rest House at Manola (SIH) - Painting work of Rest House Manola).

Estimated Cost: - Rs. 101503.00  
 Earnest Money :- Rs. 2500.00  
 Time Limit :- Two Month

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Providing and applying plaster of Paris Putty of 2mm (Two millimeter) thickness over plastered surface to prepare the surface even and smooth complete as per direction of the Engineer-In-Charge including carriage of materials within all leads and lift and other incidental. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax GST or any other taxes imposed by the Government.	284.28			Per Square Metre	
2	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer Asian Paints/ Nerolac Surksha Paints/ Berger Paints/ Delux Paint two or more coats applied on walls @ 1.25 lit/10 sqm (One point two five liter per ten square meter) over and including one coat of special primer applied @ 0.75 lit/sqm (Zero point seven five liter per square meter) as per direction of the Engineer-In-Charge including carriage of materials within all leads and lift and other incidental. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax GST or any other taxes imposed by the Government.	284.28			Per Square Metre	
2	Painting one coat on previously painted wood or wood based surface with enamel paint Asian Paints/ Nerolac surksha Paints/ Berger Paints/ Delux Paint to give a even shade including cleaning of all dirt, dust and other foreign matter sand papering and stopping with enamel paint other than white within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax GST or any other taxes imposed by the Government.	215.67			Per Square Metre	
	<b>Total: -</b>					

  
 Engineer  
 Dalhousie Division,  
 HP PWD, Dalhousie

## Schedule of Qty.

Estimated Cost: - Rs.	451500.00
Earnest Money :- Rs.	9500.00
Time Limit :-	Two Month


Name of work: - Restoration of rain damage on various roads under Banikhet Sub-Division HP PWD Banikhet (SH:- Hiring of Excavator cum Loader for removal of slips in various roads).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period / execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	430.00			Per Cubic Meter	
					<b>Total</b>	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availability of funds

  
 Executive Engineer  
 Dalhousie Division,  
 HPPWD Dalhousie

## Schedule of Qty.

Name of work: - Restoration of rain damage on various roads under HP PWD Division Dalhousie (SH:- Supplying and stacking of Calcium Chloride for spraying on Snow Bounded roads).

Estimated Cost: - Rs.	73500.00
Earnest Money :- Rs.	1500.00
Time Limit :-	Three Month

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Supplying and stacking for Calcium Chloride in form of Powder/slacked for spraying on frozen snow bounded roads in 50kg (fifty kilogramme) bag and asper the direction of the Engineer-In-Charge. The material shall confirm to the MORD specification. including carriage of materials within all leads and lift and other incidental. The rate quoted by the contractor shall be inclusive of all taxes such as municipal, octroi, Malkana royalty toll tax, GST and other local taxes imposed by the Government.	2450.00			Per Kilogramme	
					Total	

 Engineer  
 Dalhousie Division,  
 HP PWD, Dalhousie

## Schedule of Qty.

Estimated Cost: - Rs.	495600.00
Earnest Money :- Rs.	100000.00
Time Limit :-	Two Month

Name of work: - Restoration of rain damage on various roads under Dallhousie Sub Division (SH:- removal of Slips/Snow on Banikhet Dallhousie Khajjar road Km. 0/0 to 6/400 & 15/600 to 27/00, Dalhousie Jandrihat Chambva via Kohhari road Km. 0/0 to 11/040, Link road to village Ruliyani Km. 0/0 to 3/0 & Link road to village Kathlog to Bharera Km. 0/0 to 2/180).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	472.00			Per Hour	
					<b>Total</b>	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


  
**Executive Engineer**  
 Dalhousie Division,  
 H.P.P.W.D. Dalhousie

## Schedule of Qty.

Estimated Cost: - Rs.	161865.00
Earnest Money :- Rs.	3500.00
Time Limit :-	Three Month

Name of work: - Restoration of rain damage on various roads under HPPWD Sub Division Dalhousie (SH:- Supplying and stacking of WBM-III, sand for rectification of various road thereof).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Supplying and stacking of approved quality fine crushed sand defined as passing 2.36mm (two point three six millimetre) sieve and retained on 180 (one hundred eighty) microns sieve and free from deleterious, organic or any other foreign matter properly washed and stacked in proper stacks of half cubic metre along road side clear from the road formation as per directions of the Engineer-in Charge. The material shall confirm to the MORD specification. The rate quoted by the contractor shall be inclusive of all taxes such as municipal, octroi, forest Malkana royalty toll tax, GST and other local taxes imposed by the Government and including carriage of material within all leads and lifts and other incidentals. The voids will be deducted as per latest instructions of the department.	34.00			Per Cubic Meter	
	Supplying and stacking of approved quality crushed stone aggregate size 53 mm to 22.4 mm (Fifty three millimetre to Twenty two point four millimetre) nominal size free from deleterious, organic or any other foreign matter properly washed and stacked in proper stacks of half cubic metre along road side clear from the road formation as per directions of the Engineer-in Charge. The material shall confirm to the MORD specification. The rate quoted by the contractor shall be inclusive of all taxes such as municipal, octroi, forest Malkana royalty toll tax GST and other local taxes imposed by the Government and including carriage of material within all leads and lifts and other incidentals. The voids will be deducted as per latest instructions of the department	65.13			Per Cubic Meter	
	<b>Total</b>					

  
 Executive Engineer  
 Dalhousie Division,  
 HPPWD, Dalhousie