

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No.PW-MDI(Padhar)E-Tender-NIT/2023-24- 22157-58 Dated:- 9/2/24

To

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.

Executive Engineer,
Mandi Division No.1,
HP. PWD. at Padhar

Copy forwarded the Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and further necessary action please.

Executive Engineer,
Mandi Division No.1,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed percentage rate tender on form No. 6&8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 21.02.2024 up to 12:00 Noon and the same shall be opened on the same day at 12:30 P.M. in the presence of the Contractors or their authorized representatives who may be present. The tender application will be received in this office on 19.02.2024 upto 10.00 A.M. to 1:00 P.M. and tender form can be held from this office against cash payment (Non Refundable) on 20.02.2024 from 2.00 P.M. to 5.00 P.M.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.

Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Restoration of rain damages on Barot Mayot road Km 0/0 to 7/960. (SH:- Construction of Retaining wall at R.D. 7/110 to 7/125)	4,86,587.98	9,700/-	350/-	One month
2	Restoration of rain damages on Tikkan Thaltukhod road Km 0/0 to 4/500. (SH:- Construction of retaining wall at R.D. 3/180 to 3/195)	4,16,926.40	8,300/-	350/-	One month
3	Restoration of rain damages on Tikkan Thaltukhod road Km 0/0 to 4/500. (SH:- Construction of retaining wall at R.D. 3/195 to 3/210)	4,17,504.40	8,300/-	350/-	One month
4	Restoration of rain damages on Tikkan Thaltukhod road Km 0/0 to 4/500. (SH:- Construction of retaining wall at R.D. 3/210 to 3/225)	4,16,487.35	8,300/-	350/-	One month
5	Restoration of rain damages on Thaltukhod Graman Panjound road Km 0/0 to 4/500. (SH:- Construction of retaining wall at R.D. 0/570 to 0/585)	4,17,440.09	8,300/-	350/-	One month
6	Restoration of rain damages on Ghasasni Jhatingri Tikkan Barot road Km 0/0 to 25/0. (SH:- Construction of retaining wall at R.D. 3/750 to 3/756)	3,24,513.61	6,500/-	350/-	One month
7	Restoration of rain damages on Ghasasni Jhatingri Tikkan Barot road Km 0/0 to 25/0. (SH:- Construction of retaining wall at R.D. 3/756 to 3/762)	3,24,224.61	6,500/-	350/-	One month
8	Restoration of rain damages on Ghasasni Jhatingri Tikkan Barot road Km 0/0 to 25/0. (SH:- Construction of retaining wall at R.D. 7/030 to 7/042)	4,33,188.42	8,700/-	350/-	One month
9	Restoration of rain damages on Tikkan Silhbudhani road Km 0/0 to 16/110. (SH:- Construction of wire crated retaining wall at R.D. 9/120 to 9/170)	3,27,248.91	6,500/-	350/-	One month
10	Restoration of rain damages on Sakrog Tikkar road Km 0/0 to 3/420 Mohal. (SH:- Construction of retaining wall in P.C.C. at R.D. 1/340 to 1/343.50)	1,03,455.02	2,100/-	350/-	One month

11	Restoration of rain damages on Balh to Tikkar road Km 0/0 to 3/0. (SH:- Construction of Breast wall at R.D. 1/630 to 1/646)	3,66,775.42	7,300/-	350/-	One month
12	Restoration of rain damages on Balh to Tikkar road Km 0/0 to 3/0. (SH:- Construction of Breast wall at R.D. 1/646 to 1/663)	3,66,830.15	7,300/-	350/-	One month
13	Restoration of rain damages on Balh to Tikkar road Km 0/0 to 3/0. (SH:- Construction of Breast wall at R.D. 1/663 to 1/680)	3,66,830.15	7,300/-	350/-	One month
14	Restoration of rain damages on Balh Ropa road Km 0/0 to 5/100. (SH:- Construction of Retaining wall at R.D. 2/220 to 2/226)	1,29,0785.54	2,600/-	350/-	One month
15	Restoration of rain damages on Balh Ropa road Km 0/0 to 5/100. (SH:- Construction of Retaining wall at R.D. 3/435 to 3/443)	3,84,171.51	7,700/-	350/-	One month
16	Restoration of rain damages on Balh Ropa road Km 0/0 to 5/100. (SH:- Construction of Retaining wall at R.D. 4/050 to 4/061)	2,32,076.69	4,600/-	350/-	One month
17	Construction of Balh to Ropa road at Km 0/0 to 5/100. (SH:- Construction of wing walls at R.D. 4/510 to 4/518 Left side of Existing Hume pipe culvert at RD 4/509)	2,67,699.77	5,400/-	350/-	One month
18	R.R.D. on Ropa to Kathog road at Km 0/0 to 5/0. (SH:- Construction of Retaining wall at R.D. 4/065 to 4/073)	2,10,385.32	4,200/-	350/-	One month
19	Restoration of rain damages on Tikkan Silhbudhani road Km 0/0 to 16/110. (SH:- Construction of wire crate Breast wall at R.D. 14/525 to 14/570)	3,73,846.22	7,500/-	350/-	One month
20	Construction of Drang Sirdhar Soyala Banog road Km 0/0 to 3/500. (SH:- Construction of 900mm dia Hume pipe culvert at R.D. 1/525 with wing walls)	3,62,901.49	7,300/-	350/-	Three months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.
5. Only two tenders form will be issued to the contractor/firms which may be noted.
6. The intending Contractors are requested to see the site of the work before submitting the tender.
7. The offer of the tender shall remain valid upto 75 days after the opening of tender.
8. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


 Executive Engineer,
 Mandi Division No. I,
 HPPWD., at Padhar Distt. Mandi (H.P.)
 on behalf of Governor of Himachal Pradesh

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 486587.98

Earnest Money Rs:- 9700.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of rain damages on Barot Mayot road Km. 0/0 to 7/960. (Sub Head:- Construction of Retaining wall at R.D. 7/110 to 7/125.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sl. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	40.12	Per cubic metre	461.00	Rupees Eighteen Thousand Four Hundred Ninety Five and Paise Thirty Two Only	18495.32
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	86.46	Per cubic metre	5285.00	Rupees Four Lakh Fifty Six Thousand Nine Hundred Forty One and Paise Ten Only	456941.10
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	5.80	Per cubic metre	1433.20	Rupees Eight Thousand Three Hundred Twelve and Paise Fifty Six Only	8312.56
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	10.00	Each	283.90	Rupees Two Thousand Eight Hundred Thirty Nine Only	2839.00
Total in figure :					Rupees Four Lakh Eighty Six Thousand Five Hundred Eighty Seven and Paise Ninety Eight Only	486587.98
Total in Words :		Rupees Four Lakh Eighty Six Thousand Five Hundred Eighty Seven and Paise Ninety Eight Only				


 Executive Engineer,
 Mandi Division No.I,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 416926.40

Earnest Money Rs:- 8300.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandl Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of rain damages on Tikkan Thatukhod road Km. 0/0 to 4/500. (Sub Head:- Construction of retaining wall at R.D. 3/180 to 3/195.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	28.80	Per cubic metre	461.00	13276.80	Rupees Thirteen Thousand Two Hundred Seventy Six and Paise Eighty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	66.70	Per cubic metre	5473.00	365049.10	Rupees Three Lakh Sixty Five Thousand Forty Nine and Paise Ten Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	22.50	Per cubic metre	1433.00	32242.50	Rupees Thirty Two Thousand Two Hundred Forty Two and Paise Fifty Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	22.00	Each	289.00	6358.00	Rupees Six Thousand Three Hundred Fifty Eight Only
Total in figure :					416926.40	Rupees Four Lakh Sixteen Thousand Nine Hundred Twenty Six and Paise Forty Only
Total in Words :					Rupees Four Lakh Sixteen Thousand Nine Hundred Twenty Six and Paise Forty Only	


 Executive Engineer,
 Mandl Division No. I,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 417504.40

Earnest Money Rs:- 8300.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP. PWD. at Padhar.						
Name of work :- Restoration of rain damages on Tikkan Thaltukhod road Km. 0/0 to 4/500. (Sub Head:- Construction of retaining wall at R.D. 3/195 to 3/210.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	28.80	Per cubic metre	461.00	13276.80	Rupees Thirteen Thousand Two Hundred Seventy Six and Paise Eighty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	66.70	Per cubic metre	5473.00	365049.10	Rupees Three Lakh Sixty Five Thousand Forty Nine and Paise Ten Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	22.50	Per cubic metre	1433.00	32242.50	Rupees Thirty Two Thousand Two Hundred Forty Two and Paise Fifty Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	24.00	Each	289.00	6936.00	Rupees Six Thousand Nine Hundred Thirty Six Only
Total in figure :					417504.40	Rupees Four Lakh Seventeen Thousand Five Hundred Forty Only
Total in Words :		Rupees Four Lakh Seventeen Thousand Five Hundred Forty and Paise Forty Only				


 Executive Engineer,
 Mandi Division No. I,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 416487.35
Earnest Money Rs:- 8300.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of rain damages on Tikkan Thaltukhod road Km. 0/0 to 4/500. (Sub Head:- Construction of retaining wall at R.D. 3/210 to 3/225.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	25.05	Per cubic metre	461.00	11548.05	Rupees Eleven Thousand Five Hundred Forty Eight and Paise Five Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	66.70	Per cubic metre	5473.00	365049.10	Rupees Three Lakh Sixty Five Thousand Forty Nine and Paise Ten Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	23.40	Per cubic metre	1433.00	33532.20	Rupees Thirty Three Thousand Five Hundred Thirty Two and Paise Twenty Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	22.00	Each	289.00	6358.00	Rupees Six Thousand Three Hundred Fifty Eight Only
Total in figure :					416487.35	Rupees Four Lakh Sixteen Thousand Four Hundred Eighty Seven and Paise Thirty Five Only
Total in Words :		Rupees Four Lakh Sixteen Thousand Four Hundred Eighty Seven and Paise Thirty Five Only				


 Executive Engineer,
 Mandi Division No.I,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 417440.09
Earnest Money Rs:- 8300.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.

Name of work :- Restoration of rain damages on Thaltukhod Graman Panjoundroad Km. 0/0 to 4/500. (Sub Head:- Construction of retaining wall at R.D. 0/570 to 0/585.)

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	33.79	Per cubic metre	461.00	15577.19	Rupees Fifteen Thousand Five Hundred Seventy Seven and Paise Nineteen Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	66.70	Per cubic metre	5491.00	366249.70	Rupees Three Lakh Sixty Six Thousand Two Hundred Forty Nine and Paise Seventy Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	20.40	Per cubic metre	1433.00	29233.20	Rupees Twenty Nine Thousand Two Hundred Thirty Three and Paise Twenty Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	22.00	Each	290.00	6380.00	Rupees Six Thousand Three Hundred Eighty Only
Total in figure :					417440.09	Rupees Four Lakh Seventeen Thousand Four Hundred Forty and Paise Nine Only
Total in Words :						Rupees Four Lakh Seventeen Thousand Four Hundred Forty and Paise Nine Only


 Executive Engineer,
 Mandi Division No.1,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 324513.61
Earnest Money Rs:- 6500.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP, PWD. at Padhar.						
Name of work :- Restoration of rain damages on Ghatasni Jhatigri Tikkan Barot road Km. 0/0 to 25/0. (Sub Head:- Construction of retaining wall at R.D. 3/750 to 3/756.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	21.18	Per cubic metre	461.00	9763.98	Rupees Nine Thousand Seven Hundred Sixty Three and Paise Ninety Eight Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification-clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	53.03	Per cubic metre	5473.00	290233.19	Rupees Two Lakh Ninety Thousand Two Hundred Thirty Three and Paise Nineteen Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	13.68	Per cubic metre	1433.00	19603.44	Rupees Nineteen Thousand Six Hundred Three and Paise Forty Four Only
4	Providing weep hole in brick masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical into twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	17.00	Each	289.00	4913.00	Rupees Four Thousand Nine Hundred Thirteen Only
Total in figure :					324513.61	Rupees Three Lakh Twenty Four Thousand Five Hundred and Paise Sixty One Only
Total In Words :					Rupees Three Lakh Twenty Four Thousand Five Hundred Thirteen and Paise Sixty One Only	

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 324224.61
Earnest Money Rs:- 6500.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.

Name of work :- Restoration of rain damages on Ghatasni Jhatingri Tikkan Barot road Km. 0/0 to 25/0. (Sub Head:- Construction of retaining wall at R.D. 3/756 to 3/762.)

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	21.18	Per cubic metre	461.00	9763.98	Rupees Nine Thousand Seven Hundred Sixty Three and Paise Ninety Eight Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	53.03	Per cubic metre	5473.00	290233.19	Rupees Two Lakh Ninety Thousand Two Hundred Thirty Three and Paise Nineteen Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	13.68	Per cubic metre	1433.00	19603.44	Rupees Nineteen Thousand Six Hundred Three and Paise Forty Four Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical into twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	16.00	Each	289.00	4624.00	Rupees Four Thousand Six Hundred Twenty Four Only
Total in figure :					324224.61	Rupees Three Lakh Twenty Four Thousand Two Hundred and Paise Sixty One Only
Total in Words :					Rupees Three Lakh Twenty Four Thousand Two Hundred Twenty Four and Paise Sixty One Only	



Executive Engineer,
Mandi Division No.1,
HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 433188.42
Earnest Money Rs:- 8700.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.						
Name of work :- Restoration of rain damages on Ghatasni Jhatingri Tikkan Barot road Km. 0/0 to 25/0. (Sub Head:- Construction of retaining wall at R.D. 7/030 to 7/042.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of Items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	29.04	Per cubic metre	461.00	13387.44	Rupees Thirteen Thousand Three Hundred Eighty Seven and Paise Forty Four Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	73.02	Per cubic metre	5473.00	399638.46	Rupees Three Lakh Ninety Nine Thousand Six Hundred Thirty Eight and Paise Forty Six Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	10.44	Per cubic metre	1433.00	14960.52	Rupees Fourteen Thousand Nine Hundred Sixty and Paise Fifty Two Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	18.00	Each	289.00	5202.00	Rupees Five Thousand Two Hundred Two Only
Total in figure :					433188.42	Rupees Four Lakh Thirty Three Thousand One Hundred Eighty Eight and Paise Forty Two Only
Total in Words :		Rupees Four Lakh Thirty Three Thousand One Hundred Eighty Eight and Paise Forty Two Only				


 Executive Engineer,
 Mandi Division No.1,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 327248.91

Earnest Money Rs:- 6500.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP, PWD. at Padhar.

Name of work :- ~~Restoration of rain damages on Tikkan Silhbudhani road Km. 0/0 to 16/110.~~ (Sub Head:- Construction of Wire crated retaining wall at R.D. 9/120 to 9/170.)

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	27.30	Per cubic metre	461.00	12585.30	Rupees Twelve Thousand Five Hundred Eighty Five and Paise Thirty Only
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	123.68	Per cubic metre	2418.00	299058.24	Rupees Two Lakh Ninety Nine Thousand Fifty Eight and Paise Twenty Four Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	10.89	Per cubic metre	1433.00	15605.37	Rupees Fifteen Thousand Six Hundred Five and Paise Thirty Seven Only
Total in figure :					327248.91	Rupees Three Lakh Twenty Seven Thousand Two Hundred and Paise Ninety One Only
Total in Words :					Rupees Three Lakh Twenty Seven Thousand Two Hundred Forty Eight and Paise Ninety One Only	

Executive Engineer,
Mandi Division No. I,
HP, PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 103455.02
 Earnest Money Rs:- 2100.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP. PWD. at Padhar.						
Name of work :- Restoration of rain damages on Sakrog Tikkar road Km. 0/0 to 3/420 Mohal. (Sub Head:- Construction of retaining wall in P.C.C. at R.D. 1/340 to 1/343.50.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	9.13	Per cubic metre	461.00	4208.93	Rupees Four Thousand Two Hundred Eight and Paise Ninety Three Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	17.51	Per cubic metre	5387.50	94335.13	Rupees Ninety Four Thousand Three Hundred Thirty Five and Paise Thirteen Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	2.83	Per cubic metre	1433.20	4055.96	Rupees Four Thousand Fifty Five and Paise Ninety Six Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	3.00	Each	285.00	855.00	Rupees Eight Hundred Fifty Five Only
Total in figure :					103455.02	Rupees One Lakh Three Thousand Four Hundred Fifty Five and Paise Two Only
Total in Words :		Rupees One Lakh Three Thousand Four Hundred Fifty Five and Paise Two Only				


 Executive Engineer,
 Mandi Division No.1,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 366775.42
Earnest Money Rs:- 7300.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.	
Name of work :- Restoration of rain damages on Balh to Tikkar road Km. 0/0 to 3/0. (Sub Head:- Construction of Breast wall at R.D. 1/630 to 1/646.)	
Contract No. :	
Bidder Name :	

SCHEDULE OF WORKS						
Sr. No.	Description of Items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	36.61	Per cubic metre	461.00	16877.21	Rupees Sixteen Thousand Eight Hundred Seventy Seven and Paise Twenty One Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	62.77	Per cubic metre	5473.00	343540.21	Rupees Three Lakh Forty Three Thousand Five Hundred Forty and Paise Twenty One Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	22.00	Each	289.00	6358.00	Rupees Six Thousand Three Hundred Fifty Eight Only
Total in figure :					366775.42	Rupees Three Lakh Sixty Six Thousand Seven Hundred Seventy Five and Paise
Total in Words :		Rupees Three Lakh Sixty Six Thousand Seven Hundred Seventy Five and Paise Forty Two Only				


Executive Engineer,
Mandi Division No.I,
H.P. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 366830.15
Earnest Money Rs:- 7300.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of work :- Restoration of rain damages on Balh to Tikkar road Km. 0/0 to 3/0. (Sub Head:- Construction of Breast wall at R.D. 1/646 to 1/663.)

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	36.61	Per cubic metre	461.00	16877.21	Rupees Sixteen Thousand Eight Hundred Seventy Seven and Paise Twenty One Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	62.78	Per cubic metre	5473.00	343594.94	Rupees Three Lakh Forty Three Thousand Five Hundred Ninety Four and Paise Ninety Four Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical to twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204,3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	22.00	Each	289.00	6358.00	Rupees Six Thousand Three Hundred Fifty Eight Only
Total in figure :					366830.15	Rupees Three Lakh Sixty Six Thousand Eight Hundred Thirty and Paise Fifteen Only
Total in Words :						Rupees Three Lakh Sixty Six Thousand Eight Hundred Thirty and Paise Fifteen Only


Executive Engineer,
Mandi Division No.1,
HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 366830.15
Earnest Money Rs:- 7300.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD, at Padhar.						
Name of work :- Restoration of rain damages on Balh to Tikkar road Km. 0/0 to 3/0. (Sub Head:- Construction of Breast wall at R.D. 1/663 to 1/680.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	36.61	Per cubic metre	461.00	16877.21	Rupees Sixteen Thousand Eight Hundred Seventy Seven and Paise Twenty One Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	62.78	Per cubic metre	5473.00	343594.94	Rupees Three Lakh Forty Three Thousand Five Hundred Ninety Four and Paise Ninety Four Only
3	Providing weep hole in Brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	22.00	Each	289.00	6358.00	Rupees Six Thousand Three Hundred Fifty Eight Only
Total in figure :					366830.15	Rupees Three Lakh Sixty Six Thousand Eight Hundred Thirty and Paise Fifteen Only
Total in Words :						Rupees Three Lakh Sixty Six Thousand Eight Hundred Thirty and Paise Fifteen Only


 Executive Engineer,
 Mandi Division No.I,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 129075.54

Earnest Money Rs:- 2600.00

Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP, PWD, at Padhar.

Name of work :- Restoration of rain damages on Bath Ropa road Km. 0/0 to 5/100. (Sub Head:- Construction of Retaining wall at R.D. 2/220 to 2/226).

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	9.84	Per cubic metre	461.00	4536.24	Rupees Four Thousand Five Hundred Thirty Six and Paise Twenty Four Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	21.60	Per cubic metre	5388.00	116380.80	Rupees One Lakh Sixteen Thousand Three Hundred Eighty and Paise Eighty Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	6.00	Each	285.00	1710.00	Rupees One Thousand Seven Hundred Ten Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	4.50	Per cubic metre	1433.00	6448.50	Rupees Six Thousand Four Hundred Forty Eight and Paise Fifty Only
Total in figure :					129075.54	Rupees One Lakh Twenty Nine Thousand Seventy Five and Paise Fifty Four Only
Total in Words :		Rupees One Lakh Twenty Nine Thousand Seventy Five and Paise Fifty Four Only				


 Executive Engineer,
 Mandi Division No.I,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 384171.51
Earnest Money Rs:- 7700.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP. PWD. at Padhar.						
Name of work :- Restoration of rain damages on Bah Ropa road Km. 0/0 to 5/100. (Sub Head:- Construction of Retaining wall at R.D. 3/435 to 3/443).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	31.20	Per cubic metre	461.00	14383.20	Rupees Fourteen Thousand Three Hundred Eighty Three and Paise Twenty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	66.73	Per cubic metre	5295.00	353335.35	Rupees Three Lakh Fifty Three Thousand Three Hundred Thirty Five and Paise Thirty Five Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	282.00	3384.00	Rupees Three Thousand Three Hundred Eighty Four Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	9.12	Per cubic metre	1433.00	13068.96	Rupees Thirteen Thousand Sixty Eight and Paise Ninety Six Only
Total in figure :					384171.51	Rupees Three Lakh Eighty Four Thousand One Hundred Seventy One and Paise Fifty One Only
Total in Words :		Rupees Three Lakh Eighty Four Thousand One Hundred Seventy One and Paise Fifty One Only				


 Executive Engineer,
 Mandi Division No.I,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 232076.69
Earnest Money Rs:- 4600.00
Time One month


Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of rain damages on Balh Ropa road Km. 0/0 to 5/100. (Sub Head:- Construction of Retaining wall at R.D. 4/050 to 4/061).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	18.04	Per cubic metre	461.00	8316.44	Rupees Eight Thousand Three Hundred Sixteen and Paise Forty Four Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	39.60	Per cubic metre	5295.00	209682.00	Rupees Two Lakh Nine Thousand Six Hundred Eighty Two Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	8.00	Each	282.00	2256.00	Rupees Two Thousand Fifty Six Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	8.25	Per cubic metre	1433.00	11822.25	Rupees Eleven Thousand Eight Hundred Twenty Two and Paise Twenty Five Only
Total in figure :					232076.69	Rupees Two Lakh Thirty Two Thousand Seventy Six and Paise Sixty Nine Only
Total in Words :		Rupees Two Lakh Thirty Two Thousand Seventy Six and Paise Sixty Nine Only				


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 267699.77
 Earnest Money Rs:- 5400.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP, PWD. at Padhar.						
Name of work :- Construction of Bath to Ropa road at Km. 0/00 to 5/100. (Sub Head:- Construction of wing wall at R.D. 4/510 to 4/513 Left side of Exiting Hume pipe culvertat Rd. 4/509).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	17.04	Per cubic metre	461.00	7855.44	Rupees Seven Thousand Eight Hundred Fifty Five and Paise Forty Four Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	49.14	Per cubic metre	4990.00	245208.60	Rupees Two Lakh Forty Five Thousand Two Hundred Eight and Paise Sixty Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	7.81	Per cubic metre	1433.00	11191.73	Rupees Eleven Thousand One Hundred Ninety One and Paise Seventy Three Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	287.00	3444.00	Rupees Three Thousand Four Hundred Forty Four Only
Total in figure :					267699.77	Rupees Two Lakh Sixty Seven Thousand Six Hundred Ninety Nine and Paise
Total in Words :					Rupees Two Lakh Sixty Seven Thousand Six Hundred Ninety Nine and Paise Seventy Seven Only	


 Executive Engineer,
 Mandi Division No.I,
 HP, PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 210385.32
Earnest Money Rs:- 4200.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP, PWD. at Padhar.						
Name of work : R.R.D. on Ropa to Kathog road at Km. 0/00 to 5/00. (Sub Head: - Construction of Retaining wall at R.D. 4/065 to 4/073).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	25.60	Per cubic metre	461.00	11801.60	Rupees Eleven Thousand Eight Hundred One and Paise Sixty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	40.04	Per cubic metre	4691.00	187827.64	Rupees One Lakh Eighty Seven Thousand Eight Hundred Twenty Seven and Paise Sixty Four Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	5.76	Per cubic metre	1433.00	8254.08	Rupees Eight Thousand Two Hundred Fifty Four and Paise Eight Only
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical into twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	9.00	Each	278.00	2502.00	Rupees Two Thousand Five Hundred Two Only
Total in figure :					210385.32	Rupees Two Lakh Ten Thousand Three Hundred Eighty Five and Paise Thirty Two Only
Total in Words :		Rupees Two Lakh Ten Thousand Three Hundred Eighty Five and Paise Thirty Two Only				

Executive Engineer
Mandi Division No. 1,
HP, PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 373846.22
 Earnest Money Rs:- 7500.00
 Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP, PWD, at Padhar.						
Name of work :- Restoration of rain Damages on Tikkan Silbhudhani Road Km. 0/00 to 16/110. (Sub Head: - Construction of Wire Crate Breast wall at R.D. 14/525 to 14/570).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	44.03	Per cubic metre	461.00	20298.00	Rupees Twenty Thousand Two Hundred Ninety Eight Only
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	140.64	Per cubic metre	2326.55	327206.00	Rupees Three Lakh Twenty Seven Thousand Two Hundred Six Only
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	18.38	Per cubic metre	1433.20	26342.22	Rupees Twenty Six Thousand Three Hundred Forty Two and Paise Twenty Two Only
Total in figure :					373846.22	Rupees Three Lakh Seventy Three Thousand Eight Hundred Forty Six and Paise Twenty Two Only
Total in Words :		Rupees Three Lakh Seventy Three Thousand Eight Hundred Forty Six and Paise Twenty Two Only				


 Executive Engineer,
 Mandi Division No.I,
 HP, PWD, at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 362901.49
 Earnest Money Rs:- 7300.00
 Time :- Three months

Tender Inviting Authority: Executive Engineer, Mandi Division No. 1 HP, PWD, at Padhar.

Name of work:- Construction of Drang, Sirdhar, Soyala, Banog Road Km. 0.00 to 3/500. (Sub Head:- Construction of 900mm dia. Hume Pipe culvert at R.D. 1/525 with wing walls).

Contract No.:-

Name of Bidder/Bidding Firm/ Company:-

SCHEDULE OF WORKS

Sr. No.	Item Description	Quantity	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	49.20 Per cubic metre	461.00	22661.20	Rupees Twenty Thousand Six Hundred Eighty One and Paise Twenty Only
2	Providing and laying concrete Mechanically mixed and vibrated mix 1:3:12 (one cement: six sand: twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain/reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	3.40 Per cubic metre	4379.50	14890.30	Rupees Fourteen Thousand Eight Hundred Ninety and Paise Thirty Only
3	Providing concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement : three sand : twelve graded, crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	11.55 Per cubic metre	5706.00	65604.30	Rupees Sixty Thousand Nine Hundred Four and Paise Thirty Only
4	Providing and laying reinforced cement concrete 900mm (Nine hundred millimetre) diameter pipe NP2 as per design for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) but excluding excavations, protection works, back filling, concrete and masonry works in head walls and parapets as per drawings and technical specifications for Rural roads clause 1101 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7.50 Per running metre	3263.10	24473.25	Rupees Twenty Thousand Four Hundred Seventy Three and Paise Twenty Five Only
5	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1303. Rubble stone laid in cement mortar 1:3 (one cement : three sand) (Excavation for preparation of bed and cement concrete bedding to be measured and paid for separately) including curing complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	0.49 Per cubic metre	5095.70	2496.89	Rupees Two Thousand Four Hundred Ninety Six and Paise Eighty Nine Only
6	Providing and laying concrete mechanically mixed and vibrated mix 1:5:10 (one cement: five sand: ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain/reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts or as per the entire satisfaction and direction of Engineer-in-Charge.	49.33 Per cubic metre	4531.00	223514.23	Rupees Two Lakh Twenty Three Thousand Five Hundred Fourteen and Paise Twenty Three Only
7	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	6.00 Each	272.00	1632.00	Rupees One Thousand Six Hundred Thirty Two Only

Sr. No.	Item Description	Quantity	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	7
8	Back filling behind abutment wing wall and return wall complete as per drawing and technical specifications clause 1206.3 with Granular material complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	5.10 Per cubic metre	1433.20	7309.32	Rupees Seven Thousand Three Hundred Nine and Paise Thirty Two Only
Total in Figure				302901.49	Rupees Three Lakh Sixty Two Thousand Nine Hundred One and Paise Forty Nine Only
Quoted Rate in Words		Rupees Three Lakh Sixty Two Thousand Nine Hundred One and Paise Forty Nine Only			


 Executive Engineer,
 Mandi Division No. 1,
 HP.PWD. at Padhar