

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No:-PW-NCD-E-Tender-NIT/2023:- 13937-44

Dated:- 19-02-2024.

To

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2


Subject: -

Publishing of tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of works as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Pncipal Secretary (PW), to the Govt. of H.P. letter No.PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA: - Notice Inviting Tender.
(56 Nos. Works)


Executive Engineer,
HP.PWD., Division,
Nerchowk.

Copy forwarded to for information:-


Copy forwarded to the Superintending Engineer, 1st Circle, HP.PWD.,
Mandi for information please.

Copy to all the Assistant Engineers, working under this Division.

Copy to Account Branch in this office.

Copy to Drawing Branch in this office.

Notice Board.


Executive Engineer,
HP.PWD., Division,
Nerchowk.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDER"

Engineer, Nerchowk, H.P.PWD. Nerchowk for the following works from the approved and eligible contractors enlisted in H.P.PWD. so as to reach in this office on or before **02.03.2024 upto 01.30 P.M.** and will be opened on the same day at **3.00 P.M.** in the presence of interesting contractors or their authorized representatives who may like to be present. If it happen to be holiday on the tender will be open on next working day. The application for obtaining the tender form will be received up to **12:00 Noon on 01.03.2024** and tender form will be issued on dated **02.03.2024 upto 11:30 AM.** The EMD should be attached during the submission of application for obtaining the tender form. The application will not be accepted without Earnest Money & Cost of tender form.

The earnest money in the shape of FDR National Saving Certificate/Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany with each tender. The conditional tender's and the tender's received without earnest money will summarily be rejected. The earnest money should be attached with application. The offer of the tender shall be kept open for **90 days.** The Executive Engineer reserves the right to reject the tender's without assigning any reason:-

Sr. No	Name of work	Estimated Cost (Rs.)	Earnest Money (Rs.)	Cost of Tender From (Rs.)	Time limit	Eligible Class of Contractor
1	Construction of Kalkhar Galoo to Naundhar Upper Dibhri, Lower Dibhri Bhout Sidhyani road km 0/00 to 4/600. (SH:- Constructioun of 900mm dia RCC Hume pipe culvert at RD.4/200 alongwith both side wing walls).	385090	7700	350	Two Months	"D"
2	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (SH:- Upgradation of Nerchowk Ratti Kalkhar road km. 0/0 to 13/300. Under NABARD, Distt. Mandi (HP) and up-gradation of Nerchowk Ratti Kalkhar road km. 0/0 to 13/300 Under CRF Distt. Mandi (HP). (Two Nos received DPR therof).	99000	2000	350	One Month	"D"
3	Restoration of rain damages on Leda Ghangoon road km. 0/0 to 12/00. (Sub Head:- Construction of Retaining wall at RD. 6/750 to 6/770).	329214	6600	350	Two Months	"D"
4	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Gagal section) (SH:- Hiring of JCB clearing of debries, drains and dressing of berms etc.).	252000	5100	350	One month	"D"
5	Construction of link road from Damka-Samlon-Galma-Pargipul-Bag Sidhkothi- Bairi Samlehar- Badhkari-Tarwai road km. 0/0 to 2/660, (SH:- Providing and laying WBM G-I in km. 2/0 to 2/600) Under OTMNP.	467646	9400	350	Three Months	"D"
6	Construction of Kalkhar galu to Noundhar Upper Dibhri Lower Dibhri Bhout Sidhyani road km. 0/00 to 5/0 (SH:- Providing and laying WBM G-I at RD. 3/830 to 4/490) Under OTMNP	485654	9700	350	Two Months	"D"
7	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Ratti section) (SH:- Hiring of JCB clearing of debris, drains and dressing of berms etc.).	252000	5100	350	One month	"D"
8	Construction of Ner Dhangu and Link road from Chandyal to Saayah via SC Basti Sayahal Km. 0/00 to 2/200. (SH:- Providing and laying cement concerte paver blocks in km. 2/262 to 2/300.)	343024	6900	350	Two Months	"D"
9	Restoration of rain damages on Manjhyali Ghour Sardhwar road km. 0/0 to 13/00 (SH:- Construction of Retaining wall at RD. 1/480 to 1/483.50)	122083	2500	350	Two Months	"D"
10	A/R & M/O SLBSGMC & Hospital at Nerchowk (SH:- Distempering with OBD in Hospital building (BOCK-B) Third floor and fourth floor.	489756	9800	350	One month	"D"
11	Additional and alteration work in PRA building in SLBSGMC & H in Nerchowk Distt. Mandi (SH:- C/O ward robs in PRA second floor male and female doormetry) Job No.-1	376639	7600	350	One month	"D"
12	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Nerchowk Section) (SH:- Hiring of JCB for clearing of debries drains and dressing of berms etc.).	252000	5100	350	One Month	"D"
13	RRD on Ratti to Kalkhar road km. 0/0 to 10/00. (SH:- Construction of PCC retaining wall at RD. 6/520 to 6/540).	434539	8700	350	Two Months	"D"

14	A/R & M/O SLBSGMC & Hospital at Nerchowk Distt. Mandi (HP). (SH:- Distempering with OBD in Hospital building (Block-A) Fifth and sixth floor.	486407	9800	350	One month	"D"
15	A/R & M/O SLBSGMC & Hospital at Nerchowk Distt. Mandi (HP). (SH:- Distempering with OBD in Hospital building (Block-B) Ground floor.	313412	6300	350	One month	"D"
16	Restoration of rain damages on Ratti to Randhara road km. 0/0 to 9/00. (SH:- Repair of 6 mtr. Span RCC span culvert at RD. 8/220).	234725	4700	350	Three Months	"D"
17	Restoration of road damages caused due to laying of optical fiber cable on Ratti Kalkhar road km 0/00 to 10/00. (SH:- Construction of PCC Retaining wall at RD. 2/355 to 2/366) Deposit work.	289333	5800	350	Two Months	"D"
18	Routine day to day repair and maintenance of non residential building of SLBSGMC & H at Nerchowk Distt. Mandi (HP) (SH:- Providing and fixing MS ladder and working platform in various ducts in hospital building (Block-A & Block-B) in SLBSGMC&H Nerchowk).	293355	5900	350	One month	"D"
19	A/R & M/O SLBSGMC & Hospital at Nerchowk (SH:- Distempering with OBD in Hospital building (Block-B) First floor and second floor.	497613	9950	350	One month	"D"
20	A/R & M/O SLBSGMC & Hospital at Nerchowk Distt. Mandi (HP). (SH:- Distempering with OBD in Hospital building (Block-C) Ground floor and first floor.	465249	9300	350	One month	"D"
21	Restoration of rain damages on Ratti Meramasit Leda road km 0/00 to 14/850. (SH:- Construction of Retaining wall at RD. 7/010 to 7/025).	316531	6400	350	Two Months	"D"
22	Restoration of rain damages on Malthehar by pass road km. 0/00 to 1/045 (SH:- Construction of Breast wall at RD. 0/730 to 0/745).	242696	4900	350	One month	"D"
23	Restoration of rain damages on Malthehar to Karehari road km. 0/00 to 2/00 (SH:- Construction of Retaining wall at RD. 0/640 to 0/652).	264649	5300	350	Two Months	"D"
24	A/R & M/O SLBSGMC & Hospital at Nerchowk Distt. Mandi (HP) (SH:- Distempering with OBD in Hospital building (Block-C) Second floor & Third floor.	441637	8800	350	One month	"D"
25	Additional and alteration work in PRA building in SLBSGMC & H in Nerchowk Distt. Mandi (SH:- C/o ward robs in PRA second floor male and female doormetry) Job No.-2	394965	7900	350	One month	"D"
26	Restoration of road damages caused due to laying of optical fibre cable on Ratti Dharwahan Grencha road km. 0/0 to 6/00 (SH:- Providing and laying interlocking paver block at RD. 1/044 to 1/117).	486593	9800	350	Two Months	"D"
27	A/R & M/O SLBSGMC & Hospital at Nerchowk Distt. Mandi (HP) (SH:- Distempering with OBD in Hospital building (Block-C) Fourth floor and sixth floor.	438247	8800	350	One month	"D"
28	A/R & M/O SLBSGMC & Hospital at Nerchowk Distt. Mandi (HP) (SH:- Distempering with OBD in Hospital building (Block-C) Fifth floor.	268834	5400	350	One month	"D"
29	Construction of hostel for MBBS students in the campus of SLBSGMC&H Distt. Mandi (H.P.) (SH:- Preparation of detail estimate and DNIT).	132052	2700	350	One month	"D"
30	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Gagal Section) (SH:- Hiring of Tractor with trolley for carriage of muck/debris and shifting of material etc.).	99000	2000	350	Two Months	"D"
31	Restoration of rain damages on Ratti Meramasit Leda road km 0/00 to 14/580. (SH:- Construction of Breast wall at RD. 7/012 to 7/032).	287743	5800	350	One month	"D"
32	Restoration of rain damages on Majhyali Ghour Sardhar up to village Batahan road km. 0/0 to 13/00 (SH:- Construction of Breast wall at RD. 7/012 to 7/032)	407001	8200	350	One Month	"D"
33	A/R & M/O SLBSGMC & Hospital at Nerchowk (SH:- Distempering with OBD in Hospital building (Block-B) Fifth floor and sixth floor.	497753	10000	350	One month	"D"
34	Restoration of rain damages on Chakkar to Chalah road 0/00 to 3/00 (SH:- Construction of PCC drain in 1:3:6 at RD. 0/030 to 0/340) Deposit work.	147987	3000	350	Two Months	"D"


35	Restoration of rain damages on Lunapari Gehra Sain road 0/00 to 6/900 (SH:- Construction of Breast wall PCC in 1:5:10 at RD. 5/355 to 5/369).	297331	6000	350	Two Months	"D"
36	Construction of road from Dehrialoo Dhar-II Uper Lehra Tandehri Chir Badanu Lower Lehra Rihri Hour (Bah) km. 0/0 to 5/0 (SH:- Construction of Retaining wall at RD. 1/005 to 1/017). Under SCDP.	329644	6600	350	Two Months	"D"
37	Restoration of rain damages on Kalkhar Leda Sundernagar road in km. 0/0 to 13/500 (SH:- C/O Breast wall at RD. 7/375 to 7/387)	243229	4900	350	One month	"D"
38	Restoration of rain damages on Rewalsar Pingla Thona Dharpur road in km. 0/0 to 10/00 (SH:- C/O Retaining wall at RD. 0/981 to 0/990)	361815	7200	350	Two Months	"D"
39	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (SH:- Preparation of detailed project reports of widening /Improvement of Nagchala-Chakrari road km. 0/0 to 1/0, Improvement and widening of Mandi Gagah Nalsar road km. 0/0 to 16/0 (Portion pool gharat to NH-4 lane Malori Tunnel km. 0/0 to 1/650, M/T on Chapru-Nallah, Khakhrina road (0/00 to 5/00, C/o double lane road at RD. 0/0 TO 2/600 to the site of National disaster response (NDRF) Battalion in the State (at Behna Distt. Mandi) and Upgradation of Bagla Badsu road 0/0 top 5/300).).	446275	9000	350	One month	"D"
40	Restoration of rain damages on Galma Manjhyali road in km. 0/0 to 9/00 (SH:- C/O PCC Retaining wall at RD. 1/550 to 1/558.50)	282658	5700	350	Two Months	"D"
41	Restoration of road damages caused due to laying of optical fibre cable on Ratti Kalkhar road km 0/00 to 10/00. (SH:-Removal of formation deficiencies /widening of curve in km. 3/405 to 3/435 & 9/780 to 10/0).	422924	8500	350	One month	"D"
42	Restoration of rain damages on Mandi Gagah Chailchowk Janjehli Chatri Rana Ka Bag Nagan road in km. 0/0 to 16/190 (SH:- Construction of Retaining wall at RD. 13/680 to 13/692)	197299	4000	350	Two Months	"D"
43	Additional and alteration work in Intern Hostel building in the SLBSGMC & H in Nerchowk Distt. Mandi (SH:- C/O common Toilet and supplying of bricks).	203232	4100	350	One month	"D"
44	RRD on Mandi Gagah Chailchowk Janjehli Chatri Rana Ka Bag Nagan road km. 0/0 to 16/190 (SH:- Dressing of berms and removal of slips various reachies in km. 0/0 to 15/00) Gagah Section.	282242	5700	350	Two Months	"D"
45	Restoration of rain damages on various roads under Rewalsar Sub Division HPPWD Rewalsar (Sardhwar section) (SH:- Removal of slips at various reaches).	204441	4100	350	One month	"D"
46	Restoration of road damages caused due to laying of optical fibre cable on Ratti Meramasit Leda road km 0/00 to 14/580. (SH:- Removal of formation deficiencies/ widening of curve in km. 12/480 to 12/750).	371211	7500	350	One Month	"D"
47	Restoration of rain damages on various roads under Rewalsar Sub Division HPPWD Rewalsar (Rewalsar section) (SH:- Hiring of Earth cutting/Excavating machine for removal of slips, clearing of debris drains and dressing of berms etc).	220500	4400	350	One Month	"D"
48	Annual repair and maintenance of various roads under Chakkar Sub Division HPPWD Nerchowk (SH:- Supplying of precast 5th km. stones ordinary km. stones and 200 mtr. Stones and boundary pillar)	174337	3500	350	One Month	"D"
49	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Gagah Section) (SH:- Hiring of JCB clearing of debris drains and dressing of berms etc.).	220500	4500	350	One Month	"D"
50	Construction of 92. mtr. Long span PSC Bow string bridge over Suketi Khad at RD. 0/810 in Distt. Mandi (SH:- Geological Investigation of soil/Strata). Job No 2.	477015	9600	350	One Month	"D"
51	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (SH:- Supplying and stacking dual direction rectangular delinators for road side with plastic head unbreakable at neck). (Ratti section).	188760	3800	350	One month	"D"

52	Construction of Balhi, Jagar Lusaika road km. 0/0 to 1/0 (SH:- Providing and laying (WBM-I in km. 0/646 to 0/675 and WBM G-II in km. 0/0 to 0/675) Under OTMNP	426681	8600	350	Two Months	"D"
53	Construction of Stadium Near GPS Arthi GP Mandal, Development Block Balh at Nerchowk (SH:- Construction of stadium at RD. 0/0 to 0/017).	499733	10000	350	Two Months	"D"
54	Construction of link road from Mandi Rewalsar road to village Ghour Tibba Khel Gharwahan Dev Sat Balakameshwar & Ghandalas road km. 0/00 to 1/500 (Portion Harder Re Ghari to Dev Sat Balakameshwar km. 0/0 to 1/500) (SH:- Construction of Retaining wall at RD. 0/900 to 0/915). Under OTMNP	324273	6500	350	Two Months	"D"
55	Restoration of road damages caused due to laying of optical fibre cable on Ratti Dharwahan Grencha road km. 0/0 to 6/00 (SH:- Providing and laying interlocking paver block at RD. 1/117 to 1/189).	479934	9600	350	Two Months	"D"
56	Restoration of road damages caused due to laying of optical Fiber cable on Ratti Meramasit Leda road km 0/0 to 14/580. (SH:- Providing and laying cement concrete pavement in km 2/250 to 2/290 & 2/350 to 2/370).	358088	7200	350	Two Months	"D"

It is certified that the above tenders are very "urgent nature", so may be uploaded on department website in public interest.

Note:- The Contractors/Firms should possess the following documents (Photo copy to be attached).

1. The Contractor/Firm should be enlisted with the HP.PWD. & Registration/Renewal copy attached.
2. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
3. The list of similar type of work executed and work done performance certificate issued by the concerned Executive Engineer required to be produced by the contractor along with application.
4. **Only two tenders shall be issued to each contractor.**
5. The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactory including adherence to quality parameters further work will be awarded to him. All under taking/affidavit alongwith application that he is not having more than two works in hand in HP.PWD for execution failing which the application for issuing the tender forms shall not be accepted.
6. The contractor/firm shall be issued tenders on the production of valid GST/income tax clearance certificate.
7. As per Govt. Notification No.PBW (B)A(3)1/2020-I dated 07.10.2021, in case the tendered amount of the lowest bidder comes more than 5% in 1st call the negotiation can be conducted with him but the negotiated amount should remain within 5% of the amount put to tender (on market rate) and vide Govt notification No.PBW (B)A(3)1/2020-I dated 10.05.2023 tendered amount below 30% of the estimated cost will be accepted.


Executive Engineer,
HP.PWD. Division,
Nerchowk.

Draft Schedule of Quantity

Estimated Cost:- Rs. 385090.00
 Earnest Money:- Rs. 7700.00
 Time:- Two Months

Name of work:- Construction of Kalkhar Galoo to Naundhar Upper Dibhri, Lower Dibhri Bhout Sidhyani road Km 0/0 to 4/600
Sub Head:- Construction of 900mm dia RCC Hume Pipe Culvert at RD. 4/200 alongwith both side wing walls

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge	7.02 Cubic metre	172.00	Rupees one hundred seventy two and paise nil only	Per cubic metre	1207.00
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	50.15 Cubic metre	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	14393.00
3	Providing and laying concrete mechanically mixed and vibrated P.C.C. M-10 (ten) grade for plain concrete in open foundations and plinths or similar works complete as per drawings and technical specification clauses 1202, 1203 and curing complete including the cost of form work and carriage of materials in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	13.02 Cubic metre	4770.00	Rupees four thousand seven hundred seventy and paise nil only	Per cubic metre	62105.00
4	Providing and laying concrete Mechanically mixed and vibrated mix 1:5:10 (one cement: five sand: ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts or as per the entire satisfaction and direction of Engineer-in-Charge.	60.34 Cubic metre	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	255842.00
5	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203 Plain cement concrete nominal mix 1:6:12 (one cement six sand twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge	2.59 Cubic metre	3090.00	Rupees three thousand ninety and paise nil only	Per cubic metre	8003.00
6	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7.00 metre	3550.00	Rupees three thousand five hundred fifty and paise nil only	Per Running metre	24850.00



Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
7	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diametre) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709.1204 3.7 including carriage of material and other other incidentals as per direction of Engineer-in-Charge.	15.00 Nos	287.00	Rupees two hundred eighty seven and paise nil only	Each	4305.00
8	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	13.70 Cubic metre	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	14385.00
					Total:-	385090.00

Draft schedule of quantity checked and approved for Rs. 385090 (Rupees three lac eighty five thousand ninety) only.

[Signature]
Executive Engineer,

HP, PWD, Division,

Nerchowk

[Signature]

9

DNI P.S. NO (390) for the year 2013-24.

Draft SCHEDULE OF QUANTITY

Estimated Cost: 99000.00
Earns Money: 2000.00
Time: One month

Name of work:- A/R and M/O Various road under Chakkar Sub-division, HPPWD Ner-chowk

Sub Head:- Up-gradation of Ner-chowk Ratti-Kalkhar road km. 0/0 to 13/300. under NABARD, Distt. Mandi (HP) and Up-gradation of Ner-chowk Ratti-Kalkhar road km. 0/0 to 13/300. under C.R.F., Distt. Mandi (HP) (Two Nos Revised DPR thereof)

Sr.No.	Description	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Job work for Peperation of Revised DPRs i/c Computer Typing and other necessary provision taken in estimate (four sets computerized along with binding) and submission of the same to higher office for approval. If any correction/ amendments has desired by the head office, the same may be corrected as desired as per direction of Executive Engineer Ner-chowk Division ,HPPWD Ner-chowk.	2 Nos Job	49500.00	Rupees Forty nine thousand five hundred only	Per Job	99000.00
					TOTAL	99000.00

Draft schedule of quantity approved for ₹ 99,000/- only.

Assistant Engineer,
Chakkar Sub-Division
HPPWD, Ner Chowk

Executive Engineer
Ner-chowk Division
HPPWD Ner-chowk

DNR S.No (176) for the year 2023-24

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Leda Ghagnoo road Km. 0/00 to 12/00. (SH:- Construction of Retaining wall at RD. 6/750 to 6/770).


Estimated Cost:- 329214.00

Earnest Money :- 6600.00

Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
			1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.		
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	70.70	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	299768.00
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	28.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	8036.00
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 Granular material and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	8.20	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	8610.00
Total						329214.00

Draft Schedule of quantity approved for ₹ 3,29,214/- only.


 Executive Engineer,
 HPPWD Division,
 HPPWD Nerchowk

④
DNIPB NO 445 for the year 2023-24.

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Gagal section)

(SH: - Hiring of JCB clearing of debris drains and dressing of berms etc.)

Estimated Cost Rs. 252000/-
Earnest Money Rs. 5100/-
Time: -One Month.

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	240 hours	1050.00	Rupees one Thousand fifty only	Per hours	252000.00
					Total:-	252000.00

Draft schedule of quantity approved for Rs. 2,52,000/-

Assistant Engineer,
Chakkar Sub Division,
HPPWD Nerchowk.

Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk.

(5)

DMFS.No (371) for the year 2023-24.

DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of link road from Damka-Samloun-Galma-PargiPul-Bag-Sidhkothi-Beri-Samlehar-Badhkari-Tarwai Km. 0/00 to 2/660. (SH:- Providing and laying WBM G-I in km. 2/00 to 2/600) Under OTMNP

Estimated Cost:- 467646.00

Earnest Money :- 9400.00

Time :-Three Months

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Preparation of sub grade by dressing to combor (Earth work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per HP.PWD specifications including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	2110.50	1.58	Rupees One and paise fifty eight only.	Per Square Metre	3335.00
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub-grade completed as per HP.PWD specifications including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	2110.50	1.00	Rupees One and zero only.	Per Square Metre	2111.00
3	Providing, laying, spreading and compacting stone aggregate of sizes 90-45mm (Ninety to forty five millimetres) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty by hundred Kilo Newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-I by manual means as per technical specification Clause 405 including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	211.05	2190.00	Rupees Two thousand one hundred ninety and paise zero only.	Per Cubic Metre	462200.00
					Total	467646.00

Draft schedule of quantity approved for 2,67,646/-

Executive Engineer,
HPPWD Division
Nerchowk

6

DNIT S.NO. 196 for the year 2023-24

Draft Schedule of Quantity

Estimated Cost:- 485654.00
Earnest Money:- 9700.00
Time:- Two Months

Name of work:- Construction of Kalkhar Galu to Noundhar Upper Dibhri, Lower Dibhri Bhout Sidhyani road km. 0/0 to 5/000.
Sub Head:- Providing and laying soling (WBM G-I) at RD. 3/830 to 4/490. Under OTMNP

Sr. No.	Description of item	Qty.	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In Words		
1	Providing, laying, spreading and compacting stone aggregates by mechanical means of 90mm to 45mm (Ninety millimetre to forty five millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-one hundred kilo newton) static roller in stages to proper grade and camber applying and brooming stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-1 (one) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	221.76 Cum.	2190.00	Rupees two thousand one hundred ninety and paise nil only.	Per cubic metre	485654.00
				Total:-		485654.00

Draft schedule of quantity checked and approved for Rs. 485654/- (Rupees four lac eighty five thousand five hundred fifty four) only.

Executive Engineer,
H.P.P.W.D. Division,
Nerchowk

7

DMPS-NO (455) for the year 2023-24

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Ratti section)

Estimated Cost Rs. 252000/-
Earnest Money Rs. 5100/-
Time: -One Month.

(SH: - Hiring of JCB clearing of debris drains and dressing of berms etc.)

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	240 hours	1050.00	Rupees one Thousand fifty only	Per hours	252000.00
Total:-						252000.00

Draft schedule of quantity approved for 2,52,000/-

Assistant Engineer,
Chakkar Sub Division,
HPPWD Nerchowk.

Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk.

8

DMF S.No. 498

DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of Ner Dhangu & link road from Chandyal to Sayah via SC Basti Sayahal km. 0/00 to 2/200. (SH:- Providing and laying cement concrete paver block in km. 2/262 to 2/300)

Estimated Cost:- 343024.00

Earnest Money :- 6900.00

Time :- Two Months

S.No	Description of Item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Construction of granular sub-base by providing well graded material, spreading in uniform layers with Tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, grading-I complete as per Technical Specification Clause 401 including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	22.28	1877.00	Rupees One thousand eight hundred seventy seven and paise zero only.	Per Cubic Metre	41820.00
2	Providing, laying, spreading and compacting stone aggregate of sizes 63-45mm (Sixty three to forty five millimetres) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty by hundred Kilo Newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-II by manual means as per technical specification Clause 405 including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	9.55	2240.00	Rupees Two thousand two hundred forty and paise zero only	Per Cubic Metre	21392.00
3	Providing and laying plain/reinforced cement concrete in foundation/substructure as per drawing and technical specification clause 802,803,1202 and 1203 PCC nominal mix 1:3:6 (One cement, three sand six graded stone aggregate) 40 mm (forty millimetre) nominal size of aggregates including carriage of material with in all leads and lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	12.73	4770.00	Rupees Four thousand seven hundred seventy and paise zero only.	Per Cubic Metre	60722.00
4	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm (fifty millimetre) thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, 80 mm (eighty millimetre) thick cement concrete paver block of M-30 (thirty) grade with approved colour, design pattern including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	127.30	1610.00	Rupees One thousand six hundred ten and paise zero only	Per square Metre	204953.00
5	Providing and laying plain/reinforced cement concrete in foundation/substructure as per drawing and technical specification clause 802,803,1202 and 1203 P.C.C nominal mix 1:2:4 (One cement, two sand, four graded stone aggregate) 40 mm (forty millimetre) nominal size of aggregates including carriage of material with in all leads, lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	2.45	5770.00	Rupees Five thousand seven hundred seventy and paise zero only.	Per Cubic Metre	14137.00
					Total	343024.00

Draft schedule of quantity approved for 343024/-

Executive Engineer,
HPWD Division
Nerchowk

19

DNIT S.NO. (259) For the year 2023-24

Draft Schedule of Quantity

Estimated Cost:- Rs. 122083.00
Earnest Money:- Rs. 2500.00
Time:- Two Months

Name of work:- Restoration of rain damages on Manjhyall Ghour Sardhwar road Km. 0/000 to 13/000.
Sub Head:- Construction of Retaining wall at R.D. 1/480 to 1/483.50.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.45 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	2712.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1.5.10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	26.78 Cum	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	113547.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	3.36 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	3528.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	8.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	2296.00
					Total	122083.00

Draft schedule of quantity approved for Rs. 122083/- (Rupees one lac twenty two thousand eighty three) only.

Executive Engineer,
H.P.W.D. Division,
Nerchowki

10

Draft Schedule of quantity *DNI No 38 for F.Y. 2023-24.*

Name of work :- A/R & M/O SLBSGMC&H at Nerchowk Distt. Mandi (HP) SH:- Distempering with OBD in Hospital building
(Block-B) Third floor and fourth floor.

Estimated Amount-	489756.00
Earnest money -	9800.00
Time -	One month
Total amount with all taxes Including GST in Rs. P.	

Sl. No.	Item Description	Quantity	Rate	Units	Total amount with all taxes Including GST in Rs. P.
			Figure	Word	
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	110.41	14.62	Rupees Fourteen and Paise SixtyTwo Only	1614.00
2	Providing and applying white cement based putty(Asian wall putty true care/equivalent) of average thickness 1 mm, over the plastered wall surface to prepare the surface even and smooth complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	110.41	117.25	Rupees One Hundred Seventeen and Paise TwentyFive Only	12946.00
3	Distempering on ceiling/sloping surfaces with oil bound washable distemper(Asian tractor uno OBD/equivalent) to give an even shade : Old work (one coat) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	1710.52	47.25	Rupees FourtySeven and Paise TwentyFive Only	80822.00
4	Extra over every sub sequent coat of distempering with oil bound washable distemper(Asian tractor uno OBD/equivalent) (On ceiling/sloping surfaces) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	1710.52	41.60	Rupees FourtyOne and Paise Sixty Only	71158.00
5	Distempering on walls surfaces with oil bound washable distemper(Asian tractor uno OBD/equivalent) to give an even shade : Old work (one coat) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	4135.84	41.85	Rupees FourtyOne and Paise EightyFive Only	173085.00
6	Extra over every sub sequent coat of distempering with oil bound washable distemper(Asian tractor uno OBD/equivalent) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	4135.84	36.30	Rupees ThirtySix and Paise Thirty Only	150131.00
Total					489756.00

Draft Schedule of quantity approved for Rs. 489756.00/- only


 Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk
fnv

Draft Schedule of quantity DNT No. 40 for F.V. 2022-24

Name of work- Addition and alteration work in PRA building in SLBS/GMC&H in Nerchowk Distt. Mandi. (SI:- C/o ward robs in PRA second floor male and female dormetry) Job no.1

Estimated Amount- 376639.00
 Earnest money - 7600.00
 Time - One month

Sl. No.	Item Description	Quantity	Rate		Units	Total amount with all taxes including GST in Rs.
			Figure	Word		
1	Providing and fixing Action TESA HDHMR board IS: 14587:1998 marked, with both side balancing lamination Grade-I (exterior grade) in shelves with screws and fittings wherever required, edges to be sealed with PVC edge bending tape 1.00 mm thick of approved brand (fittings to be paid separately). Pre-laminated with balancing lamination both side Board 8 mm thick confirming to IS:14587 complete including all lead and lifts and as per direction of Engineer-in-Charge.	48.00	1277.42	Rupees One Thousand Two Hundred SeventySeven and Paise FortyTwo Only	Sqm	61316.00
2	Providing and fixing Action TESA HDHMR board IS: 14587:1998 marked, Both side balancing lamination Grade-I (exterior grade) in shelves with screws and fittings wherever required, edges to be sealed with PVC edge bending tape 1.00 mm thick of approved brand (fittings to be paid separately). Pre-laminated with balancing lamination both side Board 18 mm thick confirming to IS:14587 complete including all lead and lifts and as per direction of Engineer-in-Charge.	72.00	2144.25	Rupees Two Thousand One Hundred FortyFour and Paise TwentyFive Only	Sqm	154386.00
3	Providing and fixing Action TESA HDHMR board IS: 14587:1998 marked, Balancing lamination one side and Plain on other side Grade-I (exterior grade) in shelves with screws and fittings wherever required, edges to be sealed with PVC edge bending tape 1.00 mm thick of approved brand (fittings to be paid separately). Pre-laminated with Balancing lamination one side and Plain on other side Board 18 mm thick confirming to IS:14587 complete including all lead and lifts and as per direction of Engineer-in-Charge.	24.00	2059.90	Rupees Two Thousand FiftyNine and Paise Ninety Only	Sqm	49438.00
4	Providing & Fixing Century Ply LUCIDA decorative high pressure laminated sheet of plain / wood grain in gloss / matt/ suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S, including cost of adhesive of approved quality. 1 mm thick complete including all lead and lifts and as per direction of Engineer-in-Charge.	24.00	1154.50	Rupees One Thousand One Hundred FiftyFour and Paise Fifty Only	Sqm	27708.00
5	Providing and fixing bright /matt finished handles of approved quality & make with necessary screws etc all complete. 100 mm (Evolve) complete including carriage of material with in all lead and lifts and other incidentals as per the direction of the Engineer-in-Charge.	30.00	179.95	Rupees One Hundred SeventyNine and Paise NinetyFive Only	Each	5399.00
6	Providing and fixing Dorset soft Close 3D Adjustable Hing IGSC3D0C Soft close Clip On Hinge 0 Crank with 3D mounting Plate with screws etc. complete including all lead and lifts and as per direction of Engineer-in-Charge :	60.00	455.85	Rupees Four Hundred FiftyFive and Paise EightyFive Only	P.pair	27351.00
7	Providing and fixing Dorset soft Close 3D Adjustable Hing IGSC3D0C Soft close Clip On Hinge 0 Crank with 3D mounting Plate with screws etc. complete including all lead and lifts and as per direction of Engineer-in-Charge :	60.00	482.10	Rupees Four Hundred EightyTwo and Paise Ten Only	P.pair	28926.00
8	Providing and fixing bright /matt finished handles of approved quality & make with necessary screws etc all complete. 200 mm (Evolve) complete including carriage of material with in all lead and lifts and other incidentals as per the direction of the Engineer-in-Charge.	30.00	305.70	Rupees Three Hundred Six and Paise Seventy Only	Each	9201.00
9	Providing and fixing dorset ball bearing full extension slide 46mm zinc(45kg),ball bearing zinc 46-500mm ISBB500 make with necessary screws etc.all complete including all lead and lifts and as per direction of Engineer-in-charge.	15.00	610.91	Rupees Six Hundred Ten and Paise NinetyOne Only	P.pair	9164.00
10	Providing and fixing curtain rods of Stainless steel SS grade 304, 25 mm dia 1.20mm thick, with SS brackets fixed with screws and wooden plugs, etc., wherever necessary complete including all lead and lifts and as per direction of Engineer-in-charge.	15.00	250.00	Rupees Two Hundred Fifty Only	Prmt	3750.00
					Total	376639.00

Draft Schedule of quantity approved for Rs. 376639.00/- only

Executive Engineer
 Nerchowk Division
 HBPWD Nerchowk

12

DNIT Sr. No 513.

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Nerchowk section)

(SH: - Hiring of JCB clearing of debris drains and dressing of berms etc.)

Estimated Cost Rs. 252000/-
Earnest Money Rs. 5100/-
Time: -One Month.

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	240 hours	1050.00	Rupees one Thousand fifty only	Per hours	252000.00
Total:-						252000.00

Draft schedule of quantity approved for Rs. 2,52,000/-

Assistant Engineer,
Chakkar Sub Division,
HPPWD Nerchowk.

Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk.

13

DNI P S NO (348) for May 2023-24.

DRAFT SCHEDULE OF QUANTITY

Name of work:- RRD on Ratti Kalkhar road km. 0/00 to 10/00. (SH:- C/O P.C.C. Retaining wall at RD. 6/520 to 6/540)

Estimated Cost:- 434539.00

Earnest Money :- 8700.00

Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
			1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.		
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	91.56	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	388214.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 Granular material and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	23.40	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	24570.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	36.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	10332.00
					Total	434539.00

Draft Schedule of Quantity approved for 2,434,539/-

Executive Engineer,
HPPWD Division,
HPPWD Nerchowk

14

Draft Schedule of quantity

Draft schedule for FY 2023-24

o/c

NAME OF WORK:- A/R & M/O SLBSGMC&H at Nerchowk Distt. Mandi (HP) SH:- Distemping with OBD in Hospital building (Block-A)Fifth floor and sixth floor.

Estimated Amount- 486407.00
Earnest money - 9800.00
Time - One month

Sl. No.	Item Description	Quantity	Rate		Units	Total amount with all taxes Including GST in Rs. P.
			Figure	Word		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as per all carriage,lead and lifts and as per direction of Engineer in charge.	116.25	14.62	Rupees Fourteen and Paise SixtyTwo Only	PSqm	1700.00
2	Providing and applying white cement based putty(Asian wall putty true care/equivalent) of average thickness 1 mm, over the plastered wall surface to prepare the surface even and smooth complete as per all carriage,lead and lifts and as per direction of Engineer in charge.	116.25	117.25	Rupees One Hundred Seventeen and Paise TwentyFive Only	PSqm	13630.00
3	Distemping on ceiling/sloping surfaces with oil bound washable distemper(Asian tractor uno OBD/equivalent) to give an even shade : Old work (one coat) complete as per all carriage,lead and lifts and as per direction of Engineer in charge.	1570.41	47.25	Rupees FourtySeven and Paise TwentyFive Only	PSqm	74202.00
4	Extra over every sub sequent coat of distemping with oil bound washable distemper(Asian tractor uno OBD/equivalent) (On ceiling/sloping surfaces)complete as per all carriage,lead and lifts and as per direction of Engineer in charge.	1570.41	41.60	Rupees FourtyOne and Paise Sixty Only	PSqm	65329.00
5	Distemping on walls surfaces with oil bound washable distemper(Asian tractor uno OBD/equivalent) to give an even shade : Old work (one coat) complete as per all carriage,lead and lifts and as per direction of Engineer in charge.	4242.43	41.85	Rupees FourtyOne and Paise EightyFive Only	PSqm	177546.00
6	Extra over every sub sequent coat of distemping with oil bound washable distemper(Asian tractor uno OBD/equivalent) complete as per all carriage,lead and lifts and as per direction of Engineer in charge.	4242.43	36.30	Rupees ThirtySix and Paise Thirty Only	PSqm	154000.00

Total 486407.00

Draft Schedule of quantity approved for Rs. 486407.00/-

g/c
Executive Engineer
Nerchowk Division
HPPWD Nerchowk
Jus

15

Draft Schedule of quantity

D/NIT no 35 for F.Y. 2023-24

o/c

Name of work :- A/R & M/O SLB5GMC&H at Nerchowk Distt. Mandi (HP) SH:- Distempering with OBD in Hospital building
(Block-B)Ground floor.Estimated Amount-
Earnest money -
Time -313412.00
6300.00
One month

Sl. No.	Item Description	Quantity	Rate		Units	Total amount with all taxes including GST in Rs. P.
			Figure	Word		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	74.94	14.62	Rupees Fourteen and Paise SixtyTwo Only	PSqm	1096.00
2	Providing and applying white cement based putty(Asian wall putty true care/equivalent) of average thickness 1 mm, over the plastered wall surface to prepare the surface even and smooth complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	74.94	117.25	Rupees One Hundred Seventeen and Paise TwentyFive Only	PSqm	8787.00
3	Distempering on ceiling/sloping surfaces with oil bound washable distemper(Asian tractor uno OBD/equivalent) to give an even shade : Old work (one coat) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	995.40	47.25	Rupees FourtySeven and Paise TwentyFive Only	PSqm	47033.00
4	Extra over every sub sequent coat of distempering with oil bound washable distemper(Asian tractor uno OBD/equivalent) (On ceiling/sloping surfaces)complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	995.40	41.60	Rupees FourtyOne and Paise Sixty Only	PSqm	41409.00
5	Distempering on walls surfaces with oil bound washable distemper(Asian tractor uno OBD/equivalent) to give an even shade : Old work (one coat) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	2752.24	41.85	Rupees FourtyOne and Paise EightyFive Only	PSqm	115181.00
6	Extra over every sub sequent coat of distempering with oil bound washable distemper(Asian tractor uno OBD/equivalent) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	2752.24	36.30	Rupees ThirtySix and Paise Thirty Only	PSqm	99906.00
Total						313412.00

Draft Schedule of quantity approved for Rs. 313412.00/- only

9/c
Executive Engineer
Nerchowk Division
HPPWD Nerchowk

(16)

Draft No (527)

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Ratti to Randhara road Km. 0/0 to 9/00.
Repair of 6 mtr. RCC span culvert at RD. 8/220)

(SH:- Estimated Cost:- Rs. 234725.00
Earnest Money :- Rs. 4700.00
Time :- Three Months

S. No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	2	3	4	5	6	7
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	18.90	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	5424.00
2	Providing and laying concrete mechanically mixed and vibrated mix 1:3:6 (one cement: three sand: six graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in abutments, open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	39.32	4770.00	Rupees Four thousand seven hundred seventy and paise zero only.	Per Cubic Metre	187556.00
3	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600 mm (Six hundred millimetre) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 including carriage of material within all leads, lifts/depths or as per the entire satisfaction and direction of Engineer-in-Charge.	32.90	1268.85	Rupees One thousand two hundred sixty eight and paise eighty five only.	Per Cubic Metre	41745.00
					Total	234725.00

Draft schedule of quantity approved for Rs. 2,34,725/-

Executive Engineer,
HPPWD Division,
Nerchowk

(17)

DM P.S. NO (520)

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages caused due to laying of optical cable on Ratti Kalkhar road km. 0/0 to 10/00.
(SH:- Construction of PCC Retaining wall at RD. 2/355 to 2/366) Deposit work

Estimated Cost:- 289333.00

Earnest Money :- 5800.00

Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P.			
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	30.91	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	8871.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	62.37	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	264449.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	8.69	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	9125.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge.	24.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	6888.00
					Total	289333.00

Draft schedule of quantity approved for Rs 2,89,333/-

Executive Engineer,
HPPWD Division,
HPPWD Nerchowki

(18)

Draft Schedule of quantity

D.M.T. no. 36 for F.Y. 2023-24

Name of work- Routine day to day repair & maintenance of non-residential buildings of SLBSGMC&H at Nerchowk (SH:- Providing and fixing MS ladder and working platform in various ducts in hospital building(Block-A&Block -B) in SLBSGMC&H Nerchowk)

Estimated Amount- 293355.00
Earnest money - 5900.00
Time - One month

Sl. No.	Item Description	Quantity	Rate	Units	Total amount with all taxes including GST in Rs.
			Figure	Word	
1	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete of approved brand including all lead and lift and as per direction of Engineer-in-charge.	2203.19	127.54	Rupees One Hundred TwentySeven and Paise FiftyFour Only	280995.00
2	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade two or more coat on new work complete including all lead, lifts and all incidental and as per direction of Engineer in charge.	150.00	82.40	Rupees EightyTwo and Paise Fourty Only	12360.00
Total					293355.00

Draft Schedule of quantity approved for Rs. 293355.00/- only


Executive Engineer
Nerchowk Division
HPPWD Nerchowk

19

Draft Schedule of quantity

DINIT no 37 for F.Y. 2023-24

0/6


Name of work :- A/R & M/O SLBSGMC&H at Nerchowk Distt. Mandi (HP) SH:- Distempering with OBD in Hospital building
(Block-B) First floor and second floor.

Estimated Amount- 497613.00
Earnest money - 9950.00
Time - One month

Sl. No.	Item Description	Quantity	Rate		Units	Total amount with all taxes including GST in Rs. P.
			Figure	Word		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	129.30	14.62	Rupees Fourteen and Paise SixtyTwo Only	PSqm	1890.00
2	Providing and applying white cement based putty(Asian wall putty true care/equivalent) of average thickness 1 mm, over the plastered wall surface to prepare the surface even and smooth complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	129.30	117.25	Rupees One Hundred Seventeen and Paise TwentyFive Only	PSqm	15160.00
3	Distempering on ceiling/sloping surfaces with oil bound washable distemper(Asian tractor uno OBD/equivalent) to give an even shade : Old work (one coat) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	1872.51	47.25	Rupees FourtySeven and Paise TwentyFive Only	PSqm	88476.00
4	Extra over every sub sequent coat of distempering with oil bound washable distemper(Asian tractor uno OBD/equivalent) (On ceiling/sloping surfaces)complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	1872.51	41.60	Rupees FourtyOne and Paise Sixty Only	PSqm	77896.00
5	Distempering on walls surfaces with oil bound washable distemper(Asian tractor uno OBD/equivalent) to give an even shade : Old work (one coat) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	4020.36	41.85	Rupees FourtyOne and Paise EightyFive Only	PSqm	168252.00
6	Extra over every sub sequent coat of distempering with oil bound washable distemper(Asian tractor uno OBD/equivalent) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	4020.36	36.30	Rupees ThirtySix and Paise Thirty Only	PSqm	145939.00

Total 497613.00

Draft schedule of quantity approved for Rs. 497613.00/-


Executive Engineer
Nerchowk Division
HPPWD Nerchowk

20

DNIT No. 42 for F.Y. 2023-24

Draft Schedule of quantity

Name of work :- A/R & M/O SLB5GMC&H at Nerchowk Distt. Mandi (HP) SH:- Distempering with OBD in Hospital building
(Block-C) Ground floor and first floor .

Estimated Amount- 465249.00
Earnest money - 9300.00
Time - One month

Sl. No.	Item Description	Quantity	Rate		Units	Total amount with all taxes including GST in Rs. P.
			Figure	Word		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	111.03	14.62	Rupees Fourteen and Paise SixtyTwo Only	PSqm	1623.00
2	Providing and applying white cement based putty(Asian wall putty true care/equivalent) of average thickness 1 mm, over the plastered wall surface to prepare the surface even and smooth complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	111.03	117.25	Rupees One Hundred Seventeen and Paise TwentyFive Only	PSqm	13018.00
3	Distempering on ceiling/sloping surfaces with oil bound washable distemper(Asian tractor uno OBD/equivalent) to give an even shade : Old work (one coat) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	1563.51	47.25	Rupees FourtySeven and Paise TwentyFive Only	PSqm	73876.00
4	Extra over every sub sequent coat of distempering with oil bound washable distemper(Asian tractor uno OBD/equivalent) (On ceiling/sloping surfaces) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	1563.51	41.60	Rupees FourtyOne and Paise Sixty Only	PSqm	65042.00
5	Distempering on walls surfaces with oil bound washable distemper(Asian tractor uno OBD/equivalent) to give an even shade : Old work (one coat) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	3988.36	41.85	Rupees FourtyOne and Paise EightyFive Only	PSqm	166913.00
6	Extra over every sub sequent coat of distempering with oil bound washable distemper(Asian tractor uno OBD/equivalent) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	3988.36	36.30	Rupees ThirtySix and Paise Thirty Only	PSqm	144777.00

Total 465249.00

Draft Schedule of quantity approved for Rs. 465249.00/- only

g/c
Executive Engineer
Nerchowk Division
HPPWD Nerchowk

(21)

DNI 95-NO (522)

Draft Schedule of Quantity

Estimated Cost:- Rs. 316531.00
Earnest Money:- Rs. 6400.00
Time:- Two Months

Name of work:- Restoration of rain damages on Ratti Meramasit Leda road Km. 0/000 to 14/580
Sub Head:- Construction of Retaining wall at R.D. 7/010 to 7/025.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	29.85 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	8567.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement five sand ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	65.85 Cum	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	279204.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	17.55 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	18428.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diametre) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	36.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	10332.00
					Total	316531.00

Draft schedule of quantity approved for 2 316531.00

Executive Engineer,
H.P.P.W.D. Division,
Nerchowk

22

531
DNIT S.NO. For the year 2023-24

Draft Schedule of Quantity

Estimated Cost:- 242696.00
Earnest Money:-Rs. 4900.00
Time:- One Month

Name of work:- Restoration of rain damages on Malthehar by pass road km. 0/00 to 1/045
Sub Head:- Construction of Breast wall at R.D. 0/730 to 0/745.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Excavation in soil in hilly area by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	21.60 Cum.	172.00	Rupees one hundred seventy two and paise nil only	Per cubic metre	3715.00
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	19.35 Cum.	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	5553.00
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	53.70 Cum.	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	227688.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	20.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	5740.00
					Total	242696.00

Draft schedule of quantity approved for Rs. 242696/- only


Executive Engineer,
H.P.P.W.D. Division,
Nerchowk

23

DNIP S.No. 530 for the year 2023-24

Draft Schedule of Quantity

Estimated Cost:- Rs. 264649.00
Earnest Money:- Rs. 5300.00
Time:- Two Months

Name of work:- Restoration of rain damages on Mahotla to Karehari road km. 0/00 to 2/000.
Sub Head:- Construction of Retaining wall at R.D.0/640 to 0/652.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	23.88 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	6854.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	55.97 Cum	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	237313.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	14.04 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	14742.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	20.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	5740.00
					Total	264649.00

Draft schedule of quantity approved for Rs. 2,64,649/-

Executive Engineer,
H.P.P.W.D. Division,
Nerchowk

Draft Schedule of quantity

DMD No 42 For F.Y. 2023-24

Name of work :- A/R & M/O SLBSGMC&H at Nerchowk Distt. Mandi (HP) SH:- Distempering with OBD in Hospital building
(Block-C) Second floor and third floor.Estimated Amount- 441637.00
Earnest money - 8800.00
Time - One month

24

Sl. No.	Item Description	Quantity	Rate	Units	Total amount with all taxes including GST in Rs. P.
			Figure	Word	
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	105.12	14.62	Rupees Fourteen and Paise SixtyTwo Only	PSqm 1537.00
2	Providing and applying white cement based putty(Asian wall putty true care/equivalent) of average thickness 1 mm, over the plastered wall surface to prepare the surface even and smooth complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	105.12	117.25	Rupees One Hundred Seventeen and Paise TwentyFive Only	PSqm 12325.00
3	Distempering on ceiling/sloping surfaces with oil bound washable distemper(Asian tractor uno OBD/equivalent) to give an even shade : Old work (one coat) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	1598.42	47.25	Rupees FourtySeven and Paise TwentyFive Only	PSqm 75525.00
4	Extra over every sub sequent coat of distempering with oil bound washable distemper(Asian tractor uno OBD/equivalent) (On ceiling/sloping surfaces) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	1598.42	41.60	Rupees FourtyOne and Paise Sixty Only	PSqm 66494.00
5	Distempering on walls surfaces with oil bound washable distemper(Asian tractor uno OBD/equivalent) to give an even shade : Old work (one coat) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	3656.51	41.85	Rupees FourtyOne and Paise EightyFive Only	PSqm 153025.00
6	Extra over every sub sequent coat of distempering with oil bound washable distemper(Asian tractor uno OBD/equivalent) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	3656.51	36.30	Rupees ThirtySix and Paise Thirty Only	PSqm 132731.00

Draft Schedule of quantity approved for Rs. 441637.00 only

Total 441637.00

g/c
Executive Engineer
Nerchowk Division
HPPWD Nerchowk

Draft Schedule of quantity

D.N.T.No. 43 For. F.Y. 2023-24

61C

Name of work- Addition and alteration work in PRA building in SLBSGMC&H in Nerchowk Distt. Mandi.(SH:- C/o ward robs in PRA second floor male and female doormetry) Job no.2

Estimated Amount- 394965.00
Earnest money - 7900.00
Time - One month

29

Sl. No.	Item Description	Quantity	Rate		Units	Total amount with all taxes including GST in Rs. p.
			Figure	Word		
1	Providing and fixing Action TESA HDHMR board IS: 14587:1998 marked, with both side balancing lamination Grade-I (exterior grade) in shelves with screws and fittings wherever required, edges to be sealed with PVC edge bending tape 1.00 mm thick of approved brand (fittings to be paid separately).Pre-laminated with balancing lamination both side Board 8 mm thick confirming to IS:14587 complete including all lead and lifts and as per direction of Engineer-in-Charge.	54.40	1277.42	Rupees One Thousand Two Hundred SeventySeven and Paise FourtyTwo Only	Sqm	69492.00
2	Providing and fixing Action TESA HDHMR board IS: 14587:1998 marked, Both side balancing lamination Grade-I (exterior grade) in shelves with screws and fittings wherever required, edges to be sealed with PVC edge bending tape 1.00 mm thick of approved brand (fittings to be paid separately).Pre-laminated with balancing lamination both side Board 18 mm thick confirming to IS:14587 complete including all lead and lifts and as per direction of Engineer-in-Charge.	81.60	2144.25	Rupees Two Thousand One Hundred FourtyFour and Paise TwentyFive Only	Sqm	174971.00
3	Providing and fixing Action TESA HDHMR board IS: 14587:1998 marked, Balancing lamination one side and Plain on other side Grade-I (exterior grade) in shelves with screws and fittings wherever required, edges to be sealed with PVC edge bending tape 1.00 mm thick of approved brand (fittings to be paid separately).Pre-laminated with Balancing lamination one side and Plain on other side Board 18 mm thick confirming to IS:14587 complete including all lead and lifts and as per direction of Engineer-in-Charge.	27.20	2059.90	Rupees Two Thousand FiftyNine and Paise Ninety Only	Sqm	56029.00
4	Providing & Fixing Century Ply LUCIDA decorative high pressure laminated sheet of plain / wood grain in gloss / matt/ suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S, including cost of adhesive of approved quality.1 mm thick complete Including all lead and lifts and as per direction of Engineer-in-Charge.	27.20	1154.50	Rupees One Thousand One Hundred FiftyFour and Paise Fifty Only	Sqm	31402.00
5	Providing and fixing bright /matt finished handles of approved quality & make with necessary screws etc all complete. 100 mm (Evolve) complete including carriage of material with in all lead and lifts and other incidentals as per the direction of the Engineer-in Charge.	34	179.95	Rupees One Hundred SeventyNine and Paise NinetyFive Only	Each	6118.00
6	Providing and fixing Dorset soft Close 3D Adjustable Hing IGSC3D0C Soft close Clip On Hinge 0 Crank with 3D mounting Plate with screws etc. complete including all lead and lifts and as per direction of Engineer-in-Charge :	34	455.85	Rupees Four Hundred FiftyFive and Paise EightyFive Only	P.pair	15499.00
7	Providing and fixing Dorset soft Close 3D Adjustable Hing IGSC3D0C Soft close Clip On Hinge 0 Crank with 3D mounting Plate with screws etc. complete including all lead and lifts and as per direction of Engineer-in-Charge :	34	482.10	Rupees Four Hundred EightyTwo and Paise Ten Only	P.pair	16391.00
8	Providing and fixing bright /matt finished handles of approved quality & make with necessary screws etc all complete. 200 mm (Evolve) complete including carriage of material with in all lead and lifts and other incidentals as per the direction of the Engineer-in Charge.	34	306.70	Rupees Three Hundred Six and Paise Seventy Only	Each	10428.00
9	Providing and fixing dorset ball bearing full extension slide 46mm zinc(45kg).ball bearing zinc 46-500mm ISBB500 make with necessary screws etc all complete.including all lead and lifts and as per direction of Engineer-in-charge.	17	610.91	Rupees Six Hundred Ten and Paise NinetyOne Only	P.pair	10385.00
10	Providing and fixing curtain rods of Stainless steel SS grade 304, 25 mm dia 1.20mm thick , with SS brackets fixed with screws and wooden plugs, etc., wherever necessary complete including all lead and lifts and as per direction of Engineer-in-charge.	17.00	250.00	Rupees Two Hundred Fifty Only	Prmt	4250.00
					Total	394965.00

Draft scheduled of quantity approved for Rs. 394965.00/- only


 Executive Engineer
 Nerchowk Division
 HPWD Nerchowk

26

DNIP S.NO. 488 for the year 2023-24.

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages due to laying of optical fibre cable on Ratti Dharwan Grencha road km. 0/00 to 6/00. (SH:- Providing and laying interlocking paver blocks at RD. 1/044 to 1/117)

Estimated Cost:- 486593.00
Earnest Money :- 9800.00
Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Providing and laying plain/reinforced cement concrete in foundation/substructure as per drawing and technical specification clause 802.803.1202 and 1203 P.C.C nominal mix 1:2:4 (One cement: two sand: four graded stone aggregate) 40 mm (forty millimetre) nominal size of aggregates including carriage of material with in all leads, lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	4.38	5810.00	Rupees Five thousand eight hundred ten and paise zero only.	Per Cubic Metre	25448.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203, 1:4:8 (one cement: four sand: eight graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of materials with in all leads, lifts and other incidentials and as per the entire satisfaction and direction of Engineer-in-Charge	22.49	4408.00	Rupees Four thousand four hundred eight and paise zero only.	Per cubic Metre	99136.00
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm (fifty millimetre) thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm (eighty millimetre) thick cement concrete paver block of M-30 (thirty) grade with approved colour, design pattern including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	224.85	1610.00	Rupees One thousand six hundred ten and paise zero only	Per square Metre	362009.00
Total						486593.00

Draft schedule of quantity approved for ₹ 4,86,593/-

Executive Engineer,
HPPWD Division
Nerchowk

27

Draft Schedule of quantity DNIT No 44 for F.Y. 2023-24

Name of work :- A/R & M/O SLBSGMC&H at Nerchowk Distt. Mandi (HP) SH:- Distemping with OBD in Hospital building (Block-C)Fourth floor and sixth floor.

Estimated Amount- 438247.00
Earnest money - 8800.00
Time - One month

Sl. No.	Item Description	Quantity	Rate		Units	Total amount with all taxes Including GST in Rs. P.
			Figure	Word		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	104.45	14.62	Rupees Fourteen and Paise SixtyTwo Only	PSqm	1527.00
2	Providing and applying white cement based putty(Asian wall putty true care/equivalent) of average thickness 1 mm, over the plastered wall surface to prepare the surface even and smooth complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	104.45	117.25	Rupees One Hundred Seventeen and Paise TwentyFive Only	PSqm	12247.00
3	Distemping on ceiling/sloping surfaces with oil bound washable distemper(Asian tractor uno OBD/equivalent) to give an even shade : Old work (one coat) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	1522.26	47.25	Rupees FourtySeven and Paise TwéntyFive Only	PSqm	71927.00
4	Extra over every sub sequent coat of distemping with oil bound washable distemper(Asian tractor uno OBD/equivalent) (On ceiling/sloping surfaces)complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	1522.26	41.60	Rupees FourtyOne and Paise Sixty Only	PSqm	63326.00
5	Distemping on walls surfaces with oil bound washable distemper(Asian tractor uno OBD/equivalent) to give an even shade : Old work (one coat) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	3700.83	41.85	Rupees FourtyOne and Paise EightyFive Only	PSqm	154880.00
6	Extra over every sub sequent coat of distemping with oil bound washable distemper(Asian tractor uno OBD/equivalent) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	3700.83	36.30	Rupees ThirtySix and Paise Thirty Only	PSqm	134340.00
Total						438247.00

Draft Schedule of quantity approved for Rs. 4 38 247.00 only

Executive Engineer
Nerchowk Division
HPPWD Nerchowk

Draft Schedule of quantity

DNIT/2015 For E.Y. 2023-24

Name of work :- A/R & M/O SLBSGMC&H at Nerchowk Distt. Mandi (HP) SH:- Distempering with OBD in Hospital building
(Block-C)Fifth floor.Estimated Amount-
Earnest money -
Time -

268834.00

5400.00

One month

28

Sl. No.	Item Description	Quantity	Rate		Units	Total amount with all taxes including GST in Rs. P.
			Figure	Word		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	64.23	14.62	Rupees Fourteen and Paise SixtyTwo Only	PSqm	939.00
2	Providing and applying white cement based putty(Asian wall putty true care/equivalent) of average thickness 1 mm, over the plastered wall surface to prepare the surface even and smooth complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	64.23	117.25	Rupees One Hundred Seventeen and Paise TwentyFive Only	PSqm	7531.00
3	Distempering on ceiling/sloping surfaces with oil bound washable distemper(Asian tractor uno OBD/equivalent) to give an even shade ; Old work (one coat) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	873.73	47.25	Rupees FourtySeven and Paise TwentyFive Only	PSqm	41284.00
4	Extra over every sub sequent coat of distempering with oil bound washable distemper(Asian tractor uno OBD/equivalent) (On ceiling/sloping surfaces)complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	873.73	41.60	Rupees FourtyOne and Paise Sixty Only	PSqm	36347.00
5	Distempering on walls surfaces with oil bound washable distemper(Asian tractor uno OBD/equivalent) to give an even shade ; Old work (one coat) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	2338.24	41.85	Rupees FourtyOne and Paise EightyFive Only	PSqm	97855.00
6	Extra over every sub sequent coat of distempering with oil bound washable distemper(Asian tractor uno OBD/equivalent) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	2338.24	36.30	Rupees ThirtySix and Paise Thirty Only	PSqm	84878.00

Total

268834.00

Draft Schedule of quantity approved for Rs. 268834.00/- only

Executive Engineer
Nerchowk Division
HPWD Nerchowk

29

DRAFT SCHEDULE OF QUANTITY


DNIT No. 47 for F. Y. 2023-24

Name of work :- Construction of hostel for MBBS students in the campus of SLBSGMC&H Distt. Mandi(H.P.). (SH:- Preparation of detail estimate and DNIT).

Estimated cost Rs. 1,32,052/-
Earnest Money Rs. 2700/-
Time:- one month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Job work for preparation of detail estimate and DNIT i/c computer typing and other necessary provision taken in estimate and DNIT as per approved drawings and specification (four set computerized along with binding) and submission of the same to higher office for approval, If any correction/amendments has desired by the head office, the same may be corrected as desired as per direction of Executive engineer Nerchowk Division, HPPWD Nerchowk along with submission of soft copy of the approved estimate and DNIT in the undersigned office.	1no	1,32,052.00	Rupees One Lakh Thirty Two Thousand Fifty Two Only	Per Job	1,32,052.00
				Total		1,32,052.00

Draft Schedule of quantity approved for Rs. 132052.00/- only


ASSISTANT ENGINEER
HPPWD (CIVIL) SUB DIVISION
SLBSGMC&H NERCHOWK


Executive Engineer,
Nerchowk Division
HP. PWD, Nerchowk

30

DNIP S. NO 475 for the years 2023-24.

DRAFT SCHEDULE OF QUANTITY

Name of work: - A/R & M/O various roads under Chakkar Sub Division, H.P.PWD, Nerchowk. (Gagal Section)

Estimated Cost Rs.99000/-
Earnest Money Rs. 2000/-
Time: -Two Month

(SH: - Hiring of Tractor with trolley for carriage of muck/debris and shifting of material etc.

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of tractor with trolley with hydraulic lift system for carriage of material to different sites of work with in all leads & lifts and to the entire satisfaction of the Engineer-in-Charge. The tractor should work minimum 8 hours from 9 AM to 5 PM daily, any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the tractor owner which shall have to be fully compensated by him in all cases. The expenditure for fuel, lubricants, driver and repair work shall have to be borne by the tractor owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in Charge.	60 days	1650.00	Rupees one thousand Six Hundred Fifty only	Per Days	99000.00
					Total -	99000.00

Draft schedule of quantity approved for ₹ 99,000/-

[Signature]
Assistant Engineer,
Chakkar Sub Division,
HPPWD Nerchowk.

[Signature]
Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk.

31

D.M.P.S. NO. 530

Draft Schedule of Quantity

Estimated Cost:- 287743.00
Earnest Money:-Rs. 5800.00
Time:- One Month

Name of work:- Restoration of rain damages on Ratti Meramasit Leda road Km. 0/000 to 14/580.
Sub Head:- Construction of Breast wall at R.D. 7/012 to 7/032.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	22.40 Cum.	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	6429.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	65.40 Cum.	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	277296.00
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	14.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	4018.00
					Total	287743.00

Draft schedule of quantity approved for Rs. 2,87,743/-

Executive Engineer,
H.P.P.W.D. Division,
Nerchowk

32

DNIP9-NO272

Draft Schedule of Quantity

Estimated Cost:- 407001.00
Earnest Money:-Rs. 8200.00
Time:- One Month

Name of work:- Restoration of rain damages on Manjhyali Ghour Sardhwar upto vill. Batahan road Km. 0/000 to 13/000.
Sub Head:- Construction of Breast wall at R.D. 7/012 to 7/032.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Excavation in soil in hilly area by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	61.00 Cum.	172.00	Rupees one hundred seventy two and paise nil only	Per cubic metre	10492.00
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	16.20 Cum.	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	4649.00
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	90.66 Cum.	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	384398.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	26.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	7462.00
					Total	407001.00

Draft schedule of quantity approved for 2,40,700/-

Executive Engineer
H.P.P.W.D. Division,
Nerchowk

33

Draft Schedule of quantity *DNT No 39 for F.Y. 2023-24*

Name of work :- A/R & M/O SLBSGMC&H at Nerchowk Distt. Mandi (HP) SH:- Distempering with OBD in Hospital building (Block-B) Fifth floor and sixth floor.

Estimated Amount- 497753.00
Earnest money - 10000.00
Time - One month

Sl. No.	Item Description	Quantity	Rate		Units	Total amount with all taxes Including GST in Rs. P.
			Figure	Word		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	126.78	14.62	Rupees Fourteen and Paise SixtyTwo Only	PSqm	1854.00
2	Providing and applying white cement based putty(Asian wall putty true care/equivalent) of average thickness 1 mm, over the plastered wall surface to prepare the surface even and smooth complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	126.78	117.25	Rupees One Hundred Seventeen and Paise TwentyFive Only	PSqm	14865.00
3	Distempering on ceiling/sloping surfaces with oil bound washable distemper(Asian tractor uno OBD/equivalent) to give an even shade : Old work (one coat) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	1718.52	47.25	Rupees FourtySeven and Paise TwentyFive Only	PSqm	81200.00
4	Extra over every sub sequent coat of distempering with oil bound washable distemper(Asian tractor uno OBD/equivalent) (On ceiling/sloping surfaces)complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	1718.52	41.60	Rupees FourtyOne and Paise Sixty Only	PSqm	71490.00
5	Distempering on walls surfaces with oil bound washable distemper(Asian tractor uno OBD/equivalent) to give an even shade : Old work (one coat) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	4201.46	41.85	Rupees FourtyOne and Paise EightyFive Only	PSqm	175831.00
6	Extra over every sub sequent coat of distempering with oil bound washable distemper(Asian tractor uno OBD/equivalent) complete as per all carriage, lead and lifts and as per direction of Engineer in charge.	4201.46	36.30	Rupees ThirtySix and Paise Thirty Only	PSqm	152513.00

Total 497753.00

Draft Schedule of quantity approved for Rs. 497753.00 only

[Signature]
Executive Engineer
Nerchowk Division
HPPWD Nerchowk

34

DMIS NO. 527

Draft Schedule of Quantity

Estimated Cost:-Rs. 147987.00
Earnest Money:- Rs. 3000.00
Time:- Two Months

Name of work:- Restoration of rain damages on Chakkar to Chalah road km. 0/000 to 3/000.
Sub Head:- Construction of P.C.C. drain in 1:3:6 at RD 0/030 to 0/340. (Deposit work)

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	53.55 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	15369.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:3:6 (one cement three sand six graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	26.02 Cum	4770.00	Rupees four thousand seven hundred seventy and paise nil only.	Per cubic metre	124115.00
3	Providing and laying 450mm (four hundred fifty millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material including fixing collar with cement sand mortar 1:2 (one cement two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7.50 Rmt	1133.70	Rupees one thousand one hundred thirty three and paise seventy only.	Per running metre	8503.00
					Total:-	147987.00

Draft schedule of quantity approved for 21,47,987/-

Executive Engineer,
HP PWD Division
Nerchowk

35

DIT S.No. 526 for the year 2023-24

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Lunapani Gehra Sain road km. 0/0 to 6/900. (SH:- C/O Breast wall in PCC 1:5:10 at RD. 5/355 to 5/369)

Estimated Cost:- 297331.00

Earnest Money :- 6000.00

Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
			1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.		
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	65.54	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	277890.00
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	48.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	13776.00
					Total	297331.00

Draft Schedule of quantity approved for ₹ 2,97,331 only

Executive Engineer,
HPPWD Division,
HPPWD Nerchowk

36

DNIT S.No. (275) For the year 2023-24

Draft Schedule of Quantity

Estimated Cost:- Rs. 329644.00
Earnest Money:- Rs. 6600.00
Time:- Two Months

Name of work:- Construction of road from Dehrigaloo Dhar-I, Dhar-II Upper Lehra Tandehri Chir Badanu Lower Lehra Rihri Gour (Balh) Km. 0/0 to 5/0.
Sub Head:- Construction of Retaining wall at R.D. 1/005 to 1/017. Under SCDP

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	40.56 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	11641.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	70.52 Cum	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	299005.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	10.44 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	10962.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	28.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	8036.00
					Total	329644.00

Draft schedule of quantity checked and approved for Rs. 329644/- (Rupees three lac twenty nine thousand six hundred forty four) only.

Executive Engineer,
H.P.P.W.D. Division,
Nalchowk

37

DNIT S.NO. (273) For the year 2023-24

Draft Schedule of Quantity

Estimated Cost:- Rs. 243229.00

Earnest Money:- Rs. 4900.00

Time:- One Month

Name of work:- Restoration of rain damages on Kalkhar Leda Sunder Nagar road Km. 0/000 to 13/500.
Sub Head:- Construction of Breast wall at R.D. 7/375 to 7/387.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Excavation in soil in hilly area by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	32.40 Cum.	172.00	Rupees one hundred seventy two and paise nil only	Per cubic metre	5573.00
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.72 Cum.	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	2790.00
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	54.31 Cum.	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	230274.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3 7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	16.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	4592.00
					Total	243229.00

Draft schedule of quantity checked and approved for Rs 243229/- (Rupees two lac forty three thousand two hundred twenty nine) only.

Executive Engineer,
H.P.P.W.D. Division,
Nerchowk

38

DNIT S.NO. (274) For the Year 2023-24

Draft Schedule of Quantity

Estimated Cost:- Rs. 361815.00

Earnest Money:- Rs. 7200.00

Time:- Two Months

Name of work:- Restoration of rain damages on Rewalsar Pingla Thona Dharampur road Km. 0/000 to 10/000.

Sub Head:- Construction of Retaining wall at R.D. 0/981 to 0/990.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	45.27 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	12992.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	78.97 Cum	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	334833.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	9.77 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	10259.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	13.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	3731.00
					Total	361815.00

Draft schedule of quantity checked and approved for Rs. 361815/- (Rupees three lac sixty one thousand eight hundred fifteen) only.

Executive Engineer,
H.P.P.W.D. Division,
Nerchowkda

391

DMP S.No!-

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk.
 (Sub Head :- Preparation of detailed project reports of Widening /Improvement of Nagchala - Chakrari road km 0/000 to 1 /00, Improvement and widening of Mandi Gagaj Nalsar Road Km 0/000 to 16/190 (Portion Pool ghart to NH -4 lane Maroli Tunnel Km 0/000 to 1/650, M/T on Chapru -Nallah ,Khakhriana road (0/000 to 5/00, C/O Double Lane road at RD.0/0 to 2/600 to the site of National Disaster response Force (NDRF) Battalion in the State (at Behna Distt Mandi) and Upgradation of Bagla Badsu Road 0/000 to 5/300)

Estimated Cost:- 446275.00

Earnest Money :- 9000.00

Time :- One Month

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Surveying and Investigation for preparation of manuscript copy of detailed Estimate such as L-section, Cross-section, Plans, Cross-drainage work, Retaining Walls, Breast Walls & other necessary provision taken in the Estimate, Preparation of Detailed Estimate in the Shape of manuscript copy duly approved from the Circle Office & Chief office. Preparation of approved copies of Detailed Estimate along with relevant working drawings. (Five sets of DPR's and five additional sets of working drawing complete) and soft copies in the form of Compact Disc (C.D.) of above mentioned DPR's including Estimate and Drawings.					
a)	Widening /Improvement of Nagchala - Chakrari road km 0/000 to 1 /00	1.000	29500.00	Rupees Twenty NineThousand Five Hundred and paise zero only.	Per Kilometre	29500.00
b)	Improvement and widening of Mandi Gagaj Nalsar Road Km 0/000 to 16/190 (Portion Pool ghart to NH -4 lane Maroli Tunnel Km 0/000 to 1/650)	1.650	29500.00	Rupees Twenty NineThousand Five Hundred and paise zero only.	Per Kilometre	48675.00
c)	M/T on Chapru -Nallah ,Khakhriana road (0/000 to 5/00)	5.000	29500.00	Rupees Twenty NineThousand Five Hundred and paise zero only.	Per Kilometre	147500.00
d)	C/o Double Lane road at RD.0/0 to 2/600 to the site of National Disaster response Force (NDRF) Battalion in the State (at Behna Distt Mandi)	2.600	40000.00	Rupees Forty Thousand and paise zero only.	Per Kilometre	104000.00
e)	Upgradation of Bagla Badsu Road 0/000 to 5/300.	5.300	22000.00	Rupees Twenty Two Thousand and paise zero only.	Per Kilometre	116600.00
					Total	446275.00

Draft schedule of quantity approved for 2 4,46,275/-

Executive Engineer,
 HPPWD Division
 Nerchowk

40

DM P.S.ND 524

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Galma Manjhyali road km. 0/0 to 9/00. (SH:- Construction of PCC Retaining wall at RD. 1/550 to 1/558.50)

Estimated Cost:- 282658.00

Earnest Money :- 5700.00

Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P.			
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	19.55	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	5611.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203, 1:4:8 (one cement: four sand: eight graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of materials with in all leads, lifts and other incidentals and as per the entire satisfaction and direction of Engineer-in-Charge	59.42	4408.00	Rupees Four thousand four hundred eight and paise zero only.	Per cubic Metre	261923.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	10.03	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	10532.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	16.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	4592.00
					Total	282658.00

Draft schedule of quantity approved for 2,82,658/-

[Signature]
 Executive Engineer,
 HPPWD Division,
 HPPWD Nerchowk

41

Dm P.S. ND! (522)

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages caused due to laying of optical fibre cable on Ratti Kalkhar road km. 0/0 to 10/0. (SH:- Removal of formation deficiencies/ widening of curve in km. 3/405 to 3/435 & 9/780 to 10/0)

Estimated Cost:- 422924.00

Earnest Money :- 8500.00

Time :- One Month

S.N o	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
			1	Excavation in soil in hilly area all heights and depths, in all kind of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-Charge at site according to technical specifications clause 1603.1 & 1603.2 sorting out useful unuseful materials and stacking the same in all leads and lift and transportation of useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means) along with its levelling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if required). Recovery of useful stone of 112.45 cum. @ 300/- per cubic metre amounting to Rs.33,735/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect including all leads and lift of materials or as per direction of Engineer in-Charge.		
Total						422924.00

Draft schedule of quantity approved for 4,22,924/-

Executive Engineer,
HPPWD Division
Nerchowk

42

DNI PS-NO! - 525

Draft Schedule of Quantity

Estimated Cost:- Rs. 197299.00
Earnest Money:- Rs. 4000.00
Time:- Two Months

Name of work:- Restoration of rain damages on Mandi Gagaj Chailchowk Janjehli Chattri Rana ka Bag Nagan road Km. 0/000 to 16/190.
Sub Head:- Construction of Retaining wall at R.D. 13/680 to 13/692.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	26.76 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	7680.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	42.42 Cum	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	179861.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	4.92 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	5166.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	16.00 Nos	287.00	Rupees two hundred eighty seven and paise nil only	Each	4592.00
					Total	197299.00

Draft schedule of quantity approval for Rs. 1,97,299/-

Executive Engineer,
H.P.W.D. Division,
Nerchowk

43

Draft Schedule of quantity

D/NIT No. 31 For F.Y. 2023-24

Name of work:- Addition and Alteration Work in Intern Hostel Building in the SLBSGMC&H at Nerchowk Distt Mandl (HP)
(SH:- Construction of common Toilet and supplying of bricks)

Estimated Amount - 203232.00/-
Earnest money - 4100.00/-
Time - One month

S. No	Item Description	Quantity	Rate		Units	Total amount with all taxes Including GST in Rs. P.
			Figure	Word		
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead For thickness of tiles 10 mm to 25 mm including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.610	12.93	Rupees Twelve and Paise NinetyThree Only	Sqm	8.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand): 10 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.910	4240.00	Rupees Four Thousand Two Hundred Fourty Only	cum	3858.00
3	Brick work with modular extruded burnt fly ash clay sewer bricks (Conforming to IS: 4885) in foundation and plinth :Cement Mortar 1:4 (1 cement : 4 coarse sand) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.620	6829.04	Rupees Six Thousand Eight Hundred TwentyNine and Paise Four Only	cum	17892.00
4	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size). Including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.280	6593.52	Rupees Six Thousand Five Hundred NinetyThree and Paise FiftyTwo Only	Cum	8440.00
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Hot rolled deformed bars including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	102.770	96.30	Rupees NinetySix and Paise Thirty Only	kg	9897.00
6	15 mm cement plaster on rough side of single or half brick wall of mix:1:6 (1 cement: 6 coarse sand) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.690	203.81	Rupees Two Hundred Three and Paise EightyOne Only	sqm	141.00
7	Centering and shuttering including strutting, propping etc. and removal of form for all heights :Suspended floors, roofs, landings, balconies and access platform including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.620	484.35	Rupees Four Hundred EightyFour and Paise ThirtyFive Only	Sqm	785.00
8	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.Flexible pipe.32 mm dia including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.000	65.95	Rupees SixtyFive and Paise NinetyFive Only	each	132.00
9	Providing and fixing PTMT liquid soap container 109 mm wide, 125 mm high and 112 mm distance from wall of standard shape with bracket of the same materials with snap fittings of approved quality and colour, weighing not less than 105 gms including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.000	130.48	Rupees One Hundred Thirty and Paise FourtyEight Only	each	130.00

431

10	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water thinnable priming coat with cement primer including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.690	107.49	Rupees One Hundred Seven and Paise FortyNine Only	sqm	74.00
11	Providing and fixing long CP Brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms. 15 mm nominal bore.F2002152 CERA or equivalent including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.000	1225.00	Rupees One Thousand Two Hundred TwentyFive Only	No.	2450.00
12	Providing and fixing VECTUS Polyethylene-Aluminium-Polyethylene PE-AL-PE Composite Pressure Pipes conforming to IS - 15450, U.V. stabilized with carbon black having thermal stability for hot & cold water supply, capable to withstand temperature up to 80°C, including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) e.g. elbows, tees, reducers, couplers & connectors etc., with clamps at 1.00 metre spacing. This includes testing of joints complete as per direction of the Engineer in charge INTERNAL WORK - EXPOSED ON WALL 1620 (20 mm OD) pipe including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	20.000	264.8	Rupees Two Hundred SixtyFour and Paise Eighty Only	meter	5296.00
13	Providing and fixing VECTUS / or equivalent Polyethylene-Aluminium- Polyethylene PE-AL-PE Composite Pressure Pipes conforming to IS - 15450, U.V. stabilized with carbon black having thermal stability for hot & cold water supply, capable to withstand temperature up to 80°C, including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) e.g. elbows, tees, reducers, couplers & connectors etc., with clamps at 1.00 metre spacing. This includes the costs of cutting chases and including testing of joints complete as per direction of the engineer in charge. Concealed work, including cutting chases and making good the wall etc.1620 (20 mm OD) pipe including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	20.000	393.8	Rupees Three Hundred NinetyThree and Paise Eighty Only	meter	7876.00
14	Providing and fixing SS304 connection pipe with PTMT Nuts, collar and bush of approved quality and colour, 18" SS304 B2CH218 EssEss/or equivalent including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	4.000	170	Rupees One Hundred Seventy Only	each	680.00
15	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.Flexible pipe.32 mm dia including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.000	65.95	Rupees SixtyFive and Paise NinetyFive Only	each	132.00
16	Providing and fixing VECTUS or equivalent Premium SWR Fittings-Ring FIT unplasticised conforming to IS : 13592 , including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion coupler 75mm including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	5.000	240.65	Rupees Two Hundred Fourty and Paise SixtyFive Only	each	1203.00
17	Providing and fixing VECTUS or equivalent Premium SWR Fittings-Ring FIT unplasticised conforming to IS : 13592 , including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansionBend 87.5° 75mm including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	5.000	119.4	Rupees One Hundred Nineteen and Paise Fourty Only	each	597.00
18	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.690	117	Rupees One Hundred Seventeen Only	sqm	81.00
19	Providing and fixing Vectus or equivalent SWR soil pipes conforming to IS : 13592 Type B Ring Fit, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion,110 mm diameter including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	20.000	712.3	Rupees Seven Hundred Twelve and Paise Thirty Only	meter	14246.00

432

20	Providing and fixing VECTUS or equivalent Premium SWR Fittings-Ring FIT fitting conforming to IS : 13592 , including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion coupler 110 mm including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	5.000	314.35	Rupees Three Hundred Fourteen and Paise ThirtyFive Only	each	1572.00
21	Providing and fixing VECTUS or equivalent Premium SWR Fittings-Ring FIT fitting conforming to IS : 13592 , including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion Bend 87.5° 110 mm including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	5.000	318.6	Rupees Three Hundred Eighteen and Paise Sixty Only	each	1593.00
22	Providing and fixing VECTUS or equivalent Premium SWR Fittings-Ring FIT fitting conforming to IS : 13592 , including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion Single Tee 110mm including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	5.000	410.15	Rupees Four Hundred Ten and Paise Fifteen Only	each	2051.00
23	Providing and fixing VECTUS or equivalent Premium SWR Fittings-Ring FIT Fitting conforming to IS : 13592 , including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion Pipe Clip 110mm including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	5.000	71.7	Rupees SeventyOne and Paise Seventy Only	each	359.00
24	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge. .	38.400	102.1	Rupees One Hundred Two and Paise Ten Only	kg	3921.00
25	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.300	82.4	Rupees EightyTwo and Paise Fourty Only	sqm	190.00
26	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :For fixed portion Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	24.640	637	Rupees Six Hundred ThirtySeven Only	kg	15696.00

153

27	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	21.230	660	Rupees Six Hundred Sixty Only	kg	14012.00
28	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer in-charge. (Cost of aluminium snap beading shall be paid in basic item):With float glass panes of 4.00 mm thickness weight not less than 10.00 kg/ sqm including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.800	1000.05	Rupees One Thousand and Paise Five Only	sqm	1800.00
29	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :125mm including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.000	63.31	Rupees SixtyThree and Paise ThirtyOne Only	each	127.00
30	Providing and laying Ceramic tiles of size as per requirement (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:1 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	28.880	1068.52	Rupees One Thousand SixtyEight and Paise FiftyTwo Only	sqm	30859.00
31	Providing 0.47mm thick with zinc coating corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	7.970	754.34	Rupees Seven Hundred FiftyFour and Paise ThirtyFour Only	sqm	6012.00
32	Providing 0.37mm thick with zinc coating Linear G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	7.970	593.57	Rupees Five Hundred NinetyThree and Paise FiftySeven Only	sqm	4731.00

4304

33	Providing 0.47 mm thick with zinc coating ridges or hips of width 40 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	12.160	393.06	Rupees Three Hundred NinetyThree and Paise Six Only	meter	4780.00
34	Providing and fixing C.P. brass angle Valve REAC102 Royale Square angle cock Wall Flange essess or equivalent for basin mixer and geyser points of approved quality conforming to IS:8931 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-In-Charge.	4.000	1088	Rupees One Thousand EightyEight Only	each	4352.00
35	Providing and fixing towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour, EssEss AC-701 Towel Rail (61cm) or equivalent including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.000	1354	Rupees One Thousand Three Hundred FiftyFour Only	each	1354.00
36	Providing and fixing C.P. brass overhead shower, 1 flow with arm OH-107A EssEss or equivalent including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.000	1491.7	Rupees One Thousand Four Hundred NinetyOne and Paise Seventy Only	each	1492.00
37	Providing and fixing of single lever concealed diverter for overhead shower upper parts for E2248 EssEss TARIM or equivalent including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.000	2114.8	Rupees Two Thousand One Hundred Fourteen and Paise Eighty Only	each	2115.00
38	Providing and fixing of Bath tub spout with wall Flange TM-119 EssEss TARIM or equivalent including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.000	1675.9	Rupees One Thousand Six Hundred SeventyFive and Paise Ninety Only	No.	1676.00
39	Providing and fixing of Health Faucet ABS body with 1 meter PVC Silver Fall Connection Pipe F8030104ab of quality and make as approved by Engineer - in - charge	1.000	1446	Rupees One Thousand Four Hundred FortySix Only	No.	1446.00
40	Providing and fixing white vitreous china pedestal type water closet Perryware Elite EWC C0297/C0278 (S/P) Trap 530*380*400 (European type W.C. pan) with Perryware Toilet Seat Cover Petite Plus seat and lid, Perryware SLIMLINE E8057 Economy D/F cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :W.C. pan with ISI marked white solid plastic seat and lid including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.000	7497	Rupees Seven Thousand Four Hundred NinetySeven Only	No.	7497.00
41	Providing and fixing Perryware Casa C0404 Basin (570*440*200mm) wash basin with C.I. brackets, 15 mm C.P. brass pillar taps Bathsense Mystic MYBM101 Single lever basin mixer without popo up waste system, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.000	10073	Rupees Ten Thousand SeventyThree Only	No.	10073.00
42	Demolishing Cement Concrete blocks with Plaster and Granite, Cement Concrete with Tile, Cement Concrete blocks with Plaster and Wotop with Granite etc. manually/ by mechanical means and disposal of material within 50 metres lead including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.170	474.52	Rupees Four Hundred SeventyFour and Paise FiftyTwo Only	cum	81.00
43	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.860	287	Rupees Two Hundred EightySeven Only	cum	247.00

43/5

44	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :150x10 mm including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.000	50	Rupees Fifty Only	each	100.00
45	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete :200*16 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.000	205.1	Rupees Two Hundred Five and Paise Ten Only	each	205.00
46	Providing and fixing Action Tessa 12 mm thick pre-laminated HDHMR board in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge. Pre-laminated HDHMR board with balancing lamination on both side including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.890	990.77	Rupees Nine Hundred Ninety and Paise SeventySeven Only	sqm	1873.00
47	Providing and fixing to the inlet mouth of rain water pipe cast iron grating 15 cm diameter and weighing not less than 440 grams including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.000	50	Rupees Fifty Only	each	100.00
48	Supplying of bricks work including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1000.000	9	Rupees Nine Only	Each	9000.00
Total						203232.00

Draft Schedule of quantity approved for Rs. 203232.00/- only


 Executive Engineer
 Nerchowk Division
 APJWD Nerchowk


144

DMPS No. 380 for the year 2023-24

DRAFT SCHEDULE OF QUANTITY

Name of work:- RRD on Mandi Gagal Chailchowk Janjheli Chattri Rana Ka Bag Nagan road Km. 0/00 to 16/190. (SH:- Dressing of berms and removal of slips various reaches in km. 0/00 to 15/00) (Gagal Section)

Estimated Cost:- 282242.00

Earnest Money :- 5700.00

Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Maintenance of Earthen shoulder (filling with fresh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC including carriage of material with in all leads and lifts as per technical specification Clause 1903 and as per the entire satisfaction and direction of Engineer-in-Charge.	1850.00	42.00	Rupees Forty two and paise zero only	Per square Metre	77700.00
2	Maintenance of Earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	1850.00	14.00	Rupees Fourteen and paise zero only	Per square Metre	25900.00
3	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	1790.00	99.80	Rupees Ninety nine and paise eighty only.	Per Cubic Metre	178642.00
					Total	282242.00

Draft schedule of quantity approved for 2,82,242/-

Assistant Engineer
Chakkar Sub-Division
H.P.P.W.D. Ner Chowk

Executive Engineer,
HPPWD Division,
HPPWD Nerchowk

45

DNIT S. NO. (276) for the year 2023-24

Draft Schedule of Quantity

Estimated Cost:- Rs. 204441.00

Earnest Money:- Rs. 4100.00

Time:- One month

Name of work:- Restoration of rain damages on various roads in Rewalsar Sub-Division HP.PWD. Rewalsar (Sardhwar Section).
Sub Head:- Removal of slips at various reaches.

Sr. No.	Description of item	Qty.	Rate with all taxes including GST in Rs. P		Unit	Amount
			In Figure	In Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto any height and carriage of material upto any lead, lift and other incidental complete in all respect as per Technical specification 302 3.5 and 1611 and as per direction of Engineer-in-Charge.	2049.53 Cum.	99.75	Rupees ninety nine and paise seventy five only	Per cubic metre	204441.00
Total:-						204441.00

Draft schedule of quantity checked and approved for Rs. 2,04,441/- (Rupees two lac four thousand four hundred forty one) only.

Executive Engineer,
Nerchowk Division,
HP.PWD. Nerchowk

46

DNIP S.No 528

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages caused due to laying of optical fibre cable on Ratti Meramasit Leda road km. 0/0 to 14/580. (SH:- Removal of formation deficiencies/ widening of curve in km. 12/480 to 12/750)

Estimated Cost:- 371211.00

Earnest Money :- 7500.00

Time :- One Month

S.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P.			
			In figure	In word		
1	Excavation in soil in hilly area all heights and depths, in all kind of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-Charge at site according to technical specifications clause 1603.1 & 1603.2 sorting out useful unuseful materials and stacking the same in all leads and lift and transportation of useful materials for filling in road ways. embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means) along with its levelling fine dressing and all labour, machineries. materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if required). Recovery of useful stone of 98.70 cum. @ 300/- per cubic metre amounting to Rs.29,610/- only shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect including all leads and lift of materials or as per direction of Engineer in-Charge.	1974.00	188.05	Rupees One hundred eighty eight and paise zero five only.	Per cubic Metre	371211.00
Total						371211.00

Draft schedule of quantity approved for 2,37,211/-

Executive Engineer,
HPPWD Division
Nerchowk

47

DNIT S.NO. (278) for the year 2023-24

Draft Schedule of Quantity

Estimated Cost:- 220500.00
Earnest Money:-Rs 4400.00
Time:- One month

Name of work:-Restoration of rain damages on various roads under Rewalsar Sub-Division HP.PWD. Rewalsar. (Rewalsar Section)
Sub Head:- Hiring of Earth cutting / Excavating machine for removal of slips,clearing of debris drains and dressing of berms etecetra.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of earth cutting/excavating machineries to be deployed for removal of slips/earth cutting/filling/cleaning of unlined drains and catchpits including cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/owner at his own risk shifting of machinery from one place to other place will be absolute responsibility of the contractor, Only actual working hour will be accounted for the payment. Earth cutting in all kind of soils including loading in to tipper/truck and disposal of all excavated earth in all leads and lifts to the entire satisfaction of Engineer-in-Charge.	210.00 Hours	1050.00	Rupees one thousand fifty and paise nil only	Per hour	220500.00
				Total:-		220500.00

Conditions:-

Contractor should have his own machinery or he should have an agreement with the owner of the machinery.

Draft schedule of quantity checked and approved for Rs. 220500/- (Rupees two lac twenty thousand five hundred) only.

Assistant Engineer,
Rewalsar Sub-Division,
HP.PWD. Rewalsar.

Executive Engineer,
Nerchowk Division,
HP.PWD. Nerchowk

48

DNIT S.NO (382) For the year 2023-24.

Draft Schedule of Quantity

Estimated Cost:- 174337.00
Earnest Money:- 3500.00
Time:- One Month

Name of work:- Annual repair & Maintenance of various roads under Chakkar Sub Division HP. PWD Nerchowk.

Sub Head:- Supplying of precast 5th KM stones, Ordinary Kilometre Stones & 200 Metre stones and boundary pillar.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying of precast reinforced cement concrete M 15 grade kilometre stone / local stone of standard design as per IRC:8 at site as per drawing and technical specification clause 1703 complete including carriage of materials with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.					
i)	5th Kilometre stone	8.00 Nos.	3413.30	Rupees three thousand four hundred thirteen and paise thirty only	Each	27306.00
ii)	Ordinary Kilometre stone	22.00 Nos.	2236.75	Rupees two thousand two hundred thirty six and paise seventy five only	Each	49209.00
iii)	200 Metre stone	38.00 Nos.	612.55	Rupees six hundred twelve and paise fifty five only	Each	23277.00
2	Supplying and stacking of Reinforced cement concrete M15 grade boundary pillars of standard design as per IRC:25 as per drawing and Technical Specification Clause 1704 including carriage of materials with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.	218.00 Nos.	341.95	Rupees three hundred forty one and paise ninety five only	Each	74545.00
				Total:-		174337.00

Draft schedule of quantity approved for 2,174,337/- only.

Assistant Engineer,
Chakkar Sub-Division
HP P.W.D. Ner Chowk

Executive Engineer,
Nerchowk Division
HP.PWD. Nerchowk

219

DNIPS.NO) - 559 for the year 2023-24.

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Gagal section)

(SH: - Hiring of JCB clearing of debris drains and dressing of berms etc.)

Estimated Cost Rs. 220500/-
Earnest Money Rs. 4500/-
Time: -One Month.

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	210 hours	1050.00	Rupees one Thousand fifty only	Per hours	220500.00
					Total:-	220500.00

Draft schedule of quantity approved for 2,20,500/-

Assistant Engineer,
Chakkar Sub Division,
HPPWD Nerchowk.

Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk.

50

DNIPS.NO 532

DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of 92mtr. long span PSC Bow string bridge over Suketi Khad at RD. 0/810 in Distt. Mandi.
(SH:- Geological Investigation of soil/Strata) Job No 2

Estimated Cost:- 477015.00

Earnest Money :- 9600.00

Time :- One Month

S.N o	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In figure	In word		
			1	Sub- soil investigation in all type of soil / strata by drilling bore holes of NX size 75mm (seventy five millimeter) diameter ranging from 10 meter or above in depth for investigation of soil / rock conditions at site of work including mobilization and de-mobilization, shifting of machinery to bore site, making platform and water arrangement for drilling etc., the scope of work includes collection of disturbed and undisturbed core samples, plugging of bore holes, preservation of core including relevant fields and laboratory tests and submissions of geological report of complete site of work as per direction of Engineer-In-Charge including carriage of material in all leads, lifts and other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.		
Total						477015.00

Draft schedule of quantity approved for 24.77, 951/-

Executive Engineer,
HPPWD Division
Nerchowk

DNI PS.No (255) for the year 2023-24.

51

DRAFT SCHEDULE OF QUANTITY

Name of work : A/R & M/O various roads under Chakkar Sub Division HP. PWD Nerchowk. (SH:- Supplying & stacking dual direction rectangular delinators for road side with plastic head unbreakable at neck.) Ratti section				Estimated Cost : Rs. 188760.00		
				Earnest Money : Rs. 3800.00		
				Time : One Month.		
Sr. No.	Description of item	Qty.	Rate		Unit	Amount included all taxes
			In figure	In words		
1	2	3	4	5	6	7
1	Supplying & stacking F.O.R. at site dual direction delineator made out of dia MS pipe 60 mm (sixty millimetre) dia of size 75mmx75 mm (seventy five into seventy five millimetre) and of length 600 mm (six hundred millimetre) pipe stove enameled and baked to 120 (one hundred twenty) C/powder coated head made of rectangular moulded with flat face provided with high intensity prismatic reflector of colour (white/yellow) of size 100 mmx125 mm (one hundred into one hundred twenty five millimetre) with additional to reflect strips of 25mm (twenty five millimetre) wide make green light including hauling of materials in all leads, lifts and other incidental or as per the entire specification and direction of Engineer in-Charge.	220.00	858.00	Rupees eight hundred and fifty eight only.	Each.	188760.00
Total :-						188760.00

Draft schedule of quantity approved for ₹ 1,88,760/- only

Assistant Engineer
Subdivision Chakkar
HPPWD Nerchowk

Executive Engineer,
HPPWD Division,
HPPWD, Nerchowk.

52

DNIT S.No. 493 for the year 2023-24

Draft Schedule of Quantity

Estimated Cost:- 426681.00
Earnest Money:- 8600.00
Time:- Two Months

Name of work:- Construction of Balhi, Jagar Lusaika road Km. 0/0 to 1/0.

Sub Head:- Providing and laying WBM G-I in Km.0/646 to 0/675 and WBM G-II in Km. 0/000 to 0/675. Under OTMNP

Sr. No.	Description of item	Qty.	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In Words		
1	Providing, laying, spreading and compacting stone aggregates by mechanical means of 90mm to 45mm (Ninety millimetre to forty five millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-one hundred kilo newton) static roller in stages to proper grade and camber applying and brooming stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-1 (one) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	29.00 Cum.	2190.00	Rupees two thousand one hundred ninety and paise nil only.	Per cubic metre	63510.00
2	Providing, laying, spreading and compacting by mechanical means stone aggregates 63mm to 45mm (sixty three millimetre to forty five millimetre) of sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-one hundred kilo newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-2 (two) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges as per direction of Engineer-in-Charge.	162.13 Cum.	2240.00	Rupees two thousand two hundred forty and paise nil only.	Per cubic metre	363171.00
				Total:-		426681.00

Draft Schedule of quantity approved for Rs. 426681/- only.

Executive Engineer
H.P.W.D. Division,
Nerchowk

(53)

DMFS-NO. 499

DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of Stadium Near GPS Arthi GP Mandal, Development Block Balh at Nerchowk. (SH:- Construction of Stadium at RD. 0/00 to 0/017)

Estimated Cost:- 499733.00

Earnest Money :- 10000.00

Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	25.84	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	7416.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	9.69	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	41086.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	24.31	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	25526.00
4	Providing and laying in position reinforced cement concrete 1:2:4 (one cement : two coarse sand : four graded stone aggregate 40 mm (forty millimetre) nominal size), excluding the cost of centering, shuttering, finishing and reinforcement all work up to plinth level including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	61.86	5810.00	Rupees Five thousand eight hundred ten and paise zero only.	Per cubic metre	359407.00
5	Providing and laying in position cement concrete 1:4:8 (one cement : four coarse sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) mechanically mixed and curing complete excluding the cost of centering and shuttering all work up to plinth level including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	7.65	4408.00	Rupees Four thousand four hundred eight and paise zero only.	Per cubic metre	33721.00
6	Steel work welded in built up section/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. in grating frames, guard bar, ladder railing, brackets, gates and similar work including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	227.91	102.50	Rupees One hundred two and paise fifty only.	Per Kilogramme	23361.00
7	15 mm (Fifteen millimetre) thick cement plaster to ceiling with cement mortar 1:4 (one cement :four sand) with curing complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	100.78	91.45	Rupees Ninety one and paise forty five only.	Per square metre	9216.00
					Total	499733.00

Draft schedule of quantity approved for 4,99,733/-

Executive Engineer, HPPWD Division, HPPWD Nerchowk

(54)

DNIPS.NO.1-279 for the year 2023-24.

Draft Schedule of Quantity

Estimated Cost:- Rs. 324273.00
Earnest Money:- Rs. 6500.00
Time:- Two Months

Name of work:- Construction of link road from Mandi Rewalsar road to Village Ghour Tibba Khel Gharwahan Dev Sat Balakameshwar & Ghandalas road Km. 0/00 to 1/500 (Portion Harder Re Ghari to Dev Sat Bala Kameshwar Km. 0/0 to 1/500).

Sub Head:- Construction of Retaining wall at R.D.0/900 to 0/915. Under OTMNP

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	47.10 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	13518.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	69.82 Cum	4240.00	Rupees four thousand two hundred forty and paise nil only	Per cubic metre	296037.00
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	8.55 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	8978.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	20.00 Nos.	287.00	Rupees two hundred eighty seven and paise nil only	Each	5740.00
					Total	324273.00

Draft schedule of quantity approved for ₹ 3,24,273/-

Executive Engineer,
H.P.P.W.D. Division,
Nerchowk

35

Draft S.M.O (490) for the year 2023-24.

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages due to laying of optical fibre cable on Ratti Dharwan Grencha road km. 0/00 to 6/00. (SH:- Providing and laying interlocking paver blocks at RD. 1/117 to 1/189)

Estimated Cost:- 479934.00

Earnest Money :- 9600.00

Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Providing and laying plain/reinforced cement concrete in foundation/substructure as per drawing and technical specification clause 802.303.1202 and 1203 P.C.C nominal mix 1:2:4 (One cement: two sand: four graded stone aggregate) 40 mm (forty millimetre) nominal size of aggregates including carriage of material with in all leads, lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	4.32	5810.00	Rupees Five thousand eight hundred ten and paise zero only.	Per Cubic Metre	25099.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203, 1:4:8 (one cement: four sand: eight graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of materials with in all leads, lifts and other incidentials and as per the entire satisfaction and direction of Engineer-in-Charge	22.18	4408.00	Rupees Four thousand four hundred eight and paise zero only.	Per cubic Metre	97769.00
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm (fifty millimetre) thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, 80 mm (eighty millimetre) thick cement concrete paver block of M-30 (thirty) grade with approved colour, design pattern including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	221.78	1610.00	Rupees One thousand six hundred ten and paise zero only	Per square Metre	357066.00
					Total	479934.00

Draft schedule of quantity approved for Rs 4,79,934/-

Executive Engineer,
HPPWD Division
Nerchowki

(56)

DM P.S. NO 533

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages caused due to laying of optical fibre cable on Ratti Meramasit Leda road km. 0/00 to 14/580.
(SH:- Providing and laying cement concrete pavement in km. 2/250 to 2/290 & 2/350 to 2/370)

Estimated Cost:- 358088.00

Earnest Money :- 7200.00

Time :- Two Months

S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Re.	P.		
			In figure	In word		
1	Providing, laying, spreading and compacting stone aggregate of sizes 63-45mm (Sixty three to forty five millimetres) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty by hundred Kilo Newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-II by manual means as per technical specification Clause 405 including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	20.25	2190.00	Rupees Two thousand one hundred ninety and paise zero only	Per Cubic Metre	44348.00
2	Providing and laying plain/reinforced cement concrete in foundation/substructure as per drawing and technical specification clause 802.803.1202 and 1203 P.C.C nominal mix 1:2:4 (One cement: two sand: four graded stone aggregate) 40 mm (forty millimetre) nominal size of aggregates including carriage of material with in all leads, lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	54.00	5810.00	Rupees Five thousand eight hundred ten and paise zero only.	Per Cubic Metre	313740.00
					Total	358088.00

Draft schedule of quantity approved for Rs. 3,58,088/-

Executive Engineer,
HRPWD Division
Nerchowk