

Himachal Pradesh
Public Works Department
PW-RD-GA-Tender-2023-24-
To

24349

dated:- 20-2-20

The Executive Engineer (IT Cell)
Nigam Bihar, Shimla-2.

Subject: - Tender notice.

Enclosed please find herewith the tender notice of work as given in the notice inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of H.P. letter N. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th July 2021.

1. Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.

DA:- Notice inviting tender & schedule of quantity.

Executive Engineer,
B&R Division, HPPWD,
Rohru.

**Himachal Pradesh
Public Works Department
"NOTICE INVITING TENDERS"**

Sealed item rate tender on form PWD 6&8 are invited by the Executive Engineer Rohru Division HPPWD, on behalf of Governor of H.P. for the following works from the approved and eligible contractors enlisted in HPPWD, So as to reach in this office as per time schedule given below:-

1. *Date of receipt of applications for tender forms:- 01.03.2024 upto 1:00PM*
2. *Date of issue/sale of tender forms:- 01.03.2024 upto 2:00PM to 3.00PM*
3. *Date of receipt of tender:- 02.03.2024 upto 3:30PM*

Sl.	Name of work	Estimated cost	Earnest money	Time Allowed
1	S/R to Rest House at Sungri in Tehsil Rohru Distt, Shimal HP. (SH:- C/O U-Shape drain and Greeting over drain etc.)	478902	9578	Two month
2	R/R damages on Udho Niwas Jakhar Niwas Jakhar Rantari road km 0/0 to 12/0 (SH:- C/o R/Wall in stone masonry at RD. 0/332 to 0/354)	456143	9123	Two month
3	R/R damages on Dhara Bhalara Malkhoon road km 0/0 to 6/0 (SH:- C/O 900mmdia HP. At RD. 3/225)	429089	8582	Two month
4	C/o Rantari Kandai road km 0/0 to 2/235 (SH:- C/o 5/7 mtr.wide formation cutting at RD. 1/780 to 1/990)	499433	9989	Two month
5	R/R damages on Khadralla to Bajeshal road km 0/0 to 4/0 (SH:- C/o R/Wall in PCC at RD 3/0 to 3/009)	418028	8361	Two month
6	R/R damages on link road to village Jakhar (SH:- C/O R/Wall at RD 0/300 to 0/315)	439198	8784	Two month
7	R/R Damages to Summerkot Tikkri Shalwat Road km.0/00 to 3/00 (SH:- C/O B/Wall in Wire crate at RD. 2/600 to 2/640)	402845	8057	Two month
8	C/O Shalawat Wali Karetly road (SH:- Widening of road for Bus Stand at Rd 2/195 to 2/225)	174930	3499	Two month
9	R/R damages to Thamtari Junidhar school Nauna Pani road km 0/0 to 4/500 (SH:- C/O R/Wall at RD 0/150 to 0/158)	349627	6993	Two month
10	R/R damages to Podhar Mandeori road km 0/00 to 12/00 (SH:- C/O R/Wall at Rd 0/510 to 0/540)	469610	9392	Two month
11	R/R damages to Podhar Mandeori road km 0/00 to 12/00 (SH:- C/O R/Wall at Rd 0/580 to 0/590)	287664	5753	Two month
12	R/R damages on Jakhar Besrala Thakulidhar Bartu road km 0/0 to 3/500 (SH:- C/O B/Wall in wire crate at RD 0/085 to 0/105)	401939	8039	Two month
13	R/R damages on Annu Thamtari Road km 0/0 to 1/250 (SH:- C/O of R/Wall at Rd 0/99 to 0/103)	391986	7840	Two month
14	R/R damages on Kansakoti Kutara Dalgaon road km 0/0 to 15/300 (SH:- W/o narrow reaches at various RDs. 10/900 to 10/960, 11/210 to 11/315, 11/315 to 11/750)	488369	9767	Two month
15	C/O Badda Nallah to Muslim Basti gad km 0/0 to 1/450 (SH:- C/o R/Wall at RD. 0/0 to 0/09.4)	495751	9915	Two month
16	C/o link road Kalu Nallah to HB. Shakti nagar in GP. Karasa (SH:- C/o B/Wall in wire crate at RD 0/240 to 0/295)	432454	8649	Two month
17	R/R damages on Machoti Dhara Kui road km 0/0 to 9/0 (SH:- C/o R/Wall in wire crate at RD 4/0 to 4/040)	388875	7778	Two month
18	R/R damages on Khopru Nallah to Village Shardu km 0/0 to 3/0 (SH:- R/Wall at RD. 1/320 to 1/320)	491590	9832	Two month
19	C/O Anu Matan to Karalash Kanchi road km 0/0 to 2/500 (SH:- Widening of road at Rd 0/105 to 0/315)	481255	9625	Two month

20	R/R Damages on Narkanda Baghi Sungri Khadralla Rohru road km RD 0/00 to 67/00 (SH:- F/C widening of Black spot at RD. 57/305 to 57/470)	436118	8722	Two month
21	C/O Chiku Dabbar Gaddali Road km 0/0 to 1/00 (SH:- F/C 5/7 mtr wide road at Rd 0/240 to 0/270)	469619	9392	Two month
22	R/R Damage to Bhatwari Hingwala Gawas road km 0/00 to 7/00 (SH:- C/O 900mm Dia Hume Piope Culvert in PCC 1:4:8 at RD 0/320 & Wing wall)	416508	8330	Two month
23	R/R damages on various road under Rohru Sub-Division (Rohru Section) (SH:- Hiring of JCB for removal of slips , slush/land slide and maintenance of road etc.)	252000	5040	Two month
24	C/O Buthara Nursry to Katmori road km 0/0 to 1/500 (SH:-F/C 5/7 mtr wide road ar Rd 0/00 to 0//285)	499721	9994	Two month
25	C/O link road from Kaneora to Harijan Basti Bhamnallaha km 0/00 to 1/500 (SH:- C/OR/Wall in PCC at RD 0/145 to 0/165) under SCCP	466778	9336	Two month
26	R/R damages on various roads under Rohru Section Sub-Division Rohru (SH:- Hiring of JCB for remocal of slips and land slide maintenance of road)	495000	9900	Two month
27	RR damages on various roads under Rohru Sectar sub-Division Rohru (SH:- Hiring of JCB. For removal of slips at various RDs, maintenance of road & dressing of road surface.)	252000	5040	Two month
28	R/R damges on various roads under Kansakoti section (Rohru Sub-Division) (SH:- Hiring of JCB. For removal of slips and land slide maintenance of road)	495000	9900	Two month
29	Improvement of RCD road km 0/0 to 2/200 (SH:- Widening of Road at RD 2/115 to 2/150)	276264	5525	Two month
30	R/R damages on various roads under Rohru section Rohru sub-division (SH:- Hiring of Tipper for carriage of muck etc.)	123200	2464	Two month
31	R/R Damage on Udho Niwas Jakhar Rantari Road km 0/0 to 12/0 (SH:- C/O R/Wall at Rd 0/788 to 0/795)	455107	9102	Two month
32	R/R damages to various roads under Rohru section sub-Division Rohru (SH:- Hiring of JCB for removal of slips at various RDs , maintenance of road and dressing of road surface)	252000	5040	Two month
33	R/R Damage to Bhaloon Kanchi to Kui road km 0/0 to 9/100(SH:- C/O R/Wall at Rd 8/994 to 9/0	414419	8288	Two month
34	A/R & M/O to various road under Samoli Section Sub-Division Rohru (SH:-Hiring of JCB for removal of slip and land slide , maintenance of road)	378000	7560	Two month
35	C/O Link road khorsu to gujjar basti Basharli km 0/00 to 2/00 (SH:- C/O R/Wall at RD 0/150 to 0/160)	388488	7770	Two month
36	R/R damages on Po-Dhar Mendeori road 0/0 to 12/00 (SH:- C/O R/Wall inPCC at RD 9/220 to 9/236)	482822	9656	Two month
37	R/R damages to various road under Rohru section sub-division Rohru (SH:- Hiring of of JCB for removal of slips at various RDs , maintenance of road and dressing of road surface.)	252000	5040	Two month
38	R/R Damages to Narkanda Baghi Sungri Khadralla Rohru Raod km RD 0/00 to 67/00 (SH:- C/O R/Wall at RD 63/045 to 63/060)	429869	8597	Two month

39	R/R damages to various road under Summerkot section Sub -division Rohru Tehsil Rohru Distt Shimla (HP) (SH:- Hiring of Tipper for carriage of muck and excavated soil)	116600	2332	Two month
40	C/O Narkanda Baggi Khadralla Sungri Rohru road km 0/0 to 67/0 (SH:- C/o R/Wall in wire crate at RD 40/565 to 40/587.50)	354708	7094	Two month
41	R/R damages on Bhloon Kenchi to Bhagoon road km 0/0 to 4/0 (SH:- C/O B/Wall in PCC 1:4:8 & wire crate at RD 2/535 to 2/560)	446797	8936	Two month
42	R/R damages on various roads under Rohru Section Sub-Division Rohru (SH: Hiring of Tipper for carriage of excavated earth muck etc.)	297000	5940	Two month
43	R/R damages to various roads under Rohru section sub-Division Rohru (SH:- Hiring of JCB for removal of slips and land slide , Maintenance of road)	495000	9900	Two month
44	R/R damages to various roads under Rohru section sub-Division Rohru (SH:- Hiring of Tipper for carriage of excavated earth muck etc.)	297000	5940	Two month
45	R/R Damages to Narkanda Baghi Sungri Khadralla Rohru Raod km RD 0/00 to 67/00 (SH:- C/O R/Wall in PCC 1:4:8 at Rd 51/625 to 51/643)	471802	9436	Two month
46	R/R damages Udoniwas Jakhar road km 0/0 to 5/0 (SH:-C/O B/Wall in wire crate at Rd 0/550 to 0/565)	226426	4529	Two month
47	R/R Damages to various road under Samoli section Sub- Division Rohru (SH: Hiring of Tipper for Carriage of excavated earth muck etc.)	297000	5940	Two month
48	R/R damages to Machoti Chhapoti Kui road km 0/0 to 9/0 (SH:- C/O R/Wall at Rd 1/050 to 1/062)	459663	9193	Two month
49	C/O Dhara Barara Jhaltu road km 0/00 to 2/500 (SH:- C/O B/Wall at Rd 1/399.50 to 1/447	406089	8122	Two month
50	R/R damages on Narkanda Baggi Sungri Khadralla Rohru road km 0/0 to 67/0 (SH:- Widening of black spot at Rd 50/710 to 50/890)	490495	9810	Two month
51	R/R damages on Junidhar kurtu road km (SH:- C/O B/Wall at Rd 2/445 to 2/460)	363905	7278	Two month
52	R/R damages on link road village Barara km 0/0 to 1/0 (SH:- C/O R/Wall at RD 0/550 to 0/570)	445171	8903	Two month
53	C/o main road Lowerkoti to Vahan km 0/00 to 1/300 (SH:- F/C 5/7mtr wide road at Rd 0/180 to 0/225)	437655	8753	Two month
54	R/R Damages to Jakhar to Thakuli Bartu road km 0/00 to 3/00 (SH:- C/O B/Wall at Rd 1/500 to 1/523.1)	498097	9962	Two month
55	R/R Damages on link road to village Baretali road km 0/0 to 1/0 (SH:- C/o B/Wall in PCC 1:4:8 at RD 0/345 to 0/365 & 0/725 to 0/745)	465436	9309	Two month
56	R/R Damages to Bashla Antapu Saraidhar road km 0/0 to 9/0 (SH:- C/O R/Wall at Rd 0/00 to 0/025)	431268	8625	Two month
57	R/R Damages on Dhumadhar Jhatwari mastot Naser Road km Rd km 0/0 to 7/00 (SH:- C/O R/Wall in PCC 1:4:8 at RD 0/165 to 0/180)	436490	8730	Two month
58	R/R damages on Dumadhar Jhatwari Mastot Naser Road km 0/0 to 7/00 (SH:- C/O B/Wall at Rd 1/495 to 1/515)	468680	9374	Two month
59	R/R Damages to Brasli Kenchi Runnda Jhaltu Road km 0/00 to 5/100 (SH:- C/O R/Wall at RD 1/980 to 2/00	491881	9838	Two month
60	C/O Dhara Takroli Barara Jhaltu Road km 0/0 to 2/500 (SH:- C/O Wing wall in PCC 1:4:8 at RD 0/615)	484433	9689	Two month
61	C/O Link road to Village Lakhadhar Mini Gadam Road km (SH:- C/O R/Wall in PCC 1:4:8 at RD 0/600 to 0/612.50)	486553	9731	Two month
62	C/O Link road to Village Lakhadhar Mini Gadam Road km (SH:- C/O R/Wall in PCC 1:4:8 at RD 0/612.50 to 0/625)	486553	9731	Two month

63	R/R Damages to Shalawat Wali Karetali Road (SH:- C/O B/Wall at RD 1/652 to 1/671)	272156	5443	Two month
64	R/R Damages to Hingwala Bagi Nauridhar road km 0/0 to 5/0 (SH:- C/AO R/Wall in wire crate at RD 1/150 to 1/165)	220791	4416	Two month
65	R/R Damages to Samoli Sainji Bhatwari road km 0/0 to 7/0 (SH:- C/O B/Wall in wire crate at RD 4/435 to 4/455)	207565	4151	Two month
66	R/R Damages to Dhara Kapandli Road km 0/0 to 0/600 (SH:- C/O R/Wall at RD 0/335 to 0/345)	473672	9473	Two month
67	R/R Damages on Bhatwari Hingwala Gawas Road km 0/0 to 7/00 (SH:- C/O R/Wall in wire crate at RD 2/980 to 2/985)	468903	9378	Two month
68	R/R Damages to link road from Dashali to Thamanpuri km 0/0 to 2/500 (SH:- C/O R/Wall in PCC 1:4:8 at RD 0/680 to 0/694)	464355	9287	Two month
69	R/R Damages to link road from Dashali to Thamanpuri km 0/0 to 2/500 (SH:- C/O R/Wall in PCC 1:4:8 at RD 0/450 to 0/464)	464355	9287	Two month
70	R/R Damages to link road from Dashali to Thamanpuri km 0/0 to 2/500 (SH:- providing Laying Essential Kharanja stone soling portion Between RD 0/0 to 0/370)	485105	9702	Two month
71	R/R Damages to link road from Dashali to Thamanpuri km 0/0 to 2/500 (SH:- providing Laying Essential Kharanja stone soling portion Between RD 0/370 to 0/740)	485105	9702	Two month
72	Improvement of black spot on Rohru Sungri road km 0/0 to (SH:- Improvement of narrow reaches at Rd 60/560 to 60/605	499211	9984	Two month
73	Improvement of black spot on Rohru Sungri road km 0/0 to (SH:- Improvement of narrow reaches at Rd 60/635 to 60/665)	497895	9958	Two month
74	R/R damages to various roads under Rohru section sub-Division Rohru (SH:- Hiring of JCB for removal of slip and land slide , maintenance of road)	495000	9900	Two month
75	R/R damages on Khorsu kuttu road km RD 0/00 to (SH:- C/O B/Wall in PCC 1:3:6 at RD 0/300 to 0/317)	498025	9961	Two month
76	R/R Damages on Road from Anupam Hotelto Chirgaon Junction km 0/0 to 0/600 (SH:- P/F wire Mesh at RD 0/0 to 0/034	223673	4473	Two month
77	R/R Damages on kansakoti kutara Dalgaon Road km 0/0 to 15/00 (SH:- C/o B/Wall at RD 12/720 to 12/740)	446250	8925	Two month
78	C/O Mastot to Bagi kainchi road km 0/00 to 1/235 (SH:- F/C 5/7 mtr wide road at RD 0/00 to 0/345)	485096	9702	Two month
79	RR Damages to various road under Badiyara section Sub-Division Chirgoan (SH:- Hiring of Tipper for carriage of excavated earth muck)	489600	9800	Two month
80	RR Damages to various road under Badiyara section Sub-Division Chirgoan (SH:- Hiring of Tipper for carriage of excavated earth muck)	489600	9800	Two month
81	RR Damages to various road under Badiyara section Sub-Division Chirgoan (SH:- Hiring of JCB for remaoval of slips and maintenance of road)	489300	9800	Two month
82	RR Damages to various road under Seema section Sub-Division Chirgoan (SH:- Hiring of JCB for remaoval of slips and maintenance of road)	495000	9900	Two month
83	RR Damages to various road under Seema section Sub-Division Chirgoan (SH:- Hiring of JCB for remaoval of slips and maintenance of road and clearance of drain)	495000	9900	Two month
84	RR Damages to various road under Seema section Sub-Division Chirgoan (SH:- Hiring of JCB for remaoval of slips and maintenance of road and clrarance of drain)	495000	9900	Two month
85	RR Damages to various road under Kansakoti Section Sub-Division Chirgoan (SH:- Hiring of JCB for remaoval of slips and construction of unlined surface drain , opening of culv ert and surface of road)	495000	9900	Two month

Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.

Terms and conditions:-The tender document shall be issued only to these contractors/firms who fulfill the following criteria and submit the following document with the application.

1. The Earnest-money for the above works should be submitted with the application for the purchase of the tender-documents.
2. The Contractors should quote the rates of all the items in the tenders both in figures and words.
3. Income tax & GST No latest clearance certificate.
4. The contrs / firm shall accompany his enlistment/renewal & EPF submit before the award of tender.
5. The contractors should apply for two works only at a time for tenders.
6. The Executive Engineer reserves the right to accept/rejected any tender/application or all tenders without assigning any reason.

Executive Engineer,
B&R Division HPPWD,
Rohru.

NO.:-PW-RD-AB-Tender /2023-24- 24249-24348

Dated:- 20-2-2024

Copy forwarded for information and wide publicity to:-

1. The Chief-Engineer(S), HPPWD, Shimla-2.
3. The S E 14th Circle HPPWD, Rohru
4. All the E.E.'s under 14th Circle, HPPWD, Rohru
5. All the A.E.'s working under this Division (B&R).
6. The Sub Divisional Magistrate, Rohru.
7. The B.D.O. Rohru and Chirgaon.
8. The Tehsildhar, Rohru/Chirgaon and Tikkar.
9. The Chairman, N.A.C. Rohru.
10. A/B. and D/B. in this Office.
11. Notice-Board.

Executive Engineer,
B&R Division HPPWD
Rohru.

A/B.

③ ①

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O to HP.PWD. Rest House at Surgri in Tehsil Rohru Dist. Shimla HP. (SH:-C/O U-Shape drain and greating over drain)

Estimated Cost:-478901/-
Earnest Money:-9600/-
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m. dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	20.53	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	8356
2	Plain reinforced cement concrete (1:3:6) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 as directed by the Engineer-in-Charge	29.75	6972.00	Rupees:-Six Thousand Nine Hundred Seventy Two Paisa Zero only.	Cum	207417
3	Steel work welded in built up sections, trusses and framed work, included cutting, hoisting, fixing in position and applying a priming coat of red lead paint gratings framed guard bars, leaders railing brackets and similar work as directed by the Engineer-in-Charge	19.71	13350.00	Rupees:-Thirteen Thousand Three Hundred Fifty Paisa Zero Only.	Cum	263129
Total:-						478901
DNIT No. Approved for Rs.478901/- only for the Year 2023-2024						
Quoted rate in figure						
Quoted rate in words						
Signature of contractor with address:-						

Executive Engineer
B&R Division
HP PWD Rohru

SCHEDULE OF QUANTITY

NAME OF WORK:-R/R damages Udho Niwas Jakhar Niwas Jakhar Rantari road km.0/0 to 12/0 (SH:-C/O R/wall at RD.0/332 to 0/354)

Job No. 2
Estimated Cost:-456143/-
Earnest Money:-9122/-
Time:-Two Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	21.67	183.20	Rupees:-One Hundred Eighty Three and Paisa Two Zero only	Cum	3970
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	31.02	430.00	Rupees:-Four Hundred Thirty and Paisa Zero only	Cum	13339
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	9.46	5234.90	Rupees:-Five Thousand Two Hundred Thirty Four and Paisa Nine Zero only	Cum	49522
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	3.74	5758.00	Rupees:-Five Thousand Seven Hundred Fifty Eight and Paisa Zero only	Cum	21535
5	Random Rubble Stone masonry in cement mortar 1:6 (1 Cement : 6 sand) for foundation complete as as per drawings and technical specification Clauses 702, 704,1202 and 1203 including carriage of material within all leads and lifts as per directions of Engineer in charge	31.90	5250.00	Rupees:-Five Thousand Two Hundred Fifty Paisa Zero Only.	Cum	167475
6	Construction of dry rubble masonry for retaining wall . breast walls , revement walls and parapets etc for sub-structure and super structure complete as per drawings and technical specification Clauses 704.6,1302.5. as directed by the Engineer-in-Charge	47.480	3937.70	Rupees:-Three Thousand Nine Hundred Thirty Seven Paisa Seven Zero only	Cum	186962
7	Providing and laying of back filling behind abutment wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	10.89	1225.00	Rupees:-One Thousand Two Hundred Twenty Five Paisa Zero only.	Cum	13340
				Total:-		456143
	Quoted rate in figure					
	Quoted rate in words					
	Signature of contractor with address:-					

Executive Engineer
B&R Division
HP.PWD Rohru

~~16/1~~ SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages to Dhara Bhalara road km. 0/0 to 6/0 (SH:-C/O Hume pipe culvert at RD.3/225 H=365 Mtrs.)

Job No.
Estimated Cost:-403568/-
Earnest Money:-8100/-
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and technical Specification Clause 1603.1 as directed by the Engineer-in-charge	12.80	324.80	Rupees-Three Hundred Twenty-Four and Paise Eighty only	Cum	4158
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-charge	44.68	407.00	Rupees-Four Hundred Seven and Paise Zero only	Cum	18185
3	Plain reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 as directed by the Engineer-in-charge	6.518	6314.00	Rupees-Six Thousand Three Hundred Fourteen Paise Zero Only.	Cum	41155
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 as directed by the Engineer-in-charge	5.82	6656.00	Rupees-Six Thousand Six Hundred Fifty Six Paise Zero Only.	Cum	38738
5	Randon Rubble Stone masonry in cement mortar for sub structure complete as per drawings and technical specification Clauses 702, 704, 1202 and 1203 in cement mortar 1:5 as directed by the Engineer-in-charge	7.71	6567.89	Rupees-Six Thousand Five Hundred Sixty Seven Paise Eighty Nine Only.	Cum	50638
6	Randon Rubble Stone masonry in cement mortar for sub structure complete as per drawings and technical specification Clauses 702, 704, 1202 and 1204 random rubble masonry in cement mortar 1:6 as directed by the Engineer-in-charge	21.62	5400.00	Rupees-Five Thousand Four Hundred Paise Zero Only	Cum	116748
7	Construction of dry rubble masonry for retaining wall, breast walls, revement walls and parapets etc for sub-structure and super structure complete as per drawings and technical specification Clauses 704.6, 302.5 as directed by the Engineer-in-charge	18.176	4082.27	Rupees-Four Thousand Eighty Two Paise Twenty Seven only	Cum	74199
8	Providing and laying of back filling behind abutment wing wall and return walls with granular material complete as per (MOR) technical specification clause 1204.3.8 as directed by the Engineer-in-charge	11.76	1474.00	Rupees-One Thousand Four Hundred Seventy Four Paise Zero only.	Cum	17334

9	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection works backing filling concrete and masonry works in head walls and parapets clause 1106 as directed by the Engineer-in-Charge	7.50	4439.32	Rupees:-Four Thousand Four Hundred Thirty Nine Paissa Thirty Two only.	Cum	33295
10	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1303 as directed by the Engineer-in-Charge	0.49	14189.51	Rupees:-Fourteen Thousand One Hundred Eighty Nine Paissa Fifty One only.	Cum	6953
11	Providing and laying of earth filling lift up to 1050 mtrs. And disposal u to 20 mtrs. with in all leads and lifts as directed by the Engineer-in-Charge	6.24	346.92	Rupees:-Three Hundred Forty Six Paissa Ninety Two only.	Cum	2165
				Total:-		403568
				Approved for Rs.403568/- only for the Year 2023-2024		
				DNIT No.		
				Quoted rate in figure		
				Quoted rate in words		
				Signature of contractor with address:-		
				Executing Engineer B&R Division I. P. W D Rohru		

Executive Engineer
 B&R Division
 PWD Kohru

Job No.	4
Estimated Cost:-	499433/-
Earnest Money:-	10000/-
Time:-	One Month

Estimated Cost:-499433/-
Earnest Money:-10000/-
Time:-One Month

Time:-One Month

NAME OF WORK:-C/O Rantari Kandari road km.0/0 to 2/235 (SH:-F/C 5/7 Mtrs. Wide road at RD.1/780 to 1/990)	Time:-0
Sl.no.	
Item of work	

	ITEM OR WORK	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300, 1603.1, 1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber, embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machineries, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 269.19 cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.	1755.60	284.480	Rupees:-Two Hundred Eighty Four and Paise Four Eight Zero only	Cum	499433
				Total:-		499433
	Quoted rate in figure		%			
	Quoted rate in words		%			
	Signature of contractor with address:-					

Executive Engineer
B&R Division
HP.PWD Rohru

**Executive Engineer
B&R Division
HP.PWD Rohru**

26

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages to Khadrata Bajeshal road km. 0/0 to 4/0 (SH-C/O R/wall in PCC wall at RD.3/0 to 3/09)

Job No. **5**
Estimated Cost:-418027/-
Earnest Money:-8400/-
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	8.33	324.80	Rupees:-Three Hundred Twenty Four and Paisa Eighty only	Cum	2706
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.as directed by the Engineer-in-Charge	13.59	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	5531
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203.as directed by the Engineer-in-Charge	3.42	5642.86	Rupees:-Five Thousand Six Hundred Forty Two and Paisa Eight Six only	Cum	19299
4	Plain/reinforced cement concrete (1:3:6) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203.as directed by the Engineer-in-Charge	47.61	6972.00	Rupees:-Six Thousand Nine Hundred Seventy Two Paisa Zero only.	Cum	331937
5	Providing weephole in brick masonry /stone masonry .plain /reinforced concrete abutment wing wall, return wall with 100mm dia AC pipe extending through the full width of the structures with slope of 1 (V):20(H) towards drawing face complete as per drawings and technical specification Clauses614,709,1204,3,7.as directed by the Engineer-in-Charge	22.50	464.79	Rupees:-Four Hundred Sixty Four Paisa Seven Nine only.	No.	10458
6	Providing and laying of back filling behind abutment wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	32.63	1474.00	Rupees:-One Thousand Four Hundred Seventy Four Paisa Zero only.	Cum	48097
Total:-						418027

DNT No. Approved for Rs.418027/- only for the Year 2023-2024

Quoted rate in figure
Quoted rate in words
Signature of contractor with address:-

Executive Engineer
B&R Division
HP,PWD Rohru

SCHEDULE OF QUANTITIES

NAME OF WORK:- Restoration of rain damages on Link road to village Jakhar (SH:- C/O Retaining wall at RD. 0/300 to 0/315)

Job No. (6)

ESTIMATED COST:-Rs. 4,39,198.00

EARNEST MONEY:- Rs. 8800.00

TIME ALLOWED:- One Month

Sr.N	Sub-Head and Item of works.	Quantity	Rate in figures.	Rate in words.	Unit	Amount.
1	Excavation in soil in Hilly Area in all kind of sand by mechanical/manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead and lift as per Technical Specification Clause 1603.1 and as per HPPWD, specification of 1990 Volume-1, or as directed by the Engineer-In-Charge.	18.30	303.17	Rupees Three Hundred & Three - Paise Seventeen Only	Per cubic metre	5548.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a any lead and lift, dressing of sides and bottom and backfilling in trenches with excavated suitable material useful material available from excavation to be properly stacked and handed over to the department free of cost including all leads and lifts, as per HPPWD, specification of 1990 volume-1 or as directed by the Engineer-In-Charge	13.50	529.17	Rupees Five Hundred & Twenty Nine - Paise Seventeen Only	Per cubic metre	7144.00
3	Providing and Laying concrete 1:6:12 (1cement: 6 sand: 12 graded stone aggregate 40mm nominal size)for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 702, 802, 803, 1202 and 1203 including all leads and lifts, as per HPPWD, specification of 1990 volume-1 or as directed by the Engineer-In-Charge	4.73	5400	Rupees Five Thousand Four Hundred Only	Per cubic metre	25542.00
4	Providing and Laying concrete 1:3:6 (1cement: 3 sand: 6 graded stone aggregate 40mm nominal size)for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 702, 802, 803, 1202 and 1203 including all leads and lifts, as per HPPWD, specification of 1990 volume-1 or as directed by the Engineer-In-Charge	56.93	6810	Rupees Six Thousand Eight Hundred & Ten Only	Per cubic metre	387693.00
5	Backfilling with Granular material behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including all leads and lifts, as per HPPWD, specification of 1990 volume-1 or as directed by the Engineer-In-Charge	10.95	1212	Rupees One Thousand Two Hundred & Twelve Only	Per cubic metre	13271.00
Total						

D.N.I.T No: for the year 2023-24 duly approved for 439198.00

Rates quoted by the contractor (in Figure) in percentage%(Above or Below)

Rates quoted by the contractor (in Word) in percentage%(Above or Below)

Sign & Name of Contractor with address:-

Executive Engineer,
Rohru Division
HP.PWD., Rohru.

Schedule of Qty

Name of Work:- R/R Damage to Summerkot Tilkari Shalwat road km 0/00 to 3/00 (SH:- C/o B/wall in wire crate at RD 2/600 to 2/640)

Name of Work:- R/R Damage to Summerkot Tilkari Shalwat road km 0/00 to 3/00 (SH:- C/o B/wall in wire crate at RD 2/600 to 2/640)							ESTIMATED COST		341964
							EARNEST MONEY		6839
							TIME LIMIT:		Two Month
Sr. No	Description of items.	Qty	Unit	Rate		In Words	Amount.		
				In Fig.	5			6	7
1	2 Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	3	4 cum	5 324.83	6 Rupees Three Hundred & Twenty Four - Paise Eighty Three Only	7 10914			
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	16.8	cum	407	Rupees Four Hundred & Seven Only	6838			
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	125	cum	2593.7	Rupees Two Thousand Five Hundred & Ninety Three - Paise Seventy Only	324213			
Total						341964			

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer
B&R Division HPPWD
Rohru

SCHEDULE OF QUANTITY

NAME OF WORK:-C/O Shalawat Wali Kareilly road (SH:-Widening of road for Bus Stand at RD.2/195 to 2/225)

Job No.	19
Estimated Cost:-174930/-	
Earnest Money:-3500/-	
Time:-Two Month	

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. Technical Specification Clause 300.1603.1, 1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber, embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing and carriage of machines materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work, hard rock 1/6th (One sixth) blasting work, soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 112.00 cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge	600.00	291.550	Ruppes:-Two Hundred Ninety One and Paise Five Five Zero only	Cum	174930
Total:-						174930

Quoted rate in figure	%
Quoted rate in words	%
Signature of contractor with address:-	

Executive Engineer
B&R Division
H.P.W.D Rohru

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages to Thamtari Junidhar School Naunapani road km. 0/0 to 4/500 (SH:-C/O R/wall at RD.0/150 to 0/158)

Job No. 9
Estimated Cost:-349627/-
Earnest Money:-7000/-
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 within all leads and lifts as per directions of Engineer in charge	24.48	324.83	Rupees:-Three Hundred Twenty Four and Paisa Eighty Three only	Cum	7952
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. within all leads and lifts as per directions of Engineer in charge	19.10	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	7774
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	6.32	5109.04	Rupees:-Five Thousand One Hundred Nine and Paisa Zero Four only	Cum	32289
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	3.76	5710.66	Rupees:-Five Thousand Seven Hundred Ten Paisa Six Six Only.	Cum	21472
5	Random Rubble Stone masonry in cement mortar 1:6 (1 Cement : 6 sand) for foundation complete as per drawings and technical specification Clauses 702, 704, 1202 and 1203 including carriage of material within all leads and lifts as per directions of Engineer in charge	29.12	5400.00	Rupees:-Five Thousand Four Hundred Paisa Zero Only.	Cum	157248
6	Construction of dry masonry in retaining walls, breast walls etc.as per drawings and technical specification including carriage of material within all leads and lifts as per directions of Engineer in charge	31.42	3677.35	Rupees:-Three Thousand Six Hundred Seventy Seven Paisa Three Five Only.	Cum	115542
7	Providing and laying of back filling behind abutment wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	5.52	1331.51	Rupees:-One Thousand three Hundred thirty one and Paisa Five One only	Cum	7350
Total:-						349627
	Quoted rate in figure			%		
	Quoted rate in words			%		
	Signature of contractor with address:-					

Executive Engineer
B&R Division
HP.PWD Rohru

~~PART~~ SCHEDULE OF QTY.

10

Name of Work:- R/R Damage to Paudhar to Mandevari road km 0/00 to 12/00 (SH:- C/o B/wall at Rd 0/510 to 0/540)

Sr. No	Description of items.	Qty	Unit	Rate	In Words	Amount.
				In Fig.		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	24.00	cum	176.83	Rupees One Hundred & Seventy Six - Paise Eighty Three Only	4244
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	34.50	cum	430.5	Rupees Four Hundred & Thirty - Paise Fifty Only	14852
3	P/L Cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate forty millimeter nominal size)for plain/ reinforced concrete work in open foundation complete as per drawing and technical specification Clauses 802,803,1202& 1203.	11.50	cum	4693.08	Rupees Four Thousand Six Hundred & Ninety Three - Paise Eight Only	53970
4	Stone masonry in cement mortar for substructure complete as per drawing& technical specification Clause 702,704,1202 and1204 Random rubble masonry in cement motar(1:6).	82.25	cum	4821.19	Rupees Four Thousand Eight Hundred & Twenty One - Paise Nineteen Only	396543
Total			cum			469610

DNIT No.....approved for amounting to Rs.-469610/- for the year 2023-24

Executive Engineer
B&R Division HPPWD
Rohru

(11)

BRIEF SCHEDULE OF WORKS

Name of Work:- R/R Damage to Paudhar to mandevari road km 0/00 to 12/00 (SH:- C/o R/wall at Rd 0/580 to 0/590)

Name of Work:- R/R Damage to Paudhar to mandevari road km 0/00 to 12/00 (SH:- C/o R/wall at Rd 0/580 to 0/590)		ESTIMATED COST		287664		
		EARNEST MONEY		5753		
		TIME LIMIT:		2 Months		
Sr. No	Description of items.	Qty	Unit	Rate	In Words	Amount.
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	14.50	cum	176.83	Rupees One Hundred & Seventy Six - Paise Eighty Three Only	2564
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	21.40	cum	430.5	Rupees Four Hundred & Thirty - Paise Fifty Only	9213
3	P/L Cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate forty millimeter nominal size)for plain/ reinforced concrete work in open foundation complete as per drawing and technical specification Clauses 802,803,1202& 1203.	6.80	cum	4693.08	Rupees Four Thousand Six Hundred & Ninety Three - Paise Eight Only	31913
4	Providing concrete for plain/reinforced concrete in open foundation R/B walls complete as per drawing and technical specification clause 802,803,1202 & 1203 Grade (1:4:8) 1cement :4 sand : 8 graded stone aggregate.	4.30	cum	5216.02	Rupees Five Thousand Two Hundred & Sixteen - Paise Two Only	22429
5	Stone masonry in cement mortar for substructure complete as per drawing& technical specification Clause 702,704,1202 and1204 Random rubble masonry in cement motar(1:6).	24.50	cum	4821.19	Rupees Four Thousand Eight Hundred & Twenty One - Paise Nineteen Only	118119
6	Construction of dry masonry in Retaining walls etc . As per HPPWD specification	29.36	No	3275.42	Rupees Three Thousand Two Hundred & Seventy Five - Paise Fourty Two Only	96153
7	Back filling behind abutment,wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material.	6.00	cum	1212.19	Rupees One Thousand Two Hundred & Twelve - Paise Nineteen Only	7273
Total			cum			287664

DNIT No.....approved for amounting to Rs.-287664/- for the year 2023-24

Executive Engineer
B&R Division HPPWD
Rohru

12

SCHEDULE OF QUANTITY

NAME OF WORK:-R/R damages to Jakhar Besraia Thakulidhar Bartu road km.0/0 to 3/500(SH:-C/O B/wall in wire crate at RD. 0/085 to 0/105)

Job No. _____
 Estimated Cost:-401939/-
 Earnest Money:-8100/-
 Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	105.00	324.80	Rupees:-Three Hundred Twenty Four and Paisa Eighty only	Cum	34104
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	30.00	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	12210
3	Providing and laying of boulder apron laid in wire crates with 4 mm (four) millimetre dia GI wire conforming to 18280 and IS: 4826 in 100 mm x 100 mm (hundred millimetre x hundred molimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps end joints laid with stone boulders weighing not less than 2.5 (twenty five)kilogramme each as per drawing and MORD Technical Specifications Clause 1301 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	125.00	2845.00	Rupees:-Two Thousand Eight Hundred Forty Five and Paisa Zero only	Cum	355625
	Total:-					401939
	Quoted rate in figure					
	Quoted rate in words					
	Signature of contractor with address:-					

Executive Engineer
B&R Division
HP.PWD Rohru

Name of work :- R/R Damages on Annu Thamtari road km. 0/0 to 1/250 (SH:- C/O R/Wall at RD 0/99 to 0/103).

SCHEDULE OF QUANTITY

Job No:-10

Estimated Cost Rs. 3,91,986.00
Earnest Money Rs. 7900.00
Time one Month

Sr No	Description Of Items	Quantity	Rate		Unit	Amount
1	Excavation in hilly areas in soil by manual means . Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per drawing and Technical Specification Clause 1603.1	11.40	324.80	Rupees three hundred twenty four and paise eighty only	Per cubic meter.	3703.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a any lead and lift , dressing of sides and bottom and backfilling in trenches with excavated suitable material,useful material available from excavation to be properly stacked and handed over to the department free of cost including all leads and lifts, as per HPPWD, specification of 1990 volume-I or as directed by the Engineer-In-Charge	13.20	407.00	Rupees four hundred seven only	Per cubic meter.	5372.00
3	Plain/reinforced cement concrete (1:3:6) in open foundation completed as per drawings and technical specification clauses 802,803,1202 & 1203. as directed by the Engineer -In Charge.	52.50	6965.00	Rupees six thousand nine hundred seventy six five Only.	Per cubic meter.	365663.00
4	Back filling behind abutment wing wall and return complete as per drawing and technical specification including all leads and lifts as per directed by the Engineer In Charge.	6.30	1422.70	Rupees one thousand four hundred twenty two and paise seventy only.	Per cubic meter.	8963.00
5	Providing weephole in brick masonry/stone masonry ,plain/reinforcement cement concrete abutment,wing wall, return wall with 100mm dia AC pipe extending through the full width of structure with slop of 1(V);20(H) towards drawing face complete as per drawing and technical specification clauses614,709,1204.3.7.	20.00	414.27	Rupees four hundred fourteen and paise twenty seven only	Each	8285.00
	Total					391986.00

Quoted rate in figure :-

do words :-

Signature of Contractor with address :-

DNIT No. for the year 2023-24 duly approved for Rs. 3,91,986/- only.

Executive Engineer,
Rohru Division,
H.P. PWD, Rohru

SCHEDULE OF QUANTITY

Job No. 14
Estimated Cost:-488369/-
Earnest Money:-9800/-
Time:-One Month

NAME OF WORK:-R/R damages to Kansakoti Kutara Dalgaon road km.0/0 to 15/300(SH:-Widening of road at RD.10/900 to 10/960 & 11/210 to 11/315,11/315 to 11/750)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1603.1,1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber, embankments for grade improvements and disposal of all of transportation including head load or animals transport or mechanical means, through all modes levelling fine dressing and carriage of machines, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 261.22 cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.	1819.65	268.386	Rupees:-Two Hundred Sixty and Paise Three Eight Six only	Cum	488369
Total:-						488369
	Quoted rate in figure					
	Quoted rate in words					
	Signature of contractor with address:-					

Executive Engineer
B&R Division
HP.PWD Rohru

15

Estimated Cost:-495727/-
Earnest Money:-9915/-

Time:-Two Month

**Executive Engineer
B&R Division
HP.PWD Rohru**

Job No.:- 16

SCHEDULE OF QUANTITY

Estimated Cost:-432454/-

Earnest Money:-8700/-

Time:- Three Month

NAME OF WORK:-C/O link road from Kalu Nallah to HB.Shakti Nager Gram Panchyat Karasa road(SH:-C/O B/wall in wire crate at RD. 0/240 to 0/295)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	45.00	324.83	Rupees:-One Hundred Ninety Six and Paisa Thirty only	Cum	14617
2	Earthwork in excavation for structures as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	28.12	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	11445
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	140.62	2890.00	Rupees:-Two Thousand Eight Hundred Ninety Paissa Zero only.	Cum	406392
				Total:-		432454
		DNIT No. Approved for Rs.432454/- only for the Year 2023-2024				
Quoted rate in figure		%				
Quoted rate in words		%				
Signature of contractor with address:-		Executive Engineer B&R Division HP.PWD Rohru				

Executive Engineer
B&R Division
HP.PWD Rohru

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages to Machoti Dhara Kui road km.0/0 to 9/0(SH:-C/O B/wall in wire crate at RD.4/0 to 4/040)

Job No. 17
 Estimated Cost:-388875/-
 Earnest Money:-7700/-
 Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	64.00	324.80	Rupees:-Three Hundred Twenty Four and Paisa Eighty only	Cum	20787
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	16.80	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	6838
3	Providing and laying of boulder apron laid in wire crates with 4 mm (four) millimetre dia GI wire conforming to 18280 and IS: 4826 in 100 mm x 100 mm (hundred millimetre x hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps end joints laid with stone boulders weighing not less than 2.5 (twenty five)kilogramme each as per drawing and MORD Technical Specifications Clause 1301 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	125.00	2890.00	Rupees:-Two Thousand Eight Hundred Ninety and Paisa Zero only	Cum	361250
Total:-						388875
	Quoted rate in figure					
	Quoted rate in words					
	Signature of contractor with address:-					

Executive Engineer
 B&R Division
 HP.PWD Rohru

SCHEDULE OF QUANTITY

Estimated cost Rs. 491590/-
Earnest Money Rs 9800/-
Time one month

of work :- R/R damages from Khorpu Nailah to village Sharu Km 0/0 to 3/0 (SH- C/O R/wall at RD 1/320 to 1/332)

Description of Items	Quantity	Rate in Figure.	Rate in Words	Unit	Amount
Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per drawing and Technical Specification Clause 1603.1 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	21.89	324.83	Rs three hundred twenty four & paise eighty three only	per cubic metre	7111
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. in ordinary rocks up to 3 mtr depth within all leads and lifts as per directions of Engineer in charge	21.89	407.00	Rs four hundred seven hundred only.	per cubic metre	8909
Providing and laying cement concrete 1:6:12 (one cement six sand twelve graded stone aggregate 40mm nominal size for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 including carriage of materials within all leads and lifts as per directions of Engineer in charge	7.92	5839.05	Five thousand eight hundred thirty nine & paise five only	per cubic metre	46245
Providing and laying mechanical mixed and vibrated cement concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:4:8 (One cement : four sand : eight graded crushed stone aggregate) 25 mm specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	5.28	6656.00	Rs six thousand six hundred fifty six only	per cubic metre	35144
Random rubble masonry polygonal rubble masonry uncoursed brought to courses with hard stone of approved quality in foundation and plinth cement mortar 1:6 (1cement:6sand)breast wall and retaining wall within all leads and lifts as per directions of Engineer in charge	41.72	5400.00	Rs five thousand four hundred only	per cubic metre	225288
Construction of dry rubble masonry for retaining walls breast wall revementment walls and parapets etc for sub structure complete as per drawing and technical specification clause 704.6 and 1305 within all leads and lifts as per direction of Engineer in charge	37.80	4082.00	Rs four thousand eighty two only	per cubic metre	154300
Back filling behind abutment wing wall and return wall with granular materials complete as per drawing and technical specification clause 1204.3.8 including carriage of materials within all leads and lifts as per directions of Engineer in charge	9.90	1474.00	Rs one thousand four hundred seventy four only	per cubic metre	14593
Total:-					491590

DNIT NO Approved for Rs:491590/- for the year 2023-24

Rate in figure (+) (-)
Rate in Words (+) (-)
%

of Contractor with full Address

Executive Engineer
B&R Divn HP, PWD
Khorpu

SCHEDULE OF QUANTITY

Job No. **19**
 Estimated Cost:-481255/-
 Earnest Money:-9700/-
 Time:- One Month

NAME OF WORK:-C/O Anu Maian to Karlash Kanchi road km.0/0 to 2/500 (SH:-Widening of road at RD.0/105 to 0/315)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1,603.1,1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber, embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machineries, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government A recovery of useful stones 133.95 cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.	2135.74	225.334	Rupees:-Two Hundred Twenty Five and Paise Three Three Four only	Cum	481255
Total:-						481255
DNIT No.						Approved for Rs.481255/- only for the Year 2023-2024
Quoted rate in figure						%
Quoted rate in words						%
Signature of contractor with address:-						

Executive Engineer
 B&R Division
 HP.PWD Rohru

BRIEF SCHEDULE OF QUANTITY

Job No. 20
 Estimated Cost:-436118/-
 Earnest Money:-8700/-
 Time:-One Month

NAME OF WORK:-R/R damages on Narkanda Baggi Sungri Khadirala Rohru road km. 0/0 to 67/0 (SH:-F/C Widening of Black spot at RD. 57/305 to 57/470)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/vee-ging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 360.1, 603.1, 1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, canker embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing and carriage of machineries, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (One Tenth) juniper work in all cases filling which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Maikana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 329.31 cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be reported by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified dimension in all leads and lift as per the direction of Engineer in charge.	1097.70	397.302	Rupees:-Three Hundred Ninety Seven and Paise Three Zero Two only	Cum	436118
Total:-						436118
DNIT No. <u>1546</u> Approved for Rs.436118/- only for the Year 2023-2024						
Quoted rate in figure						
Quoted rate in words						
Signature of contractor with address:-						

Executive Engineer
 B&R Division
 HP.PWD Rohru

OF SCHEDULE OF QUANTITY .

Estimated cost Rs.469619/-
Earnest money Rs 9300/-
TIME : Two month

21

Name of work : -C/O Chiku Dabbar Gaddali road km 0/0 to 1/0 (SH- 5/7 metre wide road at Rd 0/240 to 0/270)

Sr No	Description of items	Quantity	Rate in Figure.	Rate in Words	unit	Amount
1	Excavation in earth work in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side. Water pollution, etc and to protect soil stability of hill side rock shall be excavated with chiselling and wedging our rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to line, grades, slopes, width, camber, super elevation and level as shown on the drawing as per direction of Engineer in Charge in conformity with the requirement of technical specification for rural roads august 2004 clause 16.2 of general conditions of contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and stage, disposal of unsuitable cut material in specified manner, trimming/filling of unevenness blindage and finishing of the road to specified dimensions or as directed by Engineer in charge for smooth riding. The recovery of useful stones shall be made @300/-per cubic meter on prorata basis in each running bill. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified /dimension in all leads and lifts as per the direction of Engineer in Charge.	1547.81	303.40	Three hundred three & paise forty only	per cubic metre	469619/-
	Total:-					469619.00

DNIT NO Approved for Rs 4,69,619/-for the year 2023-2024

Quoted Rate in figure (+)(-)

%

Quoted Rate in Words (+)(-)

%

Singture of Contractor with full Address

Executive Engineer
B&R Dym HP.PWD
Rohru

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages on Bhatwari Hingwala Gawas road km. 0/0 to 7/0 (SH:-C/O 900mm Dia Hume Pipe culvert in PCC 1:4:8 at RD.0/320 and wing wall)

Job No. 22
Estimated Cost:-416508/-
Earnest Money:-8400/-
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	10.52	290.00	Rupees:-Two Hundred Ninety and Paisa Zero only	Cum	3051
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	25.90	495.00	Rupees:-Four Hundred Ninety Five and Paisa Zero only	Cum	12821
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	7.02	5490.00	Rupees:-Five Thousand Four Hundred Ninety and Paisa Zero only	Cum	38540
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	46.74	6210.00	Rupees:-Six Thousand Two Hundred Ten Paisa Six Six Only	Cum	290255
5	Providing and laying concrete 1:2:4 (1 Cement, 2 sand, 4 graded stone aggregate 20mm nominal size) for compacting concrete and curing complete excluding cost of form work reinforcement for reinforced concrete work with in all leads and lifts as per directed by the Engineer-in-Charge	1.90	8450.00	Rupees:-Eight Thousand Four Hundred Fifty and Paisa Zero only	Per Cum	16055
6	Providing and laying of back filling behind abutment wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3, 8 as directed by the Engineer-in-Charge	5.84	1400.00	Rupees:-One Thousand Four Hundred Paisa Zero only.	Cum	8176
7	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection works backing filling concrete and masonry works in head walls and parapets clause 1106 as directed by the Engineer-in-Charge	7.50	5600.00	Rupees:-Five Thousand Six Hundred Paisa Zero only.	Cum	42000
8	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1202 & 1204 (1:2:4) as directed by the Engineer-in-Charge	0.49	11450.00	Rupees:-Eleven Thousand Four Hundred Fifty Paisa Zero only	Cum	5611
				Total:-		416508
	Quoted rate in figure					
	Quoted rate in words			%		
	Signature of contractor with address:-			%		

Executive Engineer
B&R Division
HP.PWD Rohru

Job No.: 23

SCHEDULE OF QUANTITY

NAME OF WORK--:R/R damages on various road under Rohru Sub-Division (Rohru Section)(SH:-Hiring of JCB for removal of slips ,slush/liquid slide & maintenance of road etc.)		Job No.:- 25		Estimated Cost:-	252000	
				Earnest Money:-	5040	
		Time:-		One Month		
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Hiring of JCB (Excavator cum loader)front end loader 0.50cum/ hour including POL charges shifting and other ancillary equipments as required at site of work for removal of slips in all heights and all kinds of soils such as kankar moorum shingle boulders decomposed or soft variety of soil such a spade work pick work junner work soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this undrivable materials has to be done in the acquired width of the road to avoid the damage to the properties of the people or in case any damage took place the contractor shall be liable for its. All salvaged materials such as quarried stone shall belong to the department and mankurnam useful quantity of stones from removal of slips shall be to be neatly stacked along road side on road berms minimum 18.00 cubice metre of earth work shall be done by the machine in one hours ans 200 cum of snow shell be removed from the road surface in one hour other wise number of hours shall be reduced accordingly. The work shall have to be carried out as per ministry of transport and as per instruction of the Engineer in charge including all leads and lifts	30.00	8400.00	Rupess:-Eight Thousand Four Hundred and Paise Zero only	Per Day	252000
		Total:-				252000
						%
						%
						Quoted rate in figure
						Quoted rate in words
						Signature of contractor with address:-

Executive Engineer
B&R Division
HP,PWD Rohru

Executive Engineer
B & R Division
H.P.W.D Rohru

211

SCHEDULE OF QUANTITY

NAME OF WORK:-C/O Butthara Nursery to Katmori road km.0/0 to (SH-F/C 5/7 Mtrs. Wide road at RD. 0/0 to 0/285)

Job No. 24
Estimated Cost:-499721/-
Earnest Money:-10000/-
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
4	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300,1603.1,1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber, embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machineries, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 63.59 cum. metre @ RS. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.	2700.00	185.082	Rupees:-One Hundred Eighty Five and Paisa Zero Eight Two only	Cum	499721
	Total:-					499721

Quoted rate in figure	%
Quoted rate in words	%
Signature of contractor with address:-	

Executive Engineer
B&R Division
HP.PWD Rohru

SCHEDULE OF QUANTITY

Job No. **25**
 Estimated Cost:-466778/-
 Earnest Money:-9400/-
 Time:-One Month

NAME OF WORK:- C/O link road from Kancora to Harijan Basti Bhammalah km. 0/0 to 1/500 (SH-C/O R/wall in PCC at RD-0/145 to 0/165) under SCCP

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	9.00	304.00	Rupees:-Three Hundred Four and Paisa Fifty only	Cum	2736
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material, with in all leads and lifts as per directed by the Engineer-in-Charge	20.40	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	8303
3	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	63.00	6656.00	Rupees:-Six Thousand Six Hundred Fifty Six Paisa Zero Only.	Cum	419328
4	Providing weephole in brick masonry /stone masonry, plain/ reinforced concrete abutment wing wall, return wall with 100mm dia AC pipe extending through the full width of the structures with slope of 1 (V):20(H) towards drawing face complete as per drawings and technical specification Clauses 614, 709, 1204, 3.7 as directed by the Engineer-in-Charge	26.00	414.00	Rupees:-Four Hundred Forteen Paisa Zero only.	No.	10764
5	Providing and laying of back filling behind wing wall and return walls with granular material complete as per MORID technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	17.40	1474.00	Rupees:-One Thousand Four Hundred Seventy Four and Paisa Zero only	Cum	25648
Total:-						466778
DNIT No. _____ Approved for Rs.466778/- only for the Year 2023-2024						
Quoted rate in figure						99
Quoted rate in words						99
Signature of contractor with address:-						

Executive Engineer
 B&R Division
 HP.PWD Rohru

Job No.:-

160
(21)

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages on various road under Rohru Sub-Division (Rohru Section)(SH:-Hiring of JCB for removal of slips and land slide maintenance of roas and drain)	Estimated Cost:-	495000
	Earnest Money:-	9900
	Time:-	Two Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1						
1	Hiring of JCB (Excavator cum loader) front end loader 0.50 cum/ hour including POL charges shifting charge and other ancillary equipments as required at site of work for removal of slips in all heights and all kinds of soils such as kankar moorum shingle boulders decomposed or soft variety of soil such a spade work pick work junner work soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this undervicable materials has to be done in the acquired width of the road to avoid the damage to the properties of the people or in case any damage took place the contractor shall be liable for its. All salvaged materials such as quirted stone shall belong to the department and manikunum useful quantity of stones from removal of slips shall be to be neatly stacked along road side on road berms minimum 18.00 cubice metre of earth work shall be done by the machine in one hours ans 200 cum of snow shell be removed from the road surface in one hour other wise number of hours shall be reduced accordingly. The work shall have to be carried out as per ministry of transport and as per instruction of the Engineer in charge including all leads and lifts	450.00	1100.00	Ruppes:- One Thousand One Hundred and Paise Zero only	Per Hours	495000
Total:-						495000
Quoted rate in figure						
Quoted rate in words						
Signature of contractor with address:-						

Executive Engineer
B&R Division
HP.PWD Rohru

Estimated Cost:-252000/-

Time:-One Month

SH: Hiring of JCB for removal of slips at various RDs.

**Executive Engineer
B&R Division
HP.PWD Rohru**

Job No.

28

SCHEDULE OF QUANTITY

Estimated Cost:-495000/-
 Earnest Money:-10000/-
 Time:-One Month

NAME OF WORK:- R/R damages on various road under Kansakoti Section (Rohru Sub-Division)(SH:-Hiring of JCB for removal of slips and land slide maintenance of road)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Hiring of JCB (Excavator cum loader having bucket capacity 0.50cum including POL. charges shifting charge and other ancillary equipments as required at site of work for removal of slips in all heights and all kinds of soils such as kankar morum shingle boulders decomposed or soft variety of soil such a spade work pick work inner work soft rock hard rock including their intermediate classification of soil including mechanical transport if and when required The disposal of this underecable materials has to be done in the acquired width of the road to avoid the damage to the properties of the people or in case any damage took place the contractor shall be liable for its. All salvaged materials such as quarried stone shall belong to the department and manikamam useful quantity of stones from removal of slips shall be to be neatly stacked along road side on road berms minimum 30.00 cubicmetre of earth work shall be done by the machine in one hours other wise number of hours shall be reduced accordingly. The work shall have to be carried out as per ministry of transport and as per instruction of the Engineer in charge	450.00	1100.00	Ruppes:-One Thousand One Hundred and Paia Zero only	Per Hour	495000
Total:-						495000
DNIT No. 1620 Approved for Rs.495000/- only for the Year 2023-2024						
Quoted rate in figure						
Quoted rate in words						
Signature of contractor with address:-						

Executive Engineer
 B&R Division
 HP,PWD Rohru

SCHEDULE OF QUANTITY

NAME OF WORK:- Improvement of RCD road km.0/0 to 2/200 (SH:- Widening of road at RD.2/115 to 2/150)

Job No. 29
Estimated Cost:-276264/-
Earnest Money:-5600/-
Time:-One Month

Sl.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/weighing out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. Technical Specification Clause 300.1603.1, 1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber, embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing and carriage of machineries, materials tools equipments and safety means and other materials necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1.6m (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Mahakama toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 115.97 cum. metric @ Rs. 300/- Per cubic metric shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be recovered by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified dimension in all leads and lift as per the direction of Engineer in charge	1142.55	241.796	Rupees:-Two Hundred Forty One and Paisa Seven Nine Six only	Cum	276264
	Total:-					276264
	DNIT No.					
	Quoted rate in figure					
	Quoted rate in words					
	Signature of contractor with address:-					

Approved for Rs.276264/- only for the Year 2023-2024

Executive Engineer
B&R Division
HP.PWD Rohru

SCHEDULE OF QUANTITY.

Estimate Cost 123200/-
Earnest Money 6600/-
Time 60days

30

Name of work :- R/R damages to various road under Rohru i section sub Divn Rohru SH- Hiring of Tipper for carriage of muck gravel

Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount
1	Hiring of Tipper for carriage of material having capacity 400cft including P.L.O charges shifting charges and other ancillary equipment at site of work. The work shall have to carried out as per ministry of Transport specifications of Engineer in charge within all leads and lifts	22.00	5600.00	Rs five thousand six hun dred onler	per hours	123200.00
Total					Total	123200.00

Quoted rate in Fmg (+)(-)	%
Quoted rate in words (+)(-)	

Executive Engineer
B&R Divn HP, PWD
Rohru

DRAFT SCHEDULE OF QUANTITY

Name of work :- R/R damages on Udho Niwas Jakhar Rantari road km 0/0 to 120(SH- C/O R/wall at RD 0/788 to 0/795)

Estimated cost Rs 455107/-
Earnest Money Rs9000-
Time one month

Sr No	Description of items	Quantity	Rate in Figure.	Rate in Words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per drawing and Technical Specification Clause 1603.1 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	26.00	306.64	Rs three hundred six & paise sixty four only	per cubic metre	7973
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. in ordinary rocks up to 3 mtr depth within all leads and lifts as per directions of Engineer in charge	23.44	407.00	Rs four hundred seven hundred only.	per cubic metre	9540
3	Providing and laying cement concrete 1:6:12 (one cement six sand twelve graded stone aggregate 40mm nominal size for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803,1202 and 1203 including carriage of materials within all leads and lifts as per directions of Engineer in charge	7.04	6314.00	Rs six thousand three hundred fourteen only	per cubic metre	44451
4	Providing and laying mechanical mixed and vibrated cement concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:4:8 (One cement : four sand : eight graded crushed stone aggregate) 25 mm specification clauses 802.803, 1202 and 1203 as per direction of Engineer-in-Charge including carriage of material through all modes of transportation with in all leads and lifts and other incidentals.	4.16	6656.00	Rs six thousand six hundred fifty six only	per cubic metre	27689
5	Random rubble masonry polygonal rubble masonry uncoursed brought to courses with hard stone of approved quality in foundation and plinth cement mortar 1:6(1 cement:6sand)breast wall and retaining wall within all leads and lifts as per directions of Engineer in charge	38.82	5400.00	Rs five thousand four hundred only	per cubic metre	209628
6	Construction of dry rubble masonry for retaining walls breast wall revementment walls and parapets etc for sub structure complete as per drawing and technical specification clause 704.6 and 1305, within all leads and lifts as per direction of Engineer in charge	36.25	4082.00	Rs four thousand eighty two only	per cubic metre	147973
7	Back filling behind abutment wing wall and return wall with granular materials complete as per drawing and technical specification clause 1204.3,8 including carriage of materials within all leads and lifts as per directions of Engineer in charge	5.52	1422.69	Rs one thousand four hundred seventy four only	per cubic metre	7853
	Total:-					
DNIT NO Approved for Rs: 455107/- for the year 2023-24						455107

Quoted Rate in figure (+) (-)
Quoted Rate in Words (+) (-)

%
%

Signature of Contractor with Full Address

Executive Engineer
B&R Divn HP PWD
Rohru

38 33

SCHUELDE OF QUANTITY

Estimate CostRs 252000/-
Earnest Money 5040.00
Time 30 days

Name of work:- R/R damages to various road under Rohru sub Division (SH- Hiring of JCB for removal of slips at various RDS mainteance of road and dressing of road surface).

Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of J.C.B (Excavator cum Loader) front end loader 1cum buckete & 45cum/hours including P.O.L change shifting charges and other ancillary equipment as required at site of work for cutting in earth work in all kinds soil such as kankar moorum shingle boulders decomposed or soft variety of soil such as as spade work pick work jumper work soft rock hard rock etc where blasting prohibited including saturated soil including chiseling weding out rock etc where blasting disposal of this unerviceable material in all leads and lofts including mechanical transportation if necessary. The disposal of this unerviceable materials has to be done in the acquired width of the road to avoid damage to the properties of people or in case any damage took place the contractor is liable for it all salvaged materials such as quarried stone shall belong to the department and maximum usefull quantity of stone from cutting work shall have to be neatly stacked along the road side on road berms. The work involving from existing with to IRC single lane standard with formatin with 5 metre in straight and 7 metre in curves as per their radius Minium 30cum of earth work shall be done by the machine in one hour other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instruction of the Engineer in charge	30.00	8400.00	Rs eight thousand four hundred only	per days	252000
	Total					252000.00

Quoted Rate in figure (+/-)
Quoted Rate in Words (+/-)

%
%

Singture of Contractor with full Address

Executive Engineer
B&R Dym HP.PWD
Rohru.

SCHEDULE OF QUANTITY

Job No. 34
 Estimated Cost:-41419/-
 Earnest Money:-8300/-
 Time:-One Month

DNIT No.

NAME OF WORK--: R/R damages on Bhaloon Kainchi to Koi road km. 0/0 to 9/100 (SH-C/O R/wall at RD.8/994 to 9/0)						
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	12.00	324.83	Rupees:-Three Hundred Twenty Four and Paisa Eighty Three only	Cum	3898
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.as directed by the Engineer-in-Charge	19.14	407.00	Rupees:-Four Hundred Seven and Paisa only	Cum	7790
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	5.76	6314.00	Rupees:-Six Thousand Three Hundred Forteen and Paisa Zero only	Cum	36369
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203.as directed by the Engineer-in-Charge	3.36	6656.00	Rupees:- Six Thousand Six Hundred Fifty Six Paisa Zero only.	Cum	22364
5	Stone masonry in cement mortar 1:6 (1Cement :6 sand) for sub-structure complete as per drawings and technical specification Clauses 702, 704,1202 and 1204 including carriage of material within all leads and lifts as per directions of Engineer in charge	41.58	5400.00	Rupees:-Five Thousand Four Hundred Paisa Zero Only.	Cum	224532
6	Construction of dry rubble masonry for retaining wall, breast walls , revetment walls and parapets etc for sub-structure and super structure complete as per drawings and technical specification Clauses 704.6,1302.5 as directed by the Engineer-in-Charge	27.51	4082.00	Rupees:-Four Thousand Eighty Two Paisa Zero only	Cum	112296
7	Providing and laying of back filling behind abutment wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	5.04	1422.69	Rupees:-One Thousand Four Hundred Twenty Two Paisa Sixty Nine only.	Cum	7170
				Total:-		41419
DNIT No. Approved for Rs.414419/- only for the Year 2023-2024						

DNIT No.

Approved for Rs.41419/- only for the Year 2023-2024

Quoted rate in figure	%
Quoted rate in words	%
Signature of contractor with address:-	

Executive Engineer
 B&R Division

SCHEDULE OF QUANTITY

Name of work :- R/R to various road under Samoli section sub Division samoli (SH-Hiring of JCB for removal of slips and land slide maintenance of road

Estimate Cost Rs 378000/-
Earnest Money 76000/-
Time :- 60days

Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of J.C.B.(Excavator-Cum-Loader) having bucket capacity 0.45 including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burns. Minimum 18,00cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	45.00	8400.00	Rs Eight thousand four hundred	per day	378000.00
					Total	378000.00

Quoted Rate in figure (+/-)	%
Quoted Rate in Words (+/-)	%

Singlure of Contractor with full Address

Executive Engineer
B&R Dym HP.PWD
Rohru

35
35
34

35

SCHEDULE OF QUANTITY

NAME OF WORK--: C/O link road Khorsu to Gujar Basti Bashrahi road km.0/0 to 2/0 (SH--:C/O R/wall in PCC at RD.9/220 to 9/236)

Job No. **34**
Estimated Cost:-388489/-
Earnest Money:-7800/-
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	5.90	306.64	Rupees:-Three Hundred Six and Paisa Sixty Four only	Cum	1809
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	13.10	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	5332
3	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	52.90	6656.00	Rupees:-Six Thousand Six Hundred Fifty Six Paisa Zero Only.	Cum	352102
4	Providing weephole in brick masonry /stone masonry. plain/ reinforced concrete abutment wing wall, return wall with 100mm dia AC pipe extending through the full width of the structures with slope of 1 (V):20(H) towards drawing face complete as per drawings and technical specification Clauses614,709,1204.3.7.as directed by the Engineer-in-Change	24.00	414.00	Rupees:-Four Hundred Forteen Paisa Zero only.	No.	9936
5	Providing and laying of back filling behind wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Change	13.10	1474.00	Rupees:-One Thousand Four Hundred Seventy Four and Paisa Zero only	Cum	19309
Total:-						388489
DNIT No. Approved for Rs.388489/- only for the Year 2023-2024						
Quoted rate in figure %						
Quoted rate in words %						
Signature of contractor with address:-						

Executive Engineer
B&R Division
HP.PWD Rohru

27-36

SCHEDULE OF QUANTITY

Estimated Cost:-482821/-
Earnest Money:-9000/-
Time:-One Month

NAME OF WORK:- R/R damages to Po-Dhar Mendheori road km.0/0 to 12/0 (SH:-C/O R/wall in PCC at RD.9/220 to 9/236)

Job No. 37

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	13.44	303.17	Rupees:-Three Hundred Three and Paisa Seventeen only	Cum	4075
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deteriorous material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	22.56	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	9182
3	Plain/reinforced cement concrete (1:3:6) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 as directed by the Engineer-in-Charge	66.40	6972.00	Rupees:- Six Thousand Nine Hundred Seventy Two Paisa Zero only.	Cum	462941
4	Providing weep-hole in brick masonry/stone masonry ,plain/ reinforced concrete abutment wing wall, return wall with 100mm dia AC pipe extending through the full width of the structures with slope of 1 (V):20(H) towards drawing face complete as per drawings and technical specification Clauses 614, 709, 1204.3, 7 as directed by the Engineer-in-Charge	16.00	414.00	Rupees:-Four Hundred Forteen Paisa Zero only.	No.	6624
Total:-						482821
DNIT No. Approved for Rs.482821/- only for the Year 2023-2024						
Quoted rate in figure						%
Quoted rate in words						%
Signature of contractor with address:-						

Executive Engineer
B&R Division
HP.PWD Rohru

Job No.

36

(37)

DNIT/ SCHEDULE OF QUANTITY

Estimated Cost:-252000/-

Earnest Money:-5040/-

Time:-One Month

NAME OF WORK:- R/R damages to various road under Rohru Section Sub-Division Rohru (SH:-Hiring of JCB for removal of slips at various RDs, maintenance of road and dressing of road surface)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Hiring of JCB (Excavator cum loader) front end loader 1 cum bucket capacity 0.45cum/ hour including POL charges shifting charge and other ancillary equipments as required at site of work for removal of slips in all heights and all kinds of soils such as kanhar moorum shingle boulders decomposed or soft variety of soil such a spade work pick work junner work soft rock hard rock including their intermediate classification of soil including mechnacial transportation of necessary. The disposal of this underecable materials has to be done in the acquired width of the road to avoid the damage to the properties of the people or in case any damage took place the contractor shall be liable for its. All salvaged materials such as quried stone shall belong to the department and manikunum useful quantity of stones from removal of slips shall be to be neatly stacked along road side on road berms minimum 30.00 cubice metre of earth work shall be done by the machine in one hours ans 200 cum of snow shell be removed from the road surface in one hour other wise number of hours shall be reduced accordingly. The work shall have to be carried out as per ministry of transport and as per instruction of the Engineer in charge including all leads and lifts	30.00	8400.00	Rupees:-Eight Thousand Four Hundred and Paiza Zero only	Per Day	252000
		</				

Executive Engineer
B&R Division
HP.PWD Rohru

SCHEDULE OF QUANTITY

of work :- R/R Damages to Narakanda Baghi Sungri Khadrala Rohru road km 0/0 to 67/0 (SH- C/O R/wall at Rd 63/045 to 63/060)

Estimated cost Rs 429869 —
Earnest Money Rs8500/-
T Time :- one Month

Description of Items	Quantity	Rate in Figure.	Rate in Words	Unit	Amount
Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per drawing and Technical Specification Clause 1603.1 and as per the direction of the Engineer-in-Charge including cartage of material through all modes of transportation within all leads and lifts and other incidentals.	12.00	324.83	Rs three hundred twenty four & paise eighty three only	per cubic metre	3898
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. in ordinary rocks up to 3 mtr depth within all leads and lifts as per directions of Engineer in charge	17.40	407.00	Rs four hundred thirty & paise fifty only	per cubic metre	7082
Providing and laying cement concrete 1:6:12 (one cement six sand twelve graded stone aggregate 40mm nominal size for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803, 1202 and 1203 including cartage of materials within all leads and lifts as per directions of Engineer in charge	7.35	5839.05	Rs five thousand eight hundred thirty nine & paise five only	per cubic metre	42917
Providing and laying mechanical mixed and vibrated cement concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand : eight graded crushed stone aggregate) 25 mm specification clauses 802.803, 1202 and 1203 as per direction of Engineer-in-Charge including cartage of material through all modes of transportation within all leads and lifts and other incidentals.	4.50	6655.90	Rs six thousand six hundred fifty five & paise ninety only	per cubic metre	29952
Random rubble masonry polygonal rubble masonry uncoursed /brought to courses with hard stone of approved quality in foundation and plinth cement mortar 1:6 (1 cement 6sand) breast wall and retaining wall within all leads and lifts as per directions of Engineer in charge	32.10	5400.00	Rs five thousand four hundred only	per cubic metre	173340
Construction of dry rubble masonry for retaining walls breast wall revetment walls and parapets etc for sub structure complete as per drawing and technical specification clause 704.5 and 1305 within all leads and lifts as per direction of Engineer in charge	36.18	4082.27	Rs four thousand eighty two only	per cubic metre	147697
Back behind abutment wing wall return wall with Granular materials complete as per drawing and technical specification clause 1204.3.8 with all leads and lifts as per directions of Engineer in charge	16.95	1474.00	Rs one thousand four hundred seventy four only	per cubic metre	24984
					429869

DNIT NO. Approved for Rs. 429869 for the year 2023-24

ed Rate in figure (+) (-)	%
ed Rate in Words (+) (-)	%

ure of Contractor with full Address

Executive Engineer
B&R Dyb HP PWD
Rohru

34 38 34

Job No.:-

40

(39)

SCHEDULE OF QUANTITY

Estimated Cost:-116600/- 40

Earnest Money:-2400/-

Time:-One Month

NAME OF WORK:-R/R damages on various road under Summerkot Section Sub-Division Rohru (SH:- Hiring of Tipper for carriage of muck and excavated soil)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
2	Hiring of Tipper for carriage of material having capacity 200 cft. including POL charges and other ancillary equipments as required at site of work. The work shall to be carried out as per ministry of transport as per instruction of the Engineer in charge including all leads and lifts.	22.00	5300.00	Rupees:- Five Thousand Three Hundred and Paise Zero only	Per Day	116600
				Total:-		116600
	Quoted rate in figure					
	Quoted rate in words					
	Signature of contractor with address:-					

Executive Engineer
B&R Division
H.P.PWD Rohru

44
40

SCHEDULE OF QUANTITY

NAME OF WORK--: C/O Narkanda Baggi Khadrula Sungri Rohru road km. 0/0 to 67/0 (SH:-C/O R/wall in wire crate at RD.40/565 to 40/587.50)

Job No. 44
Estimated Cost:-354708/-
Earnest Money:-7100/-
Time:-One Month

Sr.No.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culvers, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil , ordinary rocks, hard rocks, chiseling/ wedging out of rocks (where blasting is prohibited) as per drawings and MORD technical specification Clause 305.1 51 104 and 1606.1 a d as per direction of the Engineer-In-Charge including setting out consuction of shoring and bracing, removal of stumps and otherdeterious materials and disposal of materials upto all leads and lifts including dressing Oisides and bottom and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 150mm (one hundred fifty miiimeters) compacted thickness including shorting and strutting and pumping and bailing out water (surface and sub soil water) upto all depth and any quantum of water including cleaning of slush which may arise out during dewatering and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals,	30.94	407.00	Rupces:-Three Hundred Seven and Paisa Eighty Three only	Cum	12593
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four) millimetre dia G.I wire conforming to 18280 and IS: 4826 in 100 mm x 100 mm (hundred millimetre x hundred molimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 2 5 (twenty five)kilogramme each as per drawing and MORD Technical Specifications Clause 1301 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within ail leads and lifts and other incidentals.	105.47	2890.00	Rupces:-Two Thousand Eight Hundred Ninety and Paisa Zero only	Cum	304808
3	Providing and laying of back filling behind R/wall,B/wall and wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	25.31	1474.00	Rupces:-One Thousand Four Hundred Seventy Four and Paisa Zero only	Cum	37307
Total:-						354708
DNIT No. Approved for Rs.533224/- only for the Year 2023-2024						
Quoted rate in figure		%				
Quoted rate in words		%				
Signature of contractor with address:-						

Executive Engineer
B&R Division
HP.PWD Rohru

~~REVENUE~~ SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages on Bhiloon Kenchi to Bhiloon road km. 0/0 to 4/0 (SH:-C/O B/wall in PCC 1:4:8 & wire crates at RD.2/535 to 2/560)

Estimated Cost:-446797/-
Earnest Money:-9000/-
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	30.75	324.83	Rupees:-Three Hundred Twenty Four and Paiza Eighty Three only	Cum	9989
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material with in all leads and lifts as per directed by the Engineer-in-Charge	7.50	407.00	Rupees:-Four Hundred Seven and Paiza Zero only	Cum	3053
3	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	30.00	6656.00	Rupees:-Six Thousand Six Hundred Fifty Six Paiza Zero Only.	Cum	199680
4	Providing and laying of boulder apron laid in wire crates with 4 mm (four) millimetre dia GI wire conforming to 18280 and IS: 4826 in 100 mm x 100 mm (hundred milimetre x hundred milimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps end joints laid with stone boulders weighing not less than 2.5 (twenty five)kilogramme each as per drawing and MORD Technical Specifications Clause 1301 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	78.13	2890.00	Rupees:-Two Thousand Eight Hundred Ninety and Paiza Zero only	Cum	225796
5	Providing weephole in brick masonry ,plain/ reinforced concrete abutment wing wall, return wall with 100mm dia AC pipe extending through the full width of the structures with spoe of 1 (V):20(H) towards drawing face complete as per drawings and technical specification Clauses614, 709, 1204.3.7 as directed by the Engineer-in-Charge	20.00	414.00	Rupees:-Four Hundred Forteen Paiza Zero only.	No.	8280
				Total:-		446797
				DNIT No.	Approved for Rs.446797/- only for the Year 2023-2024	
				Quoted rate in figure	%	
				Quoted rate in words	%	
				Signature of contractor with address:-		

Executive Engineer
B&R Division
HP.PWD Rohru

MM
 $\frac{343}{184}$ ENT.

42

SCHEDULE OF QUANTITY

Job No. **44**
 Estimated Cost:- 297000/-
 Earnest Money:- 6000/-
 Time:- Two Month

NAME OF WORK :- R/R damages to various road under Rohru Section Sub-Division Rohru(SH:-Hiring of Tipper for carriage of excavated earth muck etc.)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Hiring of Tipper for carriage of material having capacity 400 cft including POL charges and other ancillary equipments as required at site of work. The work shall to be carried out as per ministry of transport as per instruction of the Engineer in charge including all leads and lifts.	45.00	6600.00	Rupess:- Six Thousand Six Hundred and Paise Zero only	Per Day	297000
				Total:-		297000
				DNT No. 328		
				Approved for Rs.297000/- only for the Year 2023-2024		
	Quoted rate in figure					
	Quoted rate in words					
	Signature of contractor with address:-					

Executive Engineer
 B&R Division
 HP.PWD Rohru

RS Malviya
 JE

42

DNIT

SCHEDULE OF QTY

Estimate Cost 495000/-
Earnest Money 9000/-

45
(43)

(3)

Time 60 Days

Name of work :- P/R damage to various roads under Rohru section Sub-Division Rohru (SH-Hiring of JCB for removal of slip and for Maintenance of road)

Sr.N o.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of J.C.B.(Excavator-Cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charges and other ancillary equipments , with in all leads and lifts as directed By Engineer Incharge Min. 18.00 Cum of earth shall be done by Machine in one Hours , shall be deducted accordingly. J.C.B shall be deployed for dressing of burns shoulders , clearance of drain , culvert, removal of excess soil from road surface filling up of pot holes with suitable materials from borrow pits and removal of slips where ever on the road surface with in all leads and lifts as directed by Engineer In charge .	450.00	1100.00	Eleven Hundred Only	Per Hour	495000
Total					Total	495000.

DNIT No. ¹¹⁰² Approved for Rs. 495000/- Only for the year 2023-24

Assistant Engineer
B&R Sub Division
HP PWD Rohru

Executive Engineer,
B&R Division HPPWD,
Rohru.

Placed rate in figure :-

do — word :-

Signature of Contractor with address :-

DNIT

144-44

Estimated Cost -297000/-

Earnest money -6000/-

Time - 60 Days

Name of work:- R/R Damages to various road under Rohru section sub-Division Rohru.

(Sft:- Hiring of Tipper for Carriage of excavated earth muck etc.)

S.N.	Sub-Head and item of work	Qty.	Rate in figures	Rate in word.	Unit	Amount
1	Hiring of tipper for carriage of materials having capacity 400 cft including P.O.L. Charges, shifting charge and other ancillary equipment as required at site of work. The work shall have to carried out as per ministry of transport specification of the Engineer-in-Charge including all lead and lifts.	45	6600.00	six thousand Two hundred only	Per day	297000.00
TOTAL						297000.00

DNIT No-1180 approved for Rs 297000/- only for the year 2023-24

Assistant Engineer
Division HPPWD
Rohru

Executive Engineer
B&R Division HPPWD
Rohru

Quantities in figure
as words
Signature of Engineer with address

SCHEDULE OF QUANTITY

Item of work :- R/R Damages to Narkanda Baghi Sungri Khadria Rohru road km 0/0 67/0 (SH- R/wall in PCC 1:4:8 at RD 51/625 to 51/643)

Estimated cost RS 471802/-
Fairrent money 9500/-
Est Time :- one month

Description of items	Quantity	Rate in Figure.	Rate in Words	Unit	Amount
Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per drawing and Technical Specification Clause 1603.1 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	9.54	290.00	Rs two hundred ninety only	per cubic metre	2767
Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary rocks up to 3 mtr depth within all leads and lifts as per directions of Engineer in charge	16.56	470.00	Rs four hundred seventy only	per cubic metre	7783
Providing and laying cement concrete 1:6:12 (one cement six sand twelve graded stone aggregate 40mm nominal size for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 including carriage of materials within all leads and lifts as per directions of Engineer in charge.	4.86	5650.00	Rs five thousand six hundred fifty only	per cubic metre	27459
Providing and laying mechanical mixed and vibrated cement concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:4:8 (One cement: four sand : eight graded crushed stone aggregate)25 mm specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material through all modes of transportation with in all leads and lifts and other incidentals.	67.50	6200.00	Rs six thousand two hundred only	per cubic metre	418500
Back filling behind abutment wing wall and return wall with granular materials complete as per drawing and technical specification clause 1204.3,8 including carriage of materials within all leads and lifts as per directions of Engineer in charge	10.62	1440.00	Rs one thousand four hundred seventy four only	per cubic metre	15293
Total:-					471802

DNIT NO. Approved for Rs 4,71,802/- for the year 2023-24

Quoted Rate in figure	(+) (-)	%
Quoted Rate in Words	(+) (-)	%

Singlure of Contractor with full Address

Executive Engineer
B&R Divn HP/PWD
Rohru

Job No.:-

48

46

SCHEDULE OF QUANTITY**NAME OF WORK:- R/R damages Udoniwas Jakhar road Km.0/0 to 5/0(SH:-C/O B/wall in wire crate at RD. 0/550 to 0/565)**Estimated Cost:-226426/-
Earnest Money:-4600/-
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	64.35	324.80	Rupees:-Three Hundred Twenty Four and Paisa Eighty only	Cum	20901
2	Earthwork in excavation for structures as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	4.25	548.00	Rupees:-Five Hundred Forty Eight and Paisa Zero only	Cum	2329
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	70.31	2890.00	Rupees:-Two Thousand Eight Hundred Ninety Paiza Zero only.	Cum	203196
4	Providing and laying of stone filling behind R/wall, wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	0.00	1474.00	Rupees:-One Thousand Four Hundred Seventy Four and Paiza Zero only	Cum	0
				Total:-		226426
		DNIT No.		Approved for Rs.226426/- only for the Year 2023-2024		
	Quoted rate in figure		%			
	Quoted rate in words		%			
	Signature of contractor with address:-					

Executive Engineer
B&R Division
HP,PWD Rohru

DNIT / Schedule of Quantity

44
 292
 129
 292
 129

Estimated Cost -297000/-

Earnest money -6000/-

Time - 60 Days

Name of work: P/R Damages to various road under Samoli section sub-Division Rohru.

(SM:- Hiring of Tipper for Carriage of excavated earth muck etc.)

S.N.	Sub-head and item of work	Qty.	Rate in figures	Rate in word.	Unit	Amount
1	Hiring of tipper for carriage of materials having capacity 400 cft including P.O.L. Charges, shifting charge and other ancillary equipment as required at side of work. The work shall have to carried out as per ministry of transport specification of the Engineer-in-Charge including all lead and lifts.	45	6600.00	six thousand Two hundred only	Per day	297000.00
TOTAL						297000.00

DNIT No-1232 approved for Rs 297000/- only for the year 2023-24

Assistant Engineer
 Division HPPWD
 Rohru

Executive Engineer
 B&R Division HPPWD
 Rohru

Quoted Rate in figure is
 do- words is
 Signature of Contractor with address is

Job No. 48

SCHEDULE OF QUANTITY

Estimated Cost:-459663/-

Earnest Money:-9200/-

Time:-One Month

NAME OF WORK:- R/R damages to Machoti Chhapoti Kui road km. 0/0 to 9/0 (SH:-C/O R/wall at RD.1/050 to 1/062)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	28.80	324.60	Rupees:-Three Hundred Twenty and Paisa Zero only	Cum	9348
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	43.20	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	17582
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	8.64	6314.00	Rupees:-Six Thousand Three Hundred Forteen and Paisa Zero only	Cum	54553
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 as directed by the Engineer-in-Charge	5.16	6656.00	Rupees:- Six Thousand Six Hundred Fifty Six Paisa Zero only.	Cum	34345
5	Stone masonry in cement mortar 1:6 (Cement 6 sand) for sub-structure complete as per drawings and technical specification Clauses 702, 704, 1202 and 1204 including carriage of material within all leads and lifts as per directions of Engineer in charge	31.72	5400.00	Rupees:-Five Thousand Four Hundred Paisa Zero Only.	Cum	171288
6	Construction dry rubble Stone masonry for retaining walls breast wall revetment walls and parapets etc for sub structure and superstructure complete as per drawings and technical specification Clauses 704.6 and 1302.5 within all leads and lifts as per directions of Engineer in charge	40.32	4082.00	Rupees:-Four Thousand Eighty Two Paisa Zero only.	Cum	164586
7	Back filling behind abutments, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 with in all leads and lifts as per directed by the Engineer-in-Charge	5.40	1474.00	Rupees:-One Thousand Four Hundred Seventy Four Paisa Zero only.	No.	7960
		Total:-				459663
		DNT No.		Approved for Rs.459663/- only for the Year 2023-2024		
		%				
		Quoted rate in figure				
		Quoted rate in words				
		Signature of contractor with address:-				

Executive Engineer
B&R Division
HP.PWD Rohru

51 57 (49)

Schedule of Qty			
Name of Work :- R/R Damage to Dhara barara Jhatu road km 0/00 to 2/500(SH:- C/o B/wall at RD 1/399.50 to 1/447)			
		ESTIMATED COST	406089
		EARNEST MONEY	8122
		TIME LIMIT:	Two Month

Sr. No	Description of Items.	Qty	Unit	Rate		Amount
				In Fig.	In Words	
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	39.9	Cum	324.83	Rupees Three Hundred & Twenty Four - Paise Eighty Three Only	12961
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	19.95	Cum	407	Rupees Four Hundred & Seven Only	8120
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	148.44	Cum	2593.7	Rupees Two Thousand Five Hundred & Ninety Three - Paise Seventy Only	385009
Total						406089

Condition:-
 1 The rates Should be quoted for all heights including all lead and lifts.
 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.
 2 Quoted rate Figure (*/-) _____
 Quoted rate Words (*/-) _____
 Signature of the Contractor with full address:- _____

Executive Engineer
 B&R Division HPPWD
 Rohru

(50)

SCHEDULE OF QUANTITY**NAME OF WORK--:R/R damages on Narkanda Baggi Sungri Khadrula Rohru road km.0/0 to 67/0 (SH:- Widening of black spot at Rd.50/710 to 50/890)**

Job No. <u>52</u>
Estimated Cost:-490496/-
Earnest Money:-9800/-
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1603.1,1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber ,embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machineries, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 370.73 cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.	1235.76	396.918	Rupees:-Three Hundred Ninety Six and Paisa Nine One Eight only	Cum	490495
Total:-						490495
DNIT No. _____ Approved for Rs.490496/- only for the Year 2023-2024						
Quoted rate in figure						%
Quoted rate in words						%
Signature of contractor with address:-						

Executive Engineer
B&R Division
HP.PWD Rohru

DNIT/ SCHEDULE OF QUANTITY

Job No. 53
Estimated Cost:-363905/-
Earnest Money:-7300/-
Time:-One Month

NAME OF WORK--:R/R damages on Junidhar Kurtu road km. (SH:-C/O B/wall at RD.2/445 to 2/460)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	39.45	324.83	Rupees:-Three Hundred Twenty Four and Paise Eight Three only	Cum	12815
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	26.85	407.00	Rupees:-Four Hundred Seven and Paise Zero only	Cum	10928
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	7.20	6314.00	Rupees:-Six Thousand Three Hundred Forteen and Paise Zero only	Cum	45461
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	3.00	6656.00	Rupees:-Six Thousand Six Hundred Fifty Six Paise Zero Only.	Cum	19968
5	Randon Rubble Stone masonry in cement mortar 1:6 (1 Cement : 6 sand) for foundation complete as as per drawings and technical specification Clauses 702, 704, 1202 and 1203 including carriage of material within all leadsa and lifts as per directions of Engineer in charge	49.65	5400.00	Rupees:-Five Thousand Four Hundred Paise Zero Only.	Cum	268110
6	Providing weephole in brick masonry /stone masonry ,plain/ reinforced concrete abutment wing wall, return wall with 100mm dia AC pipe extending through the full width of the structures with slope of 1 (V):20(H) towards drawing face complete as per drawings and technical specification Clauses614,709,1204,3.7 as directed by the Engineer-in-Charge	16.00	414.00	Rupees:-Four Hundred Fourteen Paise Zero only.	No.	6624
Total:-						363905
DNIT No.						Approved for Rs.363905/- only for the Year 2023-2024
Quoted rate in figure						%
Quoted rate in words						%
Signature of contractor with address:-						

Executive Engineer
B&R Division
HP.PWD Rohru

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages on link road village Barara km.0/0 to 1/0 (SI:-C/O R/wall at RD.0/550 to 0/570)

Job No. 54
Estimated Cost:- 445171/-
Earnest Money:- 8900/-
Time:- One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	19.20	324.83	Rupees:-Three Hundred Twenty Four and Paisa Eighty Three only	Cum	6237
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	28.20	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	11477
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	8.60	6314.00	Rupees:-Six Thousand Three Hundred Forteen and Paisa Zero only	Cum	54300
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	3.40	6656.00	Rupees:-Six Thousand Six Hundred Fifty Six Paisa Zero Only.	Cum	22630
5	Randon Rubble Stone masonry in cement mortar 1:6 (1 Cement : 6 sand) for foundation complete as as per drawings and technical specification Clauses 702, 704, 1202 and 1203 including carriage of material within all leadsa and lifts as per directions of Engineer in charge	32.40	5400.00	Rupees:-Five Thousand Four Hundred Paisa Zero Only.	Cum	174960
6	Construction of dry masonry in retaining walls, breast walls etc as per drawings and technical specification including carriage of material within all leadsa and lifts as per directions of Engineer in charge	39.76	4082.00	Rupees:-Four Thousand Eighty Two Paisa Zero Only.	Cum	162300
7	Providing and laying of back filling behind R/wall and wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	9.00	1474.00	Rupees:-One Thousand Four Hundred Seventy Four and Paisa Zero only	Cum	13266
Total:-						445171
Quoted rate in figure						445171
Quoted rate in words						%
Signature of contractor with address:-						%

DNIT No. 1769 **Approved for Rs.445171/- only for the Year 2023-2024**

Executive Engineer
B&R Division
HP.PWD Rohru

SCHEDULE OF QUANTITY

Job No. **55**
 Estimated Cost:-437655/-
 Earnest Money:-8800/-
 Time:-One Month

NAME OF WORK:- C/O main road Lowerkoti to Vahan km.0/0 to 1/300 (SH:-F/C 5/7 mtrs.Wide road at RD.0/180 to 0/255)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1603.1,1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber, embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machineries, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 300.93 cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.	1076.25	406.648	Rupees:-Four Hundred Six and Paisa Six Four Eight only	Cum	437655
Total:-						437655
DNIT No. Approved for Rs.437655/- only for the Year 2023-2024						
Quoted rate in figure						
Quoted rate in words						
Signature of contractor with address:-						

Executive Engineer
 B&R Division
 HP.PWD Rohru

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages to Jakharto Thakuli Bartu road km.0/0 to 3/0 (SH:-C/O B/wall at RD.1/500 to 1/523.1)

Job No. 56
Estimated Cost:-498097/-
Earnest Money:-10000/-
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	12.47	186.32	Rupees:-One Hundred Eighty Six and Paise Thirty Two only	Cum	2323
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	43.66	407.00	Rupees:-Four Hundred Seven and Paise Zero only	Cum	17770
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	10.63	6314.00	Rupees:-Six Thousand Three Hundred Forteen and Paise Zero only	Cum	67118
4	Random Rubble Stone masonry in cement mortar 1:6 (1 Cement : 6 sand) for foundation complete as as per drawings and technical specification Clauses 702, 704, 1202 and 1203 including carriage of material within all leadsa and lifts as per directions of Engineer in charge	76.09	5400.00	Rupees:-Five Thousand Four Hundred Paise Zero Only.	Cum	410886
Total:-						498097
DNIT No. <u>56</u> Approved for Rs.498097/- only for the Year 2023-2024						
Quoted rate in figure						%
Quoted rate in words						%
Signature of contractor with address:-						

Executive Engineer
B&R Division
HP.PWD Rohru

Job No. 57

(55)

SCHEDULE OF QUANTITY

Estimated Cost:-465436/-
 Earnest Money:-9400/-
 Time:-One Month

NAME OF WORK:-R/R damages on link road to village Bareitali road km.0/0 to 1/0 (SH:- C/O B/wall in PCC 1:4:8 at RD.0/345 to 0/365 & 0/725 to 0/745)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	180.00	290.00	Rupees:-Two Hundred Ninety and Paise Zero only	Cum	52200
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	48.00	407.00	Rupees:-Four Hundred Seven and Paise Zero only	Cum	19536
3	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 as with in all leads and lifts as per directed by the Engineer-in-Charge	63.00	6025.77	Rupees:- Six Thousand Twenty Five Paise Seven Seven only.	Cum	379624
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall and retaining and breast wall with 100 (One hundred)dia millimetre PVC pipe extending through the full width of the structures with slope of 1 (V):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3,7 as per the direction of the Engineer-in-Charge including carriage of materials through all modes of transportation with in all leads and lifts and other incidentals, with in all leads and lifts as per directed by the Engineer-in-Charge	34.00	414.00	Rupees:- Four Hundred Fourteen Paise Zero only.	No.	14076
Total:-						465436
DNIT No. Approved for Rs.465436/- only for the Year 2023-2024						
Quoted rate in figure %						
Quoted rate in words %						
Signature of contractor with address:-						

Executive Engineer
 B&R Division
 HP.PWD Rohru

/ SCHEDULE OF QUANTITY

Job No. 59
 Estimated Cost:-431267/-
 Earnest Money:-8600/-
 Time:-One Month

NAME OF WORK--: -R/R damages on Bashla Antapu Saraidhar road km.0/0 to 9/0(SH:-C/O R/wall at RD.0/0 to 0/025)						
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	20.75	324.83	Rupees:-Three Hundred Twenty Four and Paisa Eighty Three only	Cum	6740
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	26.50	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	10786
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	8.75	6314.00	Rupees:-Six Thousand Three Hundred Forteen and Paisa Zero only	Cum	55248
4	Randon Rubble Stone masonry in cement mortar 1:6 (1 Cement : 6 sand) for foundation complete as as per drawings and technical specification Clauses 702, 704,1202 and 1203 including carriage of material within all leadsa and lifts as per directions of Engineer in charge	64.75	5400.00	Rupees:-Five Thousand Four Hundred Paisa Zero Only.	Cum	349650
5	Providing and laying of back filling behind R/wall and wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	6.00	1474.00	Rupees:-One Thousand Four Hundred Seventy Four and Paisa Zero only	Cum	8844
				Total:-		431267
		DNIT No. _____ Approved for Rs.431267/- only for the Year 2023-2024				
		%				
		Quoted rate in figure				
		Quoted rate in words				
		Signature of contractor with address:-				
		Executive Engineer B&R Division HP.PWD Rohru				

Executive Engineer
 B&R Division
 HP.PWD Rohru

Job No.

66 57

SCHEDULE OF QUANTITY**NAME OF WORK:- R/R damages on Dhumadhar Jhatwari Mastor Naser road 0/0 to 7/0 (SH:-C/O R/wall in PCC 1:4:8 at RD. 0/165 to 0/180)**

Estimated Cost:-436490/-

Earnest Money:-8700/-

Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	15.48	324.83	Ruppes:-Three Hundred Twenty Four and Paisa Eighty Three only	Cum	5028
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	19.20	407.00	Ruppes:-Four Hundred Seven and Paisa Zero only	Cum	7814
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	4.73	6314.00	Ruppes:-Six Thousand Three Hundred thirteen and Paisa Zero only	Cum	29865
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 as directed by the Engineer-in-Charge	57.38	6656.00	Ruppes:- Six Thousand Six Hundred Fifty Six Paisa Zero only.	Cum	381921
5	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall and retaining and breast wall with 100 (One hundred)dia millimetre PVC pipe extending through the full width of the structures with slope of 1 (V), 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204, 3.7 as per the direction of the Engineer-in-Charge including carriage of materials through all modes of transportation with in all leads and lifts and other incidentals with in all leads and lifts as per directed by the Engineer-in-Charge	28.65	414.00	Ruppes:- Four Hundred Forteen Paisa Zero only.	No.	11861
		Total:-		436490		
		DNIT No.		Approved for Rs.436490/- only for the Year 2023-2024		
		Quoted rate in figure		%		
		Quoted rate in words		%		
		Signature of contractor with address:-				

Executive Engineer
B&R Division
HP.PWD Rohru

Job No. 64

58

/ SCHEDULE OF QUANTITY

Estimated Cost:-468680/-
Earnest Money:-9400/-

Time:-One Month

NAME OF WORK:-R/R damages on Dumadhar Jatwari mastot Naser road km.0/0 to 7/0 (SH:-C/O B/wall at Rd.1/495 to 1/515)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	12.80	324.83	Rupees:-Three Hundred Twenty Four and Paisa Eighty Three only	Cum	4158
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	14.20	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	5779
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	4.53	5839.05	Rupees:-Five Thousand Eight Hundred Thirty Nine and Paisa Zero Five only	Cum	26451
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 as directed by the Engineer-in-Charge	3.60	6656.00	Rupees:-Six Thousand Six Hundred Fifty Six Paisa Zero only.	Cum	23962
5	Stone masonry in cement mortar 1:6 (1:Cement :6 sand) for sub-structure complete as per drawings and technical specification Clauses 702, 704, 1202 and 1204 including carriage of material within all leads and lifts as per directions of Engineer in charge	52.00	5400.00	Rupees:-Five Thousand Four Hundred Paisa Zero Only.	Cum	280800
6	Construction dry rubble Stone masonry for retaining walls breast wall reventment walls and parapets etc for sub structure and superstructure complete as per drawings and technical specification Clauses 704.6 and 1302.5 within all leads and lifts as per directions of Engineer in charge	31.24	4082.27	Rupees:-Four Thousand Eighty Two Paisa Two Seven only.	Cum	127530
		Total:-				468680
		DNIT No.				
		Quoted rate in figure				
		Quoted rate in words				
		Signature of contractor with address:-				

Approved for Rs.468680/- only for the Year 2023-2024

Executive Engineer
B&R Division
HP.PWD Rohru

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages on Barasti Kainchi Runda Jhatlu road km.0/0 to 5/100 (SI:-C/O R/wall at RD.1/980 to 2/0)

Job No. 62
Estimated Cost:- 491882/-
Earnest Money:- 9800/-
Time:- One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	29.00	324.83	Rupees:-Three Hundred Twenty Four and Paisa Eighty Three only	Cum	9420
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	33.80	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	13757
3	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	3.60	6656.00	Rupees:-Six Thousand Six Hundred Fifty Six Paisa Zero Only.	Cum	23962
4	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	8.70	6314.00	Rupees:-Six Thousand Three Hundred Forteen and Paisa Zero only	Cum	54932
5	Randon Rubble Stone masonry in cement mortar 1:6 (1 Cement : 6 sand) for foundation complete as per drawings and technical specification Clauses 702, 704, 1202 and 1203 including carriage of material within all leadsa and lifts as per directions of Engineer in charge	32.10	5400.00	Rupees:-Five Thousand Four Hundred Paisa Zero Only.	Cum	173340
6	Construction of dru masonry in retaining walls, breast walls etc.as per drawings and technical specification including carriage of material within all leadsa and lifts as per directions of Engineer in charge	44.87	4082.00	Rupees:-Four Thousand Eighty Two Paisa Zero Only.	Cum	183159
7	Providing and laying of back filling behind R/wall and wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3, 8 as directed by the Engineer-in-Charge	22.60	1474.00	Rupees:-One Thousand Four Hundred Seventy Four and Paisa Zero only	Cum	33312
Total:-						491882
DNIT No.						Approved for Rs.491882/- only for the Year 2023-2024
Quoted rate in figure						%
Quoted rate in words						%
Signature of contractor with address:-						

Executive Engineer
B&R Division
HP.PWD Rohru

SCHEDULE OF QUANTITY

Job No. **63**
 Estimated Cost:-484433/-
 Earnest Money:-9700/-
 Time:-One Month

NAME OF WORK:-C/O Dhara Takroli Barara Jhalu road km. 0/0 to (SH:-C/O Wing wall in PCC 1:4:8 left Bharara side at RD.0/615)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	11.97	287.80	Rupees:-Two Hundred Eighty Seven and Paiza Eighty only	Cum	3445
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.as directed by the Engineer-in-Charge	21.96	407.00	Rupees:-Four Hundred Seven and Paiza Seven only	Cum	8938
3	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 as directed by the Engineer-in-Charge	74.70	5990.00	Rupees:- Five Thousand Nine Hundred Ninety Paiza Fifteen only.	Cum	447453
4	Providing weephole in brick masonry /stone masonry ,plain/ reinforced concrete abutment wing wall, return wall with 100mm dia AC pipe extending through the full width of the structures with slope of 1 (V):20(H) towards drawing face complete as per drawings and technical specification Clauses614,709,1204.3.7 as directed by the Engineer-in-Charge	20.00	414.00	Rupees:-Four Hundred Forteen Paiza Zero only.	No.	8280
5	Providing and laying of back filling behind abutment wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	11.07	1474.00	Rupees:-One Thousand Four Hundred Seventy Four Paiza Zero only.	Cum	16317
Total:-						484433
DNIT No.						Approved for Rs.484433/- only for the Year 2023-2024
Quoted rate in figure						%
Quoted rate in words						%
Signature of contractor with address:-						

Executive Engineer
 B&R Division
 Rohru

/ SCHEDULE OF QUANTITY

Job No. 64

(61)

Estimated Cost:-486553/-
Earnest Money:-9800/-
Time:-One Month

NAME OF WORK:- C/O Link road to village Lakhadhar Mini Gadam road km. (SH:- C/O R/wall in PCC 1:4:8 at RD.0/600 to 0/612.50)						
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	6.63	287.80	Rupees:-Two Hundred Eighty Seven and Paisa Eighty only	Cum	1908
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	11.50	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	4681
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	3.64	6314.00	Rupees:-Six Thousand Three Hundred Forteen and Paisa Zero only	Cum	22983
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203.as directed by the Engineer-in-Charge	71.71	5990.00	Rupees:- Five Thousand Nine Hundred Ninety Paisa Zero only.	Cum	429543
5	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall, return wall and retaining and breast wall with 100 (One hundred)dia millimetre PVC pipe extending through the full width of the structures with slope of 1 (V):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 as per the direction of the Engineer-in-Charge including carriage of materials through all modes of transportation with in all leads and lifts and other incidentals,with in all leads and lifts as per directed by the Engineer-in-Charge	40.00	414.00	Rupees:- Four Hundred Forteen Paisa Zero only.	No.	16560
6	Back filling behind abutments, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 with in all leads and lifts as per directed by the Engineer-in-Charge	7.38	1474.00	Rupees:-One Thousand Four Hundred Seventy Four Paisa Zero only.	Cum	10878
				Total:-		486553
	Quoted rate in figure	DNIT No.		Approved for Rs.486553/- only for the Year 2023-2024		
	Quoted rate in words	%				
	Signature of contractor with address:-	%				
Executive Engineer B&R Division HP PWD, Baramulla						

Executive Engineer
B&R Division
HP.PWD Rohru

Job No. 65

62

SCHEDULE OF QUANTITY

Estimated Cost:-486553/-
 Earnest Money:-9800/-
 Time:-One Month

NAME OF WORK--:- C/O Link road to village Lakhadhar Mini Gadam road km. (SH:- C/O R/wall in PCC 1:4:8 at RD.0/6/12.50 to 0/6/25)						
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	6.63	287.80	Rupees:-Two Hundred Eighty Seven and Paisa Eighty only	Cum	1908
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	11.50	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	4681
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	3.64	6314.00	Rupees:-Six Thousand Three Hundred Forteen and Paisa Zero only	Cum	22983
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 as directed by the Engineer-in-Charge	71.71	5990.00	Rupees:- Five Thousand Nine Hundred Ninety Paisa Zero only.	Cum	429543
5	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall, return wall and retaining and breast wall with 100 (One hundred)dia millimetre PVC pipe extending through the full width of the structures with slope of 1 (V):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 as per the direction of the Engineer-in-Charge including carriage of materials through all modes of transportation with in all leads and lifts and other incidentals, with in all leads and lifts as per directed by the Engineer-in-Charge	40.00	414.00	Rupees:- Four Hundred Forteen Paisa Zero only.	No.	16560
6	Back filling behind abutments, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 with in all leads and lifts as per directed by the Engineer-in-Charge	7.38	1474.00	Rupees:-One Thousand Four Hundred Seventy Four Paisa Zero only.	Cum	10878
				Total:-		486553
		DNIT No.		Approved for Rs.486553/- only for the Year 2023-2024		
		%				
	Quoted rate in figure					
	Quoted rate in words					
	Signature of contractor with address:-					
				Executive Engineer B&R Division HP.PWD Rohru		

Executive Engineer
 B&R Division
 HP.PWD Rohnu

Job No. 66

63

SCHEDULE OF QUANTITY

Estimated Cost:-272156/-

Earnest Money:-5500/-

Time:-One Month

NAME OF WORK:-R/R damages on Shalawat Wali Karetali road (SH:-C/O B/wall at Rd.1/652 to 1/671)						
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Change	61.75	324.83	Rupees:-Three Hundred Twenty Four and Paisa Eighty Three only	Cum	20058
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Change	11.40	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	4640
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 as directed by the Engineer-in-Change	11.40	6656.00	Rupees:- Six Thousand Six Hundred Fifty Six Paisa Zero only.	Cum	75878
4	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Change	59.37	2890.00	Rupees:-Two Thousand Eight Hundred Ninety Paisa Zero only.	Cum	171579
Total:-						272156
DNIT No. Approved for Rs.272156/- only for the Year 2023-2024						
Quoted rate in figure		%				
Quoted rate in words		%				
Signature of contractor with address:-						

Executive Engineer
B&R Division
HP.PWD Rohru

SCHEDULE OF QUANTITY

Job No. **67**
Estimated Cost:-220791/-
Earnest Money:-4500/-
Time:-One Month

NAME OF WORK:- R/R damages to Hingwala Bagel Nauridhar road km. 0/0 to 5/0 (SH:-(SH:-C/O R/wall in wire crate at RD.1/120 to 1/160))

Sr.No.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	19.65	324.83	Rupees:-Three Hundred Twenty Four and Paisa Eighty Three only	Cum	6383
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material, with in all leads and lifts as per directed by the Engineer-in-Charge	11.25	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	4579
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	70.31	2890.00	Rupees:-Two Thousand Eight Hundred Ninety Paisa Zero only	Cum	203196
4	Providing and laying of back filling behind abutment, wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	4.50	1474.00	Rupees:-One Thousand Four Hundred Seventy Four and Paisa Zero only	Cum	6633
		Total:-				220791
		DNIT No. Approved for Rs.220791/- only for the Year 2023-2024				
		Quoted rate in figure %				
		Quoted rate in words %				
		Signature of contractor with address:-				

Executive Engineer
B&R Division
HP.PWD Rohru

(64) 67

68
(65)

SCHEDULE OF QUANTITY

Job No. 68
Estimated Cost:-207565/-
Earnest Money:-4200/-
Time:-One Month

NAME OF WORK:-R/R damages to Samoli Sainji Bhatwari road km. 0/0 to 7/0 (SH:-C/O B/wall in wire crate at RD.4/435 to 4/455)

Sr.No.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	67.40	324.83	Rupees:-Three Hundred Twenty Four and Paisa Eighty Three only	Cum	21894
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material, with in all leads and lifts as per directed by the Engineer-in-Charge	12.40	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	5047
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	62.50	2890.00	Rupees:-Two Thousand Eight Hundred Ninety Paiza Zero only.	Cum	180625
4	Providing and laying of back filling behind abutment, wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	0.00	1474.00	Rupees:-One Thousand Four Hundred Seventy Four and Paiza Zero only	Cum	0
			Total:-			207565
			DNIT No. <u> </u> Approved for Rs.207565/- only for the Year 2023-2024			
			Quoted rate in figure %			
			Quoted rate in words %			
			Signature of contractor with address:-			

Executive Engineer
B&R Division
HP.PWD Rohru

SCHEDULE OF QUANTITY

Job No. **69**
Estimated Cost:-473672/-
Earnest Money:-9500/-
Time:-One Month

NAME OF WORK:- R/R damages to Dhara Kapandli road km. 0/0 to 0/600 (SH:-C/O R/wall at RD.0/335 to 0/345)

Sr.No.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	33.20	324.83	Rupees:-Three Hundred Twenty Four and Paisa Eighty Three only	Cum	10784
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material with in all leads and lifts as per directed by the Engineer-in-Charge	33.10	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	13472
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	3.80	6314.00	Rupees:-Six Thousand Three Hundred Forteen and Paisa Zero only	Cum	23993
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	7.00	6656.00	Rupees:-Five Thousand Six Hundred Fifty Six Paisa Zero Only.	Cum	46592
5	Random Rubble Stone masonry in cement mortar 1:6 (1 Cement : 6 sand) for foundation complete as per drawings and technical specification Clauses 702, 704, 1202 and 1203 including carriage of material within all leads and lifts as per directions of Engineer in charge	38.76	5400.00	Rupees:-Five Thousand Four Hundred Paisa Zero Only.	Cum	209304
6	Construction of dry masonry in retaining walls, breast walls etc.as per drawings and technical specification including carriage of material within all leads and lifts as per directions of Engineer in charge	36.15	4082.00	Rupees:-Four Thousand Eighty Two Paisa Zero Only.	Cum	147564
7	Providing and laying of back filling behind R/wall and wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	14.90	1474.00	Rupees:-One Thousand Four Hundred Seventy Four and Paisa Zero only	Cum	21963
			Total:-			473672
Quoted rate in figure						
Quoted rate in words						
Signature of contractor with address:-						

DNIT No. **Approved for Rs.473672/- only for the Year 2023-2024**

Executive Engineer
B&R Division
HP.PWD Rohru

SCHEDULE OF QUANTITY

Est. Estimated cost Rs 4,68,903/-
Earnest Money Rs9300/-
Est. Time two Month

Name of work :- R/R Damages on Bhatwari Hingwala Gawas road km 0/0 7/0(SH- C/O R/ail in wire crate at Rd 2/980 to 2/985 and 3/0 to 3/020).

Sr No	Description of Items	Quantity	Rate in Figure.	Rate in Words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per drawing and Technical Specification Clause 1603.1 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other Incidentals	31.65	324.83	Rs three hundred twenty four & paise eighty three only	per cubic metre	10281
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. in ordinary rocks up to 3 mtr depth within all leads and lifts as per directions of Engineer in charge	15.75	407.00	four hundred seven only	per cubic metre	6410
2	Providing and laying of boulder apron laid in wire crates 4mm dia G.I wire conforming to IS 280 and IS 4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 within all leads and lifts as per directions of Engineer in charge	148.44	2890.00	Rs two thousand Eight hundred ninety only	per cubic metre	428992
3	Back filling behind the abutment, wing wall and return wall complete as per drawing and technical specification clause 1203.3, 8 Granular materials within all leads and lifts as per directions of Engineer in charge	17.20	1350.00	Rs one thousand three hundred fifty only	per cubic metre	23220
	Total:-					468903

DNIT NO Approved for Rs 4,68,903/- for the year 2023-2024

Quoted Rate in figure	(+) (-)	%
Quoted Rate in Words	(+) (-)	%

Singture of Contractor with full Address

Executive Engineer
B&R Divn HP PWD
Rohru

SCHEDULE OF QUANTITY

Estimated cost Rs 4,64,355/-
Earnest Money Rs 9200/-
Time One month

Name of work :- R/R Damages on link road from Dashalni to Thamanpuri km 0/0 to 2/500(SH- C/O R/wall in PCC 1:4:8 at Rd 0/680 to 0/694)

	Description of Items	Quantity	Rate in Figure.	Rate in Words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per drawing and Technical Specification Clause 1603.1 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	45.36	324.83	Rs three hundred twenty four & paise eighty three only	per cubic metre	14734
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. in ordinary rocks up to 3 mtr depth within all leads and lifts as per directions of Engineer in charge	26.88	407.00	Four hundred seven only	per cubic metre	10940
3	Providing and laying cement concrete 1:6:12 (one cement six sand twelve graded stone aggregate 40mm nominal size for plain/reinforced concrete in open foundation complete as per drawing and technical specification cause 802.803, 1202 and 1203 including carriage of materials within all leads and lifts as per directions of Engineer in charge	6.72	6118.50	Rs six thousand one hundred eighteen & paise fifty only	per cubic metre	41116
4	Providing and laying mechanical mixed and vibrated cement concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:4:8 (One cement: four sand: eight graded crushed stone aggregate) 25 mm specification clauses 802.803, 1202 and 1203 as per direction of Engineer-in-Charge including carriage of material through all modes of transportation with in all leads and lifts and other incidentals.	58.80	6464.67	Rs six thousand four hundred sixty four & paise sixty seven only	per cubic metre	380122
5	Providing weep hole in /stone masonry plain reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending to the full width of the structure with slope of (1V) 20(H) towards drawing face complete as per drawing and technical specification within all leads and lifts	35.00	401.18	Rs four hundred one & paise eighteen only	Each	14041
6	Back behind abutment wing wall return wall with Granular materials complete as per drawing and technical specification clause 1204.3.8 with all leads and lifts as per directions of Engineer in charge	2.52	1350.00	Rs one thousand three hundred fifty only	per cubic metr	3402
	Total:-					464355

DNIT NO. Approved for 4,64,355/- -only - for the year 2023-24

1500

Quoted Rate in figure	(+) (-)	%
Quoted Rate in Words	(+) (-)	%

Singiture of Contractor with full Address

Executive Engineer
B&R Divn HP, PWD
Bard

74

BIDDING SCHEDULE OF QUANTITY

Estimated cost Rs 4,64,355/-
Earnest Money Rs 9200/-
Time One month

73 (69)

Name of work :- R/R Damages on link road from Dashedini to Thamanpuri km 0/0 to 2/500(SH- C/O R/wall in PCC 1:4:8 at Rd 0/450 to 0/464)

Description of Items		Quantity	Rate in Figure.	Rate in Words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per drawing and Technical Specification Clause 1603.1 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	45.36	324.83	Rs three hundred twenty four & paise eighty three only	per cubic metre	14734
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back-filling in trenches with excavated suitable material. In ordinary rocks up to 3 mtr depth within all leads and lifts as per directions of Engineer in charge	26.88	407.00	Four hundred seven only	per cubic metre	10940
3	Providing and laying cement concrete 1:6:12 (one cement six sand twelve graded stone aggregate 40mm nominal size for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803, 1202 and 1203 including carriage of materials within all leads and lifts as per directions of Engineer in charge	6.72	6118.50	Rs six thousand one hundred eighteen & paise fifty only	per cubic metre	41116
4	Providing and laying mechanical mixed and vibrated cement concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:4:8 (One cement: four sand : eight graded crushed stone aggregate) 25 mm specification clauses 802.803, 1202 and 1203 as per direction of Engineer-in-Charge including carriage of material through all modes of transportation with in all leads and lifts and other incidentals.	58.80	6464.67	Rs six thousand four hundred sixty four & paise sixty seven only	per cubic metre	380122
5	Providing weep hole in /stone masonry plain reinforced concrete abutment wing wall return wall with 100mm dia A.C. pipe extending to the full width of the structure with slope of (1/V) 20(H) towards drawing face complete as per drawing and technical specification within all leads and lifts	35.00	401.18	Rs four hundred one & paise eighteen only	Each	14041
6	Back behind abutment wing wall return wall with Granular materials complete as per drawing and technical specification clause 1204.3.8 with all leads and lifts as per directions of Engineer in charge	2.52	1350.00	Rs one thousand three hundred fifty only	per cubic metre	3402
Total:-			4451			464355

DNT NO Approved for 4,64,355/- only - for the year 2023-24

1501

Quoted Rate in Figure	(+) (-)	%
Quoted Rate in Words	(+) (-)	%

Singture of Contractor with full Address

Executive Engineer
B&R Divn HP, PWD
Rajmnd

75

SCHEDULE OF QUANTITY

Thiruvananthapuram

Name of work : R/R Damages link road from Dashedini km 0/0 to 2/500(SH- Providing laying essential kharanja stone soling 0 0/0 to 0/370)

Estimated cost Rs 4,85,105/-
Earmont money Rs 9700/-
Est Time :- one month

Sr No	Description of Items	Quantity	Rate in Figure.	Rate in Words	Unit	Amount
5	Preparation of sub grade by dressing to camber (earth work for the cutting involved for sub grade to be paid for separately /depon upon the classification of soil complete as per HP.PWD specification including carriage of materials within all leads and lifts as per direction of Engineer in charge	1363.45	1.94	Rs one & paise ninety only	per square	2646
6	Consolidation of sub grade with road roller making good the undulation etc with earth quarry soil etc and re-rolling the sub grade complete as per HP.PWD specification within all leads and lifts as per directions of Engineer in charge	1768.80	1.35	Rs one & paise thirty five only	per square	1837
7	Stone soling properly hand packed filling interstices with kharanja stone and consolidating with power road roller to the requested gradient asnd camber including spreading watering and rolling of binding materials moonum earth etc complete as per HP.PWD specification 150mm within spread thickness (finished work including materials and labour)	204.52	2350.00	Rs two thousand three hundred fifty only	per cubic metre	480622
	Total:-					

Quoted Rate in figure	(+) (-)	%
Quoted Rate in Words	(+) (-)	%

DNIT NO 1444 Approved for Rs 485105/- for the year 2023-24

1504

Signature of Contractor with full Address

Executive Engineer
B&R Divn HP.PWD
Rajuru

(70)

SCHEDULE OF QUANTITY

Estimated cost Rs 4,85,105/-
 Earnment money Rs 9700/-
 Est Time :- one month

Name of work : R/R Damages link road from Dashalni km 0/0 to 2/500(SH- Providing laying essential kharanja stone soling 0/370 to 0/740)

Sr No	Description of Items	Quantity	Rate in Figure.	Rate in Words	Unit	Amount
5	Preparation of sub grade by dressing to camber (earth work for thecutting involved for sub grade to be paid for sperately)depon upon the classification of soil complete as per HP.PWD specification including carriage of materials within all leads and lifts as per dircion of Engineer in charge	1363.45	1.94	Rs one & paise ninety only	per square	2646
6	Consolidation of sub grade with road roller making good the undulation etc with earth quarry soil etc and re-rolling the sub grade complete as per HP.PWD specification within sail leads asnd lifts as per directions of Engineer in charge	1768.80	1.35	Rs one & paise thirty five only	per square	1837
7	Stone soling properly hand packed filling interstices with kharanja stone and consolidating with power road roller to the requested gradient asnd camber including spreading watering and rolling of binding materials moorum earth etc complete as per HP.PWD specification 150mm within spread thickness (finished work including materials and labour)	204.52	2350.00	Rs two thousand three hundred fifty only	per cubic metre	480622
	Total:-					
		DNIT NO <u>1485</u>		Approved for Rs 485105/- for the year 2023-24		

Quoted Rate in figure	(+) (-)	%
Quoted Rate in Words	(+) (-)	%

Singture of Contractor with full Address

Executive Engineer
 B&A Dwn HP.PWD
 Rbzu

OF SCHEDULE OF QUANTITY.

ne of work : -Improvement of Black spot on on Rohru Sungri road (SH- Improvement of narrow reaches at RD 60/560 to 0 60/6056)

Estimated cost Rs 4,99,211/-
Earnest money Rs900/-
TIME : Two month

Description of Items	Quantity	Rate In Figure.	Rate in Words	unit	Amount
Excavation in earth work in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side. Water pollution, etc and to protect soil stability of hill side rock shall be excavated with chiseling and wedging our rock (where blasting is prohibited) All earth work in cutting/excavation including rock excavation shall be carried out true to line, grades, slopes, width, camber, super elevation and level as shown on the drawing as per direction of Engineer in Charge in conformity with the requirement of technical specification for rural roads august 2004 clause 16.2 of general conditions of contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and stage, disposal of unsuitable cut material in specified manner, trimming/filling as directed by Engineer in charge for smooth riding. The recovery of useful stones shall be made @300/-per cubic meter on prorata basis in each running bill. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified /dimension in all leads and lifts as per the direction of Engineer in Charge.	1368.00	364.92	Rs three hundred sixty four & psaise ninety on ly	per cubic metre	499211.00
Total:-					499211.00

DNIT NO Approved for Rs4,99,211 -for the year 2023-2024

Quoted Rate in figure (+)/(-)	%
Quoted Rate in Words (+)/(-)	%

Signature of Contractor with full Address :

Executive Engineer
B&R Dwn HP, PWD
Rohru

76-77 (12)

SCHEDULE OF QUANTITY

Item of work : -Improvement of Black spot on on Rohru Sungri road (SH-Improvement of narrow reaches at RD 60/635 to 60/665)

Estimated cost Rs4,97,895
Earnest money Rs9000/-
TIME : Two month

Description of Items	Quantity	Rate in Figure	Rate in Words	unit	Amount
Excavation in earth work in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side. Water pollution, etc and to protect soil stability of hill side rock shall be excavated with chiseling and wedging our rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to line, grades, stops, width, camber, super elevation and level as shown on the drawing as per direction of Engineer in Charge in conformity with the requirement of technical specification for rural roads august 2004 clause 16.2 of general conditions of contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and stage, disposal of unsuitable cut material in specified manner, trimming/filling of unevenness bludge and finishing of the road to specified diamensions or as directed by Engineer in charge for smooth riding. The recovery of useful stones shall be made from the contractor and recover 365.41 . cubic meter useful stones shall be made @300/-per cubic meter on prorata basis in each running bill. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified /dimension in all leads and lifts as per the direction of Engineer in Charge.	1377.00	361.58	Rs Three hundred sixty one & paise fifty only	per cubic metre	497895.00
Total:-					
DNT NO Approved for Rs 4,97,895. -for the year 2023-2024					
Quoted Rate in figure (+)(-)					497895.00
Quoted Rate in Words (+)(-)					

Singture of Contractor with full Address

Executive Engineer
B&R Divn HP, PWD
Rohru

78-73

JOB NO:-

Schedule of Qty

Name of Work:- R/R Damage to various road under Rohru Section Sub Division Rohru(SH:- Hiring of JCB removal of slip and land slide maintenance of road)

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST	
				EARNEST MONEY	495000
1	2	3	4	TIME LIMIT:	Two Month
				Rate In Fig.	Amount.
1	Hiring of J.C.B.(Excavator-Cum-Loader) front end loader 0.45 cum bucket capacity and including P.O.L. charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	450	Per Hours	1100	Rupees One Thousand One Hundred Only
Total					495000

DNIT No..... approved for amounting to Rs:-495000/- for the year 2023-24

1 The rates Should be quoted for all heights including all lead and lifts.
 2 The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and cost.

Quoted rate Figure (+/-)
Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer
 B&R Division HPPWD
 Rohru

SCHEDULE OF QUANTITY

Estimated cost RS 4,98,025/-
Eanment money 10000/-
Time :one Month

Name of work :- R/R damages on Khorsu Kulu road km road (SH- B/wall in PCC 1:3:6 at RD 0/300 to 0/317)

Sr.No	Description of Items	Quantity	Rate in Figure.	Rate in Words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per drawing and Technical Specification Clause 1603.1 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts, and other incidentals.	6.46	303.17	Rs three hundred three & paise seventeen only	per cubic metre	1958
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. in ordinary rocks up to 3 mtr depth within all leads and lifts as per directions of Engineer in charge	28.39	407.00	Rs four hundred seven only	per cubic metre	11555
3	Providing and laying cement concrete 1:6:12 (one cement six sand twelve graded stone aggregate 40mm nominal size for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803, 1202 and 1203 including carriage of materials within all leads and lifts as per directions of Engineer in charge	5.36	6314.00	Rs Six thousand three hundred fourteen only	per cubic metre	33843
4	Providing concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803, 1202 and 1203 PCC 1:3:6 within all leads and lifts as per directions of Engineer in charge	63.75	6870.00	Rs six thousand eight hundred seventy only	per cubic metre	437962
5	Providing weephole in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC Pipe extending through the full width of the structures with slope of 1(V)20(H) towards drawing face complete as per drawing and technical specification clause 614.709, 1204.3.7 within all leads and lifts as directions of Engineer in charge	35.42	414.00	four hundred fourteen only.	Nos	14664
Total:-						4,98,025/-

DNIT NO Approved for Rs 4,98,025 - for the year 2023-24

Quoted Rate in figure	(+) (-)	%
Quoted Rate in Words	(+) (-)	%

Singture of Contractor with full Address

Executive Engineer
B&R Divn HP, PWD
Rohru

SCHEDULE OF QUANTITY .

Estimated cost Rs 2,23,673/-
EARNEST MONEY Rs 4500/-
TIME : Two month

(76)

Name of work :- R/R Damages on road from Anupum Hotel to chirgaon Junction km 0/0 to 0/600(SH- P/F wire mesh ast RD 0/0 to 0/034)

Sr No	Description of items	Quantity	Rate in Figure.	Rate in Words	unit	Amount
1	Providing and laying concrete 1:2:4 (1cement :2 sand :4 graded stone aggregate 20mm size)for plain reinforcement for cement concrete in open foundation complete as per drawing and technical specification in foundation plinth including all leads and lifts as per HP.PWD specification 1990 volume-I as directed by Engineer in charge	16.32	7600.00	Rs seven thousand six hundred only	per cubic metre	124032
2	Steel work welded in built up section gtrused and frame work including cutting hosting fixing in position and applying a priming coat of red lead paint in greating framed gard bgars ladders railing brackes and similar works including all leads and liftgs as HP.PWD specification as directed by the Engineer in charge	338.77	121.00	Rs one hundred twenty one only	per cubic metre	40991
3	supplying and fixing wovenplan G.I chain lin fencing of mesh 50mm to 50mm to any type of standarder rails stranging bolts etc including provision of foundation work stages etc and G.I wire 4mm the including all leads and lifts as per HP.PWD specification of 1990 volume or as directed by the Engineer in charge	85.00	690.00	six hundred ninety only.	per cubic metre	58650
						223673

Condition
The contr .shall procure all the materials confirming to the specification of morth at is on rick and co.st

Quoted Rate in words (+)(-)
Quoted rate in fig. (+)(-)
Sing of the contract with full Adress

Executive Engineer
B&R Divn HP.PWD
Rohru

SCHEDULE OF QUANTITY

Estimated cost Rs 4,46,250-
Eanment money 8500/-
Time One Month

e of work :- R/R Damages on Kasnakoti Kutara Dalgaon road km 0/0 to 15/0 (SH- C/O B/wall at RD 12/720 to 12/740)

Description of items	Quantity	Rate in Figure.	Rate in Words	Unit	Amount
1 Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per drawing and Technical Specification Clause 1603.1 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	44.20	324.83	Rs three hundred twenty four & paise eighty three only	per cubic metre	14357
2 Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary rocks up to 3 mtr depth within all leads and lifts as per directions of Engineer in charge	33.60	402.00	Rs four hundred two only	per cubic metre	13507
3 Providing and laying cement concrete 1:6:12 (one cement six sand twelve graded stone aggregate 40mm nominal size for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803, 1202 and 1203 including carriage of materials within all leads and lifts as per directions of Engineer in charge	9.60	6314.00	Rs six thousand three hundred fourteen only	per cubic metre	60614
4 Providing and laying mechanical mixed and vibrated cement concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:4:8 (One cement: four sand : eight graded crushed stone aggregate) 25 mm specification clauses 802.803, 1202 and 1203 as per direction of Engineer-in-Charge including carriage of material through all modes of transportation with in all leads and lifts and other incidentals.	4.00	6656.00	Six thousand six hundred fifty six only	per cubic metre	26624
5 Random rubble masonry polygonal rubble masonry uncoursed /brought to courses with hard stone of approved quality in foundation and plinth cement mortar 1:5:(1cement:5sand)breast wall and retaining wall within all leads and lifts as per directions of Engineer in charge	37.32	5830.26	Five thousand eight hundred thirty & paise twenty six only	per cubic metre	217585
6 Construction of dry rubble masonry for retaining walls breast wall revertment walls and parapets etc for sub structure complete as per drawing and technical specification clause 704.6 and 1305 within all leads and lifts as per direction of Engineer in charge	27.82	4082.00	Rs four thousand eighty two only	per cubic metre	113561
Total:-					446250

DNIT NO Approved to 4,46,250 /- for the year 2023-24

Quoted Rate in figure	(+) (-)	%
Quoted Rate in Words	(+) (-)	%

Singnture of Contractor with full Address

Executive Engineer
B&R Dm HP.PWD
Rajni

SCHEDULE OF QUANTITY.

Estimated cost Rs 4,85,096/-

Earnest money Rs 9700/-

TIME : Two month

Name of work :- C/O Mastot to Bagi Kainchi road km 0/0 to 1/235 (SH- F/C 5/7 metre wide road at Rd 0/0 to 0/345)

r No	Description of items	Quantity	Rate in Figure.	Rate in Words	unit	Amount
1	Excavation in earth work in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side. Water pollution, etc and to protect soil stability of hill side rock shall be excavated with chiseling and wedging our rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to line, grades, slopes, width, camber, super elevation and level as shown on the drawing as per direction of Engineer in Charge in conformity with the requirement of technical specification for rural roads august 2004 clause 16.2 of general conditions of contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and of unevenness blinding and finishing of the road to specified dimensions or as directed by Engineer in charge for smooth riding. The recovery 214.46 cubic meter useful stones shall be made @300/-per cubic meter on proata basis in each running bill. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified /dimenstion in all leads and lifts as per the direction of Engineer in Charge.	1987.51	244.07	Two hundred forty four & paise seven only	per cubic metre	485096.00
Total:-						
DNT NO Approved for Rs4,85,096/-for the year 2023-2024						485096.00

Quoted Rate in figure (+)/(-) %

Quoted Rate in Words (+)/(-) %

Signature of Contractor with full Address

Executive Engineer
B&R Divn HP, PWD
Rohru

78

Job No-

DNIT / SCHEDULE OF QUANTITY

DNIT / SCHEDULE OF QUANTITY							Estimated Cost	489600.00	
							Earnest Money	9800.00	
							Time	72 Days	
Name of work :- R/R Damage to Various Road under Badiyara Section Sub Division Chirgaon (SH:- Hiring of Tipper for carriage of									
Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.			
1	Hiring of Tipper for carriage of materials having capacity 400 Cft including P.O.L charges, shifting charges and other ancillary equipment as required at site of work. The work shall have to carried out as per Ministry of Transport specifications of the Engineer-In-Charge including all leads and lifts.	72.00	6800.00	Rupees Six Thousand Eight Hundred Only	Per Day	489600.00			
						Total=	489600.00		
DNIT No Approved for Rs 489600/- only for the year 2023-24									
Quoted Rate in Figure		%							
Quoted rate in Words		%							
Signature of Contractor with Address :-									

Executive Engineer,
B&R Division HPPWD,
Rohru.


 Executive Engineer,
 B&R Division HPPWD,
 Rohru.

82

Job No-

DNIT / SCHEDULE OF QUANTITY

Name of work :- R/R Damage to Various Road under Badiyara Section Sub Division Chirgaon (SH:- Hiring of Tipper for carriage of					Estimated Cost		489600.00	
					Earnest Money		9800.00	
					Time		72 Days	
Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.		
1	Hiring of Tipper for carriage of materials having capacity 400 Cft including P.O.L charges, shifting charges and other ancillary equipment as required at site of work. The work shall have to be carried out as per Ministry of Transport specifications of the Engineer-In-Charge including all leads and lifts.	72.00	6800.00	Rupees Six Thousand Eight Hundred Only	Per Day	489600.00		
Total=						489600.00		
DNIT No _____ Approved for Rs 489600/- only for the year 2023-24								
Quoted Rate in Figure %								
Quoted rate in Words %								
Signature of Contractor with Address :-								


 Executive Engineer,
 B&R Division HPPWD,
 Rohru.

Job No-

DNIT / SCHEDULE OF QUANTITY

Name of work :- R/R Damage to Various Road under Badiyara Section Sub Division Chirgaon (SH:- Hiring of J.C.B. for removal of slips and maintenance of road)

Estimated Cost	498300.00	
Earnest Money	10000.00	
Time	2 Months	

Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of J.C.B(Excavator-Cum-Loader) having bucket capacity .50 cum including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 18 cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	453.00	1100.00	Rupees One Thousand One Hundred Only	Per Hours	498300.00
					Total=	498300.00
	DNIT No Approved for Rs 498300/- only for the year 2023-24					

Executive Engineer,
B&R Division HPPWD,
Rohru.

DNT / SCHEDULE OF QUANTITY

Name of work :- R/R Damage to Various Roads in Chirgaon Sub Division (Seema Section) (SH:- Removal of slips by J.C.B. At various RD's and drassing of road surface drain clearance)

Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of J.C.B.(Excavator-Cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 18 cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	450.00	1100.00	Rupees One Thousand One Hundred Only	Per Hours	495000.00
Total=						495000.00
DNT No 1260 Approved for Rs 495000/- only for the year 2023-24						
Quoted Rate in Figure %						
Quoted rate in Words %						
Signature of Contractor with Address :-						

Executive Engineer,
B&R Division HPPWD,
Rohru.

Job No-

DNIT / SCHEDULE OF QUANTITY

Name of work :- R/R Damage to Various Roads in Chirgaon Sub Division (Seema Section) (SH:- Removal of slips by J.C.B. At various RD's and drassing of road surface drain clearence)

Estimated Cost	495000.00
Earnest Money	9900.00
Time	Two Month

Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of J.C.B.(Excavator-Cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burns. Minimum 18 cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	450.00	1100.00	Rupees One Thousand One Hundred Only	Per Hours	495000.00
Total=						495000.00
DNIT No 1262 Approved for Rs 495000/- only for the year 2023-24						

Quoted Rate in Figure	%
Quoted rate in Words	%
Signature of Contractor with Address :-	

Executive Engineer,
B&R Division HPPWD,
Rohru.

Job No-

DNIT / SCHEDULE OF QUANTITY

Name of work :- R/R Darnage to Various Roads in Chirgaon Sub Division (Seema Section) (SH:- Removal of slips by J.C.B. At various RD's and drassing of road surface drain clearance)

Estimated Cost	495000.00	
Earnest Money	9900.00	
Time	Two Month	

Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of J.C.B.(Excavator-Cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 18 cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	450.00	1100.00	Rupees One Thousand One Hundred Only	Per Hours	495000.00
DNIT No <u>1961</u> Approved for Rs 495000/- only for the year 2023-24						Total= 495000.00

Quoted Rate in Figure	%
Quoted rate in Words	%
Signature of Contractor with Address :-	

Executive Engineer,
B&R Division HPPWD,
Rohru.

8m

DNT / SCHEDULE OF QUANTITY

Job No-

Name of work :- R/R Damage to Various road Under Kansakoti Section Sub Division Rohru (SH:- Hiring of J.C.B. for removal of Slips		Estimated Cost	495000.00	
Construction of unlined surface drain and opening of culvert dressing of road surface etc.)		Earnest Money	9900.00	
		Time	450 Hours	

Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of J.C.B/Excavator-Cum-Loader) having bucket capacity .45 cum as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 18 cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	450.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	495000.00
					Total=	495000.00
Quoted Rate in Figure			DNT No 1155 Approved for Rs 495000/- only for the year 2023-24			
Quoted rate in Words						
Signature of Contractor with Address :-						

Executive Engineer,
B&R Division HPPWD,
Rohru.