

Himachal Pradesh
Public Works Department
PW-RD-GA-Tender-2023-24-
To

23341

dated:- 14/02/2

The Executive Engineer (IT Cell)
Nigam Bihar, Shimla-2.

Subject: - Tender notice.

Enclosed please find herewith the tender notice of work as given in the notice inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of H.P. letter N. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th July 2021.

1. Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.

DA:- Notice inviting tender & schedule of quantity.


Executive Engineer,
B&R Division, HPPWD,
Rohru.

**Himachal Pradesh
Public Works Department
"NOTICE INVITING TENDERS"**

*Sealed item rate tender on form PWD 6&8 are invited by the Executive Engineer
Rohru Division HPPWD, on behalf of Governor of H.P. for the following works from the approved and
eligible contractors enlisted in HPPWD, So as to reach in this office as per time schedule given below:-*

- 1.Date of receipt of applications for tender forms:- 22.02.2024 upto 1:00PM
- 2.Date of issue/sale of tender forms:- 22.02.2024 upto 2:00PM to 3.00PM
- 3.Date of receipt of tender:- 23.02.2024 upto 3:30PM

Sl.	Name of work	Estimated cost	Earnest money	Time Allowed
1	R/R damages to Umladawar Reoghati Deoridhat road km 0/0 to 7/0 (SH:- C/O B/Wall in wire crate at Rd 3/800 to 3/826 , 3/830 to 3/835 , 3/850 to 3/865)	479879	9598	Two month
2	R/R Damages to various road under Tikkar section sub - Division Tikkar (SH:- Supplying and stacking of fine Sand at site of work for spreading over snow)	496000	9920	Two month
3	R/R / Snow damages on various raods under Khadralla Section Tikkar Sub Division (SH:-Hiring of JCB for removal of snow and landslide , drain clearance , opening of culverts , filling of depression and berms,)	476000	9520	Two month
4	R/R on various roads under Tikkar Sub Division (Tikkar Section) (SH:- Hiring of Tipper)	270000	5400	Two month
5	R/R Damages of link road Pujarli koti saraidhar 0/0 to 16/600 . (SH:- Removal of slips various Rd 7/485 to 10/710)	469882	9398	Two month
6	R/R Damages of link road Pujarli koti saraidhar 0/0 to 16/600 . (SH:- Removal of slips various Rd 10/740 to 14/045)	455278	9106	Two month
7	R/R Damages to Mandharli to karchhari road km RD 0/0 to 12/200 (SH:- C/O R/Wall in wire crate at Rd 9/740 to 9/755, 8/890 to 8/911)	471542	9431	Two month
8	R/R on various roads under Tikkar Sub Division (Sheelghat Section) (SH:- Hiring of JCB for Removal of land slide drain clearance opening of culverts filling of depression	493000	9860	Two month
9	C/O link road from Tandroh Nallah to Jhanterli road km 0/0 to 1/500 (SH:- C/O Hume pipe culvert at RD 0/490)	371901	7438	Two month
10	C/O link road to H.B Hanstari Dhar km 0/00 to 1/500 (SH:- C/o R/Wall in wire crate at Rd 0/690 to 0/710)	470022	9400	Two month
11	C/O link road village Dhanoti km 0/0 to 4/500 (SH:- C/O R/Wall at Rd 2/210 to 2/226.50)	485525	9711	Two month
12	C/O link road H.B Samra Dhanoti Khalwan road km 0/00 to 3/400 (SH:- providing and laying G-III km at Rd 1/350 to 1/700 & Earthan Shoulder km 0/00 to 1/700)	350997	7020	Two month
13	C/O Link raod Tipper to Shallan kit Randeep Nagar Bihar Dogra pul km 0/0 to 3/400 (SH:- C/O R/Wall at RD 0/110 to 0/126.50)	485065	9701	Two month
14	R/R damages on Shallan Karchari Mandharli road km 0/0 to 12/0(SH:- C/o Rwall at RD. 5/690 to 5/705)	314779	6296	Two month
15	C/O Missing C.D on tutupani Nalawan road km 0/0 to 5/500 (SH:- C/O 900 mm dia HPC at RD 4/400)	486209	9724	Two month

16	Repair of JE. Office cum Residence at Pujarli No.4 Tehsil Rohru Distt. Shimla HP. (SH:- Providing, Distempering, Roofing including WS & S.I fitting etc.)	448818	8976	Two month
17	R/R damages on Deoli Khalai Dharikupper road km 0/0 to 5/0 (SH:- C/O R/Wall at RD. 4/830 to 4/838)	336105	6722	Two month
18	Suideori Bashlog road km 0/0 to 5/0 (SH:- C/O 1 No 900 mm dia HPC at RD 2/105)	447225	8945	Two month
19	R/R damages to Pujarli madidhar Road km Rd 0/0 to 4/0 (SH:- C/o R/Wall at RD 1/580 to 1/589)	473765	9475	Two month
20	R/R damages to Blakhor Sheetalvan Kalgaon Teer road km RD 0/0 to 3/500 (SH:- C/O Retaining wall at RD 2/277.50 to 2/285)	420794	8416	Two month
21	R/R damages to Blakhor Sheetalvan Kalgaon Teer road km RD 0/0 to 3/500 (SH:- C/O Retaining wall at RD 2/187.50 to 2/195)	420794	8416	Two month
22	C/O Umladwar Deorighat via Reoghati Road km 0/00 to 9/00 (SH:- Culvert Drianage work 900 mm dia Hume Pipe culvert at Rd 7/060)	425730	8515	Two month
23	R/R Damages to Narain Ghralla Mandharli Via Thana Breashtu km 0/0 to 9/0 (SH:- C/O B/Wall in wire crate at RD 8/800 to 8/810 , 4/300 to 4/310)	206246	4125	Two month
24	R/R damages on link road to village Thana km 0/00 to 4/00 (SH: C/O B/Wall at RD 3/830 to 3/845)	427300	8546	Two month
25	R/R damages on various road under Tikkar sub - Division (Pujarli section) (SH:- Hiring of JCB for removal of land slide , drain clearance , opening of culverts-filling of depression in various roads.	495000	9900	Two month
26	R/R damages on Ganasidhar Kaidwan road km 0/0 to 12/300 (SH:-C/O B/Wall in wire crate 1/490 to 1/505 and R/Wall at RD 5/015 to 5/023)	272952	5459	Two month
27	R/R Damages on link road Bhajnudharb Kewladhar Mohan lal parisar km 00/00 to 2/100 (SH:- C/o R/wall at Rd 1/165 to 1/174)	340320	6806	Two month
28	C/O Link road Tippr to Shallan Kit Randeep Nagar Biharu Dogra pul km 0/0 tio 3/400 (SH:- P/L Kharunja stone soling at RD 0/250 to 0/500)	461627	9233	Two month
29	R/R on various roads under Tikkar Sub Division (Tikkar Section) (SH:- Hiring of JCB for Removal of land slide drain clearance opening of culverts filling of depression	493000	9860	Two month
30	R/R on various roads under Tikkar Sub Division (Tikkar Section) (SH:- Providing and suppling wire crate)	360000	7200	Two month
31	R/R on various roads under Tikkar Sub Division (Tikkar Section) (SH:- Hiring of JCB for Removal of land slide drain clearance opening of culverts filling of depression	493000	9860	Two month
32	R/R on various roads under Tikkar Sub Division (Tikkar Section) (SH:- Hiring of JCB for Removal of land slide drain clearance opening of culverts filling of depression	493000	9860	Two month
33	R/R on various roads under Tikkar Sub Division (Tikkar Section) (SH:- Hiring of JCB for Removal of slips and miantenace of raod at various RD)	487200	9744	Two month
34	Repair and maintenance of JE head Quarter at Pujarli no 4 in Tehsil tikkar)	284049	5681	Two month
35	R/R damges to Madharli Shrontha km Rd 0/0 t 10/00 (SH:- Widening of Blackspot at RD 5/515 to 5/560)	457784	9156	Two month

36	C/O Bajnudhar Kewaldhar via mohan lal parisar km 0/0 to 3/500 (SH:- P/L kharnaja stone soling at Rd 0/450 to 0/550 and R/Wall in wire crate at Rd 0/500 to 0/520 and 0/615 to 0/625)	487249	9745	Two month
37	C/O link road Tippr to Shalla Kit Randeep Nagar Bihar Dogra pul km 0/0 to 3/400 (SH:- P/L Kharunja stone soling at RD 0/500 to 0/750)	479958	9599	Two month
38	R/R Damages to Mehendi Tikkar Road km Rd 0/00 to 28/300 (SH:- C/O R/Wall in wire crate at RD 24/100 to 24/120)	492969	9859	Two month
39	R/R on various roads under Tikkar Sub Division (Sheelghat Section) (SH:- Hiring of JCB for Removal of land slide drain clearance opening of culverts filling of depression	493000	9860	Two month
40	A/R & M/O Mehandli Tikkar road 0/0 to 28/500 (SH:- C/o B/Wall at Rd 10/570 to 10/590)	309387	6188	Two month
41	R/R damages on Syria Nallah Melthi kupri road km 0/0 to 6/0 (SH:- C/o R/Wall in wire crate at RD 5/285 to 5/295)	232214	4644	Two month
42	C/O link road from Syria Nallah to Methi Kupri road km 0/0 to 6/0 (SH:- C/O 900 mm dia dHume Pipe culvert at Rd 2/800 with wing wall 4.00 on both side.)	396502	7930	Two month
43	R/R damages to Syria Nallah Melthi Kupri Road km RD 0/0 to 6/0 (SH:-C/O R/Wall in wire crate at RD 5/300 to 5/310)	459910	9198	Two month
44	R/R Damages to various road under Sheelghat section sub - Division Tikkar (SH:- Supplying and stacking of fine Sand at site of work for spreading over snow)	496000	9920	Two month
45	R/R damages on various road under Tikkar Sub- Division (Tikkar Section) (SH:- Hiring of JCB for removal of land slide , drain clearance , opening of culverts , filling of depression)	493000	9860	Two month
46	R/R damages on Pujarli koti road (SH:- C/O B/Wall in wire crate in RD 7/00 to 7/030	279485	5590	Two month
47	R/R Damages on Link Road to Bharanta Basti km Rd 0/00 to 1/060) (SH:- C/O B/Wall in 0/00 to 0/025)	194018	3880	Two month
48	R/R Damage to Sua Deori Shekhal road km 0/0 to 6/00(SH:- C/o B/wall at Rd 0/150 to 0/169)	352459	7049	Two month
49	Restoration of rain /snow damages on various road under Khadralla Section (Tikkar Sub-Division) (SH:- Hiring of JCB. For removal of snow and land slide , drain clearance , opening of culverts, filling of depression and berms)	476000	9520	Two month
50	M/T of Kotkhai Khaneti Deorigat Tikkar road km 24/000 to 29/690(SH:-.Preparation of DPR under the schemes for special assistance to state for capital expenditure.	238980	4780	Two month
51	R/R Damages on various road under Sheelghat Section sub Division Tikkar (SH:- Hiring of JCB for removal of slip and snow / Land slide , Maintenance of road)	495000	9900	Two month
52	C/O link road Tandali to Dogra Khud 0/0 to 0/500 (SH:-C/o 5/7 mtr wide formation cutting at RD. 0/0 to 0/150)	497690	9954	Two month
53	R/R damages on various road under Tikkar sub Division (Tikkar section) SH:- Hiring of JCB for removal of slips slush/land slide and maintenance of road etc)	495000	9900	Two month
54	R/R damages on various road under Tikkar sub Division (Tikkar section) SH:- Hiring of JCB for removal of slips slush/land slide and maintenance of road etc)	495000	9900	Two month
55	R/R damages on various road under Tikkar sub Division (Tikkar section) (SH:- Hiring of JCB for removal of slips slush/land slide and maintenance of road etc)	495000	9900	Two month
56	R/R damages on various road under Tikkar sub Division (Tikkar section) (SH:- Hiring of JCB for removal of slips slush/land slide and maintenance of road etc)	495000	9900	Two month

57	R/R damages on various road under Tikkar sub Division (Tikkar section) (SH:- Hiring of JCB for removal of slips slush/land slide and maintenance of road etc)	495000	9900	Two month
58	C/o Link road from Kalgaon Teer to Prem Singh Dutta's House km 0/0 jto 0/315(SH:- Widening of road at RD. 0/090 to 0/315)	449472	8989	Two month
59	R/R Damages to Mandharli to Karchari road km Rd 0/0 to 12/200 (SH:- C/O R/Wall at RD 8/732 to 8/749)	443514	8870	Two month
60	R/R damges to Mandharli to karchari road km RD 0/0 to 12/200 (SH:- C/O R/Wall in wire crate at RD 8/705 to 8/721)	434036	8681	Two month
61	R/R damages on Pujarli Saraidhar Road km Rd 0/00 to 16/00 (SH:- C/O R/wall at RD 13/230 to 13/250)	442405	8848	Two month
62	R/R damages on Sheelghat to Saungi via Chota Sheel (SH:- C/O B/Wall at RD 0/915 to 0/930)	366865	7337	Two month
63	R/R Damages on Sheel Saungi Mandla Kupri road k m 0/0 to 5/0 (SH:- Hiring of Backhoe loader (like JCB) for removal of slips at various RDs and C/O road side Katcha drain etc.)	385000	7700	Two month
64	R/R Damages on various road under Sheelghat Section sub Division Tikkar (SH:- Supplying and stacking of fine sand at site of work for spreading over snow Badshal Nallah Kharla Road)	496000	9920	Two month
65	C/O Link road to Baghi km 0/0 to 3/0 (SH:- Widening of narrow reaches km 1/480 to 1/705)	475852	9517	Two month
66	R/R damages on Syria Nallah to Methi Kupri road km 0/0 to 6/0 (SH:- C/O R/Wall at RD 5/470 to 5/477 , 5/510 to 5/522.52)	461149	9223	Two month

Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.

Terms and conditions:-The tender document shall be issued only to these contractors/firms who fulfill the following criteria and submit the following document with the application.

1. The Earnest-money for the above works should be submitted with the application for the purchase of the tender-documents.
2. The Contractors should quoted the rates of all the items in the tenders both in figures and words.
3. Income tax & GST No latest clearance certificate.
4. The contrs / firm shall accompany his enlistment/renewal & EPF submit before the award of tender.
5. The contractors should apply for two works only at a time for tenders.
6. The Executive Engineer reserves the right to accept/rejected any tender/application or all tenders without assigning any reason.

Executive Engineer,
B&R Divisio HPPWD,
Rohru.

NO.:-PW-RD-AB-Tender /2023-24-

23342-441

Dated:-

19/02/2024

Copy forwarded for information and wide publicity to:-

1. The Chief-Engineer(S), HPPWD, Shimla-2.
3. The S E 14th Circle HPPWD, Rohru
4. All the E.E.'s under 14th Circle, HPPWD, Rohru
5. All the A.E.'s working under this Division (B&R).
6. The Sub Divisional Magistrate, Rohru.
7. The B.D.O. Rohru and Chirgaon.
8. The Tehsildhar, Rohru/Chirgaon and Tikkar.
9. The Chairman, N.A.C. Rohru.
10. A/B. and D/B. in this Office.
11. Notice-Board.

Executive Engineer,
B&R Division HPPWD,
Rohru.

415

Job No.:-

①

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages to Umladawar Reoghathi Deoridhat road km. 0/0 to 7/0 (SH-C/O B/wall in wire crate at RD. 3/800 to 3/826, 3/830 to 3/835, 3/850 to 3/865)					
Estimated Cost:-479879/-					
Earnest Money:-9600/-					
Time:- Two Month					
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	149.50	324.60	Rupees:- Three Hundred Twenty Four and Paisa Sixty only	Cum 48528
2	Earthwork in excavation for structures as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	39.10	407.00	Rupees:- Four Hundred Seven and Paisa Zero only	Cum 15914
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	143.75	2890.00	Rupees:- Two Thousand Eight Hundred Ninety Paisa Zero only.	Cum 415438
Total:-					479879
DNIT No. Approved for Rs.479879/- only for the Year 2023-2024					
Quoted rate in figure					
Quoted rate in words					
Signature of contractor with address:-					

Executive Engineer
B&R Division
HP.PWD Rohru

JOB NO:-

2

Schedule of Qty						
Name of Work: R/R Damage to various road under Under Sheelghat Section Sub Division Tikkar (Sh- Supplying and stacking of fine Sand at Site of work for spreading over Snow)						ESTIMATED COST
						10000
						One Month
Sr. No	Description of Items.	Qty/ Unit	Rate	TIME LIMIT:		Amount.
				In Fig.	In Words	
1	Supplying and stacking of fine sand free from dirt, dust and disintegrated pieces to deteriorious and organic matter at site of work as per direction of the Engineer-In- Charge, as per HPPWD Specification of 1990 Volume-I as directed by the Engineer-In-Charge.	310	Per Cum	1600	Rupess One Thousand Six Hundred Only	496000
Total						496000
DNIT No..... approved for amounting to Rs.-496000/- for the year 2023-24						
1 The rates Should be quoted for all heights including all head and lifts.						
The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and						
2 cost.						
Quoted rate Figure (+/-)						
Quoted rate Words (+/-)						
Signature of the Contractor with full address:-						

Executive Engineer
B&R Division HPPWD
Rohru

3

Schedule of Qty

Name of Work :- R/R Snow Damages on various road under Khadraila Section Tikkar Sub Division (SH:- Hiring of JCB for removal of snow and land slide drain clearance opening of culverts filling of depression and berms)

Sr. No	Description of items.	Qty	Unit	ESTIMATED COST		Amount.
				EARNEST MONEY	476000	
1	2	3	4	TIME LIMIT:	9520	two Month
				Rate In Fig.	In Words	
1	Hiring of J.C.B (Excavator-Cum-Loader) having 0.45cum bucket capacity and including P.O.L. charges, shifting charges and other anchoring equipments as required at site of work for removal of snow & slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	56	Per day	8500	Rupees Eight Thousand Five Hundred Only	476000
Total						476000

DNT No..... approved for amounting to Rs:-476000/- for the year 2023-24

1 The rates Should be quoted for all heights including all lead and lifts.
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure (+/-)

Executive Engineer
B&R Division HPPWD
Rohru

Signature of the Contractor with full address:-

DNIT/ SCHEDULE OF QUANTITY

Job No.

(4)

NAME OF WORK:- Restoration of rain damages to various road under Tikkar Sub-Division(SH:- Hiring of Tipper)

Estimated Cost:- 270000/-
Earnest Money:- 5400/-

Sr.no. Item of work Quantity Rate in figure Rate in words Unit Amount

1 Hiring of Tipper for carriage of material having capacity 200 cft including POL charges and other ancillary equipments as required at site of work. The work shall to be carried out as per ministry of transport as per instruction of the Engineer in charge including all leads and lifts. 60.00 4500.00 Rupees:- Four Thousand Five Hundred and Paisa Zero only Per Day 270000

DNIT No.

Total:-

270000

Approved for Rs.270000/- only for the Year 2023-2024

Quoted rate in figure
Quoted rate in words
Signature of contractor with address:-

%
%

Executive Engineer
B&R Division
HP.PWD Rohru

5

Job No.

SCHEDULE OF QUANTITY

Estimated Cost:-469882/-
Earnest Money:-9500/-
Time:-One Month

NAME OF WORK--: C/O link Road Pujrali Koti Saraidhar km.0/0 to 16/600 (SH:-Removal of slips at various RDs. .7/485 to 10/710)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by machanical means including cutting and trimming of slop and dispposal of cut material with in all leads and lifts upto 1.5m and lead upto 100 m as per technical specification 302.305 and 1611 as per directed by the Engineer in charge	2034.12	231.00	Rupees:-Two Hundred Thirty One and Paia Zero only	Per Cum	469882

DNIT No. Approved for Rs.469882/- only for the Year 2023-2024

Quoted rate in figure	%
Quoted rate in words	%
Signature of contractor with address:-	

Executive Engineer
B&R Division
HP.PWD Rohru

Job No. 6

SCHEDULE OF QUANTITY

Estimated Cost:-455278/-
Earnest Money:-9200/-

Time:-One Month

NAME OF WORK:- C/O link Road Pujrali Koti Saraidhar km.0/0 to 16/600 (SH:-Removal of slips at various RDs. .10/740 to 14/045)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by machanical means including cutting and trimming of slop and disposal of cut material with in all leads and lifts upto 1.5m and lead upto 100 m as per technical specification 302.305 and 1611 as per directed by the Engineer in charge	1970.90	231.00	Rupees:-Two Hundred Thirty One and Paise Zero only	Per Cum	455278
Total:-						455278
DNIT No. Approved for Rs.455278/- only for the Year 2023-2024						
Quoted rate in figure						
Quoted rate in words						
Signature of contractor with address:-						

Executive Engineer
B&R Division
HP.PWD Rohru

(7)

SCHEDULE OF QUANTITY

NAME OF WORK:-R/R damages to Mandhari to Karchhari road km. 0/0 to 12/200 (SH:-C/O R/ wall in wire crate at RD.9/740 to 9/755, 8/890 to 8/911)

Job No.
Estimated Cost:-471542/-
Earnest Money:-9500/-
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	35.33	407.00	Rupees:-Four Hundred Seven and Paisa Seven only	Cum	14379
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	135.94	2890.00	Rupees:-Two Thousand Eight Hundred Ninety Paisa Zero only.	Cum	392867
3	Providing and laying of back filling behind abutment wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	43.62	1474.00	Rupees:-One Thousand Four Hundred Seventy Four Paisa Zero only.	Cum	64296
			Total:-			471542
		DNIT No. Approved for Rs.471542/- only for the Year 2023-2024				
		Quoted rate in figure				
		%				
		Quoted rate in words				
		%				
		Signature of contractor with address:-				

Executive Engineer
B&R Division
Rohru

(8)

SCHEDULE OF QUANTITY

Estimate Cost Rs 493000/-

Earnest Money 10000/-

Time:-90 days

Name of work : Restoration of rain damages on various road under Tikkar Sub Divn (sheelghat section) SH-Hiring of JCB for removal of land slide drain /clearance of opening of culverts filling of depression).

Sr.No.	Sub-Head and item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of J.C.B.(Excavator-Cum-Loader) having bucket capacity 0.50 including P.O.L. charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department; and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 18.00 cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	58.00	8500	Ruppes eighty five hundred only	per day	493000.00
					Total	493000

Executive Engineer
Rohru Division, HP PWD
Rohru.

Quoted rate in figure :-
do words :-
Signature of contractor with address :-

(9)

SCHEDULE OF QUANTITY

Estimated Cost:-371901/-
 Earnest Money:-7500/-
 Time:-One Month

NAME OF WORK:-C/O link road from Tandroh Nallah to Jhanterli road km. 0/0 to 1/500 (SH:-C/O Hume pipe culvert at RD.0/490.)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	13.87	185.07	Rupees:-One Hundred Eighty Five and Paisa Zero Seven only	Cum	2567
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	48.43	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	19711
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	7.53	6314.00	Rupees:-Six Thousand Three Hundred Forteen and Paisa Zero only	Cum	47544
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	4.89	6656.00	Rupees:-Six Thousand Six Hundred Fifty Six Paisa Zero Only.	Cum	32548
5	Stone masonry in cement mortar 1:5 (1 Cement : 5 sand) for foundation complete as per drawings and technical specification Clauses 702, 704,1202 and 1203 including carriage of material within all leads and lifts as per directions of Engineer in charge	7.71	5800.00	Rupees:-Five Thousand Eight Hundred Paisa Zero Only.	Cum	44718
6	Randon Rubble Stone masonry in cement mortar 1:6 (1 Cement : 6 sand) for foundation complete as per drawings and technical specification Clauses 702, 704,1202 and 1203 including carriage of material within all leads and lifts as per directions of Engineer in charge	21.62	5400.00	Rupees:-Five Thousand Four Hundred Paisa Zero Only.	Cum	116748
7	Construction of dry masonry in retaining walls, breast walls etc.as per drawings and technical specification including carriage of material within all leads and lifts as per directions of Engineer in charge	12.50	4082.00	Rupees:-Four Thousand Eighty Two Paisa Zero Only.	Cum	51025
8	Providing and laying of back filling behind R/wall and wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	9.04	1474.00	Rupees:-One Thousand Four Hundred Seventy Four and Paisa Zero only	Cum	13325

9	Providing and laying reinforced cement concrete pipe NP2 for culverts on forst class bedding of granular material in single row icluding fixing collar with cement mortar 1:2 but excluding excavation protection works backing filling concrete and masonry works in head walls and parapets caluse 1106 .as directed by the Engineer-in-Change	7.50	5250.00	Rupees:-Five Thousand Two Hundred Fifty Paissa Zero only.	Cum	39375
10	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1303 as directed by the Engineer-in-Change	0.49	4439.32	Rupees:-Four Thousand Four Hundred Thirty Nine Paissa Thirty Two only.	Cum	2175
11	Providing and laying of earth filling lift up to 1.50 mtrs. And disposal u to 20 mtrs. with in all leads and lifts as directed by the Engineer-in-Change	6.24	346.92	Rupees:-Three Hundred Forty Six Paissa Ninety Two only.	Cum	2165
				Total:-		371901
	Quoted rate in figure	DNIT No.				
		%				
	Quoted rate in words	%				
	Signature of contractor with address:-	Approved for Rs.371901/- only for the Year 2023-2024				
Executive Engineer B&R Division HP,PWD Rohru						

Executive Engineer
B&R Division
HP.PWD Rohru

SCHEDULE OF QUANTITY

Job No. _____
Estimated Cost:-470022/-
Earnest Money:-9400/-
Time:-One Month

NAME OF WORK:-C/O link road to HB Hanstari Dhar km.0/0 to 1/500 (SH.-C/O R/Wall in wire crate at RD.0/690 to 0/710)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	48.80	249.00	Rupees:-Two Hundred Forty Nine and Paisa Zero only	Cum	12151
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	35.00	399.00	Rupees:-Three Hundred Ninety Nine and Paisa Zero only	Cum	13965
3	Providing and laying of boulder apron laid in wire crates with 4 mm (four) millimetre dia GI wire conforming to 18280 and IS: 4826 in 100 mm x 100 mm (hundred millimetre x hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 2.5 (twenty five)kilogramme each as per drawing and MORD Technical Specifications Clause 1301 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	156.25	2841.00	Rupees:-Two Thousand Eight Hundred Forty One and Paisa Zero only	Cum	443906
Total:-						470022
Quoted rate in figure			%	 Executive Engineer B&R Division HP.PWD Rohru		
Quoted rate in words			%			
Signature of contractor with address:-						

(11)

SCHEDULE OF QUANTITY

NAME OF WORK:- C/O link road to village Dhanoti km.0/0 to 4/500(SH:-Construction of R/wall at RD.2/210 to 2/226.50)

Job No.
Estimated Cost:-495283/-
Earnest Money:-9900/-
Time:-Two Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	23.93	176.83	Rupees:-One Hundred Seventy Six and Paisa Eighty Three only	Cum	4232
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	35.31	430.50	Rupees:-Four Hundred Thirty and Paisa Fifty only	Cum	15201
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	11.22	4895.53	Rupees:-Four Thousand Eight Hundred Ninety Five and Paisa Fifty Three only	Cum	54928
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	10.00	5423.71	Rupees:-Five Thousand Four Hundred Twenty Three and Paisa Seventy One only	Cum	54237
5	Randon Rubble Stone masonry in cement mortar 1:6 (1 Cement : 6 sand) for foundation complete as per drawings and technical specification Clauses 702, 704, 1202 and 1203 including carriage of material within all leads and lifts as per directions of Engineer in charge	42.94	4875.78	Rupees:-Four Thousand Eight Hundred Seventy Five and Paisa Seventy Eight only	Cum	209366
6	Construction of dry rubble masonry for retaining wall, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawings and technical specification Clauses 704.6, 1302.5 as directed by the Engineer-in-Charge	46.18	3275.42	Rupees:-Three Thousand Two Hundred Seventy Five Paisa Forty Two only	Cum	151259
7	Back filling behind abutments wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3, 8 as directed by the Engineer-in-Charge	5.00	1212.19	Rupees:-One Thousand Two Hundred Twelve and Paisa Nineteen only	Cum	6061
Total:-						495283
Quoted rate in figure						%
Quoted rate in words						%
Signature of contractor with address:-						

Executive Engineer
B&R Division
HP.PWD Rohru

(12)

SCHEDULE OF QUANTITY

NAME OF WORK:- C/O link road HB Samra Dhanoti Khalwan road km. 0/0 to 3/400 (SH:- Providing and laying G-III at RD.1/350 to 1/700 & Earthen Shoulder km. 0/0 to 1/700)

Job No.
Estimated Cost:- 317263/-
Earnest Money:- 6400/-
Time:- One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Providing and laying , spreading and compacting stone aggregate of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 km.in stages to proper grade and camber , applying and brooming , stone screening ti fill-up nthe interstices of course aggregate , watering and compacting to the required density gading 3 as per technical specification clause 405 including all leads and lift as per directed by the Engineer-in-Change	80.06	2850.00	Rupees:- Two Thousand Eight Hundred Fifty and Paisa Zero only	Cum	228171
2	Construction of Sub-grade and earthen shoulders wvith approved material obtained from borrow pits with all lifts and leads, transportation to site , spreading, grading to required slope and compacted to meet requirement to table 300.2 with lead upto 1000 m as per technical specifications Clause 303.1 including all leads and lift as per directed by the Engineer-in-Change	414.38	215.00	Rupees:- Two Hundred Fifteen and Paisa Zero only	Cum	89092
Total:-						317263
DNIT No.						
Approved for Rs.317263/- only for the Year 2023-2024						
	Quoted rate in figure		%			
	Quoted rate in words		%			
	Signature of contractor with address:-					

Executive Engineer
B&R Division
Rohru

JOB NO:-

Schedule of Qty

Name of Work :- C/o Link road Tipper to Shailan Kit Randeep nager Biharu Dogra Pul km 0/00 to 3/400 (SH:- C/o R/wall at RD 0/110 to 0/126.5)				ESTIMATED COST		485065
				EARNEST MONEY		9700
				TIME LIMIT:		Two Month
Sr. No	Description of items.	Qty	Unit	Rate	In Words	Amount.
				In Fig.		
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1	23.93	cum	176.83	Ruppes One Hundred & Seventy Six - Paise Eighty Three Only	4232
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material and as per HPPWD specification of 1990 volume-I or as directed by the Engineer-In-Charge.	35.31	cum	430.5	Ruppes Four Hundred & Thirty - Paise Fifty Only	15201
3	P/L Cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate forty millimeter nominal size) for plain/ reinforced concrete work in open foundation complete as per drawing and technical specification Clauses 802,803,1202& 1203.	11.22	cum	4882.97	Ruppes Four Thousand Eight Hundred & Eighty Two - Paise Ninety Seven Only	54787
4	Providing concrete for plain/reinforced concrete in open foundation/R/B-walls complete as per drawing and technical specification clause 802,803,1202 & 1203 grade (1:4:8 nominal mix), 1 cement, 4 and 8 graded stone aggregate, including all leads and lifts, as per HPPWD, specification of 1990 volume-I or as directed by the Engineer-In-Charge	7.09	cum	5410.87	Ruppes Five Thousand Four Hundred & Ten - Paise Eighty Seven Only	38363
5	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clause 702,704,1202 and 1204 Random rubble masonry in cement mortar (1:6) including all leads and lifts, as per HPPWD, specification of 1990 volume-I or as directed by the Engineer-In-Charge.	42.94	cum	4872.45	Ruppes Four Thousand Eight Hundred & Seventy Two - Paise Fourty Five Only	209223
6	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including all leads and lifts, as per HPPWD, specification of 1990 volume-I as directed by the Engineer-In-Charge	46.18	cum	3275.42	Ruppes Three Thousand Two Hundred & Seventy Five - Paise Fourty Two Only	151259
7	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3, 8 granular material.	9.9	cum	1212.19	Ruppes One Thousand Two Hundred & Twelve - Paise Nineteen Only	12001
Total						485065

DMIT No.:..... approved for amounting to Rs:-485065/- for the year 2023-24

1. The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer
B&R Division HPPWD
Rohru

④

Estimated Cost:-31477/-

Earnest Money:-6300/-

Time:-One Month

RD.5/690 to 5/705)

NAME OF WORK:- R/R damages on Shallan Karchhari Mandhari road km. 0/0 to 12/0 (SH:-C/O R/wall at RD.5/690 to 5/705)

Executive Engineer
B&R Division
~~Asst. PWD~~ Rohru

SCHEDULE OF QUANTITY

NAME OF WORK:- C/O Missing C.D. On Tutupani Nalwan road km. 0/0 to 5/500 (SH-C/O 900mm dia HPC at RD. 4/400)

Job No. -
Estimated Cost:-486210/-
Earnest Money:-9800/-
Time:- Two Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and technical Specification Clause 1603.1 within all leads and lifts as per directions of Engineer in charge	25.46	249.00	Rupees:-Two Hundred forty Nine and Paisa /zero only	Cum	6340
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-charge	32.02	399.00	Rupees:-Three Hundred Ninety Nine and Paisa /zero only	Cum	12776
3	Plain/reinforced cement concrete (1:3:6) in open foundation complete as per drawings and technical specification (Clauses 802, 803, 1202 and 1203 as directed by the Engineer-in-charge	1.69	5810.00	Rupees:-Five Thousand Eight Hundred Ten Paisa /Zero only.	Cum	9819
4	Stone masonry in cement mortar for sub structure complete as as per drawings and technical specification (Clauses 702, 704,1202 and 1203 including all leads and lifts or as per H.P.PWD) specification of 1990 Volume-1 in Cement Mortar 1:5 as per directions of Engineer in charge	12.12	5041.00	Rupees:-Five Thousand Forty One Paisa /zero Only.	Cum	61097
5	Random Rubble Stone masonry in cement mortar for sub structure complete as as per drawings and technical specification (Clauses 702, 704,1202 and 1204 random rubble masonry in cement mortar 1:6 within all leads and lifts as per directions of Engineer in charge	34.92	4828.00	Rupees:-Four Thousand Eight Hundred Twenty Eight Paisa /Zero Only.	Cum	168594
6	Providing and laying and joining reinforcement cement concrete pipe 900mm diameter NP-2 for culverts of first class bidding of granular material in single row including fixing collar with cement 1:2 but excluding excavation protection work, back filling concrete and concrete and masonry work in head wall and parapets as per clause 1108 900mm dia including all leads and lifts as per H.P.PWD) specification of 1990 volume-1 as per directions of Engineer in charge	7.50	5410.00	Rupees:-Five Thousand four Hundred Ten Paisa /Zero only.	RMI	40575
7	Providing and laying flowing laid over cement concrete bedding complete as per drawing and technical specification clause 1303 rubble stone laid in cement mortar 1:3 (1 Cement :3 Sand) including all leads and lifts as per H.P.PWD) specification of 1990 volume-1 as per directions of Engineer in charge	0.49	11500.00	Rupees:-Eleven Thousand Five Hundred Paisa /Zero only.	Cum	5635
8	Providing and laying of back filling behind abutment wing wall and return walls with granular material complete as per MORID technical specification clause 1204 3.8 as directed by the Engineer-in-charge	4.95	1212.00	Rupees:-One Thousand Two Hundred Twelve Paisa /Zero only.	Cum	5999

9	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	7.92	4910.00	Rupees:- Four Thousand Nine Hundred Ten and Paise Zero only	Cum	38887
10	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	4.73	5490.00	Rupees:- Five Thousand Four Hundred Ninety Paise Zero Only	Cum	25968
11	Construction dry rubble Stone masonry for retaining walls breast wall reveminent walls and parapets etc for sub structure and superstructure complete as per drawings and technical specification Clauses 704.6 and 1302.5 within all leads and lifts as per directions of Engineer in charge	31.08	3556.00	Rupees:- Three Thousand Five Hundred Fifty Six Paise Zero only	Cum	110520
			Total:-	486210		
			DNT No.	Approved for Rs.486210/- only for the Year 2023-2024		
			Quoted rate in figure			
			Quoted rate in words			
			Signature of contractor with address:-			


 Executive Engineer
 B&R Division
 HP.PWD Rohru

NAME OF WORK:- Repair of J.E. Office cum Residence at Pujarli No -4 in Tehsil Rojhru Dist Shimla (H.P) Dist Shimla (H.P) (SH:-Providing Painting, Distempering, Roofing, including W.S & S.I Fitting etc.)

Job No.:- 
ESTIMATED COST:- Rs.4,48,818.00
EARNEST MONEY:- RS. 9000/-
TIME ALLOWED:- 2 Month

Sl. No.	Sub-Head and Item of works.	Quantity	Rate in figures.	Rate in words.	Unit	Amount.
1	Distempering (two coats) with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surface on all floor to give an even shade over and including priming coat of whitening after thoroughly brushing the surface free from mortar dropping and other foreign material including preparing the surface even and sand papered smooth including carriage of materials within all leads and lifts as per the direction of Engineer-in-charge.	318	184.21	Rupees One Hundred & Eighty Four - Paise Twenty One Only	Sqm	58574.00
2	Applying priming coat over previously painted wood or wood based surface wood and wood based surfaces after and including preparing the surface by thoroughly cleaning oil, grease dirt and other foreign matter sand papering and knotting with ready mixed paint brushing wood primer pink. The rate is inclusive for carriage of materials within all leads, lifts and other incidentals of the entire satisfaction of Engineer-in Charge.	56.91	66.92	Rupees Sixty Six - Paise Ninety Two Only	Sqm	3808.00
3	Painting two coats (excluding priming costs) on previously painted wood based surfaces with enamel paint brushing to give an any shade including cleaning the surfaces of all dirt, dust and other foreign matters sand papering and stopping within all leads, lifts of materials and other incidentals of the entire satisfaction of Engineer-in Charge.	56.91	104.55	Rupees One Hundred & Four - Paise Fifty Five Only	Sqm	5950.00
4	Providing and fixing to wall ceiling floor galvanised mild steel tubes (Heavy grade), tube fittings 15mm (fifteen millimetre) nominal bore :-	36.00	248.6732	Rupees Two Hundred & Forty Eight - Paise Sixty Seven Only	Per Rmt	8952.00
5	Providing and fixing ISI marked high pressure PVC (finolex) of working pressure not less than 4.5 kg/sqm, waste and ventilating pipes including fixing with approved adhesive etc. complete including carriage of materials within all leads and lifts. :-					
	110 mm (one hundreded and Ten) nominal size :-					
6	Providing and fixing PVC (finolex) door bend with oval access door, insertion rubber washer 3 mm thick bolts and nuts ISI marked complete including fixing with approved adhesive etc. complete	3.00	386.11	Rupees Three Hundred & Eighty Six - Paise Eleven Only	each	1158.00

NO.	Quant	Rate in figures.	Rate in words.	Unit	Amount.
	(i) 110 mm (one hundreded and Ten) nominal size :-				
	(i) 75mm	2.00	Rupees Three Hundred & Fifty Nine - Paise Sixty One Only	each	719.00
7	Providing and fixing PVC (finolex) plain bend ISI marked including fixing with approved adhesive etc. complete.	2.00	Rupees Two Hundred & Sixty Only	each	520.00
	(i) 110 mm (one hundreded and Ten) nominal size :-				
	(i) 75mm	3	Rupees Two Hundred & Fifty Only	each	750.00
8	Providing and fixing PVC (finolex) collars ISI marked including fixing with approved adhesive etc. complete.	3	Rupees One Hundred & Seventy Only	each	510.00
	110 mm (one hundreded and Ten) nominal size :-				
	75mm	4	Rupees Three Hundred & Fifty Only	each	1400.00
9	Providing and fixing PVC floor trap (finolex) ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etc. complete.	4	Rupees Two Hundred & Fifty Only	each	1000.00
	(i) 75mm				
10	Providing and fixing vitreous China wash, down water closet (European Type W.C. pan) with integral 'P' or 'S' trap including jointing the trap with soil pipe in cement mortar 1:1 carriage of materials within all leads and lifts :-	3	Rupees Two Hundred & Sixty Eight - Paise Thirty Three Only	each	805.00
	Anglo Indian universal closet				
11	Providing and fixing 10.00 ltr. capacity PVC low level flushing cistern Hind ware sleek ultra design No 186575 size 42 X 39 X 14 cm or equivalent with a pair of brackets with fittings such as lead valve, syphon, 15mm nominal size PVC ball valve with polythene float, with push button, couplings for connections with inlet, outlet and overflow pipe, 40mm dia C.P. flush bend including cutting holes in walls and making good the same and connecting the flush bend with cistern and closet (overflow) pipe to be measured and paid for separately including carriage of materials within all leads and lifts :-	1	Rupees Five Thousand & Seventy Four - Paise Seventy Three Only	each	5075.00
12	Providing and fixing vitreous China Hind ware IS marked IS No. 2556 or equivalent wash basin with single hole for pillar tap with C.I. or M.S. brackets painted white including cutting holes and making good the same but excluding fitting including carriage of materials within all leads and lifts :-	1	Rupees Two Thousand One Hundred & Nineteen - Paise Ninety Two Only	each	2120.00
	Flat back :-				
	550 X 400 mm				
13	Providing and fixing C.P. brass waste for wash basin or sink including carriage of materials within all leads and lifts :-	1	Rupees Two Thousand Six Hundred & Fourty Four - Paise Fifty Five Only	each	2645.00

No.		Quantity	Rate in figures.	Rate in words.	Unit	Amount.
	32 mm dia					
14	Providing & fixing 32 mm dia, PVC waste pipe for wash basin or sink including check nut including carriage of material within all leads and lifts:-	2	1483.20	Rupees One Thousand Four Hundred & Eighty Three - Paise Twenty Only	each	2966.00
15	Providing & fixing 100 mm dia, C.P. grating including carriage of material within all leads and lifts:-	2	50	Rupees Fifty Only	each	100.00
16	Providing and fixing looking mirror of superior glass with plastic frame including carriage of materials within all leads and lifts :-	3	79.39	Rupees Seventy Nine - Paise Thirty Nine Only	each	238.00
17	Providing and fixing C.P. brass towel rail complete with C.P. brass brackets fixed to wooden plugs with C.P. brass screws including carriage of materials within all leads and lifts :-	2	1483.20	Rupees One Thousand Four Hundred & Eighty Three - Paise Twenty Only	each	2966.00
	600 X 20 mm					
18	Providing and fixing chromium plated brass soap dish with C.P. Brass brackets fixed to wooden cleats with C.P. Brass screws :-	2	687.60	Rupees Six Hundred & Eighty Seven - Paise Sixty Only	each	1375.00
19	Providing and fixing Acrylic shelf with C.P. brass bracket and guard rail complete, fixed to wooden plugs with C.P. brass screws including carriage of materials within all leads and lifts as per direction of Engineer- In- charge	2	438.91	Rupees Four Hundred & Thirty Eight - Paise Ninety One Only	each	878.00
20	Providing and fixing CP brass bib tap with capstan head including carriage of materials within all leads and lifts :-	2	150.00	Rupees One Hundred & Fifty Only	each	300.00
	15mm dia :-					
21	Providing and fixing C.P. brass angle valve cock without nuts and pipe including carriage of materials within all leads and lifts :-	5	296.51	Rupees Two Hundred & Ninety Six - Paise Fifty One Only	each	1483.00

No.	Quant ity	Rate in figures.	Rate in words.	Unit	Amount.
22	8	555.70	Rupees Five Hundred & Fifty Five Paise Seventy Only	each	4446.00
23	8	189.17	Rupees One Hundred & Eighty Nine - Paise Seventeen Only	each	1513.00
24	1	2119.92	Rupees Two Thousand One Hundred & Nineteen - Paise Ninety Two Only	each	2120.00
25	1.00	312.11	Rupees Three Hundred & Twelve Paise Eleven Only	each	312.00
26	1	347.78	Rupees Three Hundred & Forty Seven - Paise Seventy Eight Only	each	348.00
27	6	323.21	Rupees Three Hundred & Twenty Three - Paise Twenty One Only	each	1939.00
28	8	117.67	Rupees One Hundred & Seventeen - Paise Sixty Seven Only	each	941.00
29	4	114.69	Rupees One Hundred & Fourteen - Paise Sixty Nine Only	each	459.00
30	2	5000.00	Rupees Five Thousand Only	each	10000.00
31	7.006	2658.30	Rupees Two Thousand Six Hundred & Fifty Eight - Paise Thirty Only	Per Cum	18624.00
32	7.006	7004.80	Rupees Seven Thousand & Four - Paise Eighty Only	Per Cum	49074.00
	168.3	1269.68	Rupees One Thousand Two Hundred & Sixty Nine - Paise Sixty Eight Only	per sqm	213688.00

NO.	Quant ity	Rate in figures.	Rate in words.	Unit	Amount.
33	Providing and fixing ridges or hips 60cm. over all with .60mm thick mm thick prepainted steel sheet in roofing with hot dipped metallic zink coated with top coat of regular modified polyester(RNP) organic coating of 20 microne over 5micrones primer coating to back coat of polyester of 5 microns i/ c fixing with prepainted iron J or L hooks, bolts and nuts. 6 mm dia metre. as required as per direction of Engineer in Charge.	17.99	Rupees Five Hundred & Sixty Six - Paise Sixty Three Only	Per Rmt	10194.00
34	Providing and fixing Valley 60cm. over all with .60mm thick mm thick prepainted steel sheet in roofing with hot dipped metallic zink coated with top coat of regular modified polyester(RNP) organic coating of 20 microne over 5micrones primer coating to back coat	3.37	Rupees Six Hundred & Ninety Three - Paise Eighty Five Only	Per Rmt	2338.00
35	Providing and fixing 15cm wide and 45cm overall semicircular plain G.I sheet gutter with iron brackets 40x30mm size bolts and nuts and washer etc. including making necessary connection with rain water pipe complete (i) 0.63mm thick sheet including all leads and lifts, as per HP:PWD, specification of 1990 Volume-I, as directed by the Engineer-In-Charge.	45	Rupees Six Hundred & Thirty Three - Paise One Hundred Only	Per Rmt	28530.00
Total					448818.00

Rates quoted by the contractor (in Figure) in percentage% (Above or Below) only
 Rates quoted by the contractor (in Word) in percentage% (Above or Below) only
 D.N.I.T No: for the year 2023-24 duly approved for Rs. 4,48,818/-

Sign & Name of Contractor

Executive Engineer,
 Rohru Division
 HP.PWD., Rohru.

(18) (17)

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages on Deoli Khalai Dhanikupad road km. 0/0 to 5/0 (SH:-C/O R/wall at RD. 4/830 to 4/838)		Job No.	Estimated Cost:-436105/-
			Earnest Money:-8700/-
		Time:-One Month	

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	23.24	324.80	Rupees:-Three Hundred Twenty Four and Paisa Eighty only	Cum	7548
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.as directed by the Engineer-in-Charge	23.17	407.00	Rupees:-Four Hundred Seven and Paisa Seven only	Cum	9430
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	6.16	6118.50	Rupees:-Six Thousand One Hundred Eighteen and Paisa Fifty only	Cum	37690
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203.as directed by the Engineer-in-Charge	3.57	6464.67	Rupees:- Six Thousand Four Hundred Sixty Four Paisa Sixty Seven only.	Cum	23079
5	Stone masonry in cement mortar 1:6 (1Cement :6 sand) for sub-structure complete as per drawings and technical specification Clauses 702, 704,1202 and 1204 including carriage of material within all leads and lifts as per directions of Engineer in charge	58.08	5400.00	Rupees:-Five Thousand Four Hundred Paisa Zero Only.	Cum	313632
6	Construction of dry rubble masonry for retaining wall , brest walls , revement walls and parapets etc.for sub-structure and super structure complete as per drawings and technical specification Clauses 704.6,1302.5 .as directed by the Engineer-in-Charge	7.19	4082.27	Rupees:-Four Thousand Eighty Two Paisa Zero Twenty Seven only	Cum	29352
7	Providing and laying of back filling behind abutment wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3,8 as directed by the Engineer-in-Charge	10.43	1474.00	Rupees:-One Thousand Four Hundred Seventy Four Paisa Zero only.	Cum	15374
				Total:-		436105
Quoted rate in figure			%			
Quoted rate in words			%			
Signature of contractor with address:-			%			

Executive Engineer
B&R Division
Rohru

Schedule of Qty				ESTIMATED COST		447225
Name of Work :- Serodeori bashlog road km 0/00 to 5/00(SH:- C/o 1 No 900mm dia HPC at RD 2/105)				EARNEST MONEY		8950
				TIME LIMIT:		Two Month
Sr. No	Description of Items.	Qty	Unit	Rate	In Words	Amount.
				In Fig.		
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1	13.99	cum	246.65	Ruppes Two Hundred & Fourty Six - Paise Sixty Five Only	3451
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material and as per HPPWD specification of 1990 volume-1 or as directed by the Engineer-In-Charge.	55.58	cum	430.51	Ruppes Four Hundred & Thirty - Paise Fifty One Only	23928
3	P/L Cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate forty millimeter nominal size)for plain/ reinforced concrete work in open foundation complete as per drawing and technical specification Clauses 802,803, 1202& 1203.	6.41	cum	4990	Ruppes Four Thousand Nine Hundred & Ninety Only	31986
4	Providing concrete for plain/reinforced concrete in open foundation/B-walls complete as per drawing and technical specification clause 802,803, 1202 & 1203 grade (1:4:8 nominal mix) , 1 cement ,4and ,8graded stone aggregate , including all leads and lifts, as per HPPWD, specification of 1990 volume-1 or as directed by the Engineer-In-Charge	0.72	cum	5510	Ruppes Five Thousand Five Hundred & Ten Only	3967
5	Stone masonry in cement mortar for substructure complete as per drawing& technical specification Clause 702, 704, 1202 and 1204 Random rubble masonry in cement mortar(1:6) including all leads and lifts, as per HPPWD, specification of 1990 volume-1 or as directed by the Engineer-In-Charge.	63.35	cum	4950	Ruppes Four Thousand Nine Hundred & Fifty Only	313583
6	Providing concrete for plain/reinforced concrete in open foundation/B-walls complete as per drawing and technical specification clause 802,803, 1202 & 1203 grade M10 (1:3:6 nominal mix) , 1 cement ,3 Sand ,6 graded stone aggregate , including all lead and lifts.	1.47	cum	5810	Ruppes Five Thousand Eight Hundred & Ten Only	8541
7	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204, 3, 8 granular material.	13.2	cum	1220	Ruppes One Thousand Two Hundred & Twenty Only	16104
8	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets Clause 1106.	7.5	mtr	5337.62	Ruppes Five Thousand Three Hundred & Thirty Seven - Paise Sixty Two Only	40032
9	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1303	0.49	cum	11500	Ruppes Eleven Thousand Five Hundred Only	5635
Total						447225

1. The rates should be quoted for all heights including all lead and lifts.
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

2. Quoted rate Figure (+/)
Quoted rate Words (+/)

Signature of the Contractor with full address:-

Executive Engineer
B&R Division HPPWD
Rohru

Schedule of Qty

Name of Work :- R/R Damages to Pujari maidhar Road km 0/00 to 4/00(Sh:- C/o R/wall at RD 1/580 to 1/589

Name of Work :- R/R Damages to Pujarli madidhar Road km 0/00 to 4/00/ Sh:- C/o R/wall at RD 1/580 to 1/589					Schedule of Qty		ESTIMATED COST	403287
					EARNEST MONEY		8066	
					TIME LIMIT:		Two Month	
Description of Items.		Qty	Unit	Rate	In Words	Amount.		
Sr. No				In Fig.				
2		3	4	5	6	7		
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1	20.25	cum	324.8	Ruppes Three Hundred & Twenty Four - Paise Eighty Only	6577		
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material and as per HPPWD specification of 1990 volume-1 or as directed by the Engineer-In-Charge.	26.91	cum	407	Ruppes Four Hundred & Seven Only	10952		
3	P/L Cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate forty millimeter nominal size)for plain/ reinforced concrete work in open foundation complete as per drawing and technical specification Clauses 802,803,1202& 1203.	7.18	cum	5109.04	Ruppes Five Thousand One Hundred & Nine - Paise Four Only	36683		
4	Providing concrete for plain/reinforced concrete in open foundation/R.B-walls complete as per drawing and technical specification clause 802,803,1202 & 1203 grade (1:4:8nominal mix) , 1 cement :4and :8graded stone aggregate , including all leads and lifts, as per HPPWD, specification of 1990 volume-1 or as directed by the Engineer-In-Charge	4.23	cum	5710.66	Ruppes Five Thousand Seven Hundred & Ten - Paise Sixty Six Only	24156		
5	Stone masonry in cement mortar for substructure complete as per drawing& technical specification Clause 702,704,1202 and1204 Random rubble masonry in cement motar(1:6) including all leads and lifts, as per HPPWD, specification of 1990 volume-1 or as directed by the Engineer-In-Charge.	27.9	cum	5523.33	Ruppes Five Thousand Five Hundred & Twenty Three - Paise Thirty Three Only	154101		
6	Construction of dry rubble masonry for retaining walls, breast walls,revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including all leads and lifts, as per HPPWD, specification of 1990 volume-1 as directed by the Engineer-In-Charge	40.39	cum	3677.35	Ruppes Three Thousand Six Hundred & Seventy Seven - Paise Thirty Five Only	148528		
7	Back filling behind abutment,wing wall and return wall complete as per drawing and technical specification clause 1204.3, 8 granular material.	16.74	cum	1331.51	Ruppes One Thousand Three Hundred & Thirty One - Paise Fifty One Only	22289		
Total						403287		

DNIT No..... approved for amounting to Rs:-403287/- for the year 2023-24

- The rates Should be quoted for all heights including all lead and lifts.
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.
- Quoted rate Figure (+/-)
- Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer
B&R Division HPPWD
Rohru

DRAFT SCHEDULE OF QUANTITY

Estimated cost RS 420794/-
 Eanrent money 8700/-
 Est Time :-one month

Name of work :- R/R Damages to Blakhor Sheetaitaan Kalgaon Teer road km 0/0 to 3/500(SH- C/O R/wall at RD 2/277.50 to 2/285)

Sr No	Description of items	Quantity	Rate in Figure.	Rate in Words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of the excavated earth with in all leads and lifts as per drawing and Technical Specification Clause 1603.1 and as per all leads and lifts and other incidentals.	24.90	324.80	Rs one hundred seventy six & paise eighty three only	per cubic metre	8088
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary rocks up to 3 mtr depth within all leads and lifts as per directions of Engineer in charge	24.83	407.00	Rs four hundred seven only	per cubic metre	10106
3	Providing and laying cement concrete 1:6:12 (one cement six sand twelve graded stone aggregate 40mm nominal size for plain/reinforced concrete in open foundation complete as per drawing and technical specification cause 802,803,1202 and 1203 including carriage of materials within all leads and lifts as per directions of Engineer in charge	6.60	6118.50	Rs six thousand six hundred eighteen & paise fifty only	per cubic metre	40382
4	Providing and laying mechanical mixed and vibrated cement concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:4:8 (One cement: four sand : eight graded crushed stone aggregate)25 mm specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material through all modes of transportation with in all leads and lifts and other incidentals.	3.83	6464.67	Rs six thousand four hundred sixty four & paise sixty seven only	per cubic metre	24760
5	Random rubble masonry polygonal rubble masonry uncoursed /brought to courses with hard stone of approved quality in foundation and plinth cement mortar 1:6(1 cement:6sand)breast wall and retaining wall within all leads and lifts as per directions of Engineer in charge	26.83	5400.00	Rs five thousand four hundred only	per cubic metre	144882
6	Construction of dry rubble masonry for retaining walls breast wall revetment walls and parapets etc for sub structure complete as per drawing and technical specification clause 704.6 and 1305, within all leads and lifts as per direction of Engineer in charge	43.14	4082.00	Rs four hundred eighty two only	per cubic metre	176097
7	Back filling behind abutment wing wall and return wall with granular materials complete as per drawing and technical specification clause 1204.3.8 including carriage of materials within all leads and lifts as per directions of Engineer in charge	11.18	1474.00	Rs one thousand four hundred seventy four only	per cubic metre	16479
	Total:-					420794

DNIT NO Approved for Rs 872353.00- for the year 2023-24

Quoted Rate in figure	(+) (-)	%
Quoted Rate in Words	(+) (-)	%

Signature of Contractor with full Address

Executive Engineer
 B&R Divn HP, PWD
 Rohtu

SCHEDULE OF QUANTITY



Estimated cost RS 420794/-
Eanrent money 8700/-
Est Time :-one month

Name of work :- R/R Damages to Blakhor Sheetaivan Kalgaon Teer road km 0/0 to 3/500(SH- C/O R/wall) at RD 2/187.50 to 2/195)

Sr No	Description of items	Quantity	Rate in Figure.	Rate in Words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per drawing and Technical Specification Clause 1603.1 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	24.90	324.80	Rs one hundred seventy six & paise eighty three only	per cubic metre	8088
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary rocks up to 3 mtr depth within all leads and lifts as per directions of Engineer in charge	24.83	407.00	Rs four hundred seven only	per cubic metre	10106
3	Providing and laying cement concrete 1:6:12 (one cement six sand twelve graded stone aggregate 40mm nominal size for plain/reinforced concrete in open foundation complete as per drawing and technical specification cause 802.803.1202 and 1203 including carrrge of materials within all leads and lifts as per directions of Engineer in charge	6.60	6118.50	Rs six thousand six hundred eighteen & paise fifty only	per cubic metre	40382
4	Providing and laying mechanical mixed and vibrated cement concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:4:8 (One cement: four sand : eight graded crushed stone aggregate)25 mm specification clauses 802.803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material through all modes of transportation with in all leads and lifts and other incidentals.	3.83	6464.67	Rs six thousand four hundred sixty four & paise sixty seven only .	per cubic metre	24760
5	Random rubble masonry polygonal rubble masonry uncoursed /brought to courses with hard stone of approved quality in foundation and plinth cement mortar 1:6:(1cement:6sand)breast wall and retaining wall within all leads and lifts as per directions of Engineer in charge	26.83	5400.00	Rs five thousand four hundred only	per cubic metre	144882
6	Construction of dry rubble masonry for retaining walls breast wall revertment walls and parapets etc for sub structe complete as per drawing and technical specification clause 704.6 and 1305 within all leads and lifts as per direction of Engineer in charge	43.14	4082.00	Rs four hundred eighty two only .	per cubic metre	176097
7	Back filling behind abutment wing wall and return wall with granular materials complete as per drawing and technical specification clause 1204.3.8 including carrrge of materials within all leads and lifts as per directions of Engineer in charge	11.18	1474.00	Rs one thousand four hundred seventy four only	per cubic metre	16479
	Total:-					
DNIT NO Approved for Rs 420794.00 for the year 2023-24						420794

Quoted Rate in Figure	(+) (-)	%
Quoted Rate in Words	(+) (-)	%

Signature of Contractor with full Address

Executive Engineer
B&R Dym HP PWD
Rohru

Name of Work : C/o Umladwar Deoghari via Reopah road km 0/00 to 9/00(SH:- C/o HPC 900 mm dia at RD 7/060)

Schedule of Qty

23

29

Sr. No	Description of Items	Qty	Unit	ESTIMATED COST		Amount
				EARNEST MONEY	TIME LIMIT:	
1	2	3	4	In Fig.	In Words	7
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1	17.64	cum	176.83	Ruppes One Hundred & Seventy Six - Paise Eighty Three Only	3119
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 30 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material and as per HPPWD specification of 1990 volume-1 or as directed by the Engineer-In-Charge	50.87	cum	430.5	Ruppes Four Hundred & Thirty - Paise Fifty Only	21900
3	P/L Cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate forty millimeter nominal size) for plain reinforced concrete work in open foundation complete as per drawing and technical specification Clauses 802, 803, 1202 & 1203	8.13	cum	4950	Ruppes Four Thousand Nine Hundred & Fifty Only	40244
4	Providing concrete for plain reinforced concrete in open foundation B-walls complete as per drawing and technical specification clause 802, 803, 1202 & 1203 grade (1:4:8 nominal mix), 1 cement, 4 sand, 8 graded stone aggregate including all leads and lifts, as per HPPWD, specification of 1990 volume-1 or as directed by the Engineer-In-Charge	5.82	cum	5470	Ruppes Five Thousand Four Hundred & Seventy Only	31835
5	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204 Coursed rubble masonry (1st sort) In cement mortar (1:4) including all lead and lifts	11.84	cum	6031.79	Ruppes Six Thousand & Thirty One - Paise Seventy Nine Only	71416
6	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clause 702, 704, 1202 and 1204 Random rubble masonry in cement mortar (1:5) including all leads and lifts, as per HPPWD, specification of 1990 volume-1 or as directed by the Engineer-In-Charge	22.98	cum	4790	Ruppes Four Thousand Seven Hundred & Ninety Only	110074
7	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including all leads and lifts, as per HPPWD, specification of 1990 volume-1 as directed by the Engineer-In-Charge	25.73	cum	3415.13	Ruppes Three Thousand Four Hundred & Fifteen - Paise Thirteen Only	87871
8	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material	11.3	cum	1212.19	Ruppes One Thousand Two Hundred & Twelve - Paise Nineteen Only	13698
9	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets Clause 1106	7.5	rmt	5250	Ruppes Five Thousand Two Hundred & Fifty Only	39375
10	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1303	0.49	cum	12648.78	Ruppes Twelve Thousand Six Hundred & Fourty Eight - Paise Seventy Eight Only	6198
Total						425730

DMIT No..... approved for amounting to Rs.-425730/- for the year 2023-24

1 The rates Should be quoted for all heights including all lead and lifts.

2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer
B&R Division HPPWD
Rajni

Job No.

(24) (23)

SCHEDULE OF QUANTITY

Estimated Cost:-206246/-
Earnest Money:-4200/-
Time:-One Month

NAME OF WORK:- R/R damages to Narain Ghralia Mandharhi via Thana Breashtu road km. 0/0 to 9/0 (SH:-C/O B/wall in wire crate at Rd.8/800 to 8/810 ,4/300 to 4/3100

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Change	68.40	324.60	Ruppes:- Three Hundred Twenty Four and Paiza Sixty only	Cum	22203
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Change	8.40	407.00	Ruppes:- Four Hundred Seven and Paiza Zero only	Cum	3419
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Change	62.50	2890.00	Ruppes:- Two Thousand Eight Hundred Ninety Paiza Zero only.	Cum	180625
Total:-						206246
DNT No.						Approved for Rs.206246/- only for the Year 2023-2024
Quoted rate in figure						%
Quoted rate in words						%
Signature of contractor with address:-						

Executive Engineer
B&R Division
HP.PWD Rohru

Job No.

25/24

SCHEDULE OF QUANTITY

NAME OF WORK--:R/R damages on link road to village Thana km. 0/0 to 4/0 (SH:-C/O B/wall at RD. 3/830 to 3/845)

Estimated Cost:-427300/-
Earnest Money:-8600/-
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	47.25	249.00	Rupees:-Two Hundred Forty Nine and Paisa only	Cum	11765
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	22.56	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	9182
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	4.73	6314.00	Rupees:-Six Thousand Three Hundred Forteen and Paisa Zero only	Cum	29865
4	Plain/reinforced cement concrete (1:3:6) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203.as with in all leads and lifts as per directed by the Engineer-in-Charge	54.00	6972.00	Rupees:- Six Thousand Nine Hundred Seventy Two Paisa Zero only.	Cum	376488
Total:-						427300
DNIT No. Approved for Rs.427300/- only for the Year 2023-2024						
Quoted rate in figure %						
Quoted rate in words %						
Signature of contractor with address:-						

Executive Engineer
B&R Division
H.P.W.D Rohru

243
20 extend.

DNIT / SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damages on various road under Tikkar sub Division (Pujari section)/SH- Hiring of JCB for removal of lande slide ,drain clearance ,opening of culverts filling of depression in Various roads .

Estimate Cost 495000.00
Earnest Money 10000.00
Time 450 Hours

Sr.No. Sub-Head and Item of works

Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of JCB (Excavator cum loader gavubg bucket capacity 0.50 cum including POL charges shifting charge and other ancillary equipments as required at site of work for removal of slips in all hegiths and all kinds of soils such as kankar moorum shingle boulders decomposed or soft variety of soil such a spade work pick work jumer work soft rock hard rock including their intermediate classification of soil including mechnacial transport it and when required. The disposal of this underevable materials has to be done in the acquired width of the road to avoid the dange to the properties of the people or in case any damage took place the contractor shall be liable for its. All salvaged materials such as qurried stoen shall belong to the department and manikumum useful quantity of stones from removal of slips shall be to be neatly stacked along road side on road berms minium 30.00 cubicmetre of earth work shall be done by the machine in one hours other wise nu umber of hours shall be reduced accordingly. The work shall have to be carried out as per ministry of transport and as per instruction of he Engineer in charge	450.00	1100.00	Rs Eleven Thousand Only	Per Hour	495000
					Total	495000.00

DNIT No. APPROVED FOR Rs 495000/- (Rs four ninty five hundred only

Assistant Engineer
B&R Sub Division HPPWD
Tikkar

Executive Engineer
B&R Divn HP PWD
Rohru

Quoted Rate in figure :-
do - words :-
Signature of contractor with address :-

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages on Ganasidhar Kadiwan road km. 0/0 to 10/300 (SH:-C/O B/wall in wire crate at RD. 1/490 to 1/505 and R/wall at RD.5/015 to 5/023)

Job No.
Estimated Cost:-272952/-
Earnest Money:-5500/-
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	31.64	247.00	Rupees:-Two Hundred Forty Seven and Paisa Zero only	Cum	7815
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	22.11	395.00	Rupees:-Three Hundred Ninety Five and Paisa Zero only	Cum	8733
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	3.84	4810.00	Rupees:-Four Thousand Eight Hundred Ten and Paisa Zero only	Cum	18470
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 as directed by the Engineer-in-Charge	1.60	5390.00	Rupees:- Five Thousand Three Hundred Ninety Paisa Zero only.	Cum	8624
5	Stone masonry in cement mortar 1:6 (1Cement 6 sand) for sub-structure complete as per drawings and technical specification Clauses 702, 704, 1202 and 1204 including carriage of material within all leads and lifts as per directions of Engineer in charge	13.29	4736.00	Rupees:-Four Thousand Seven Hundred Thirty Six Paisa Zero Only.	Cum	62941
6	Construction of dry rubble masonry for retaining wall , breast walls , reventment walls and parapets etc for sub-structure and super structure complete as per drawings and technical specification Clauses 704.6, 1302.5 .as directed by the Engineer-in-Charge	11.77	3521.00	Rupees:-Three Thousand Five Twenty One Paisa Zero only	Cum	41442
7	Providing and laying of boulder apron laid in wire crates with 4 mm (four) millimetre dia GI wire conforming to 18280 and IS: 4826 in 100 mm x 100 mm (hundred milimetre x hundred milimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps end joints laid with stone boulders weighing not less than 2.5 (twenty five)kilogramme each as per drawing and MORD Technical Specifications Clause 1301 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	46.88	2552.00	Rupees:-Two Thousand Five Hundred Fifty Two and Paisa Zero only	Cum	119638
8	Providing and laying of back filling behind abutment wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	4.37	1210.00	Rupees:-One Thousand Two Hundred Ten Paisa Zero only.	Cum	5288
				Total:-		272952
Quoted rate in figure				%		
Quoted rate in words				%		
Signature of contractor with address:-						
Executive Engineer B&R Division						

Executive Engineer
B&R Division
Rohru

Job No.

(28) (27)

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages on link road Bajnudhar Kewaldhar Mohanla Pariser road km. 0/0 to 2/100 (SH-C/O R/wall at RD.1/165 to 1/174)						Estimated Cost:-340321/-
						Earnest Money:-6800/-
						Time:-One Month
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	10.70	324.83	Rupees:-Three Hundred Twenty Four and Paisa Eighty Three only	Cum	3476
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	16.92	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	6886
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	6.48	6314.00	Rupees:-Six Thousand Three Hundred Forteen and Paisa Zero only	Cum	40915
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 as directed by the Engineer-in-Charge	3.87	6656.00	Rupees:-Five Thousand Five Hundred Forty Paisa Zero only.	Cum	25759
5	Stone masonry in cement mortar 1:6 (1Cement:6 sand) for sub-structure complete as per drawings and technical specification Clauses 702, 704, 1202 and 1204 including carriage of material within all leads and lifts as per directions of Engineer in charge	23.76	5400.00	Rupees:-Five Thousand Four Hundred Paisa Zero Only.	Cum	128304
6	Construction dry rubble Stone masonry for retaining walls breast wall revementment walls and parapets etc for sub structure nd superstructure complete as per drawings and technical specification Clauses 704.6 and 1302.5 within all leads and lifts as per directions of Engineer in charge	30.24	4082.00	Rupees:-Four Thousand Eighty Two Paisa Zero only.	Cum	123440
7	Providing and laying of back filling behind abutment wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	7.83	1474.00	Rupees:-One Thousand Four Hundred Seventy Four Paisa Zero only.	Cum	11541
Total:-						340321
DNIT No. Approved for Rs.340321/- only for the Year 2023-2024						
%						
Quoted rate in figure						
Quoted rate in words						
Signature of contractor with address:-						

Executive Engineer
B&R Division
HPPWD Rohru

(28)

SCHEDULE OF QUANTITY

NAME OF WORK:- C/O link road Tipper to Shallan Kiti Randeep Nagar Biharua Dogra Pul km.0/0 to 3/400 (SH.-P/L Kharanja stone soling at RD.0/250 to 0/500)

Job No.
Estimated Cost:- 461627/-
Earnest Money:- 9300/-
Time:- One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Preparation of sub grade by dressing to camber (earth work for the cutting involved for sub grade to paid for sprepatly depending upon the classification of soil completed as per HP.PWD specification within all leads and lifts as per directions of Engineer in Charge.	921.25	1.58	Rupees:-One and Paisa Five Eight only	Sqm	1456
2	Consolidation of sub grade with road roller including making good the undulation etc, with earth or quarry soil etc. and rerolling the sub-grade completed as per HP.PWD specifications and as directed by the Engineer in Charge.	921.25	1.28	Rupees:-One and Paisa Two Eight only	Sqm	1179
3	Stone soling masonry hand packed filling interstices with kharanja stone and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding material moorum of earth etc complete as per HP.PWD specification 230mm spread thickness finished work including materials and labour complete includin g carriage of materials within all leadsa and lifts as per directions of Engineer in charge	211.89	2166.18	Rupees:-Two Thousand One Hundred Sixty Six and Paisa One Eight only	Cum	458992
				Total:-		461627
	Quoted rate in figure			%		
	Quoted rate in words			%		
	Signature of contractor with address:-					

Executive Engineer
B&R Division
HP.PWD Rohru

(30) (29)

SCHEDULE OF QUANTITY

Estimate Cost Rs 493000/-
Earnest Money 10000/-
Time:-90 days

Name of work : Restoration of rain damages on various road under Tikkar Sub Divn (Tikkar section) SH-Hiring of JCB for removal of land slide drain /clearance of opening of culverts filling of depression).

Sr. No.	Sub-Head and Item of works	Quantity	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of J.C.B.(Excavator-Cum-Loader) having bucket capacity 0.50including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burns. Minimum 18.00cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	58.00	8500	Rs eight thousand five hundred	per day	493000
	Total					493000

Executive Engineer
Rohru Division, HP PWD
Rohru.

(30)

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages on various road under Tilkar Su-Division (SH:-Providing and supplying wire crate)

Job No. _____
Estimated Cost:-360000/-
Earnest Money:-7200/-
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Providing and laying of boulder apron laid in wire crates with 4 mm (four) millimetre dia GI wire conforming to 18280 and IS: 4826 in 100 mm x 100 mm (hundred millimetre x hundred molimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps end joints laid with stone boulders weighing not less than 2.5 (twenty five)kilogramme each as per drawing and MORD Technical Specifications Clause 1301 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	2343.75	153.60	Rupees:-One Hundred Fifty Three and Paisa Six Zero only	Cum	360000
				Total:-		360000
	Quoted rate in figure		%			
	Quoted rate in words		%			
	Signature of contractor with address:-					

Executive Engineer
B&R Division

NAME OF WORK--:R/R dan
culverts , filling of depression)

cumverts, filling of depression)

Estimated Cost:-	493000
Earnest Money:-	10000
Time:-	90 Days

90 Days

Sr.no.

Item of work

Description of work		Quantity	Rate in figure	Rate in words	Unit	Amount
1	Hiring of JCB (Excavator cum loader) front end loader 0.50 cum/hour including POL charges shifting charge and other ancillary equipments as required at site of work for removal of slips in all heights and all kinds of soils such as Kankar moonum shingle boulders decomposed or soft variety of soil such as spade work pick work junner work soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this undervacable materials has to be done in the acquired width of the road to avoid the damage to the properties of the people or in case any damage took place the contractor shall be liable for its. All salvaged materials such as quarried stone shall belong to the department and manikunum useful quantity of stones from removal of slips shall be to be neatly stacked along road side on road berms minimum 18.00 cubice metre of earth work shall be done by the machine in one hour and number of hours shall be reduced accordingly. The work shall have to be carried out as per ministry of transport and as per instruction of the Engineer in charge including all leads and lifts	58.00	8500.00	Rupees:- Eight Thousand Five Hundred and Paise Zero only	Per Day	493000
Total:-						493000
Quoted rate in figure						

Total:-

493000

Quoted rate in figure

Quoted rate in words

Signature of contractor with address:-

**Executive Engineer
B&R Division
HP.PWD Rohru**

Schedule of Qty

Name of Work:- Restoration of Rain damages on Various road under Tikkar Sub Division(SH:- Hiring of JCB removal of land slide,drain clearance,opening of culvert,filling of depression)				ESTIMATED COST		493000
				EARNEST MONEY		10000
				TIME LIMIT:		90 Days
Sr. No	Description of items.	Qty	Unit	Rate		Amount.
				In Fig.	In Words	
1	2	3	4	5	6	7
1	Hiring of J.C.(Backhoe-Cum-Loader) front end loader 0.50 cum bucket capacity and including P.O.L. charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as bankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	58	Per day	8500	Rupees Eight Thousand Five Hundred Only	493000
Total						493000

DNIT No..... approved for amounting to Rs.:493000/- for the year 2023-24

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure (+/-)

Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer
B&R Division HPPWD
Rohru

35

Schedule of Qty

Name of Work:- Restoration of Rain damages on Various road under Tikkar Sub Division section Tikkar (SH:- Hiring of JCB removal of slips/ and maintenance of road at various RD)				ESTIMATED COST	
				EARNEST MONEY	487200
				TIME LIMIT:	9744
					58 days
Sr. No	Description of Items.	Qty	Unit	Rate	Amount.
				In Fig.	
1	2	3	4	5	6
1	Hiring of J.C.B (Excavator-Cum-Loader) with rock breaker having 0.50 cum bucket capacity and including P.O.L. charges, shifting charges and other ancillary equipments as required at site of work for removal of snow & slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30 cubic meter of earth work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	58	Per day	8400	Rupees Eight Thousand Four Hundred Only
					487200
Total					487200

DNT No..... approved for amounting to Rs.:487200/- for the year 2023-24

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and

2 cost.

Quoted rate Figure (+/-)
Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer
B&R Division HPPWD
Rohru

35 (34)

Schedule of Qty

Name of Work:- Repair and Maintenance of JE head Quarter at Pujari in tehsil Tikkar Distt Shimla(SH:- C/o Protection wall Behind Building)				ESTIMATED COST		284066
				EARNEST MONEY		5681
				TIME LIMIT:		Two Month
Sr. No	Description of Items.	Qty	Unit	Rate	In Words	Amount
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1	33.28	cum	167	Ruppes One Hundred & Sixty Seven Only	5558
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material and as per HPPWD specification of 1990 volume-1 or as directed by the Engineer-In-Charge.	25.6	cum	399	Ruppes Three Hundred & Ninety Nine Only	10214
3	P/L Cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate forty millimeter nominal size)for plain/reinforced concrete work in open foundation complete as per drawing and technical specification Clauses 802,803,1202&1203.	5.17	cum	5070	Ruppes Five Thousand & Seventy Only	26212
4	Providing concrete for plain/reinforced concrete in open foundation/RB-walls complete as per drawing and technical specification clause 802,803,1202 & 1203 grade (1:4:8nominal mix) , 1 cement :4and :8graded stone aggregate . including all leads and lifts, as per HPPWD, specification of 1990 volume-1 or as directed by the Engineer-In-Charge	3.36	cum	5717	Ruppes Five Thousand Seven Hundred & Seventeen Only	19209
5	Stone masonry in cement mortar for substructure complete as per drawing& technical specification Clause 702,704,1202 and 1204 Random rubble masonry in cement mortar(1:6) ncluding all leads and lifts, as per HPPWD, specification of 1990 volume-1 or as directed by the Engineer-In-Charge.	32.25	cum	5089	Ruppes Five Thousand &Eighty Nine Only	164120
6	Construction of dry rubble masonry for retaining walls, breast walls,revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including all leads and lifts, as per HPPWD, specification of 1990 volume-1 as directed by the Engineer-In-Charge	17.67	cum	3325	Ruppes Three Thousand Three Hundred & Twenty Five Only	58753
Total						284066

DNIT No..... approved for amounting to Rs:-284066/- for the year 2023-24

- 1 The rates Should be quoted for all heights including all lead and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Quoted rate Figure (+/)
Quoted rate Words (+/)

Signature of the Contractor with full address:-

Executive Engineer
B&R Division HPPWD
Rohrd

36 35

SCHEDULE OF QUANTITY

NAME OF WORK:-R/R damages on Mandharhi Shrontha road km.0/0 to 10/0 (SH:- Widening of black spot at RD-5/515 to 5/560)

Job No.
Estimated Cost:-457784/-
Earnest Money:-9200/-
Time:- One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1603.1, 1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber, embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machineries, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 346.01 cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The serviceable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.	1153.35	396,917	Rupees:- Three Hundred Ninety Six and Paise Nine One Seven only	Cum	457784
Total:-						457784
DNIT No.						Approved for Rs.457784/- only for the Year 2023-2024
Quoted rate in figure						%
Quoted rate in words						%
Signature of contractor with address:-						

Executive Engineer
B&R Division
HP.PWD Rohru

(34)

SCHEDULE OF QUANTITY

NAME OF WORK:- C/O Bainudhar Kewaldhar Mohan Lal Pariser road km. 0/0 to 3/500 (SH:-P/L. Kharanja stone soling at RD.0/450 to 0/550 & R/wall at in wire crate RD.0/500 to 0/520, 0/615 to 0/625)

		Job No.		Estimated Cost:-487260/-		Earnest Money:-9700/-		Time:-One Month	
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words		Unit	Amount		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	19.20	183.16	Rupees:-One Hundred Eighty Three and Paisa Sixteen only		Cum	3517		
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	18.75	494.57	Rupees:-Four Hundred Ninety Four and Paisa Fifty Seven only		Cum	9273		
3	Providing and laying of boulder apron laid in wire crates with 4 mm (four) millimetre dia G1 wire conforming to 18280 and IS: 4826 in 100 mm x 100 mm (hundred millimetre x hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps end joints laid with stone boulders weighing not less than 25 (twenty five)kilogramme each as per drawing and MORD Technical Specifications Clause 1301 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	93.740	2847.00	Rupees:-Two Thousand Eight Hundred Forty Seven and Paisa Zero only		Cum	266878		
4	Providing and laying of back filling behind R/wall and wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	12.00	1300.00	Rupees:-One Thousand Three Hundred and Paisa Zero only		Cum	15600		
5	Preparation of sub grade by dressing to camber (earth work for the cutting involved for sub grade to paid for separately depending upon the classification of soil completed as per HP.PWD specification within all leads and lifts as per directions of Engineer in Charge.	368.50	1.84	Rupees:-One and Paisa Eighty Four only		Sqm	678		
6	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub-grade completed as per HP.PWD specifications and as directed by the Engineer in Charge.	368.50	1.28	Rupees:-One and Paisa Twenty Eight only		Sqm	472		

7	Stone soling masonry hand packed filling interstices with kharanja stone and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding material moorum of earth etc complete as per HP.PWD specification 230mm spread thickness finished work including materials and labour complete including carriage of materials within all leads and lifts as per directions of Engineer in charge	84.76	2251.56	Rupees:-Two Thousand Two Hundred Fifty One and Paise Fifty Six only	Cum	190842
				Total:-		487260
		DNIT No. Approved for Rs.487260/- only for the Year 2023-2024				
	Quoted rate in figure					
	Quoted rate in words					
	Signature of contractor with address:-					


 Executive Engineer
 B&R Division
 HP.PWD Rohru

(38) (37)

SCHEDULE OF QUANTITY

NAME OF WORK:- C/O link road Tipper to Shallaan kit Randep Nager Biharu Dogra Pul road km. 0/0 to 3/400 (SH:-P/L Kharanja stone soling at RD.0/500 to 0/750 & R/wall at in wire crate RD.0/500 to 0/520, 0/615 to 0/625)

Job No. _____
Estimated Cost:-479957/-
Earnest Money:-9600/-
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Preparation of sub grade by dressing to camber (earth work for the cutting involved for sub grade to paid for sprepatly depending upon the classification of soil completed as per HP.PWD specification within all leads and lifts as per directions of Engineer in Charge.	921.25	1.84	Rupees:-One and Paisa Eighty Four only	Sqm	1695
2	Consolidation of sub grade with road roller including making good the undulation etc, with earth or quarry soil etc. and rerolling the sub-grade completed as per HP.PWD specifications and as directed by the Engineer in Charge.	921.25	1.28	Rupees:-One and Paisa Twenty Eight only	Sqm	1179
3	Stone soling masonry hand packed filling interstices with kharanja stone and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding material moorum of earth etc complete as per HP.PWD specification 230mm spread thickness finished work including materials and labour complete includin g carriage of materials within all leadsa and lifts as per directions of Engineer in charge	211.89	2251.56	Rupees:-Two Thousand Two Hundred Fifty One and Paisa Fifty Six only	Cum	477083
Total:-						479957
DNIT No. _____ Approved for Rs.479957/- only for the Year 2023-2024						
Quoted rate in figure _____ %						
Quoted rate in words _____ %						
Signature of contractor with address:- _____						

Executive Engineer
B&R Division
HP.PWD Rohru

Job No.

(30)

SCHEDULE OF QUANTITY

Estimated Cost:-492969/-

Earnest Money:-9800/-

Time:-One Month

NAME OF WORK:-R/R damages on Mehandi Tikkar road km.0/0 to 28/300 (SH:-C/O R/wall in wire crate at Rd.24/100 to 24/120)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	55.00	324.83	Rupees:-Three Hundred Twenty Four and Paise Eighty Three only	Cum	17866
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material with in all leads and lifts as per directed by the Engineer-in-Charge	35.00	407.00	Rupees:-Four Hundred Seven and Paise Zero only	Cum	14245
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS-280 and IS-4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	156.25	2836.29	Rupees:-Two Thousand Eight Hundred thirty Six Paise Two Nine only	Cum	443170
4	Providing and laying of back filling behind abutment wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	12.00	1474.00	Rupees:-One Thousand Four Hundred Seventy Four Paise Zero only	Cum	17688
				Total:-		492969
	Quoted rate in figure					
	Quoted rate in words					
	Signature of contractor with address:-					

DNIT No.

Approved for Rs.492969/- only for the Year 2023-2024

Executive Engineer
B&R Division
HP.PWD Rohru

40 39

NAME OF WORK--:K/R damages on various road under Tikkar Sub-Division (Sheelghat Section (SH--Hiring of JCB for removal of land slide, drain clearance ,opening of culverts , filling of depression)	Time--	90 Days

NAME OF WORK--:K/R damages on various road under Tikkar Sub-Division (Sheelghat Section (SH--Hiring of JCB for removal of land slide, drain clearance ,opening of culverts , filling of depression)	Time--	90 Days

**Executive Engineer
B&R Division
HP.PWD Rohru**

42

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O Mehandli Tikkar road km. 0/0 to 28/500 (SH:-C/O B/wall at RD. 10/570 to 10/590)

Job No. _____
Estimated Cost:-309404/-
Earnest Money:-6200/-
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	12.80	246.65	Rupees:-Two Hundred Forty Six and Paise Six Five only	Cum	3157
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	14.20	430.51	Rupees:-Four Hundred Thirty and Paise Five One only	Cum	6113
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	4.40	4990.00	Rupees:-Four Thousand Nine Hundred Ninety and Paise Zero only	Cum	21956
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 as directed by the Engineer-in-Charge	3.00	5410.00	Rupees:- Five Thousand Four Hundred Ten Paise Zero only.	Cum	16230
5	Stone masonry in cement mortar 1:6 (1:Cement :6 sand) for sub-structure complete as per drawings and technical specification Clauses 702, 704, 1202 and 1204 including carriage of material within all leads and lifts as per directions of Engineer in charge	16.81	4890.00	Rupees:-Four Thousand Eight Hundred Ninety Paise Zero Only.	Cum	82201
6	Construction of dry rubble masonry for retaining wall , breast walls , revement walls and parapets etc. for sub-structure and super structure complete as per drawings and technical specification Clauses 704, 6, 1302.5 as directed by the Engineer-in-Charge	52.55	3420.49	Rupees:-Three Thousand Four Twenty One Paise Four Nine only	Cum	179747
Total:-						309404
	Quoted rate in figure					%
	Quoted rate in words					%
	Signature of contractor with address:-					

Executive Engineer
B&R Division
R&Hru

41

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages on Syria Nallah Melhi Kupri road km. 0/0 to 6/0 (SH:-C/O R/wall in wire crate at RD.5/285 to 5/295)

Job No.
Estimated Cost:-232214/-
Earnest Money:-4700/-
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	13.76	407.00	Rupees:-Four Hundred Seven and Paise Zero only	Cum	5600
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four) millimetre dia GI wire conforming to 18280 and IS: 4826 in 100 mm x 100 mm (hundred millimetre x hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps end joints laid with stone boulders weighing not less than 2.5 (twenty five)kilogramme each as per drawing and MORD Technical Specifications Clause 1301 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	62.50	2890.00	Rupees:-Two Thousand Eight Hundred Ninety and Paise Zero only	Cum	180625
3	Providing and laying of back filling behind R/wall and wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	31.20	1474.00	Rupees:-One Thousand Four Hundred Seventy Four and Paise Zero only	Cum	45989
		Total:-		232214		
		DNIT No.		Approved for Rs.232214/- only for the Year 2023-2024		
		Quoted rate in figure		%		
		Quoted rate in words		%		
		Signature of contractor with address:-				

Executive Engineer
B&R Division
HP.PWD Rohru

49

SCHEDULE OF QUANTITY

Job No. _____
Estimated Cost:-396502/-
Earnest Money:-8000/-
Time:-One Month

NAME OF WORK:-C/O link road from Syria Nallah to Melthi Kupri road km. 0/0 to 6/0 (SH:-SH:-C/O 900mm dia Hume pipe culvert at RD.2/800 with wing wall 4.00 on both side.)

Sl.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	44.79	324.83	Rupees:-Three Hundred Twenty Four and Paisa Eighty Three only	Cum	14549
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material, with in all leads and lifts as per directed by the Engineer-in-Charge	45.82	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	18649
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	25.42	6314.00	Rupees:-Six Thousand Three Hundred Forten and Paisa Zero only	Cum	160502
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	1.92	6656.00	Rupees:-Six Thousand Six Hundred Fifty Six Paisa Zero Only.	Cum	12780
5	Stone masonry in cement mortar 1:5 (1 Cement : 5 sand) for foundation complete as per drawings and technical specification Clauses 702, 704,1202 and 1203 including carriage of material within all leads and lifts as per directions of Engineer in charge	12.11	5800.00	Rupees:-Five Thousand Eight Hundred Paisa Zero Only.	Cum	70238
6	Randon Rubble Stone masonry in cement mortar 1:6 (1 Cement : 6 sand) for foundation complete as per drawings and technical specification Clauses 702, 704,1202 and 1203 including carriage of material within all leads and lifts as per directions of Engineer in charge	1.01	5400.00	Rupees:-Five Thousand Four Hundred Paisa Zero Only.	Cum	5454
7	Construction of dry masonry in retaining walls, breast walls etc.as per drawings and technical specification including carriage of material within all leads and lifts as per directions of Engineer in charge	13.68	4082.00	Rupees:-Four Thousand Eighty Two Paisa Zero Only.	Cum	55842
8	Providing and laying of back filling behind R/wall and wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3, 8 as directed by the Engineer-in-Charge	6.78	1474.00	Rupees:-One Thousand Four Hundred Seventy Four and Paisa Zero only	Cum	9994

9	Providing and laying reinforced cement concrete pipe NP2 for culverts on forst class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection works backing filling concrete and masonry works in head walls and parapets caluse 1106 .as directed by the Engineer-in-Change	7.50	5250.00	Rupees:-Five Thousand Two Hundred Fifty Paissa Zero only.	Cum	39375
10	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification clause 1303 as directed by the Engineer-in-Change	0.49	14193.96	Rupees:-Fourteen Thousand One Hundred Ninety Three Paissa Ninety Six only.	Cum	6955
11	Providing and laying of earth filling lift up to 1.50 mtrs. And disposal u to 20 mtrs. with in all leads and lifts as directed by the Engineer-in-Change	6.24	346.92	Rupees:-Three Hundred Forty Six Paissa Ninety Two only.	Cum	2165
				Total:-		396502
	Quoted rate in figure	DNIT No.		Approved for Rs.396502 only for the Year 2023-2024		
	Quoted rate in words	%				
	Signature of contractor with address:-	%				


 Executive Engineer
 B&R Division
 HP.PWD Rohru

SCHEDULE OF QUANTITY

Job No.
Estimated Cost:-459910/-
Earnest Money:-9200/-
Time:-One Month

NAME OF WORK:- R/R damages on Syria Nallah Melhi Kupri road km. 0/0 to 6/0 (SH:-C/O R/wall in wire crate at RD.5/300 to 5/310)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	56.40	407.00	Rupees:- Four Hundred Seven and Paise Zero only	Cum	22955
2	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	26.50	6464.83	Rupees:- Six Thousand Four Hundred Sixty Four Paise Eighty Three Only.	Cum	171318
3	Providing and laying of boulder apron laid in wire crates with 4 mm (four) millimetre dia GI wire conforming to 18280 and IS: 4826 in 100 mm x 100 mm (hundred millimetre x hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps end joints laid with stone boulders weighing not less than 2.5 (twenty five) kilogramme each as per drawing and MORD Technical Specifications Clause 1301 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	78.13	2890.00	Rupees:- Two Thousand Eight Hundred Ninety and Paise Zero only	Cum	225796
4	Providing and laying of back filling behind R/wall and wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	31.10	1474.00	Rupees:- One Thousand Four Hundred Seventy Four and Paise Zero only	Cum	45841
Total:-						465910
DNIT No. Approved for Rs.459910/- only for the Year 2023-2024						
	Quoted rate in figure		%			
	Quoted rate in words		%			
	Signature of contractor with address:-					

Executive Engineer
B&R Division
IP-PWD Rohru

(44)

JOB NO:-

Schedule of Qty				ESTIMATED COST	496000	
Name of Work: R/R Damage to various road under Under Sheelphat Section Sub Division Tikkar (Sh:- Supplying and stacking of fine Sand at Site of work for spreading over Snow)				EARNEST MONEY	10000	
Sr. No	Description of Items.	Qty	Unit	TIME LIMIT:		Amount.
				Rate	In Words	
5				In Fig.	6	7
1	Supplying and stacking of fine sand free from dirt,dust and disintegrated pieces to deleterious and organic matter at site of work as per direction of the Engineer-In- Charge, as per HPPWD Specification of 1990 Volume-I as directed by the Engineer-In-Charge.	310	Per Cum	1600	Rupees One Thousand Six Hundred Only	496000
Total						496000

DNT No..... approved for amounting to Rs.-496000/- for the year 2023-24

1 The rates should be quoted for all heights including all lead and lifts.
The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

2 cost.

Quoted rate Figure (+/)

Quoted rate Words (+/)

Signature of the Contractor with full address:-

Executive Engineer
B&R Division HPPWD
Rehru

48
45

NAME OF WORK--:R/R damages on various road under Tikkar Sub-Division (Tikkar Section (SH:-Hiring of JCB for removal of land slide, drain clearance ,opening of culverts , filling of depression)	Time:-	90 Days

NAME OF WORK--:R/R damages on various road under Tikkar Sub-Division (Tikkar Section (SH:-Hiring of JCB for removal of land slide, drain clearance ,opening of culverts , filling of depression)	Time:-	90 Days

Executive Engineer
B&R Division
~~HPWD~~ Rohru

Job No.

46

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages to Pujari Koti road km.0/0 to (SH:-C/O B/wall in wire crate at Rd.7/0 to 7/030)					
				Estimated Cost:-279485/-	
				Earnest Money:-5600/-	
				Time:-One Month	
Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit Amount
1	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material with in all leads and lifts as per directed by the Engineer-in-Charge	21.00	407.00	Rupees-Four Hundred Seven and Paise Zero only	Cum 8547
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS 280 and IS-4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 as directed by the Engineer-in-Charge	93.75	2890.00	Rupees-Two Thousand Eight Hundred Ninety Paise /zero only.	Cum 270938
		Total:-			279485
DNIT No. Approved for Rs.279485/-only for the Year 2023-2024					
Quoted rate in figure %					
Quoted rate in words %					
Signature of contractor with address:-					

Executive Engineer
B&R Division
HP.PWD Rohru

DEPARTMENT SCHEDULE OF QUANTITY

Estimated cost Rs 1,94,018/-
 Earnment money 4000/-
 Time One Month

Name of work :- R/R Damages on Bharanta Basti Road (SH- C/O B/wall at Rd 0/0 to 0/025)

	Description of Items	Quantity	Rate in Figure.	Rate in Words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per drawing and Technical Specification Clause 1603.1 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	6.40	324.83	Rs three hundred twenty four & paise eighty three only	per cubic metre	2079
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material, in ordinary rocks up to 3 mtr depth within all leads and lifts as per directions of Engineer in charge	9.97	407.00	Rs four hundred two only	per cubic metre	4058
3	Providing and laying cement concrete 1:6:12 (one cement six sand twelve graded stone aggregate 40mm nominal size for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts as per directions of Engineer in charge	3.15	6314.00	Six thousand three hundred fourteen only	per cubic metre	19889
4	Random rubble masonry polygonal rubble masonry uncoursed /brought to courses with hard stone of approved quality in foundation and plinth cement mortar 1:6:(1cement:6sand)breast wall and retaining wall within all leads and lifts as per directions of Engineer in charge	31.11	5400.00	five thousand four hundred only	per cubic metre	167994
	Total:-					194018

DNIT NO Approved for Rs 1,94,018/- for the year 2023-24

Quoted Rate in figure	(+) (-)	%
Quoted Rate in Words	(+) (-)	%

Singture of Contractor with full Address

Executive Engineer
 B&R Div HP PWD
 Rohru

48

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages to Sua Deori Shakal road km.0/0 to 6/0 (SH:-C/O B/wall at RD.0/150 to 0/169)

Job No. _____
Estimated Cost:- 352460/-
Earnest Money:- 7100/-
Time:- One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	45.22	324.80	Rupees:- Three Hundred Twenty Four and Paisa Eighty Zero only	Cum	14687
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	30.78	407.00	Rupees:- Four Hundred Seven and Paisa Zero only	Cum	12527
4	Plain/reinforced cement concrete (1:4:8) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	5.13	6464.67	Rupees:- Six Thousand Four Hundred Sixty Four and Paisa Six Seven only	Cum	33164
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	3.88	6314.00	Rupees:- Six Thousand Three Hundred Forteen and Paisa Zero only	Cum	24498
5	Random Rubble Stone masonry in cement mortar 1:6 (1 Cement : 6 sand) for foundation complete as per drawings and technical specification Clauses 702, 704, 1202 and 1203 including carriage of material within all leads and lifts as per directions of Engineer in charge	29.18	5400.00	Rupees:- Five Thousand Four Hundred Paisa Zero Only.	Cum	157572
6	Construction of dry rubble masonry for retaining wall, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawings and technical specification Clauses 704.6, 1302.5 as directed by the Engineer-in-Charge	30.630	3591.62	Rupees:- Three Thousand five Hundred Ninety One Paisa Six Two only	Cum	110011
			Total:-			352460
Quoted rate in figure						
Quoted rate in words						
Signature of contractor with address:-						

Executive Engineer
B&R Division
HP.PWD Rohru

SCHEDULE OF QUANTITY

Job No.

52-49

NAME OF WORK:- Restoration of Rain/Snow damages on various roads under Khadralla Section (Tikkar Sub-Division)(SH:-Hiring of JCB for removal of snow and land slide, drain clearance ,opening of culverts, filling of depression and berms)

Estimated Cost:-476000/-
Earnest Money:-9500/-
Time:-90 Days

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Hiring of JCB (Excavator cum loader)front end loader 0.50cum/ hour including POL charges shifting charge and other ancillary equipments as required at site of work for removal of slips in all heighths and all kinds of soils such as kankar moorum shingle boulders decomposed or soft variety of soil such a spade work pick work jumer work soft rock hard rock including their intermediate classification of soil including mechnacial transportation of necessary . The disposal of this underevable materials has to be done in the acquired width of the road to avoid the damage to the properties of the people or in case any damage took place the contractor shall be liable for its .All salvaged materils such as qurried stone shall belong to the department and manikunum useful quantity of stones from removal of slips shall be to be neatly stacked along road side on road berms minium 18.00 cubice metre of earth work shall be done by the machine in one hours ans 200 cum of snow shall be removed from the road surface in one hour other wise number of hours shall be reduced accordingly. The work shall have to be carried out as per ministry of transport and as per instruction of the Engineer in charge including all leads and lifts	56.00	8500.00	Rupees:-Eight Thousand Five Hundred and Paise Zero only	Per Day	476000
		Total:-				476000
		DNIT No.		Approved for Rs.476000/- only for the Year 2023-2024		
		Quoted rate in figure				
		Quoted rate in words				
		Signature of contractor with address:-				

Executive Engineer
B&R Division
H.P.PWD Rohru

SCHEDULE OF QUANTITY

Name of Work :- M/T of Kotkhai Khaneti Deorighat Tikkar road km 24/000 to 29/690. Preparation of DPR under the schemes for special assistance to state for capital expenditure.)

Estimated Cost
Earnest Money

Rs. 2,38,980.00
Rs. 4800.00
One Month

Sr No	Sub Head/items of work.	Qty.	Rate in figures	Rate in world	Unit.	Amount
1	A) Topography survey by Digital total station with two second accuracy, showing all features on survey plan like trees, culvert, bridge, electric pole, telephone poles, hand pumps, school, habitant villages. B) Draw cross section at 15 m (fifteen meter) interval, L-section & calculate the quantity of earth work in standart format of autocad showing all layer of pavement components as applicable. C) Prepration of survey plan showing all provision and preparation of detailed project report as per MORD guidelines.	5.69	12000	Rupees Twelve Thousand Only	Per Kilometre	68280.00
	Prepration of detailed estimate with detailed design and drawings of pavement and structural componenets as per relevant irc codes and rate analysis as per MORTH guidelines.	5.69	15000	Rupees Fifteen Thousand Only	Per Kilometre	85350.00
	Prepration of Technical Sanction.	5.69	5000	Rupees Five Thousand Only	Per Kilometre	28450.00
	Prepration of Working Estimate	5.69	5000	Rupees Five Thousand Only	Per Kilometre	28450.00
	Prepration of DNIT	5.69	5000	Rupees Five Thousand Only	Per Kilometre	28450.00
	Total					238980.00
	Quoted rates in figure (+/-)					%
	Quoted rates in word (+/-)					%

Signature of Contractor with full address:-

Executive Engineer,
R&R Division,
D.P.W.D., Rohru.

Job No.:-

51

SCHEDULE OF QUANTITY

NAME OF WORK:-R/R damages on various road under Sheelghat Section Sub-Division Tikkar (SH:-Hiring of JCB for removal of slips land Snow/, land slide maintenance of road)

Estimated Cost:-	495000
Earnest Money:-	10000
Time:-	450 Hours

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Hiring of JCB (Excavator cum loader)front end loader 0.50cum/ hour including POL charges shifting charge and other ancillary equipments as required at site of work for removal of slips in all heighths and all kinds of soils such as kankar moorum shingle boulders decomposed or soft variety of soil such a spade work pick work junner work soft rock hard rock including their intermediate classification of soil including mechnacial transportation of necessary . The disposal of this underevable materials has to be done in the acquired width of the road to avoid the damage to the properties of the people or in case any damage took place the contractor shall be liable for its . All salvaged materils such as quried stone shall belong to the department and manikunum useful quantity of stones from removal of slips shall be to be neatly stacked along road side on road berms minium 18.00 cubice metre of earth work shall be done by the machine in one hours ans 200 cum of snow shell be removed from the road surface in one hour other wise number of hours shall be reduced accordingly; The work shall have to be carried out as per ministry of transport and as per instruction of the Engineer in charge including all leads and lifts	450.00	1100.00	Ruppes:-One Thousand One Hundred and Paisa Zero only	Per Hours	495000
				Total:-		495000
	Quoted rate in figure					
	Quoted rate in words					
	Signature of contractor with address:-					

Executive Engineer
B&R Division
PPWD Rohru

52

SCHEDULE OF QUANTITY

Job No. _____
Estimated Cost:-497690/-
Earnest Money:-9900/-
Time:-One Month

NAME OF WORK:-Link road Tandali to Dogra Khad km.0/0 to 0/500 (SH:-F/C 5/7 mtrs.Wide of road at RD.0/0 to 0/150)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
4	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300,1603,1,1603,2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, canber, embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machineries, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government A recovery of useful stones 250.70 cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.	1966.510	253.083	Rupees:-Two Hundred Fifty Three and Paise Zero Eight Three only	Cum	497690

Executive Engineer
B&R Division Rohru
H.P. PWD. Rohru


NAME OF WORK--: Restoration of Rain damages on various roads under Tikkar Sub-Division(Tikkar Section)(SH--:Hiring of JCB for removal of slips slush/land slide and maintenance of road etc.)

Earnest Money:-9900/-

on(Tikkar Section)(S

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Hiring of JCB (Excavator cum loader) front end loader 0.50cum/hour including POL charges shifting charge and other ancillary equipments as required at site of work for removal of slips in all heights and all kinds of soils such as kankar moorum shingle boulders decomposed or soft variety of soil such a spade work pick work jumer work soft rock hard rock including their intermediate classification of soil including mechnacial transportation of necessary . The disposal of this underecable materials has to be done in the acquired width of the road to avoid the damage to the properties of the people or in case any damage took place the contractor shall be liable for its . All salvaged materis such as qurried stone shall belong to the department and manikunnum useful quantity of stones from removal of slips shall be to be neatly stacked along road side on road berms minimum 18.00 cubice metre of earth work shall be done by the machine in one hours ans 200 cum of snow shell be removed from the road surface in one hour other wise number of hours shall be reduced accordingly; The work shall have to be carried out as per ministry of transport and as per instruction of the Engineer in charge including all leads and lifts	450.00	1100.00	Rupees:-One Thousand One Hundred and Paise Zero only	Per Hour	495000
				Total:-		495000
	Quoted rate in figure		%			
	Quoted rate in words		%			
	Signature of contractor with address:-					

Executive Engineer
B&R Division
HP.PWD Rohru



**Executive Engineer
B&R Division
HP.PWD Rohru**

Job No.

(54)

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of Rain damages on various roads under Tikkar Sub-Division(Tikkar Section)(SH:-Hiring of JCB for removal of slips slush/land slide and maintenance of road etc.)

Estimated Cost:-495000/-
Earnest Money:-9900/-
Time:-Two Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Hiring of JCB (Excavator cum loader)front end loader 0.50cum/ hour including POL charges shifting charge and other ancillary equipments as required at site of work for removal of slips in all heghths and all kinds of soils such as kankar moorum shingle boulders decomposed or soft variety of soil such a spade work pick work jumer work soft rock hard rock including their intermediate classification of soil including mechnacial transportation of necessary . The disposal of this undereveable materials has to be done in the acquired width of the road to avoid the damage to the properties of the people or in case any damage took place the contractor shall be liable for its . All salvaged materis such as qurried stone shall belong to the department and manikurnum useful quantity of stones from removal of slips shall be to be neatly stacked along road side on road berms minium 18.00 cubice metre of earth work shall be done by the machine in one hours ans 200 cum of snow shell be removed from the road surface in one hour other wise number of hours shall be reduced accordingly. The work shall have to be carried out as per ministry of transport and as per instruction of the Engineer in charge including all leads and lifts	450.00	1100.00	Rupces:-OneThousand One Hundred and Paise Zero only	Per Hour	495000
				Total:-		495000
	Quoted rate in figure		%			
	Quoted rate in words		%			
	Signature of contractor with address:-					

Executive Engineer
B&R Division
HP.PWD Rohru

55

NAME OF WORK--: Restoration of Rain damages on various roads under Tikkar Sub-Division(Tikkar Section)(SH--Hiring of JCB for removal of slips slush/land slide and maintenance of road etc.)	1 MAR-12 TO 30 APR 11

Estimated Cost:-495000/-
Earnest Money:-9900/-
Time:-Two Month

**Executive Engineer
B&R Division
HP.PWD Rohru**

Job No.

(56)

SCHEDULE OF QUANTITY

Estimated Cost:-495000/-

Earnest Money:-9900/-

Time:-Two Month

NAME OF WORK:- Restoration of Rain damages on various roads under Tikkar Sub-Division(Tikkar Section)(SH:-Hiring of JCB for removal of slips slush/and slide and maintenance of road etc.)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Hiring of JCB (Excavator cum loader)front end loader 0.50cum/ hour including POL charges shifting charge and other ancillary equipments as required at site of work for removal of slips in all heights and all kinds of soils such as kankar moorum shingle boulders decomposed or soft variety of soil such a spade work pick work junner work soft rock hard rock including their intermediate classification of soil including mechnacial transporion of necessary . The disposal of this undereccable materials has to be done in the acquired width of the road to avoid the damage to the properties of the people or in case any damage took place the contractor shall be liable for its . All salvaged materils such as qurried stone shall belong to the department and manikumum useful quantity of stones from removal of slips shall be to be neatly stacked along road side on road berms minium 18.00 cubice metre of earth work shall be done by the machine in one hours ans 200 cum of snow shell be removed from the road surface in one hour other wise number of hours shall be reduced accordingly. The work shall have to be carried out as per ministry of transport and as per instruction of the Engineer in charge including all leads and lifts	450.00	1100.00	Rupees:-OneThousand One Hundred and Paise Zero only	Per Hour	495000
				Total:-		495000
	Quoted rate in figure		%			
	Quoted rate in words		%			
	Signature of contractor with address:-					

Executive Engineer
B&R Division
HP.PWD Rohru

NAME OF WORK--: Restoration of Rain damages on various roads under Tikkar Sub-Division(Tikkar Section)(SH-:Hiring of JCB for removal of slips slush/land slide and maintenance of road etc.)

**Executive Engineer
B&R Division
HP.PWD Rohru**

58

Estimated Cost:-449472/-

Time:-One Month

Sr.no.

1:-F/C Widening of road at RD. 0/090 to 0/315)

**Executive Engineer
B&R Division
HP.PWD Rohru**

59

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages on Mandharli to Karchari road km. 0/0 to 12/200 (SH:-C/O R/wall at RD.8/732 to 8/749)

Sr.no.

Item of work

Quantity

Rate in figure

Rate in words

Unit

Amount

1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 with in all leads and lifts as per directed by the Engineer-in-Charge	16.51	324.83	Rupees:- Three Hundred Twenty Four and Paisa Eighty three only	Cum	5363
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. with in all leads and lifts as per directed by the Engineer-in-Charge	20.48	407.00	Rupees:- Four Hundred Seven and Paisa Zero only	Cum	8335
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	5.04	5683.00	Rupees:- Five Thousand Six Hundred Eighty Three and Paisa Zero Four only	Cum	28642
4	Random Rubble Stone masonry in cement mortar 1:6 (1 Cement : 6 sand) for foundation complete as per drawings and technical specification Clauses 702, 704, 1202 and 1203 including carriage of material within all leads and lifts as per directions of Engineer in charge	71.400	4860.00	Rupees:- Four Thousand Eight Hundred Sixty Paisa Zero Only.	Cum	347004
5	Back filling behind abutments wing wall and return walls with granular material complete as per MORO technical specification clause 1204.3, 8 as directed by the Engineer-in-Charge	36.75	1474.00	Rupees:- One Thousand Four Hundred Seventy Four and Paisa Zero only	Cum	54170
Total:-						443514
Quoted rate in figure						%
Quoted rate in words						%
Signature of contractor with address:-						%

Executive Engineer
B&R Division
H.P.W.D Rohru

DRAFT SCHEDULE OF QUANTITY

Estimated cost Rs 434036/-
Earnest Money Rs 8600/-
Time One month

Name of work :- R/R damages to Mandhari to Karchari road km 0/0 to 12/200(SH- C/O R/wall in wire crate at RD 8/705 to 8/721).

Sr No	Description of items	Quantity	Rate in Figure.	Rate in Words	Unit	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary rocks up to 3 mtr depth within all leads and lifts as per directions of Engineer in charge	54.08	407.00	Rs four hundred seven only	per cubic metre	22011
2	Providing and laying of boulder apron laid in wire crates 4mm dia G.I wire conforming to IS 280 and IS 4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 within all leads and lifts as per directions of Engineer in charge	117.19	2890.00	Rs two thousand Eight hundred ninety only	per cubic metre	338679
3	Back filling behind abutment wing wall and return wall with granular materials complete as per drawing and technical specification clause 1204.3.8 including carriage of materials within all leads and lifts as per directions of Engineer in charge	49.76	1474.00	Rs one thousand four hundred seventy four only	per cubic metre	73346
	Total:-					434036
DNT NO Approved for Rs 434036/- for the year 2023-24						

Quoted Rate in figure	(+) (-)	%
Quoted Rate in Words	(+) (-)	%

Signature of Contractor with full Address

Executive Engineer
B&R Divn HP, PWD
Rohru

(61)

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages on Punjari Saraidhar road km. 0/0 to 16/0 (SH:-C/O B/wall at RD.13/230 to 13/250)

Job No.
Estimated Cost:-442405/-
Earnest Money:-8900/-
Time:-One Month

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	20.64	324.83	Rupees:-Three Hundred Twenty Four and Paise Eighty Three only	Cum	6704
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	25.60	407.00	Rupees:-Four Hundred Seven and Paise Zero only	Cum	10419
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	6.30	5683.00	Rupees:-Five Thousand Six Hundred Eighty Three and Paise Zero only	Cum	35803
4	Randon Rubble Stone masonry in cement mortar for sub structure complete as per drawings and technical specification Clauses 702, 704,1202 and 1204 rendam rubble masonary in cement mortar 1:6 as directed by the Engineer-in-Charge	76.50	4860.00	Rupees:-Four Thousand Eight Hundred Sixty Paise Zero Only.	Cum	371790
5	Back filling behind abutments wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	12.00	1474.00	Rupees:-One Thousand Four Hundred Seventy Four and Paise Zero only	Cum	17688
Total:-						442405
Quoted rate in figure						%
Quoted rate in words						%
Signature of contractor with address:-						

Executive Engineer
B&R Division
HP.PWD Rohru

SCHEDULE OF QUANTITY

Job No. _____
Estimated Cost:-366865/-
Earnest Money:-5500/-
Time:-One Month

NAME OF WORK:- R/R damages on Sheelghat Saungi via Chota Sheel road km. 0/0 to (SH:-C/O R/wall at RD. 0/915 to 0/930)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 as directed by the Engineer-in-Charge	15.48	324.83	Rupees:-Three Hundred Twenty Four and Paisa Eighty Three only	Cum	5028
2	Earthwork in excavation for structures upto 3 depth as per as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by the Engineer-in-Charge	19.20	407.00	Rupees:-Four Hundred Seven and Paisa Zero only	Cum	7814
3	Plain/reinforced cement concrete (1:6:12) in open foundation complete as per drawings and technical specification Clauses 802, 803, 1202 and 1203 within all leads and lifts as per directions of Engineer in charge	6.30	5109.04	Rupees:-Five Thousand One Hundred Nine and Paisa Zero Four only	Cum	32187
4	Stone masonry in cement mortar 1:6 (1Cement :6 sand) for sub-structure complete as per drawings and technical specification Clauses 702, 704, 1202 and 1204 including carriage of material within all leads and lifts as per directions of Engineer in charge	57.38	5400.00	Rupees:-Five Thousand Four Hundred Paisa Zero Only.	Cum	309852
5	Providing and laying of back filling behind abutment wing wall and return walls with granular material complete as per MORD technical specification clause 1204.3.8 as directed by the Engineer-in-Charge	9.00	1331.51	Rupees:-One Thousand Four Hundred Seventy Four and Paisa Zero only	Cum	11984
				Total:-		366865
	Quoted rate in figure		%			
	Quoted rate in words		%			
	Signature of contractor with address:-					

Executive Engineer
B&R Division
Rohru

63

Job No. 2

SCHEDULE OF QUANTITY

Estimated Cost:-385000/-
Earnest Money:-7700/-
Time:-Two Months

NAME OF WORK:- R/R damages to Sheel Sungri Mandla kupri road km. 0/0 to 5/0 (SH:-Hiring of Backhoe loader (Like JCB) for removal of slipsat various Rds and c/o road side kachcha drain)

Sr.no.	Item of work	Quantity	Rate in figure	Rate in words	Unit	Amount
1	Hiring of Backhoe loader(JCB) having bucket capacity 0.45 cum including POL charges shifting charge and other ancillary equipments as required at site as per instruction of the Engineer in charge including all leads and lifts.	350.00	1100.00	Rupees:-One Thousand One Hundred and Paisa Zero only	Per Hour	385000
Total:-						385000
DNIT No. _____						
Quoted rate in figure _____ %						
Quoted rate in words _____ %						
Signature of contractor with address:- _____						

Approved for Rs.385000/- only for the Year 2023-2024

Executive Engineer
B&R Division
HP.PWD Rohru

JOB NO.:-

(65)

Schedule of Qty

Name of Work: R/R Damage to various road under Under Sheelghat Section Sub Division Tikkar (Sh:- Supplying and stacking of fine Sand at Site of work for spreading over Snow badshal Nallah Kharia Road)				ESTIMATED COST	
				EARNEST MONEY	10000
				TIME LIMIT:	One Month
Sr. No	Description of Items.	Qty	Unit	Rate	In Words
				In Fig.	Amount.
1	Supplying and stacking of fine sand free from dirt, dust and disintegrated pieces to deteriorous and organic matter at site of work as per direction of the Engineer-In-Charge, as per HPPWD Specification of 1990 Volume-I as directed by the Engineer-In-Charge.	310	Per Cum	1600	Ruppes One Thousand Six Hundred Only
					496000
Total					496000

DNIT No.1708 approved for amounting to Rs:-496000/- for the year 2023-24

1 The rates Should be quoted for all heights including all lead and lifts.

The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.

Quoted rate Figure (+/-)	
Quoted rate Words (+/-)	

Signature of the Contractor with full address:-

Executive Engineer
B&R Division HPPWD
Rohru

JOB NO.:-

65

Schedule of Qty

Name of Work:- C/o Link road to baghi km 0/00 to 3/00(SH:- Widening of narrow reaches km 5/7 mtr wide km RD 1/480 to 1/705)		ESTIMATED COST		475852
		EARNEST MONEY		9517
		TIME LIMIT:		Two Month
Sr. No	Description of items.	Qty	Unit	Rate
				In Fig. In Words
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300.1603.1,1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road way, camber, embankments for grade improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its levelling fine dressing, and carriage of machineries, materials tools equipments and safety means and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th (One sixth) blasting work soft rock 1/10th (one 10th) jumper work in all cases failing which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the entire Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones 251.50cum. metre @ Rs. 300/- Per cubic metre shall be done on pro-rata basis in each running bill for this item. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified/ dimension in all leads and lift as per the direction of Engineer in charge.	1934.64	cum	245.964
				Rupees Two Hundred & Fourty Five - Paise Ninety Six Only
				475852
	Total			475852

Condition:-

1 The rates Should be quoted for all heights including all lead and lifts.

2 cost. The Contractor shall procure all the materials confirming to the specification of MORTH at his own risk and

Quoted rate Figure (+/ -)
Quoted rate Words (+/ -)

Signature of the Contractor with full address:-

Executive Engineer
B&R Division HPPWD
Rohru

66

Name of Work:- R/R Damage on Syria Nallah to Meethi Kupri road km 0/00 to 6/00(Sh:- C/o R/wall at RD 5/470 to 5/477.5/510 to 5/525)

Schedule of Qty

Sr. No	Description of Items.	Qty	Unit	ESTIMATED COST	
				EARNEST MONEY	460007
				TIME LIMIT:	9200
1	2	3	4	Rate	Amount.
				In Fig.	
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	20.9	cum	324.83	Ruppes Three Hundred & Twenty Four - Paise Eighty Three Only
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	9.46	cum	407	Ruppes Four Hundred & Seven Only
3	Plain/rein forced cement concrete (1:6:12) in open foundation complete as per drawing and technical specification Clauses 802,803,1202&1203	9.46	cum	5109.04	Ruppes Five Thousand One Hundred & Nine - Paise Four Only
4	Plain/rein forced cement concrete (1:4:8) in open foundation complete as per drawing and technical specification Clauses 802,803,1202&1203	4.4	cum	5710.66	Ruppes Five Thousand Seven Hundred & Ten - Paise Sixty Six Only
5	Stone masonry in cement mortar for substructure complete as per drawing& technical specification Clause 702,704,1202 and1204 Random rubble masonry in cement mortar(1:6)	64.24	cum	5523.33	Ruppes Five Thousand Five Hundred & Twenty Three - Paise Thirty Three Only
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8	15.84	cum	1331.51	Ruppes One Thousand Three Hundred & Thirty One - Paise Fifty One Only
Total					460007

- The rates should be quoted for all heights including all lead and lifts.
- The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost.
- Quoted rate Figure (+/-)
- Quoted rate Words (+/-)

Signature of the Contractor with full address:-

Executive Engineer
B&R Division HPPWD
Rohru