

**Himachal Pradesh
Public Works Department
NOTICE INVITING TENDER**

Sealed tenders on item rates on PWD form 6 & 7 are hereby invited by the Executive Engineer Tauni Devi Division and HPPWD Tauni Devi for the following works. The tender shall be received in this office on or before 26.02.2024 up to 11:00 AM and the same shall be opened on the same day at 11:30 AM in the presence of the contractor/firm. The application for the issue of tender document shall be received on dated 22.02.2024 upto 2:30PM and the tender form will be sold on cash payment (non refundable) on dated 23.02.2024 from 10:30 AM to 4:00 PM.


Sr. No.	Name of Work	Estimated Cost (Rs.)	Earnest Money	Time limit	Cost of form
1.	C/O link road to the house of Jaisi Ram village Sanu (SH:- C/o 5/7 mtr wide formation cutting from RD 0/065 to 0/144.40) Deposit work	1,24,881	2500/-	Two month	350/-
2.	C/O link road from Bharaiyan Di Dahr to Jangled Khad via Lamber road (km 0/00 to 3/525) (SH:- Preparation of Detailed Project Report) (C/O link road from Gubber to Bakkar Khad via Lambri (km 0/00 to 5/00) (SH:- Preparation of Detailed Project Report) C/O link road from Khanli to Bakkar Khad via Touru and Hathan (Km 0/00 to km 5/200) C/O link road from Purli to Jangled Khad via Barota road (km 0/00 to km 2/500) & C/O Science Lab at Kakkar School (SH:- Survey & Contour site plan	4,99,255	10000/-	Two month	350/-
3.	DPR for C/O Degree College Building at Tauni Devi Distt Hamirpur (HP) (SH:- C/O building portion ,water supply and sanitary installation ,rain water harvesting tank ,site development and approach road	1,30,990	2600/-	Two month	350/-
4.	R/R damages on Purli to Kujahalh via Jiana road km 0/00 to 4/600 (Sh:- C/o wire crate at RD 3/500 to 3/510 & 3/225 to 3/237.50 & 3/250 to 3/260	4,66,935	9300/-	Two month	350/-
5.	R/R damages on Uhal to Baghera via Jandroo road km 0/00 to 27/00 (Sh:- P/L patch work at RD 17/015 to 22/00)	4,80,080	9600/-	Two month	350/-
6.	R/R damages on Uhal to Baghera via Jandroo road km 0/00 to 27/00 (Sh:- P/L patch work at RD 9/00 to 16/00)	4,85,179	9700/-	Two month	350/-
7.	R/R damages on Uhal to Baghera via Jandroo road km 0/00 to 27/00 (Sh:- ROFD and imp of curves and grade at RD 16/870 to 16/945)	4,03,021	8100/-	Two month	350/-
8.	R/R damages on Uhal to Baghera via Jandroo road km 0/00 to 27/00 (Sh:- ROFD and imp of curves and grade at RD 16/945 to 17/000)	3,90,922	7800/-	Two month	350/-
9.	C/O link road from Baghera Bridge to Harizan Basti Jol via Samouna Goushala km 0/00 to 1/200 (Sh:- C/O C.C pavement at RD 0/180 to 0/310) Under MMGSY	2,82,091	5600/-	Two month	350/-
10.	C/O link road from Baghera Bridge to Harizan Basti Jol via Samouna Goushala km 0/00 to 1/200 (Sh:- C/O PCC solid cause way at RD 0/310 to 3/350) Under MMGSY	4,71,291	9400/-	Two month	350/-
11.	C/O Balance work for the C/o play ground at Chamiyana Tehsil Sujampur Distt Hamirpur (SH:- Balance work F/C for the C/O play ground at Chamiyana) Deposit work	4,99,501	10000/-	Two month	350/-
12.	C/o link road from Basantpur to Tauni Devi Via Chahar km 0/0 to 1/00 (SH:- P/L C.C pavement from RD 0/750 to 0/870) Under OTMNP	4,64,522	9300/-	Two month	350/-
13.	C/o link road from Basantpur to Tauni Devi Via Chahar km 0/0 to 1/00 (SH:- P/L C.C pavement from RD 0/300 to 0/420) Under OTMNP	4,64,522	9300/-	Two month	350/-
14.	C/o link road from Basantpur to Tauni Devi Via Chahar km 0/0 to 1/00 (SH:- P/L C.C pavement from RD 0/870 to 0/990) Under OTMNP	4,64,522	9300/-	Two month	350/-
15.	R/R damages on various road under Kakkar sub Division (SH:- Hiring of JCB for removal of Balance slips, clearance of catch pits and drains etc)	4,29,000	8600/-	Two month	350/-
16.	R/R damages on Sujampur Sandhole road in km 0/00 to 23/00 (SH:- C/o PCC retaining wall & wire crate ,breast wall in km 13/105 to 13/120)	4,64,263	9300/-	Two month	350/-
17.	R/R damages on Kakkar to Sachuhi road in km 0/00 to 8/500 (Sh:- C/O PCC breast wall & V-shape drain at RD 7/800 to 7/819)	3,87,226	7700/-	Two month	350/-
18.	R/R damages on Kakkar to Sachuhi road in km 0/00 to 8/500 (Sh:- C/O retaining wall in km 7/500 to 7/815)	4,24,110	8500/-	Two month	350/-

19	R/R damages on Sujapur Sandhole road in km 3/00 to 10/00 (Sh:- C/O wire crate in km 3/200 to 3/214) (LHS)	4,45,248	8900/-	Two month	350/-
20	R/R damages on Sujapur Sandhole road in km 3/00 to 10/00 (MDR - 38) (Sh:- C/O wire crate in km 3/080 to 3/090) (LHS)	4,45,120	8900/-	Two month	350/-
21	Imp of black spot on Uhal to Baghera via Jandroo km 0/00 to 27/00 (SH:- C/O R/wall, crash barrier at RD 24/910 to 24/921)	4,38,615	8800/-	Two month	350/-
22	A/R & M/O Sujapur Sandhole road km 0/00 to 23/00 (Sh:- C/O C.C causeway at RD 12/190 to 12/210) Deposit work	1,15,644	2300/-	Two month	350/-
23	C/O Dalwana to Dhangota Brahmna km 0/0 to 2/050 (Sh:- P/L WMM at RD 1/350 to 2/050) Under SCSP	4,77,639	9600/-	Two month	350/-
24	C/O Dalwana to Dhangota Brahmna km 0/0 to 2/050 (Sh:- P/L G.S.B at RD 1/575 to 2/050) Under SCSP	4,98,188	10000/-	Two month	350/-
25	C/O link road Chaleli to Tikkar via Debra km 0/0 to 3/350 (Sh:- C/O roller compacted concrete pavement at RD.0/045 to 0/120) Under SCSP	4,94,924	10000/-	Two month	350/-
26	C/O link road Kuthera to Chalokhar via Dei -Ka- Naun km 0/0 to 2/700 (Sh:- P/L roller compacted concrete pavement at RD 2/205 to 2/253 & 2/300 to 2/324.40) (Under OTMNP	3,82,894	7700/-	Two month	350/-
27	R/R damages on Utpur to Bakkar Khad via Tap road km 0/0 to 4/0 (SH:- C/O R/wall at RD 0/810 to 0/831)	3,86,427	7700/-	Two month	350/-
28	R/R damages on Utpur to Bakkar Khad via Tap road km 0/0 to 4/0 (SH:- C/O R/wall at RD 1/070 to 1/082 and 2/120 to 2/132)	4,36,174	8700/-	Two month	350/-
29	R/R damages on NIT to Muthan via Khasgran km 0/0 to 3/900 (Sh:- C/O U-shape drain at RD 2/030 to 2/235)	4,79,334	9600/-	Two month	350/-
30	R/R damages on Garne da Galu to Kuthera via Panyala km 0/0 to 3/885 and link road NIT Muthan via Khas Gran km 0/0 to 3/900 (Sh:- Providing patch)	4,81,303	9600/-	Two month	350/-
31	R/R damages on link road Harizan Basti Muthan Bihalan to house of Mohinder Kumar km 0/0 to 0/700 (Sh:- C/O C.C pavement at RD 0/660 to 0/100 and 0/135 to 0/165) Deposit work	3,92,549	7900/-	Two month	350/-
32	R/R damages on link road Chowki to Bahal km 0/00 to 1/500 and link road Nadiana Sadiana road km 0/00 to 4/00 (SH:- P/L patch work)	4,69,133	9400/-	Two month	350/-
33	R/R damages on Barin Dhawal via Siswan Ghalot road km 0/00 to 5/00 (Sh:- P/L paver block at RD 4/410 to 4/435 and C/O R/wall at RD 4/405 to 4/410 & 4/435 to 4/440)	4,48,357	9000/-	Two month	350/-
34	R/R damages on langwan to Tauni Devi road in km 3/350 to 7/310 (Sh:- P/L paver block at RD 6/850 to 6/895)	4,53,092	9100/-	Two month	350/-
35	A/R & M/O on various road under Tauni Devi Division (SH:- Supply of stationary article etc for use in Division office)	3,41,400	6800/-	Two month	350/-
36	A/R & M/O on various road under Tauni Devi Division (SH:- Supply of stationary article etc for use in Division office)	3,42,250	6800/-	Two month	350/-
37	R/R damages on Kotlu Naugin road km 0/00 to 2/405 and Darkoti Mohin road km 0/0 to 3/0 (SH:- Providing patch work)	4,75,900	9500/-	Two month	350/-
38	R/R damages on Uhal to Bakkar Khad via Parnali km 0/00 to 6/00 (SH:- C/O wire crates wall at RD 3/270 to 3/280 & 3/430 to 3/442)	3,80,440	7600/-	Two month	350/-
39	C/O link road from main road to Sidh Nag Madir village Thana Tikkar (Sh:- Imp of grade and C/O R/wall at RD 0/150 to 0/158.95) Deposit work	1,70,472	3400/-	Two month	350/-
40	C/O link road from Bhatiana to house of Sh.Shali Ram km 0/0 to 0/075 (Sh:- F/C from km 0/0 to 0/075) deposit work	1,48,481	3000/-	Two month	350/-
41	R/R damages on link road Chamiyana to village Chamiyana km 0/00 to 1/00 (SH:- R.F.O.D at RD 0/240 to 0/390)	3,44,553	6900/-	Two month	350/-
42	R/R damages on link road Sujapur to Chouri via Charot km 0/00 to 3/00 (Sh:- C/O Brest wall at RD 2/890 to 2/902)	4,36,087	8700/-	Two month	350/-
43	R/R damages on Patlander Bhagolu Ree road km 0/00 to 7/120 (SH:- C/O R/wall with wire crate at RD 3/00 to 3/015)	3,91,458	7800/-	Two month	350/-
44	C/O link road from Sujapur to Chouri via Charot km 0/0 to 3/0 (Sh:- P/L interlocking concrete paver block at RD 0/600 to 0/665) Under OTMNP	4,92,606	9900/-	Two month	350/-

45	R/R damages on Kasiri Duhak Chatruru road km 0/00 to 8/00 (Sh:- C/O R/wall at RD 5/925.50 to 5/931)	3,63,122	7300/-	Two month	350/-
46	R/R damages on Kasiri Duhak Chatruru road km 0/00 to 8/00 (Sh:- C/O R/wall at RD 5/920 to 5/925.50)	3,63,122	7300/-	Two month	350/-
47	(i) A/R & M/O link road Bharmeli Majhog Kalsai km 2/00 to 4/00 (ii) A/R & M/O link road Majhog Galu to Sial km 0/0 to 1/500 (iii) A/R & M/O link road Nakher Sauran km 0/00 to 1/00 (Sh:- Repair of pot holes)	4,97,780	10000/-	Two month	350/-
48	A/R & M/O link road Hamirpur to Ropa km 0/00 to 10/615 (Sh:- Repair of pot holes at RD 0/00 to 4/00)	4,99,988	10000/-	Two month	350/-
49	A/R & M/O link road Hamirpur to Ropa km 0/00 to 10/615 (Sh:- Repair of pot holes at RD 4/00 to 10/615)	4,91,459	10000/-	Two month	350/-
50	C/O link road Kakru to Harizan Basti Nadiana Sadiana km 0/00 to 1/00 (SH:- P/L roller compacted concrete pavement from RD 0/115 to 0/230) Under MMGSY	4,91,050	9800/-	Two month	350/-
51	C/O link road Kakru to Harizan Basti Nadiana Sadiana km 0/00 to 1/00 (SH:- P/L roller compacted concrete pavement from RD 0/00 to 0/115) Under MMGSY	4,91,050	9800/-	Two month	350/-
52	C/o link road to village Sih Paneh km 0/00 to 1/300 (Sh:- P/L wet mix macadam as correction layer at RD 0/050 to 0/500 C/O brest wall at RD 0/610 to 0/650 and parapets from RD 0/00 to 1/300) Under MMGSY	4,91,668	9800/-	Two month	350/-
53	C/o link road from village Kangri to (Shay) Khajapir in km 0/0 to 0/765 (Sh:- C/O brest wall U-shpe drain and paver block at RD 0/508 to 0/536) Under OTMNP	4,70,206	9400/-	Two month	350/-
54	R/R damages on Uhal to Bagehra via Jandroo road km 0/00 to 27/00 (SH:- Imp of curves & ROFD at RD 11/945 to 12/075)	4,80,682	9600/-	Two month	350/-
55	R/R damages on Uhal to Bagehra via Jandroo road km 0/00 to 27/00 (SH:- Imp of curves & ROFD at RD 17/705 to 17/810)	4,48,835	9000/-	Two month	350/-
56	R/R damages on Uhal to Bagehra via Jandroo road km 0/00 to 27/00 (SH:- P/L patch work at RD 7/300 to 8/500)	4,95,256	9900/-	Two month	350/-
57	R/R damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri km 0/0 to 30/915 (Sh:- P/L patch work at RD 10/00 to 12/00)	4,94,499	9900/-	Two month	350/-
58	R/R damages on link road Ree to Gartholi via Balyana road km 0/00 to 2/700 (SH:- C/O R/wall at RD 0/211.25 to 0/217.25)	4,40,377	8800/-	Two month	350/-
59	R/R damages on Cahalokhar Bahal Swahal road km 0/00 to 3/00 (SH:- C/O brest wall at RD 2/785 to 2/797)	1,24,917	2500/-	Two month	350/-

TERMS AND CONDITIONS:-

The tender documents shall be issued only to those contractors/firms who fulfill the following criteria and submit documents with the application. The valid enlistment/registration of contractor in appropriate class, Permanent Account Number (PAN), Earnest money in the shape of National saving certificate/Time deposit Account in any of the Post office in H.P./F.D.R from any Nationalized Bank (I/c Kangra Central Cooperative Bank) duly pledged in favour of the Executive Engineer. Other speical terms and condition can be seen/obtain in this office on any working day. Any ambiguous/telegraphic conditional tenders by fax shall not be acceptable.


Executive Engineer
TauniDevDivision,
HPPWDTauniDevi.
On behalf Governor
of HP

No. PW/TDD/GA/N.I.T./2023-24

20140-190

Dated:- 14.02.2024


Copy forwarded for information & necessary action.

- 1 The Engineer-in-Chief, HP:PWD, Shimla.
- 2 The Chief Engineer (HZ), HP:PWD, Hamirpur.
- 3 The Superintending Engineer, 8th Circle, HP:PWD Hamirpur.
- 4 All the Superintending Engineers/Executive Engineers in HP:PWD.
- 5 The Deputy Commissioner, Hamirpur(HP)
- 6 The Director, Information and Public Relations, Suchna Avam Jan Sampark Bhawan, HP Shimla-2.
- 7 The Tehsildar, Tauni Devi.
- 8 The B.D.O Tauni Devi.
- 9 The Municipal Committee, Hamirpur(HP)
- 10 All the Assistant Engineers working under this Division.
- 11 Account Branch/Drawing Branch/Notice Board.
- 12 Lok Mitra, Tauni Devi.
- 13 Various Contractors/ Firms.


Excutive Engineer
TauniDevDivision,
HPPWDTauniDevi.
On behalf Governor
of HP

CERTIFICATE

Certificate that the tender for JOB NO. 1 to 59 are called vide this office Letter NO. 20140-190 dated 14-02-2024 are an urgent nature and in public interest .


Excutive Engineer
TauniDevDivision,
HPPWDTauniDevi.

Schedule of Quantity

NAME OF WORK: C/O link road to the house of Jaisi Nam village Samu. (SIL: C/O 5/7mtr. Wide formation cutting from R.D. 0/065 to 0/144.40) (Deposit work).

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling (wedging out of rock (where blasting is prohibited) and other intermediate classification of soil sorting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1803.1, 1603.2 sorting out useful material and stacking the same in all heads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, canker, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and cartage of machines, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including cartage of material within all heads and lifts. (Recovery of useful stone i.e. 35.57/- cubic metre shall be made from the contractor @ Rs. 300/- (three hundred only per cubic metre) amounting to Rs. 10,671/- only	395.13			Per cubic metre	
	Total					

Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tamil Dev Division,
HPPWD, Tamil Dev

Schedule of Quantity

NAME OF WORK: C/O link road from Bharatpur to Dhar to Jangal Khad via Lamber Road (Km 0/00 to 3/525) (SH:- Preparation of Detailed Project Report), C/O link road from Gubher to Bahkar Khad via Village Lamber (Km 0/000 to 5/000) (SH:- Preparation of Detailed Project Report), C/O link road from Khairat to Bahkar Khad via Toun and Haban (Km 0/000 to Km 5/200), C/O link road from Puri to Jangal Khad via Barata Road (Km 0/000 to Km 2/500) & C/O Science Lab at Kakhar School. (SH:- Survey & Contour See Plan)

Estimated Cost:- Rs. 499255.00
Earnest Money:- Rs. 10000.00
Time:- Three Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Preparation of detailed project report and drawing complete including consultancy service for survey investigation etc. in manuscript form and submission of the same in higher office for approval. If any correction/amendment required by the higher office the same may be corrected to the satisfaction of Engineer-in-Charge complete in all project. After approval of the same should be submitted in five copies in fair manner completed in all respect as per direction of Engineer-in-Charge, including entire cartage of material within all heads and lifts and other incidentals. The rates are inclusive of cart, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	16.225			Per Km	
2	Soe survey using Total station/GPS and preparation of survey and contour plan at desired intervals. The survey will be carried out to show all boundary points compound walls, roads, trees, buildings, structures, stream, electric poles, telephone poles, and any other man-made structures within survey perimeter. Structures including supply of 3(three) sets of drawings along with a soft copy of entire survey work and approval of contour plan from higher authority as per direction of Engineer-in-Charge, including entire cartage of material within all heads and lifts and other incidentals. The rates are inclusive of cart, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	0.450			Per hectare	
Total						

Terms and Condition

1. Work shall be executed as per JMD specification.


Executive Engineer,
 Rural Devt Division,
 JMD, Tauni Dohy

Schedule of Quantity

NAME OF WORK: DPR for construction of Degree College Building at Tauni Devi, Distt. Hamirpur (HP) (Shr. Estimated Cost:- Rs.130990.00)									
Construction of building portion, water supply and sanitary installation, rain water harvesting tank, septic tank, site Earnest Money:- Rs.2600.00									
Sr. No.	Description of Items	Qty.	Time:-		Rate		Two Months		Amount
			In Fig.	In Words	In Words	In Words	Unit	Amount	
1.00	Preparation of detailed project report for construction of Degree College Building at Tauni Devi, complete including consultancy services etc. in manuscript form and submission of the same to higher offices for approval. If any correction/amendment required by the higher office the same may be corrected to the satisfaction of Engineer-in-Charge complete in all project. After approval of the same should be submitted in five copies in four manner completed in all respect as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of central, royalty, madhania, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00					Per job		
Total									

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HP PWD, Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain drains on Puthi Kujabath via Hana road km. 0/00 to 4/600, (Slt:- C/O wire crate at RD.
1/700 to 3/510 & 3/225 to 3/237.50 & 3/250 to 3/260).

NAME OF WORK:- Restoration of rain drainages on Puri to Kulabakh via Jhama road km. 0/00 to 4/600 (Silt, C/O wire crate at BD, 3/500 to 3/530 & 3/225 to 3/237.50 & 3/250 to 3/260).						
Sl.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Burrmed Money:- Time-	In Words		
1	Excavation work by mechanical means (Hydraulic excavator) manual means at foundation trenches or drains (not exceeding 1 Section point five meter) in width or 10 up to ten square meter on plan) including removal of slabs and existing of bottom, lift up to 1.5 m, (one point five meter) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a limit of 50 m (fifty meter) as per the direction of the Engineer-in-charge including cartage of material within all limits and its and other incidentals. The rates are inclusive of fuel, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	69.38			Per cubic metre	
2	Providing and laying laid in wire crates with term (four millimeter) dia G.I. wire conforming to IS:320 and IS:4325 in 100x100mm (one hundred and one hundred millimeter) mesh including ten percent extra for laps and joints laid with same boulders weighing not less than 25kg (twenty five kilograms) each as per drawing and technical specification clause 1301, as per the direction of the Engineer-in-charge including cartage of material within all limits and its and other incidentals. The rates are inclusive of fuel, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	148.44			Per cubic metre	
	Total					

Terms and Conditions
1. Work shall be executed as per FWD specifications.

Executive Engineer,
Tamil Nadu Drainage,
HPPWD, Tamil Nadu

A. S. Kumar

NAME OF WORK:- Restoration of rain damages on Thul to Bagdura via Jambhoni road km. 0/00 to 27/00. (SI - P/L patch work at RD. 17/015 to 22/00).

Schedule of Quantity

Sr No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Earnest Money:-	Rs. 480000.00		
				Time:-	Two Months		
1	Providing, laying and rolling of built up spray grid layer over prepared base consisting of a two layer composite construction of crushed coarse aggregates using motor grader for aggregates. Key stone chips spreader may be use with application of bituminous binder after each layer and with key aggregates placed on top of the second layer to serve as a base conforming to the line grades and cross section specified the compacted layer thickness being 75mm (seventy five millimeter) as per technical specification clause 505 as per the direction of the Engineer-in-Charge excluding entire carriage of material within all heads and its and other incidentals. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	534.00				Per cubic metre	
2	Repair to pot holes and removal of loose material, trimming of sides, clearing of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type II with VCI-10 (ten) as per MOPED specification clause 1904 2.503 and 506.1 including entire carriage of material within all heads and its and as per entire satisfaction and direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana toll tax, side tax, GST, labour cess or other taxes imposed by the Government.	811.10				Per square metre	
Total							

Terms and Condition

1. Work shall be executed as per PWD specification.
2. The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

Executive Engineer,
Tamil Nadu Division,
HPPWD, Tamil Nadu

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Uthai to Bingehera via Janakpur road km. 0/00 to 27/00. (SH- P/L patch work at RD. 9/00 to 16/00).

NAME OF WORK:- Restoration of rain damages on Udaal to Bagebura via Jandiroo road km. 6/00 to 27/00. (SH- P/L patch work at RD. 9/00 to 16/00).						
Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Earnest Money:- Time:-	Rs.9700.00 Two Months		
			In Fig.	In Words		
1	Providing, laying and rolling of built up spray grad layer over prepared base consisting of a two layer composite construction of crushed coarse aggregates using motor grader for aggregates. Key stone chips spreader may be use with application of bituminous binder after each layer and with key aggregates placed on top of the second layer to serve as a base conforming to five line grader and cross section specified the compacted layer thickness being 75mm (seventy five millimeter) as per technical specification clause 505 as per the direction of the Engineer-in-charge including entire cartage of material within all heads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Matkara,toll tax, GST or other taxes imposed by the Government.	530.00			Per cubic metre	
2	Repair to pot holes and removal of loose material, trimming of sides, clearing of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-10 (ten) as per MCRD specification clause 1904.2,503 and 506.1 including entire cartage of material within all heads and lifts and as per entire satisfaction and direction of Engineer-in-Charge. The rates are exclusive of octroi, royalty, Matkara, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	830.23			Per square metre	
					Total	

Terms and Condition

1. Work shall be executed as per PWD specification.
2. The billmen/ernulslon will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.


 Executive Engineer,
 Tandi Deval Division,
 HPPWD, Tandi Deval.

Schedule of Quantity

NAME OF WORK: Restoration of rain damages on Uhal to Bajepura via Jantwao road km. 0/00 to 27/00 (SH- R07D and Improvement of curves and grade at RD 16/870 to 16/945).

Estimated Cost:-	Rs. 403071.00
Earliest Money:-	Rs. 8100.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling (wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades with cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302, 1503.1, 1503.2 setting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or an approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling, fine dressing and carriage of machines materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. (Recovery of useful stone i.e. 175.45/- cubic metre shall be made from the contractor @ Rs. 300/- (three hundred only per cubic metre) amounting to Rs. 52,635/- only.	957.00			Per cubic meter	
	Total					

Terms and Condition

1. Work shall be executed as per PWD specifications.


 Executive Engineer,
 Tamsi Devi Division,
 HPPWD, Tamsi Dist.

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on (bail to Bagehra via Jandion road km. 0/00 to 27/00 (SH- ROFD and improvement of curves and grade at RD. 16/945 to 17/000).

Sr. No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Rate	In Words		
				Time:-	Earliest Money:-		
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling (wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1603.1, 1603.2, setting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling, fine dressing and carriage of machines materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. (Recovery of useful stone i.e. 170:180 cubic metre shall be made from the contractor @ Rs. 300/- (three hundred only per cubic metre) amounting to Rs. 51,054/- only.	928.27				Per cubic metre	
	Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Dev) Division,
 HPPWD: Tauni D

Schedule of Quantity

NAME OF WORK:- C/O Bink road from Thagbara bridge to Haritan East lot via Samoua Gombaka km 0/00 to 1/200 (SH: C/O C.C. government at B.O. 0/100 to 0/110) (under PPH/0557)

Sr. No.	Description of Items	Qty	In Fig.	Rate		Unit	Amount
				To	From		
1	Earth work in excavation by mechanical means (hydraulic excavator) manual means over angle (exceeding 30 cm (thirty centimetres) in depth, 1.5 metre (one metre) in width as well as 10 square metres (ten (10) sqm) including grading and disposal of excavated earth laid up to 50 m and at up to 1.5 m (one point five metres) as directed by Engineer in charge. All kinds of soil as per the direction of the Engineer-in-charge including extra carriage of material within all kinds and its and other accessories. The rates are inclusive of extra, mainly, labour, fuel tax, GST or other taxes imposed by the Government.	117.00				Per Cubic metre	
2	Stone using properly hand-packed filling materials with stable and consolidating with power road roller to the required gradient and border excluding spreading, watering and rilling of bedding material (maximum of seven up to concrete as per H.P.W.D. specification 100mm (one hundred millimetre) spread thickness) finished work including materials and labour as per direction of Engineer in Charge including extra carriage of material within all kinds and its and other accessories. The rates are inclusive of extra, mainly, labour, fuel tax, GST or other taxes imposed by the Government.	59.50				Per Cubic metre	
3	Providing and laying in position cement concrete of specified grade excluding the cost of carrying and unloading. All work up to finish level 1:1.5:3 (one cement : one part fine coarse sand : three graded stone aggregate 20 millimetre (twenty millimetre) nominal size) as per the direction of Engineer in Charge including extra carriage of material within all kinds and its and other accessories. The rates are inclusive of extra, mainly, labour, fuel tax, GST or other taxes imposed by the Government.	59.50				Per Cubic metre	
	Total						

1. Work shall be executed as per H.P.W.D. specification.

Executive Engineer,
Tafel Deri Division,
Bhujpur-2001 R.P.R.

Schedule of Quantity

NAME OF WORK:- C/O Bank road from Baghera bridge to Narayan Bhatta lot via Samowa Gumbha kum. 0/00 to 1/200 (SIR:- C/O PCC
solid cause way at B.O. 0/310 to 3/250) (Under SIMGCV).

Sl.No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount
				Estimated Cost- Earliest Measure- Time-	In Words		
1	Earth work in excavation by mechanical means (hydraulic excavator) for road work (excavating 20 cm (fully settled) in depth, 1.5 (one point five) metres) in width as well as 10 (ten) square metres) on plan including grading out and disposal of excavated earth load upto 50 m and 88 upto 1.5 m (one point five metres) as directed by Engineer-in- charge. All kinds of soil, as per the direction of the Engineer-in-charge including extra carriage of material within all loads and lifts and other incidents. The rates are inclusive of items, royalty, Mahatma lot tax, sale tax, good service tax or other taxes imposed by the Government.	73.20				Per Cubic metre	
2	Processing and laying in position cement concrete of specified grade including the cost of carrying and unloading. As work up to plain level 1:3:6 (one cement: three sand: six graded stone aggregate) 20cm (twenty millimetre) nominal size, as per the direction of the Engineer-in-charge including extra carriage of material within all loads and lifts and other incidents. The rates are inclusive of items, royalty, Mahatma lot tax, GST or other taxes imposed by the Government.	51.00				Per Cubic metre	
3	Processing and laying in position cement concrete of specified grade including the cost of carrying and unloading. As work up to plain level 1:4:6 (one cement: four sand: eight graded stone aggregate) 40mm (four millimetre) nominal size, as per the direction of the Engineer-in-charge including extra carriage of material within all loads and lifts and other incidents. The rates are inclusive of items, royalty, Mahatma lot tax, GST or other taxes imposed by the Government.	20.00				Per Cubic metre	
4	Processing and laying in position cement concrete of specified grade including the cost of carrying and unloading. As work up to plain level 1:1.5:3 (one cement: one point five coarse sand: three graded stone aggregate) 20 (twenty) millimetre nominal size, as per the direction of Engineer-in-charge including extra carriage of material within all loads and lifts and other incidents. The rates are inclusive of items, royalty, Mahatma lot tax, GST or other taxes imposed by the Government.	18.00				Per Cubic metre	
	Total						

Terms and Condition

1. Work shall be executed as per PWD specifications.


 Executive Engineer,
 Tandi Devi Division,
 UPWD, Tandi Devi.

Schedule of Quantity

NAME OF WORK:- C/O Balance work for the construction of Paly ground at Channayyan Taluk, Marangur Dist, Namdipuz (5th).
Reference formation cutting for the construction of paly ground at Channayyan Taluk (Bepud work).

Estimated Cost:- Rs. 499501.00
Estimated Money:- Rs. 10000.00
Time:- Two Months

Sr No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation inilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil consisting of ordinary soil, soft rocks, hard rocks, cherting, boulding, etc. of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grasses with cutting and burning of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302, 1503.1, 1503.2 setting out useful material and stacking the same in all kinds and lifts in required width of the road and transportation of useful material for filling in road ways, cutback, embankment for grade improvement and disposal of all useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machines materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and/or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all kinds and lifts. (Recovery of useful stone i.e. 199.83/cubic metre shall be made from the contractor @ Rs. 300/-/three hundred only per cubic metre) amounting to Rs.55,945/- only.	1427.35			Per cubic metre	
	Total					

Terms and Condition
 1. Work shall be executed as per PWD specifications.

A. J. N.
 Executive Engineer,
 Tamil Nadu Division,
 HPPWD, Tamil Nadu

NAME OF WORK: C/Pb bank road from Baranpore to Taint Dey via Chakur land 70 to 1,90,258/- P/L cement concrete pavement from RD-9/750 to 8/750 (Under OTMP).

Estimated Cost:	Rs. 44,52,200
Estimated Money:	Rs. 9300,00
Time:	Two Months

Sr.No.	Description of Items	Qty.	Units		Unit	Amount
			sq. Ft.	sq. Meters		
1	Excavation work by mechanical means (hydraulic excavator) manual means is hand-dug trenches for drains (not exceeding 1.5m/one post two meter) in width or 10 sqm (ten square meter or less) including stripping of soils and turning of topsoil, up to 1.5 m. (one post two meter) including piling out the excavated soil and disposal of surplus excavated soils as directed, within a limit of 50 m (fifty meter) as per the direction of the Engineer-in-charge including entire cartage of material within all limits and the and other incidental. The rates are inclusive of octroi, royalty, Malabar, kil tax, sale tax, good service tax or other taxes imposed by the Government.	40.00			Per Cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of surveying and plotting. All work up to path level (3.6 feet above three star) car graded above appropriate 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire cartage of material within all limits and the and other incidental. The rates are inclusive of octroi, royalty, Malabar, kil tax, sale tax, good service tax or other taxes imposed by the Government.	15.00			Per Cubic metre	
3	Rebar tying by hand pushed tongs as per direction of Engineer-in-charge, including entire cartage of material within all limits and the and other incidental. The rates are inclusive of octroi, royalty, Malabar, kil tax, sale tax, good service tax or other taxes imposed by the Government.	40.00			Per Cubic metre	
4	Providing and laying in position cement concrete of specified grade including the cost of surveying and plotting. All work up to path level 1.45 (one cement) four inch, eight graded above appropriate 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire cartage of material within all limits and the and other incidental. The rates are inclusive of octroi, royalty, Malabar, kil tax, GST or other taxes imposed by the Government.	24.30			Per Cubic metre	
5	Providing and laying in position cement concrete of specified grade including the cost of surveying and plotting. All work up to path level 1.5:3 (one cement) one inch four coarse sand. Four graded above appropriate 20 (twenty millimeters) nominal size) as per the direction of Engineer-in-charge including entire cartage of material within all limits and the and other incidental. The rates are inclusive of octroi, royalty, Malabar, kil tax, GST or other taxes imposed by the Government.	32.40			Per Cubic metre	
	Total					

1. Work shall be executed as per PWD specifications.

Executive Engineer,
Tamil Canal Division,
H.F.W.D., Tamil Nadu.

Schedule of Quantities

NAME OF WORK:- C/O High road from Basanthpur to Tamsal forest via Chaudhar Jambh/O/O to 1/100 (S/L: P/L cement concrete pavement from RD. 6/200 to 6/420) (Under O.T.M.W.)

No./Rev	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Estimate Number:-	Rs. 9300 00		
				Thane:-	Two Months		
1	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.50m wide) (in width or 10 sqm) (not square) (not including disposal of soil and material) (not including of bottom, at depth 1.5 m (one point five meter) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a limit of 50 m (fifty meter) as per the direction of the Engineer-in-charge including entire carriage of material within at least and its and other incidentals. The rates are inclusive of octroi, royalty, Mahanadi toll tax, salt tax, good service tax or other taxes imposed by the Government.	4800				Per Cubic metre	
2	Graveling and laying in position cement concrete of specified grade excluding the cost of carrying and shunting - At work up to depth level 1.35 (one cement three sand six graded stone aggregate 20mm (twenty millimeter) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within at least and its and other incidentals. The rates are inclusive of octroi, royalty, Mahanadi toll tax, salt tax, good service tax or other taxes imposed by the Government.	1550				Per Cubic metre	
3	Graveling and laying in position cement concrete of specified grade excluding the cost of carrying and shunting - At work up to depth level 1.45 (one cement four sand eight graded stone aggregate 20mm (twenty millimeter) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within at least and its and other incidentals. The rates are inclusive of octroi, royalty, Mahanadi toll tax, salt tax, good service tax or other taxes imposed by the Government.	4850				Per Cubic metre	
4	Graveling and laying in position cement concrete of specified grade excluding the cost of carrying and shunting - At work up to depth level 1.45 (one cement four sand eight graded stone aggregate 20mm (twenty millimeter) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within at least and its and other incidentals. The rates are inclusive of octroi, royalty, Mahanadi toll tax, salt tax, good service tax or other taxes imposed by the Government.	2430				Per Cubic metre	
5	Graveling and laying in position cement concrete of specified grade excluding the cost of carrying and shunting - At work up to depth level 1.50 (one cement five sand nine graded stone aggregate 20mm (twenty millimeter) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within at least and its and other incidentals. The rates are inclusive of octroi, royalty, Mahanadi toll tax, salt tax, good service tax or other taxes imposed by the Government.	5040				Per Cubic metre	
	Total						

Remarks and Condition
1. Work shall be executed as per PWD specifications.

Executive Engineer,
Tamsal Forest Division,
M.P.P.O., Tamsal Forest

Schedule of Quantities

NAME OF WORK:- C/O Link road from Busanapur to Tandal Dorel via Chahar bus 5/9 to 1/90 (S/E - 1/71, cement concrete pavement from RD. 6/770 to 6/790) (C/ndy CTMWP).

Sr. No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount
				Estimated Cost- Earliest Money- Time:-	In Words		
1	Excavation work by mechanical means (hydraulic excavator) manual means at foundation trenches or drains (not exceeding 1.50m) (not less than 1.5 m) (one point for trench including getting out the excavated soil and disposal of surplus excavated soil as directed, within a limit of 50 m, (by method) as per the direction of the Engineer-in-charge including entire cartage of material within all local and the other incidents. The rates are inclusive of octroi, royalty, Mahatma, toll tax, sale tax, good service tax or other taxes imposed by the Government.	45.85				Per Cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of conveying and shunting. At work up to plain level 1:3:6 (one cement, three sand, six graded stone aggregated 20mm (twenty millimetres) nominal size, as per the direction of the Engineer-in-charge including entire cartage of material within all local and the other incidents. The rates are inclusive of octroi, royalty, Mahatma, toll tax, sale tax, good service tax or other taxes imposed by the Government.	15.50				Per Cubic metre	
3	Reinforcing dry hard packed (fully as per direction of Engineer - in Charge, including entire cartage of material within all local and the other incidents. The rates are inclusive of octroi, royalty, Mahatma, toll tax, sale tax, good service tax or other taxes imposed by the Government.	45.50				Per Cubic metre	
4	Providing and laying in position cement concrete of specified grade including the cost of conveying and shunting. At work up to plain level 1:4:8 (one cement, four sand, eight graded stone aggregated 20mm (twenty millimetres) nominal size, as per the direction of the Engineer-in-charge including entire cartage of material within all local and the other incidents. The rates are inclusive of octroi, royalty, Mahatma, toll tax, sale tax, good service tax or other taxes imposed by the Government.	24.25				Per Cubic metre	
5	Providing and laying in position cement concrete of specified grade including the cost of conveying and shunting. At work up to plain level 1:1.5:3 (one cement, one sand, three graded stone aggregated 20 millimetres (twenty millimetres) nominal size) as per the direction of Engineer-in-charge including entire cartage of material within all local and the other incidents. The rates are inclusive of octroi, royalty, Mahatma, toll tax, sale tax, good service tax or other taxes imposed by the Government.	22.45				Per Cubic metre	
	Total						

1. Work shall be executed as per PWD specification.

Engineer Engineer,
Tandal Dorel Division,
BYPAD, Tandal Dorel

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on various road under Kakhar Sub-Division,(SH)- Hiring of JCB for removal of balance slips, dressing of berms, clearance of catch pits and drains etc.).

Estimated Cost:-	Rs. 429000.00
Earnest Money:-	Rs. 8600.00

Time:	Two Months
-------	------------

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Hiring of J.C.B. (front end loader 1 cum capacity with breaker) for widening of road, repair of berms, removal of slips and clearance of drains in all kinds of soil including breaking and chiselling with breaker of soft and hard rock as per direction of Engineer in charge. The JCB or breaker should be made available by the contractor as and when required even on Sunday and other holiday. JCB should be worked minimum 8.00 hours from 9.00AM to 5.00 PM daily and any loss to the public/private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the JCB owner which shall have fully compensated by the contractor in all cases. The log book will be maintained at site which should be duly verified by the Engineer-in-charge.	330.00			Per hour	
	Total					

Terms and Condition

1. The contractor shall be responsible for any kind of breakage in the machinery and accident happens during working hours.
2. Nothing shall be paid for idle hours
3. All wear and tear and POL charges are to be born by the contractor.

Executive Engineer,
Tamil Nadu Division,
Hydro Power Tamil Nadu

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Solapur Sandhole road in Km 0/00 to 23/00. (SH- Construction of Estimated Cost:- Rs.464263.00
PCC retaining wall & wire crate, breast wall in Km 13/105 to 13/120) Earnest Money:- Rs.9300.00
Two Months

Sr.No.	Description of Items	Qty.	In Fig.		In Words	Unit	Amount
1.00	Barthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of abutting and bracing, removal of stumps and other deleterious material and disposal upto a head of 50m(fifty meter) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire cartage of material within all leads, lifts and other incidents.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	61.20				Per cubic metre	
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire cartage of material within all leads and lifts and other incidents.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	47.40				Per cubic metre	
3.00	Backfilling Granular material behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3A (granular Material) as per the direction of Engineer-in-Charge including entire cartage of material within all leads and lifts and other incidents.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	19.20				Per cubic metre	
4.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 150mm (one hundred ten millimeter) dia PVC pipe De plate /Rivets/vents having pressure 4kg per sqm (four kilogram) per square metre extending through the full width of the structures with slopes of (1V) : 20(H)[twenty] towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per the direction of Engineer-in-Charge including entire cartage of material within all leads and lifts and other incidents.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	28.00				Each	

5.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10(cen) per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogram) each as per drawing and technical specifications Clause 1301as per drawing and technical specification clauses 614, 709, 1204.17 and as per the direction of Engineer-in-Charge including entire cartage of material within all loads and lifts and other incidents. The rates are inclusive of octroi, royalty, Malabar toll tax, GST or other taxes imposed by the Government.	78.13						Per cubic metre	
Total									

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauri Devi Division,
 HP PWD, Tauri Devi

NAME OF WORK	Quantity	Rate	Amount
Restoration of rain damages on Kaddur to Sorubul road in KM 0/00 to 8/500. (SH- Construction of Estimated Cost-			Rs.387226.00
PC-C breast wall & V-shape drain at RD 7/000 to 7/819)			Rs 7700.00
Earnest Money:			

NAME OF WORK	Quantity	Rate	Amount
Restoration of rain damages on Kaddur to Sorubul road in KM 0/00 to 8/500. (SH- Construction of Estimated Cost-			Rs.387226.00
PC-C breast wall & V-shape drain at RD 7/000 to 7/819)			Rs 7700.00
Earnest Money:			

Sr. No.	Description of Items	Qty.	Time:		Unit	Amount
			Rate			
			In Fig.	In Words		
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of sludge and other deleterious material and disposal upto a lead of 50m(fifty metro) dressing of sides and bottom and backfilling in trench with excavated suitable material, necessary soil upto 4m(four metro) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive of cart, royalty, Maharashtra toll tax, GST or other taxes imposed by the Government.	38.76			Per cubic metre	
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of cart, royalty, Maharashtra toll tax, GST or other taxes imposed by the Government.	73.53			Per cubic metre	
3.00	Providing wrap holes in brick/masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 100mm / one hundred millimetre) dia PVC pipe for plant /timber/vermin having pressure 4kg per sqm (four kilogram) per square meter extending through the full width of the structures with slopes of (1V): 2.0(H)(two to 1) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of cart, royalty, Maharashtra toll tax, GST or other taxes imposed by the Government.	45.00			Each	
6.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement : three coarse sand): six graded stone aggregate 40 mm (forty millimetre) nominal size) as per the direction of Engineer-in-Charge including all incidents. The rates are inclusive of cart, royalty, Maharashtra toll tax, GST or other taxes imposed by the Government.	11.61			Per cubic metre	
					Total	

3. Work shall be executed as per IPVD specification.

Executive Engineer,
Tamil Devl Division,
HPPWD, Tamil Devl

Schedule of Quantity

NAME OF WORK: Restoration of rain damages on Kabbur Sachchi road Km 0/00 to 8/500. (SH- Construction of Estimated Cost:- Rs.424110.00)
retaining wall in Km 7/500 to 7/815) **Earliest Money:-** Rs.8500.00
Time:- Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Earthwork in excavation for structures as per drawing and technical specifications (Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a load of 500/fifty metre) dressing of sides and bottoms and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-Charge of soil (including entire carriage of material within all leads, lifts and other incidents) The rates are inclusive of cart, royalty, Mahanadi toll tax, GST or other taxes imposed	30.24			Per cubic metre	
2.00	Providing and laying in position cement concrete of specified grade including the cost of cutting and shuttering 1:4:8 (one cement : four coarse sand : eight graded stone aggregate) 40mm (four millimetre) nominal size graded stone aggregate upto plinth level including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidents The rates are inclusive of cart, royalty, Mahanadi toll tax, side tax, GST or other taxes imposed by the Government	601.79			Per cubic metre	
3.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 100mm (one hundred millimetre) dia PVC pipe. The pipe /holes/ weep holes having pressure 4kg per sqm (four kilogram) per square meter extending through the full width of the structures with slopes of 1(V): 20(H)(twenty) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204, 3.7 as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents The rates are inclusive of cart, royalty, Mahanadi toll tax, GST or other taxes imposed by the Government	34.00			Each	
4.00	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.50m (one point fifty metre) transporting to site, spreading, grading to required slope and compacting to meet requirement with a load upto 1000lb (one thousand metre) as per technical specifications 301.5 within all the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents The rates are inclusive of cart, royalty, Mahanadi toll tax, GST or other taxes imposed by the Government	33.75			Per cubic metre	
	Total					

Terms and Condition

1. Work shall be executed as per FWD specification.


 Executive Engineer,
 Tauri Devi Division,
 HPPWD, Tauri Devi

250-10

Estimated Cost:	Rs.445248.00
Earnest Money:	Rs.8500.00
Time:-	Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of sludge and other deleterious material and disposal upto a total of 50m(five metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material (ordinary soil upto 3m(three metre) depth as directed by Engineer-in-Charge all kinds of soil including entire carriage of material within all loads, lifts and other incidents The rates are inclusive of oil, royalty, Maharashtra tax, GST or other taxes imposed by the Government.	56.00			Pcc cubic metre	
2.00	Providing and laying of boulder apron laid in seven courses with joints (four millimetre) dia 63 wire conforming to IS:280 and IS:4026 to 100mm x 100mm (one hundred millimetre then one hundred millimetre) mesh (woven diagonally) including 10(cen) per cent extra for laps and joints laid with stone boulders weighing not less than 75 kg (Twenty five Kilos per) each as per drawing and technical specifications Clause 130.1 as per drawing and technical specification clauses n.4, 709, 1204.3.7 and as per the direction of Engineer-in-Charge including entire carriage of material within all loads and lifts and other incidents The rates are inclusive of oil, royalty, Maharashtra tax, GST or other taxes imposed by the Government.	150.00			Pcc cubic metre	
	Total					

10/10/2014

Executive Engineer,
Tamil Devl Division
HPMD, Tamil Devl


Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Solanjpur Sandhole road in Km 3/00 to 10/00(MDR-30), (SH- Construction of wire crate in Km 3/080 to 3/090)(LHS)

Sr. No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Rate	Amount		
			In Fig.	In Words		
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material (ordinary soil upto 1m(three metre) depth as directed by Engineer-in-Charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive of fuel, royalty, Maharashtra tax, GST or other taxes imposed by the Government.	62.50			Per cubic metre	
2.00	Providing and laying of boulder apron laid in wire crans with 4mm (four millimetre) dia 51 wire conforming of IS-200 and IS-4026 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 100mm port cement extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogram) each as per drawing and technical specifications Clause 1301as per drawing and technical specification clauses 614, 709, 1204.3.7 and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of fuel, royalty, Maharashtra tax, GST or other taxes imposed by the Government.	150.33			Per cubic metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tamil Devi Division,
 HPPWD, Tamil Nadu

Schedule of Quantity

NAME OF WORK: Improvement of black spot on Uthul to Baghlera via Jandruo Km 0/00 to 27/00. (Sls:- Construction of Estimated Cost:- Rs.438615.00
retaining wall, crash barrier at RD 26/910 to 26/921) Earnest Money:- Rs.8800.00
 Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 105.1 including setting out, construction of shoring and bracing, removal of groups and other deleterious material and disposal upto a bed of 500(fifty metre) dressing of sides and bottoms and backfilling in trenches with excavated suitable material (retaining and upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all loads, lifts and other incidents. The rates are inclusive of net royalty, Mahaswami tax, GST or other taxes imposed by the Government.	46.20			Per cubic metre	
2.00	Excavation in bddy areas in all heights and depths and in all kinds of soil by manual/mechanical means for loading saturated soil comprising of ordinary soil, soft rocks, hard rocks, chipping /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades with cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at and according to the technical specification clause 102.1603.1.1603.2 setting out useful material and stacking the same in all loads and lifts in acquired width of the road and transportation of no-useful material for filling in road ways, canals, embankment for grade improvement and disposal of all no-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling, fine dressing and carriage of machines materials, tools, equipments and safety measures and incidents necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all loads and lifts (Recovery of useful stone i.e. 17.34 cubic metre shall be made from the contractor @ Rs. 300/- per cubic metre amounting to Rs 5202/- mpy).	121.05			Per cubic metre	
3.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1-4/8 (one Cement : four coarse sand : eight graded stone aggregate 40 mm(forty millimetre) nominal size) as per the direction of Engineer-in-Charge including entire carriage of material within all loads and lifts and other incidents. The rates are inclusive of net royalty, Mahaswami tax, GST or other taxes imposed by the Government.	70.86			Per cubic metre	
4.00	Providing weep holes in brick/masonry/ gully/ reinforced concrete abutment, wing walls, return walls, retaining walls with 100mm (one hundred millimetre) dia PVC pipe (the plates /brackets/sectors having pressure 1kg per sqm (four kilogram) per square meter extending through the full width of the structures with slopes of 1(V) : 2(H)(twenty) towards drawing face complete as per drawing and technical specification clauses 616, 709, 1204.2.7 as per the direction of Engineer-in-Charge including entire carriage of material within all loads and lifts and other incidents. The rates are inclusive of net royalty, Mahaswami tax, GST or other taxes imposed by the Government.	30.00			Each	

NAME OF WORK: A/R & M/G Subhanpur to Samthole road km. 0/00 to 23/00 (SR- C/O C.C. causeway at RD. 12/190 to 12/210).
(Deposit work).

Schedule of Quantity

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
				Estimated Cost:- [Amount Money:- Time:-	Rs. 115644.00 Rs. 2300.00 Two Months	
1	Excavation work by mechanical means (hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm in plan), including dressing of sides and ramming of bottoms, (in upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a head of 50 m.(fifty metre) (Ordinary rock) as per direction of Engineer-in-Charge including cartage of material within all heads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Mahasabai tax, GST or other taxes imposed by the Government.	30.00			Per Cubic metre	
2	Stone soling properly hand packed filling interstices with Khajuria stone and consolidating with power road roller to the required gradient and camber including spraying watering and rolling of bedding materials (mugum or earth etc. compute as per H.P.W.D. - specification 150mm/one hundred millimetre) spread thickness (finished work including materials and labour) in all beds and lifts and dressing of sides and bottom and as per the direction of Engineer-in-Charge including cartage of material within all heads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Mahasabai tax, GST or other taxes imposed by the Government.	14.85			Per Cubic metre	
3	Providing and laying in position cement concrete of specified grade excluding the cost of carting and unloading - All work up to grade level 1:1.5:3 (one cement, one part five coarse sand - three parts) stone aggregate 20 mm/maximum (nominal size) as per the direction of Engineer-in-Charge including cartage of material within all beds and lifts and other incidentals.	13.95			Per Cubic metre	
					Total	

Terms and Condition

1. Work shall be executed as per PWD specification.

A. S. D. H.
Executive Engineer,
Tahsil Devel Division,
H.P.W.D. Tamsal Dist.

Schedule of Quantity

NAME OF WORK:- C/O Dalwara to Dhawaga Brahminia km. 0/0 to 2/0/50.(5th- F/A. WRM at RD. 1/350 to 2/0/50)(under SCS).

Sr. No.	Description of Items	Qty.	In To	In Words	Estimated Cost	
					Estimated Money	Rs. 477639.00
					Time:-	Two Months
					Rate	Unit
2	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 60/75 mm) (dry three millimetre to zero point zero seven five millimetre) to wet mix macadam (WMM) specification including providing the material with water at CMC in for all beds & lbs, laying in uniform layers with mechanical paver/finisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonnes capacity to achieve the desired density, complete as per specifications and directions of Engineer in- Charge, including entire carriage of material within all beds and lbs and other roadworks.	224.17				Per cubic metre
Total						

Terms and Conditions

1. Work shall be executed as per PWD specification.



 Executive Engineer,
 Tamil Eelal Derssoo,
 HIRPWD, Tamil Nadu

Schedule of Quantity

NAME OF WORK:- C/Pathana to Bhangaoti Brahmanu km. 0/0 to 2/050 (SH- P/L G.S.R. at RD. 1/575 to 2/050) (Under SCSPT).

Sr.No.	Description of Items	Qty.	Estimated Cost:-		Rs. 490108.00	
			Earnest Money:-		Rs. 10000.00	
			Time:-	Rate	Two Months	Amount
			To	From	Total	
1	Construction of granular sub-base by providing dense graded Material conforming to specifications, making in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all loads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and drawings of Engineer-in-Charge including entire carriage of material with all loads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Madan, toll tax, GST or other taxes imposed by the Government.	250.61			Per cubic metre	
Total						

Terms and Conditions
1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tandi Dist Division,
 HRPWD, Tandi Dist.

NAME OF WORK:- C/O Indira Gandhi to Thiruv. via Debra km: 0/0 to 3/350 (Sh. C/O roller completed concrete pavement at NO. 0/045 to 0/120) (Under GCSF)

Schedule of Quantity

NAME OF WORK:- C/O Indrad Chakraborty to Tihar via Debra kpi: 0/0 to 3/350 (SR:- C/O roller compacted concrete pavement at NO. 0/045 to 0/120) (Under SCSP)

Sr No	Description of Items	Qty.	In Fig.	Estimated Cost:		Unit	Amount		
				Earned Money:-					
				Time:-	Rs. 10000.00				
				Rate					
1	Laying of the ground up to a level of 300mm (three hundred millimeters) below the sub-grade level, surface graded and compacted in layers to meet requirement of Table 300.1 and 300.2 for sub-grade construction as per technical specification clause 303.5.2 and as per direction of Engineer-in-Charge as per direction of Engineer-in-Charge, including entire carriage of material within all limits and other incidentals. The rates are inclusive of octroi, royalty, Mahatma, toll tax, sale tax, good service tax or other taxes imposed by the Government.	72.00				Per cubic metre			
2	Construction of granular sub-base by providing well graded material, mixing in a mechanical mix plant at CMU, carriage of mixed material to work site up to all limits and its spreading in uniform layers with motor grader in prepared surface and compacting with smooth wheel roller to achieve the desired density, complete as per technical specification clause 401 (Grading-1) as per the direction of the Engineer-in-Charge including entire carriage of material within all limits and other incidentals. The rates are inclusive of octroi, royalty, Mahatma, toll tax, sale tax, GST or other taxes imposed by the Government.	24.00				Per cubic metre			
3	Providing and laying in position cement concrete of specified grade including the cost of carrying and discharging : All work up to slab level 14.8 (one centimetre) four level, eight graded stone aggregated 40mm (four millimeters) nominal size, as per the direction of the Engineer-in-Charge including entire carriage of material within all limits and other incidentals. The rates are inclusive of octroi, royalty, Mahatma, toll tax, sale tax, GST or other taxes imposed by the Government.	24.00				Per cubic metre			
4	Construction of roller compacted concrete pavement (RCCP) with coarse and fine aggregate conforming to IS-383, the size of coarse aggregate not exceeding 20mm (twenty five millimeters) with minimum aggregate content ratio of 5:1 mm (five : one) millimeter and with minimum cement content of 310 kg (Three hundred ten kilograms) per cubic metre aggregate gradation to be as per Table 600.2 after blending, making in concrete mixer at optimum moisture content, transporting to site, laying with wheel barrows or steel pans or with mechanical paver, compacting with 40-100 kN smooth wheel, tandem vibratory roller, to achieve the designed flexural strength, finishing and curing as per drawings and technical specification clause 1502, as per direction of Engineer-in-Charge, including entire carriage of material within all limits and other incidentals. The rates are inclusive of octroi, royalty, Mahatma, toll tax, sale tax, GST or other taxes imposed by the Government.	48.00				Per cubic metre			

Terms and Condition
1. Work shall be executed as per (PWT) specifications.

Executive Engineer,
Traffic Dept Division,
Muzaffar Nagar District

NAME OF WORK: C/O link road Koderla to Chaudhara via Raj Ka Nahi km 0/0 to 2/700 (SR- P/A roller compacted concrete pavement) in 4/2/205 to 2/2/23 & 2/300 to 2/324.409 (Under OTM) Schedule of Quantity

Sr. No.	Description of Items	Estimated Cost:			
		Estimated Money:-		Rs. 202894.00	
		Time:-	Rate	Unit	Amount
1	Excavation work by mechanical means (Hydraulic excavator, manual means in foundation trenches or drains (not starting of bottom, at upto 1.5 m, (one point line mass) including dressing of sides and surplus excavated soil as directed, within a limit of 50 m (dry mass) as per the decision of the Engineer-in-Charge. Making soil tax, GST or other taxes imposed by the Government.	Qty	In Fig.	In Words	
2	Providing, laying, spreading and compacting graded stone aggregate (size large 50 mm to 0.075 mm) to wet mix macadam (WMM) specification including priming the surface with water at QAC, to be at least 8 cm, (laying in uniform layers with mechanical powerdriven roller / loose / loose course on well prepared surface and compacting with Engineer-in-Charge, including entire carriage of material within at least and the and other incidents. The rates are inclusive of material octroi, royalty, Makara tax, GST or other taxes imposed by the Government.	16.28			Per Cubic metre
3	Construction of roller compacted concrete pavement (RCCP) with coarse and fine aggregate conforming to IS 261, the size of coarse aggregate not exceeding 25mm (lessy the maximum) with maximum aggregate cement ratio of 0.5, the (fine / coarse) materials and with minimum cement content of 310 kg. (Three hundred ten kilograms) per cubic metre aggregate gradient to be as per table 602.2 after blending, mixing in concrete mixer at optimum moisture content, transporting to site, laying with wheel barrow or small pans or with mechanical power, compacting with (IS-100) 140 smooth wheel, tandem vibratory roller, to achieve the designed flexural strength, stripping and curing as per drawings and technical specification clause 1307, as per decision of Engineer-in-Charge, including entire carriage of material within at least and the and other incidents. The rates are inclusive of material octroi, royalty, Makara tax, GST or other taxes imposed by the Government.	40.26			Per Cubic metre
Total					

1. Work shall be executed as per PWV specifications

Terms and Conditions

Executive Engineer,
Tajpur Devl Division,
B.P.W.D., Tanis Dist.

NAME OF WORK: Restoration of rain damages on Ujir to Bahbar Khad via Tap road km. 0/0 to 4/0 (SB, C/O R/Wall at HD, 0/010 to 0/031).

Schedule of Quantity

Sr. No.	Description of Items	Qty.	In Fig.	Estimated Cost- Earliest Money- Time:		Unit	Amount
				Rate	In Words		
1	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation, structure or drain (not exceeding 1.5 metre from the surface) in width or 1/2 sqm, ten square metre (on plan), including dressing of sides and retreating of bottom, its depth 1.5 m, (one cubic metre) including getting out the excavated soil and disposal of surplus excavated soil in checked within a limit of 50 m (fig means) as per the direction of the Engineer in-charge including cartage of material within at least and the and other incidental. The rates are inclusive of fuel, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	39.48				Per Cubic metre	
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pillars, columns, piers, abutments, piers, piers, buttresses, slabs or heavy courses, parapets, coping, bed blocks, anchor blocks, (plan within 1/2 sqm, surface above etc. up to four any level, including the cost of levelling, settling and bedding, 1:5:10 (one concrete, the concrete sand) ten gradable stone aggregate 40 mm (fine) minimum nominal size) as per the direction of the Engineer in-charge including cartage of material within at least and the and other incidental. The rates are inclusive of fuel, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	57.41				Per Cubic metre	
3	Providing wing walls in foundation, masonry, pier, reinforced concrete abutment, wing walls, return walls, retaining walls and broad wall with 1/2 sqm (one hundred sqm minimum) 200 PCC (RCC) De-plastering works (one having pressure 5kg per sqm) square (five kilograms per centimeter square) technology through the full width of the structures with slopes of 1V: 20H) leaving a space three centimetres in per dressing and technical specifications clause 614, 705, 1204, 121 as per direction of Engineer in-charge including cartage of material within at least and the and other incidental. The rates are inclusive of fuel, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	34.00				Each	
	Total						

Terms and Condition
1. Work shall be executed as per PWD specification.

Executive Engineer,
Tapal Beel Division,
H.P.W.D. Yamuna Nagar

(Signature)

NAME OF WORK: Restoration of ratn damages on Uppur to Birkhar Khast via Tap road km. 0/0 to 4/0 (SH- C/0 R/Wall at RD. 1/070 to 1/082 and 2/120 to 2/132).

1. Work shall be executed as per PWD specifications

Executive Engineer,
Tamil Nadu Division,
Highways and Transport

Schedule of Quantity

NAME OF WORK: Restoration of rain damages on NOT to Muthan via Khasigram km. 0/0 to 3/900 (SRI: C/O U-shape drain at RD. 2/030 to 2/235)

Sr. No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount
				Estimated Cost- Earliest Month-> Time:-	In Words		
1	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m (one foot five inches) in width or 10 sqm (ten square metres on plan), including dressing of sides and rimming of bottoms, lift upto 1.5 m. (one foot five inches) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a band of 50 m (fifty metres) as per the direction of the Engineer-in-charge including entire carriage of material within all lands and its and other incidentals. The rates are inclusive octroi, royalty, Mahatma toll tax, GST or other taxes imposed by the Government.	120.55				Per Cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of carting and spreading - All work up to depth level 1:3:6 (one cement, three sand, six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all lands and its and other incidentals. The rates are inclusive octroi, royalty, Mahatma toll tax, GST or other taxes imposed by the Government.	92.55				Per Cubic metre	
Total							

Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tamil Nadu Division,
PWD, Tamil Nadu
[Signature]

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Garne Da Galu to Kuthera via Panyala km. 0/0 to 3/985 and link road Nit Mathan via Khasgram km. 0/0 to 3/900.(SH- Providing patch work).

NAME OF WORK:- Restoration of rain damages on Garne Da Gulu to Kuthera via Panyala km. 0/0 to 3/885 and link road Nit Mathan via Khasgram km. 0/0 to 3/900.(SH- Providing patch work).						
Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Earliest Money:-			
			Time:-	Two Months		
			In Fig.	In Words		
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm /fifty three millimeter to zero point zero seven five millimeter) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all beds & lifts, laying in uniform layers with mechanical paver/finisher in sub-bases / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge, including entire carriage of material within all beds and lifts and other incidentals.	11.31			Per cubic metre	
2	Repair to patch/pot holes (any depth) in connection with repairing including sweeping free from dust and mud, scoring surface in road, patches etc. cutting around edges to at least 25mm (twenty five millimeters) in depth and removal of loose material, trimming of sides, cleaning of surface and making good by providing back coat with emulsion bitumen @ 0.300kg/sqm. (zero point three zero zero kilogramme per square metre) and then providing 20mm (twenty millimeter) thick premix carpet using VG-10 bitumen @ 1.40kg/sqm (one point four six kilogramme per square metre) and seal coat type-B with VG-10 bitumen @ 0.68kg/sqm (zero point six eight kilogramme per square metre) as per technical specification clause 1904.2.503 and 508.2 as per the direction of the Engineer-in-charge including entire carriage of material within all beds and lifts and other incidentals.	1273.02			Per Square metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification,
2. The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.


 Executive Engineer,
 Tandi Devi Division,
 H.P.W.D. Tandi Dabai.

Schedule of Quantity

NAAMA for works - Restoration of rain drainages on Turk road (Hartzen) Phase II (Urban) (Bihar) in house of Mohinder Kumar km 0/0 to 0/700 (190). C/O current village government at RD 0/000 to 0/100 and 0/125 to 0/105. (Design work)

3. Work shall be executed as per PWD specification.

Executive Engineer,
Tamil Nadu Division,
HYDRO-TAMIL Nadu, Co.

NAME OF WORK: Restoration of rain damages on link road Chowki to Bahadur km. 0/00 to 1/1500 and link road Madhama Sadhana road km. 0/00 to 4/100 (5th P/L patch work).

Schedule of Quantity

NAME OF WORK: Restoration of rain damaged on link road Chouval to Bahad km. 9/50 to 1/750 and link road Nallama Suddana road km. 0/00 to 4/00 (SB, P/L patch work).									
Sr. No.	Description of Items	Qty.	In Pkg.	Estimated Cost:-		Unit	Amount		
				Earnest Money:-	Rs. 469133.00				
				Time:-	Rs. 9400.00				
				Rate		Two Months			
1	Construction of granular sub-base by providing well graded material, mixing in a mechanical mix plant at CMZ, carriage of mixed material to work site upto all loads and lifts, spreading in uniform layers with motor grader on prepared surface and compacting with smooth wheel roller to achieve the desired density, compacts as per technical specification clause 401 (Grading-1) as per the direction of the Engineer-in-charge including entire carriage of material within all loads and lifts and other incidental. The rates are inclusive octroi, royalty, Mahsana, toll tax, sale tax, GST or other taxes imposed by the Government.	15.74				Per cubic metre			
2	Repair to patch/pot holes (any depth) in connection with repairing excluding sweeping free from dust and mud, scoring surface in road, patches etc. cutting around edges to at least 25mm (twenty five millimeters) in depth and removal of loose material, blinding of holes, clearing of surface and making good by providing tack coat with emulsion bitumen @ 0.30kg/sqm. (zero point three zero kg per square metre) and then providing 25mm (twenty millimeter) thick premix carpet using VG-10 bitumen @ 1.65kg/sqm (one point four six kg per square metre) and seal coat type-B with VG-10 bitumen @ 0.65kg/sqm (zero point six eight kg per square metre) as per technical specification clause 1904.2.503 and 508.2 as per the direction of the Engineer-in-charge including entire carriage of material within all loads and lifts and other incidental.	1269.11				Per Square metre			
		Total							

Terms and Condition
1. Work shall be executed as per PWD specifications.

Executive Engineer,
Tamil Nadu Division,
Highways, Tamil Nadu


Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Baria Dhawal via Shivan Gahlot road km. 0/00 to 5/00, (SR:- P/L
Project No.: at RD. 4/410 to 4/435 and C/O R. Wall at RD. 4/405 to 4/430 A. 4/435 to 4/440).

Sl. No.	Description of Items	Qty.	Time:-		Six Months	Amount
			In Fig.	In Words		
1	Provision work for structural repairs (Hydraulic excavator, manual pump, in foundation, footing or down pipe according to design and the nature of the work) in order to 10 sqm per square meter on plan, including dressing of stone and masonry of brickwork, etc. 1:5 or 2:4 concrete (as per design) including setting out the excavation and disposal of surplus material (as per design) and the cost of the material, etc. as per the provision of the Engineer-in-Charge including extra carriage of material within all limits and the cost of the material, etc. as per the provision of the Engineer-in-Charge.	40.55			Per cubic meter	
2	Provision and laying of structural concrete and masonry work for foundation, footing or down pipe according to design and the nature of the work, including dressing of stone and masonry of brickwork, etc. 1:5 or 2:4 concrete (as per design) including setting out the excavation and disposal of surplus material (as per design) and the cost of the material, etc. as per the provision of the Engineer-in-Charge including extra carriage of material within all limits and the cost of the material, etc. as per the provision of the Engineer-in-Charge.	16.20			Per cubic meter	
3	Provision and laying of structural concrete and masonry work for foundation, footing or down pipe according to design and the nature of the work, including dressing of stone and masonry of brickwork, etc. 1:5 or 2:4 concrete (as per design) including setting out the excavation and disposal of surplus material (as per design) and the cost of the material, etc. as per the provision of the Engineer-in-Charge including extra carriage of material within all limits and the cost of the material, etc. as per the provision of the Engineer-in-Charge.	2.01			Per cubic meter	
4	Provision and laying of structural concrete and masonry work for foundation, footing or down pipe according to design and the nature of the work, including dressing of stone and masonry of brickwork, etc. 1:5 or 2:4 concrete (as per design) including setting out the excavation and disposal of surplus material (as per design) and the cost of the material, etc. as per the provision of the Engineer-in-Charge including extra carriage of material within all limits and the cost of the material, etc. as per the provision of the Engineer-in-Charge.	162.00			Per Square meter	
5	Provision and laying of structural concrete and masonry work for foundation, footing or down pipe according to design and the nature of the work, including dressing of stone and masonry of brickwork, etc. 1:5 or 2:4 concrete (as per design) including setting out the excavation and disposal of surplus material (as per design) and the cost of the material, etc. as per the provision of the Engineer-in-Charge including extra carriage of material within all limits and the cost of the material, etc. as per the provision of the Engineer-in-Charge.	23.05			Per cubic meter	
6	Provision and laying of structural concrete and masonry work for foundation, footing or down pipe according to design and the nature of the work, including dressing of stone and masonry of brickwork, etc. 1:5 or 2:4 concrete (as per design) including setting out the excavation and disposal of surplus material (as per design) and the cost of the material, etc. as per the provision of the Engineer-in-Charge including extra carriage of material within all limits and the cost of the material, etc. as per the provision of the Engineer-in-Charge.	15.00			Each	
Total						

1. Work shall be executed as per PWD specifications.

Executive Engineer,
 Tarnali Desai Division,
 HPPWD,
 Jaipur District

NAME OF WORK: Restoration of rain damages on Lalgawan to Tauni Devi road in Km 3/350 to 7/310. (SH- Providing and laying paver block at RD 6/850 to 6/495)

Schedule of Quantity

NAME OF WORK:- Restoration of sub damages on Lalgwan to Tandi Devi road in Km 3/350 to 7/310 (SR:- Providing Estimated Cost:- Rs.453092.00
and laying paver block at RTO 6/850 to 6/995) S.No. of QUANTITY

Sr. No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount		
				Earnest Money:-					
				Time:-	Rate				
				In Words					
1.00	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 (ten) square metre) on plan,including dressing of sides and raiming of bottom. Itt upto 1.5 m(one point five metre), including getting out the excavated soil and disposal of surplus excavated soil as directed, within all heads, (Ordinary rocks) per the direction of Engineer-in-Charge including entire carriage of material within all heads and lifts and other incidents. The rates are inclusive of net, royalty, Madhama, toll tax, GST or other taxes imposed by the Government.	50.62				Per cubic metre			
2.00	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm(two three millimetre) to 0.075 mm(one point zero seven five millimetre) to wet mix macadam (WMM) specification including premixing the material with water at 0.94% in for all heads & lifts, laying in uniform layers with mechanical power/finishes in sub base / base course on well prepared surface and compacting with vibratory roller of (eight) to (10) ton, touse (capacity to achieve desired density, complete as per technical specification clause 2023 direction of Engineer-in-Charge including entire carriage of material within all heads and lifts and other incidents. The rates are inclusive of net, royalty, Madhama, toll tax, GST or other taxes imposed by the Government.	20.25				Per cubic metre			
3.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering. All work up to plinth level L3/6 (one Comment: three concrete slab, six graded stone aggregate 40 mm (four millimetre) nominal size) as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of net, royalty, madhama, toll tax, side tax, GST or other taxes imposed by the Government.	23.62				Per cubic metre			
4.00	Providing and laying heavy duty precast cement concrete interlocking paver blocks, when compacted upto M:50 (M:40) grade including binder or kuth black, grey or coloured over sub base of concrete with 25mm (twenty millimetre) thick average thickness of cement 1:4 (one cement: four sand) laid over final jointed with neat cement slurry mixed with pigment of match the shade of blocks including curing, rubbing and polishing complete (and later concrete) floor to be paid for 80mm (eighty millimetre) thick later kerching blocks (NTC) and as per the direction of Engineer-in-Charge including entire carriage of material within all heads and lifts and other incidents. The rates are inclusive of net, royalty, Madhama, toll tax, GST or other taxes imposed by the Government.	193.50				Per square metre			
Terms and Condition									
1. Work shall be executed as per PWD specification.									
Total									

Executive Engineer,
Tauni Devi Division,
HPWD, Tauni

Schedule of Quantity

NAME OF WORK: A/R & M/O on various road under Taant Devi Division. (SH- Supply of stationary article etc for use in division office)

Estimated Cost:- Rs.141400.00
Earnest Money:- Rs.6800.00

Time:-

One Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Providing and supplying Daily Register complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or other taxes imposed by the Government.	30			Each	
2.00	Providing and supplying Dispatch Register complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or other taxes imposed by the Government.	30			Each	
3.00	Providing and supplying M.A.S. Register complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or other taxes imposed by the Government.	20			Each	
4.00	Providing and supplying Main Cash Book complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or other taxes imposed by the Government.	15			Each	
5.00	Providing and supplying T.A. Bill Book complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or other taxes imposed by the Government.	10			Each	
6.00	Providing and supplying M.R. Form Book complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or other taxes imposed by the Government.	10			Each	
7.00	Providing and supplying P.W.D. complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or other taxes imposed by the Government.	1000			Each	
8.00	Providing and supplying File Cover (Perman) complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or other taxes imposed by the Government.	1500			Each	
9.00	Providing and supplying File Cover (Ordinary) complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or other taxes imposed by the Government.	1000			Each	
10.00	Providing and supplying G.P. Withdrawal form complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or other taxes imposed by the Government.	10			Each	

11.00	Providing and supplying Tender Sale Register complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10				Each	
12.00	Providing and supplying Tenber Open Register complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10				Each	
13.00	Providing and supplying Deposit Register complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10				Each	
14.00	Providing and supplying Register for complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	0				Each	
15.00	Providing and supplying Work Abstract Pad complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	30				Each	
16.00	Providing and supplying Work Abstract Book complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1				Each	
Terms and Condition						Total	

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Town Devt Division,
 H.P.W.D. Jammu Div.

Schedule of Quantity

NAME OF WORK:- A/R & M/O on various road under Tamil Nadu Division : (SH- Supply of stationary article etc for use in division office)

Sr. No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Time:-	Rate		
		In Fig.	In Words			
1.00	Providing and supplying Income Tax Register complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or other taxes imposed by the Government.	5.00			Each	
2.00	Providing and supplying M/Roll Form complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or other taxes imposed by the Government.	300.00			Each	
3.00	Providing and supplying Log Book For Vehicle complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or other taxes imposed by the Government.	15.00			Each	
4.00	Providing and supplying Schedule Docket complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or other taxes imposed by the Government.	20.00			Each	
5.00	Providing and supplying P.M.G.S.V Quality Control Reg. (Part I & Part II) complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00			Each	
6.00	Providing and supplying P.M.G.S.V Running Account Bill Form complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or other taxes imposed by the Government.	1000.00			Each	
7.00	Providing and supplying P.M.G.S.V Hindrance Register complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00			Each	
8.00	Providing and supplying Cement Consumption Register complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00			Each	

4.00	Providing and supplying P.W.D.M. complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1000.00				Each	
10.00	Providing and supplying File Cover (Printed) complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1500.00				Each	
11.00	Providing and supplying Site Order Book complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00				Each	
12.00	Providing and supplying H.P.T.R.-5 complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00				Each	
13.00	Providing and supplying Transfer Entry Order Pad complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	20.00				Each	
14.00	Providing and supplying Running Account Bill Form complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1000.00				Each	
15.00	Providing and supplying Fuelled Register complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00				Each	
16.00	Providing and supplying T&P Register complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00				Each	
17.00	Providing and supplying Agreement Register complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00				Each	
18.00	Providing and supplying Contractor's Bill Register complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00				Each	
19.00	Providing and supplying Peon Book complete as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	30.00				Each	

20.00	Providing and supplying Attendance Register complete as per the direction of Engineer in-charge including all incidentals. The rates are inclusive of octroi, royalty, malisana, toll tax, sale tax, GST or other taxes imposed by the Government.	30.00					Each	
							Total	

Terms and Condition

1. Work shall be executed as per JWD specification.

Amol
Executive Engineer
TQDI Devt Division
H.P.W.D. Tauri De

Schedule of Quantity
NAME OF WORK:- Restoration of rain damages on Kothu Nauglu road km. 0/00 to 2/405 and Darkott Mohin road km
0/00 to 3/0 (SH:- Providing patch work).

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Baromet Money:-	Rs. 95.00.00		
				Time:-	Two Months		
Rate	In Words	Per cubic metre	Total				
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) 15thy three millimeter to zero point zero seven five millimeter) to wet mix macadam (WMM) specification including premixing the material with water at CMAC in for all beds & lbs. laying in uniform layers with mechanical paver/finisher in sub-base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge, including entire cartage of material within all beds and lifts and other incidentals.	8.46				Per cubic metre	
2	Repair to patch/pot holes (any depth) in connection with repairing including sweeping free from dust and mud, scoring soaked in road, patches etc, cutting around edges to at least 25mm (twenty five millimeters) in depth and removal of loose material, blinding of sides, cleaning of surface and making good by providing tack coat with emulsion bitumen @ 0.30kg/sqm (zero point three zero zero kilogramme per square metre) and then providing 20mm (twenty millimeter) thick premix carpet using VG 10 bitumen @ 1.46kg/sqm (one point four six kilogramme per square metre) and seal coat type-B with VG-10 bitumen @ 0.68kg/sqm (zero point six eight kilogramme per square metre) as per technical specification clause 1004.2.503 and 508.2 as per the direction of the Engineer-in-charge including entire cartage of material within all beds and lifts and other incidentals.	1327.17				Per Square metre	
	Total						

Terms and Condition

1. Work shall be executed as per PWD specification.

2. The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

A. J. C. N.
 Executive Engineer,
 Tauri Devi Division,
 Haryana, Tauri Devi

NAME OF WORK: Restoration of rain damages on Chai to Bakhkar Road via Purnali line 0/00 to 6/700 (S/L: C/O wire crates wall at B/L: 3/279 to 3/280 & 3/430 to 3/442).

Schedule of Quantity

Sl. No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Lowest Money:-	Time:-		
				In Words	Two Months		
1	Excavation work by mechanical means (hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.50 metre from line) in width or 10 sqm (ten square metre) on plan) including clearing of sides and leveling of bottom. (It upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a limit of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all lands and its and other incidentals. The rates are inclusive of cart, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	54.87				Per cubic metre	
2	Transporting and laying laid in wire crates with 4mm (four millimetre) dia G.I. wire conforming to IS:200 and IS: 4020 in 100x100x10 (ten hundred into one hundred millimetre) mesh including ten percent extra for loss and joints laid with loose lockers weighing not less than 25kg. (twenty five kilograms) each as per drawing and technical specification clause 1201, as per the direction of the Engineer-in-charge including entire carriage of material within all lands and its and other incidentals. The rates are inclusive of cart, royalty, Mahanadi tax, GST or other taxes imposed by the Government.	127.86				Per cubic metre	
Total							

Terms and Conditions:
1. Work shall be executed as per PWD specification.

Executive Engineer,
Tamil Nadu Division,
Hq. Tamil Nadu Div.
[Signature]

NAME OF WORK:- C/O high road from main road to Sidh Nag Mandir village Thane Tahir. (SI) - (ump Of grade and C/O R/Wall at RD. 9/150 to 0/150 25) (Depot work).

Schedule of Quantity

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Earning Money:-	Rs. 170472.00		
				Rate	Two Months		
1	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches for about 100 excavating upto 1.5 m, (100 post line more) including opening out the excavated soil and disposal of surplus excavated soil as directed within a limit of 50 m (only more) as per the direction of the Engineer-in-charge including entire carriage of material within all limits and its and other excelsides. The rates are inclusive of fuel, oil, labour, material etc. GST or other taxes imposed by the Government.	45.80				Per Cubic metre	
2	Providing and laying concrete concrete in masonry walls with (any thickness) including attached platform, columns, piers, abutments, pillars, posts, struts, buttresses, string or facing courses, parapets, coping, wall blocks, window blocks, gable windows, side flues, partition floor etc. up to four any level, including the cost of concrete, shuttering and binding. 1:5:10 (one cement, two coarse sand) for graded above appropriate 40 mm (10mm) minimum nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all limits and its and other excelsides. The rates are inclusive of fuel, oil, labour, material etc. GST or other taxes imposed by the Government.	37.15				Per Cubic metre	
3	Providing masonry in brickwork masonry (plain reinforced concrete abutment, wing walls, return walls, retaining walls and drains with 110mm) one hundred per centum by PCC (1:2:4) concrete. Do (including) work for having previous day per centum for masonry. (Four days per per centum square) including through the full width of the structure with slopes of 1 1/2 to 2 1/2 (four days) including four concrete as per drawing and technical specifications (clause 514, 710, 1204.3.1 as per direction of Engineer in - Charge, including entire carriage of material within all limits and its and other excelsides. The rates are inclusive of fuel, oil, labour, material etc. GST or other taxes imposed by the Government).	6.00				Per Cubic	
4	Back filling with granular material between abutments, wing walls, return walls and retaining walls concrete as per drawing and all limits and its and other excelsides as per direction of Engineer in - Charge, including entire carriage of material within all limits and its and other excelsides. The rates are inclusive of fuel, oil, labour, material etc. GST or other taxes imposed by the Government.	0.00				Per Cubic metre	
Total							

Terms and Conditions
1. Work shall be executed as per PWD specifications.

Executive Engineer,
Tamil Nadu Division,
Bhavani-Tamil Nadu
A. J. A. R.

Schedule of Quantity

NAME OF WORK:- C/O Link road from Bhadana to house of Sh. Shail Ram km. 0/0 to 0/075. (S.H.- F/C from km. 0/0 to 0/075)
(Deposit work).

Estimated Cost:-	Rs. 148481.00
Earnest Money:-	Rs. 3000.00
Time:-	Two Months

Sr No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation in hilly areas in all heights and depths, and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades with cutting and turning of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1603.1, 1603.2, sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its levelling fire dressing and carriage of machines materials, tools, equipments and safety measures and incidents necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. (Recovery of useful stone i.e. 48.62-cubic metre shall be made from the contractor @ Rs. 300/- (three hundred only per cubic metre) amounting to Rs. 14,588/- only.	429.00			Per cubic metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.

A. S. S. S.
Executive Engineer,
Tamil Devl Division,
HPPWD, Tamil Dept.

Schedule of Quantity

NAME OF WORK:- Restoration of rain drainages on link road Channiyana to village Channiyana km. 0/00 to 1/00 (SH- R.O.F.D. at RD. 0/240 to 0/390).

NAME OF WORK:- Restoration of rain damages on link road Channayana to village Channayana km. 0/00 to 1/00 (SH- R.O.F.D. at RD. 0/240 to 0/390).							Estimated Cost:-	
		Earnest Money:-		Rs. 344553.00				
		Time:-		Rs. 6900.00				
		Two Months						
Sr.No.	Description of Items	Qty.	Rate		Unit	Amount		
			In Fig.	In Words				
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades with cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302, 1603.1, 1603.2 setting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and cartage of machines materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including cartage of material within all leads and lifts. (Recovery of useful stone i.e. 114.24-cubic metre shall be made from the contractor @ Rs. 300/- (three hundred only per cubic metre) amounting to Rs. 34,263/- only.	918.00			Per cubic metre			
Total								

Terms and Condition

1. Work shall be executed as per FWD specification.


 Executive Engineer,
 Tamil Devl Division,
 HPPWD: Tamil D.A.

Schedule of Quantities

NAME OF WORK: Restoration of rain damages on link road bridge for Chauri via Chauri, 0/00 to 3/70, ESH: C/0 Breast wall at RD. 2/990 to 2/992.

Sr No	Description of Items	Qty	In Fig	Estimated Cost:-		Unit	Amount
				Earnest Money:-	Time:-		
1	Earth work in excavation by mechanical means (hydraulic excavator) manual means over areas (excavating 20 cm (only continuous) in depth, 1.5 metre post line meter) in wells as well as 50 sq/ft (square meter) on plan) including getting out and disposal of excavated earth and upto 50 m and 10 upto 1.5 m (one post line meter) as directed by Engineer-in-charge. All kinds of soil, as per the direction of the Engineer-in-charge including entire carriage of material within all limits and the and other incidentals. The rates are inclusive of octroi, royalty, Mahakura, toll tax, sale tax, good service tax or other taxes imposed by the Government.	1.92				Per Cubic metre	
2	Providing and laying cement concrete in retaining walls, abutment walls, walls (any thickness) including attached pillars, columns, piers, abutments, plans, galls, struts, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plan window sills, plans, sunken floor etc., up to floor line level, including the cost of carrying, unloading and loading 15 (1) (one course) (the coarse sand) in graded stone aggregate 40 mm (any minimum nominal size) as per the direction of the Engineer-in-charge including entire carriage of material within all limits and the and other incidentals. The rates are inclusive of octroi, royalty, Mahakura, toll tax, sale tax, good service tax or other taxes imposed by the Government.	80.04				Per Cubic metre	
3	Providing weep holes in brickwork masonry (plaster) masonry concrete abutment, wing walls, main walls, retaining walls and breast wall with 1 (one) inch diameter hole (minimum) at PVC pipe (the plasterwork) within pipe having pressure 2kg per square meter (the kilogram per square meter) extending through the full width of the structure with slope of (1/1) 200 (the drawing from complete as per drawing and technical specification (issued 6/14, 7/18, 12/04, 3/2 as per direction of Engineer-in-charge, including entire carriage of material within all limits and the and other incidentals. The rates are inclusive of octroi, royalty, Mahakura, toll tax, sale tax, good service tax or other taxes imposed by the Government.	24.00				Per inch	
4	Barling excavated earth in layers, breaking down, watering, rolling each layer with 1/2 horse roller, or wooden or steel rollers, and rolling every 50 and 100-foot layer with power roller of minimum 8 tonnes and crushing up, in embankments by hand, food tanks, marginal banks, and grade banks etc., lead upto 50m (the meter) and up to 1.5m (one post line meter) as per direction of Engineer-in-charge, including entire carriage of material within all limits and the and other incidentals. The rates are inclusive of octroi, royalty, Mahakura, toll tax, sale tax, good service tax or other taxes imposed by the Government.	144.00				Per cubic metre	
	Total						

Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tajpur Devt Division,
Tajpur, Jamnagar District.

10/10/2020

Schedule of Quantity

TABLE OF WORK:- Restoration of rain damages on Panchsagar Bhagwati Rice road line 0/100 to 7/120 (S.H.- C/O R/W all with wire under at R/W 3/700 to 3/800).

Schedule of Quantity						
BANK OF INDIA: Reconstruction of rain damaged on Parliament Bhagwati Rice road km. 0/100 to 77/120 (S.H. - C/O R/Wall with wire mesh at R/W 3/00 to 3/015).						
Sl. No.	Description of Items	Qty.	Rate		Estimated Cost:-	Rs. 391450.00
			In Fig.	In Words	Estimated Money:-	Rs. 7000.00
					Two Months	
1	Excavation work by mechanical means (hydraulic excavator) manual means in trenches trenching or drain line excavating 1 (one) part line meter) in width or 10 sqm (ten square meter on plan) including dressing of sides and leveling of bottom, at upto 1.5 m (one part line meter) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a load of 50 m (fifty meter) as per the direction of the Engineer in charge including extra carriage of material within all loads and the and other incidentals. The rates are inclusive of fuel, oil, tyres, lubricants, GST or other taxes imposed by the Government.	64.50			Per cubic meter	
2	Providing and laying laid in wire crates with 4mm (four millimeters) dia. GI wire conforming to IS 200 and IS 4824 in 100x100mm (ten hundred mm) mesh including the provision of extra for laps and joints laid with above loadings weighing not less than 25kg (twenty five kilograms) each as per drawing and technical specification clause 1301, as per the direction of the Engineer-in-charge including extra carriage of material within all loads and the and other incidentals. The rates are inclusive of fuel, oil, tyres, lubricants, GST or other taxes imposed by the Government.	127.50			Per cubic meter	
3	Back filling with granular material bedded statements, wog work, round work and masonry work conforming as per drawing and MORS technical specifications clause 1204.3 B as per direction of Engineer-in-Charge, including extra carriage of material within all loads and the and other incidentals. The rates are inclusive of fuel, oil, tyres, lubricants, GST or other taxes imposed by the Government.	12.45			Per cubic meter	
	Total					

Terms and Conditions
1. Work shall be executed as per PWD specification.

Approved by
Executive Engineer,
Tamil Nadu Division,
H.P.W.D. Tamil Nadu

Schedule of Quantity
NAME OF WORK: C/O High road from Sulampur to Chavut via Chavut bus, 0/8 to 3/8 (1st), 4/1, Interlocking concrete pavement at
 WD, 0/600 to 0/565, (Under OTMMP)

Sr No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
			Time			
1	Contractors installed road surface including deposit of stones, sand upto 20 m (20 m) and consolidation of the aggregate received from quarrying with power road roller of 8 to 10 tons capacity as per direction of Engineer in Charge excluding entire carriage of material within all loads and the and other incidentals. The rates are inclusive of all taxes, Mahanul tax, GST or other taxes imposed by the Government.	221.00			Per square meter	
2	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains first exceeding 1.5m (one point five meter) in width or 10 m (ten meter) in depth including opening of shales and starting of bottom, up to 1.5 m, (one point five meter) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a load of 50 m (fifty meter) as per the direction of the Engineer in-charge including entire carriage of material within all loads and the and other incidentals. The rates are inclusive of all taxes, Mahanul tax, GST or other taxes imposed by the Government.	20.20			Per cubic meter	
3	Providing and laying in position cement concrete of specified grade including the cost of cementing and shuttering - All work up to plinth level 1:3:5 (one cement three sand, six graded stone aggregate 20mm (twenty millimeter) nominal size, as per the direction of the Engineer in-charge including entire carriage of material within all loads and the and other incidentals. The rates are inclusive of all taxes, Mahanul tax, GST or other taxes imposed by the Government.	22.75			Per cubic meter	
4	Providing and laying in position cement concrete of specified grade including the cost of cementing and shuttering - All work up to plinth level 1:2:4 (one cement two coarse sand, four graded stone aggregate 20mm (twenty millimeter) nominal size, as per the direction of the Engineer in-charge including entire carriage of material within all loads and the and other incidentals. The rates are inclusive of all taxes, Mahanul tax, GST or other taxes imposed by the Government.	7.80			Per cubic meter	
5	Providing and laying heavy duty precast cement concrete embedding precast blocks when constructed upto 150mm (150 mm) grade including border or curb black grey or coloured over sub base of concrete with 25mm (twenty millimeter) thick average thickness of cement 1:4 (one cement four sand) laid over and patted with sand cement slurry raised with pigment to match the finish of blocks including curing, watering and polishing complete (the base material) has to be paid for during night (including) that time locking slabs of N.T.C. make or its equivalent BIS certified block and as per direction of the Engineer in-charge including entire carriage of material within all loads and the. The rates are inclusive of all taxes, Mahanul tax, GST or other taxes imposed by the Government.	227.50			Per square meter	
Total						

Terms and Conditions
 1. Work shall be executed as per PWD specifications.

Executive Engineer,
 Tandi Dist Division
 H.P.W.D. Tandi Dist

NAME OF WORK: Restoration of rain damages on Fasli Dulah Chattram road km. 0/00 to 8/00 (SB-C/O R/W) at RD 5/92.50 to 5/93.5.

Terms and Condition
1. Work shall be executed as per PWD specification.

Executive Engineer,
Tamil Nadu
Public Works Dept.

Schedule of Quantity

NAME OF WORK:- Restoration of rain drainages on Kalari Puthal Chattram road km. 0/00 to 8/00 (SI:- C/O R/Wall at RD. 5/920 to 5/925.50).

Estimated Cost:- Rs. 363122.00
 Estimated Money:- Rs. 7300.00
 Time:- Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (hydraulic excavator) manual means in backfilling, trenching, or filling not exceeding 1 (one) foot (one meter) in width or 10 (ten) feet (ten meters) in depth, including hauling of soil and removal of bottom, for depth 1.5 m, (five feet) two meters, including filling and the excavation and disposal of surplus excavated soil as directed, within a limit of 50 m (fifty meters) as per the direction of the Engineer-in-Charge including extra carriage of material within all limits and the and other incidentals. The rates are inclusive of fuel, oil, electricity, maintenance tax, GST or other taxes imposed by the Government.	15.04			Per Cubic metre	
2	Transporting and laying cement concrete in sections with, within walls, with long horizontal including attached platform, columns, piers, abutments, pillars, posts, arches, buttresses, string or facing corners, parapets, coping, bed blocks, anchor blocks, plain window sills, etc., within floor etc., up to 500 mm level, including the cost of casting, finishing and finishing 1:3:10 (one cement : two coarse sand : ten graded stone aggregate 40 mm (four millimeters) nominal size) as per the direction of the Engineer-in-Charge including extra carriage of material within all limits and the and other incidentals. The rates are inclusive of fuel, oil, electricity, maintenance tax, GST or other taxes imposed by the Government.	79.20			Per Cubic metre	
3	Forming and laying concrete in backfilling, trenching, or filling horizontal concrete abutment, wing walls, retaining walls and facing wall with 150mm (one hundred and fifty) mm P.V.C. pipe. De-plantations, within pipe laying pressure 40 kg per centimeter square, (four kilograms per centimeter square) extending through the full width of the structures with slopes of 1:1, 2:1, 3:1, 4:1, 5:1, 6:1, 7:1, 8:1, 9:1, 10:1, 11:1, 12:1, 13:1, 14:1, 15:1, 16:1, 17:1, 18:1, 19:1, 20:1, 21:1, 22:1, 23:1, 24:1, 25:1, 26:1, 27:1, 28:1, 29:1, 30:1, 31:1, 32:1, 33:1, 34:1, 35:1, 36:1, 37:1, 38:1, 39:1, 40:1, 41:1, 42:1, 43:1, 44:1, 45:1, 46:1, 47:1, 48:1, 49:1, 50:1, 51:1, 52:1, 53:1, 54:1, 55:1, 56:1, 57:1, 58:1, 59:1, 60:1, 61:1, 62:1, 63:1, 64:1, 65:1, 66:1, 67:1, 68:1, 69:1, 70:1, 71:1, 72:1, 73:1, 74:1, 75:1, 76:1, 77:1, 78:1, 79:1, 80:1, 81:1, 82:1, 83:1, 84:1, 85:1, 86:1, 87:1, 88:1, 89:1, 90:1, 91:1, 92:1, 93:1, 94:1, 95:1, 96:1, 97:1, 98:1, 99:1, 100:1, 101:1, 102:1, 103:1, 104:1, 105:1, 106:1, 107:1, 108:1, 109:1, 110:1, 111:1, 112:1, 113:1, 114:1, 115:1, 116:1, 117:1, 118:1, 119:1, 120:1, 121:1, 122:1, 123:1, 124:1, 125:1, 126:1, 127:1, 128:1, 129:1, 130:1, 131:1, 132:1, 133:1, 134:1, 135:1, 136:1, 137:1, 138:1, 139:1, 140:1, 141:1, 142:1, 143:1, 144:1, 145:1, 146:1, 147:1, 148:1, 149:1, 150:1, 151:1, 152:1, 153:1, 154:1, 155:1, 156:1, 157:1, 158:1, 159:1, 160:1, 161:1, 162:1, 163:1, 164:1, 165:1, 166:1, 167:1, 168:1, 169:1, 170:1, 171:1, 172:1, 173:1, 174:1, 175:1, 176:1, 177:1, 178:1, 179:1, 180:1, 181:1, 182:1, 183:1, 184:1, 185:1, 186:1, 187:1, 188:1, 189:1, 190:1, 191:1, 192:1, 193:1, 194:1, 195:1, 196:1, 197:1, 198:1, 199:1, 200:1, 201:1, 202:1, 203:1, 204:1, 205:1, 206:1, 207:1, 208:1, 209:1, 210:1, 211:1, 212:1, 213:1, 214:1, 215:1, 216:1, 217:1, 218:1, 219:1, 220:1, 221:1, 222:1, 223:1, 224:1, 225:1, 226:1, 227:1, 228:1, 229:1, 230:1, 231:1, 232:1, 233:1, 234:1, 235:1, 236:1, 237:1, 238:1, 239:1, 240:1, 241:1, 242:1, 243:1, 244:1, 245:1, 246:1, 247:1, 248:1, 249:1, 250:1, 251:1, 252:1, 253:1, 254:1, 255:1, 256:1, 257:1, 258:1, 259:1, 260:1, 261:1, 262:1, 263:1, 264:1, 265:1, 266:1, 267:1, 268:1, 269:1, 270:1, 271:1, 272:1, 273:1, 274:1, 275:1, 276:1, 277:1, 278:1, 279:1, 280:1, 281:1, 282:1, 283:1, 284:1, 285:1, 286:1, 287:1, 288:1, 289:1, 290:1, 291:1, 292:1, 293:1, 294:1, 295:1, 296:1, 297:1, 298:1, 299:1, 300:1, 301:1, 302:1, 303:1, 304:1, 305:1, 306:1, 307:1, 308:1, 309:1, 310:1, 311:1, 312:1, 313:1, 314:1, 315:1, 316:1, 317:1, 318:1, 319:1, 320:1, 321:1, 322:1, 323:1, 324:1, 325:1, 326:1, 327:1, 328:1, 329:1, 330:1, 331:1, 332:1, 333:1, 334:1, 335:1, 336:1, 337:1, 338:1, 339:1, 340:1, 341:1, 342:1, 343:1, 344:1, 345:1, 346:1, 347:1, 348:1, 349:1, 350:1, 351:1, 352:1, 353:1, 354:1, 355:1, 356:1, 357:1, 358:1, 359:1, 360:1, 361:1, 362:1, 363:1, 364:1, 365:1, 366:1, 367:1, 368:1, 369:1, 370:1, 371:1, 372:1, 373:1, 374:1, 375:1, 376:1, 377:1, 378:1, 379:1, 380:1, 381:1, 382:1, 383:1, 384:1, 385:1, 386:1, 387:1, 388:1, 389:1, 390:1, 391:1, 392:1, 393:1, 394:1, 395:1, 396:1, 397:1, 398:1, 399:1, 400:1, 401:1, 402:1, 403:1, 404:1, 405:1, 406:1, 407:1, 408:1, 409:1, 410:1, 411:1, 412:1, 413:1, 414:1, 415:1, 416:1, 417:1, 418:1, 419:1, 420:1, 421:1, 422:1, 423:1, 424:1, 425:1, 426:1, 427:1, 428:1, 429:1, 430:1, 431:1, 432:1, 433:1, 434:1, 435:1, 436:1, 437:1, 438:1, 439:1, 440:1, 441:1, 442:1, 443:1, 444:1, 445:1, 446:1, 447:1, 448:1, 449:1, 450:1, 451:1, 452:1, 453:1, 454:1, 455:1, 456:1, 457:1, 458:1, 459:1, 460:1, 461:1, 462:1, 463:1, 464:1, 465:1, 466:1, 467:1, 468:1, 469:1, 470:1, 471:1, 472:1, 473:1, 474:1, 475:1, 476:1, 477:1, 478:1, 479:1, 480:1, 481:1, 482:1, 483:1, 484:1, 485:1, 486:1, 487:1, 488:1, 489:1, 490:1, 491:1, 492:1, 493:1, 494:1, 495:1, 496:1, 497:1, 498:1, 499:1, 500:1, 501:1, 502:1, 503:1, 504:1, 505:1, 506:1, 507:1, 508:1, 509:1, 510:1, 511:1, 512:1, 513:1, 514:1, 515:1, 516:1, 517:1, 518:1, 519:1, 520:1, 521:1, 522:1, 523:1, 524:1, 525:1, 526:1, 527:1, 528:1, 529:1, 530:1, 531:1, 532:1, 533:1, 534:1, 535:1, 536:1, 537:1, 538:1, 539:1, 540:1, 541:1, 542:1, 543:1, 544:1, 545:1, 546:1, 547:1, 548:1, 549:1, 550:1, 551:1, 552:1, 553:1, 554:1, 555:1, 556:1, 557:1, 558:1, 559:1, 560:1, 561:1, 562:1, 563:1, 564:1, 565:1, 566:1, 567:1, 568:1, 569:1, 570:1, 571:1, 572:1, 573:1, 574:1, 575:1, 576:1, 577:1, 578:1, 579:1, 580:1, 581:1, 582:1, 583:1, 584:1, 585:1, 586:1, 587:1, 588:1, 589:1, 590:1, 591:1, 592:1, 593:1, 594:1, 595:1, 596:1, 597:1, 598:1, 599:1, 600:1, 601:1, 602:1, 603:1, 604:1, 605:1, 606:1, 607:1, 608:1, 609:1, 610:1, 611:1, 612:1, 613:1, 614:1, 615:1, 616:1, 617:1, 618:1, 619:1, 620:1, 621:1, 622:1, 623:1, 624:1, 625:1, 626:1, 627:1, 628:1, 629:1, 630:1, 631:1, 632:1, 633:1, 634:1, 635:1, 636:1, 637:1, 638:1, 639:1, 640:1, 641:1, 642:1, 643:1, 644:1, 645:1, 646:1, 647:1, 648:1, 649:1, 650:1, 651:1, 652:1, 653:1, 654:1, 655:1, 656:1, 657:1, 658:1, 659:1, 660:1, 661:1, 662:1, 663:1, 664:1, 665:1, 666:1, 667:1, 668:1, 669:1, 670:1, 671:1, 672:1, 673:1, 674:1, 675:1, 676:1, 677:1, 678:1, 679:1, 680:1, 681:1, 682:1, 683:1, 684:1, 685:1, 686:1, 687:1, 688:1, 689:1, 690:1, 691:1, 692:1, 693:1, 694:1, 695:1, 696:1, 697:1, 698:1, 699:1, 700:1, 701:1, 702:1, 703:1, 704:1, 705:1, 706:1, 707:1, 708:1, 709:1, 710:1, 711:1, 712:1, 713:1, 714:1, 715:1, 716:1, 717:1, 718:1, 719:1, 720:1, 721:1, 722:1, 723:1, 724:1, 725:1, 726:1, 727:1, 728:1, 729:1, 730:1, 731:1, 732:1, 733:1, 734:1, 735:1, 736:1, 737:1, 738:1, 739:1, 740:1, 741:1, 742:1, 743:1, 744:1, 745:1, 746:1, 747:1, 748:1, 749:1, 750:1, 751:1, 752:1, 753:1, 754:1, 755:1, 756:1, 757:1, 758:1, 759:1, 760:1, 761:1, 762:1, 763:1, 764:1, 765:1, 766:1, 767:1, 768:1, 769:1, 770:1, 771:1, 772:1, 773:1, 774:1, 775:1, 776:1, 777:1, 778:1, 779:1, 780:1, 781:1, 782:1, 783:1, 784:1, 785:1, 786:1, 787:1, 788:1, 789:1, 790:1, 791:1, 792:1, 793:1, 794:1, 795:1, 796:1, 797:1, 798:1, 799:1, 800:1, 801:1, 802:1, 803:1, 804:1, 805:1, 806:1, 807:1, 808:1, 809:1, 810:1, 811:1, 812:1, 813:1, 814:1, 815:1, 816:1, 817:1, 818:1, 819:1, 820:1, 821:1, 822:1, 823:1, 824:1, 825:1, 826:1, 827:1, 828:1, 829:1, 830:1, 831:1, 832:1, 833:1, 834:1, 835:1, 836:1, 837:1, 838:1, 839:1, 840:1, 841:1, 842:1, 843:1, 844:1, 845:1, 846:1, 847:1, 848:1, 849:1, 850:1, 851:1, 852:1, 853:1, 854:1, 855:1, 856:1, 857:1, 858:1, 859:1, 860:1, 861:1, 862:1, 863:1, 864:1, 865:1, 866:1, 867:1, 868:1, 869:1, 870:1, 871:1, 872:1, 873:1, 874:1, 875:1, 876:1, 877:1, 878:1, 879:1, 880:1, 881:1, 882:1, 883:1, 884:1, 885:1, 886:1, 887:1, 888:1, 889:1, 890:1, 891:1, 892:1, 893:1, 894:1, 895:1, 896:1, 897:1, 898:1, 899:1, 900:1, 901:1, 902:1, 903:1, 904:1, 905:1, 906:1, 907:1, 908:1, 909:1, 910:1, 911:1, 912:1, 913:1, 914:1, 915:1, 916:1, 917:1, 918:1, 919:1, 920:1, 921:1, 922:1, 923:1, 924:1, 925:1, 926:1, 927:1, 928:1, 929:1, 930:1, 931:1, 932:1, 933:1, 934:1, 935:1, 936:1, 937:1, 938:1, 939:1, 940:1, 941:1, 942:1, 943:1, 944:1, 945:1, 946:1, 947:1, 948:1, 949:1, 950:1, 951:1, 952:1, 953:1, 954:1, 955:1, 956:1, 957:1, 958:1, 959:1, 960:1, 961:1, 962:1, 963:1, 964:1, 965:1, 966:1, 967:1, 968:1, 969:1, 970:1, 971:1, 972:1, 973:1, 974:1, 975:1, 976:1, 977:1, 978:1, 979:1, 980:1, 981:1, 982:1, 983:1, 984:1, 985:1, 986:1, 987:1, 988:1, 989:1, 990:1, 991:1, 992:1, 993:1, 994:1, 995:1, 996:1, 997:1, 998:1, 999:1, 1000:1, 1001:1, 1002:1, 1003:1, 1004:1, 1005:1, 1006:1, 1007:1, 1008:1, 1009:1, 1010:1, 1011:1, 1012:1, 1013:1, 1014:1, 1015:1, 1016:1, 1017:1, 1018:1, 1019:1, 1020:1, 1021:1, 1022:1, 1023:1, 1024:1, 1025:1, 1026:1, 1027:1, 1028:1, 1029:1, 1030:1, 1031:1, 1032:1, 1033:1, 1034:1, 1035:1, 1036:1, 1037:1, 1038:1, 1039:1, 1040:1, 1041:1, 1042:1, 1043:1, 1044:1, 1045:1, 1046:1, 1047:1, 1048:1, 1049:1, 1050:1, 1051:1, 1052:1, 1053:1, 1054:1, 1055:1, 1056:1, 1057:1, 1058:1, 1059:1, 1060:1, 1061:1, 1062:1, 1063:1, 1064:1, 1065:1, 1066:1, 1067:1, 1068:1, 1069:1, 1070:1, 1071:1, 1072:1, 1073:1, 1074:1, 1075:1, 1076:1, 1077:1, 1078:1, 1079:1, 1080:1, 1081:1, 1082:1, 1083:1, 1084:1, 1085:1, 1086:1, 1087:1, 1088:1, 1089:1, 1090:1, 1091:1, 1092:1, 1093:1, 1094:1, 1095:1, 1096:1, 1097:1, 1098:1, 1099:1, 1100:1, 1101:1, 1102:1, 1103:1, 1104:1, 1105:1, 1106:1, 1107:1, 1108:1, 1109:1, 1110:1, 1111:1, 1112:1, 1113:1, 1114:1, 1115:1, 1116:1, 1117:1, 1118:1, 1119:1, 1120:1, 1121:1, 1122:1, 1123:1, 1124:1, 1125:1, 1126:1, 1127:1, 1128:1, 1129:1, 1130:1, 1131:1, 1132:1, 1133:1, 1134:1, 1135:1, 1136:1, 1137:1, 1138:1, 1139:1, 1140:1, 1141:1, 1142:1, 1143:1, 1144:1, 1145:1, 1146:1, 1147:1, 1148:1, 1149:1, 1150:1, 1151:1, 1152:1, 1153:1, 1154:1, 1155:1, 1156:1, 1157:1, 1158:1, 1159:1, 1160:1, 1161:1, 1162:1, 1163:1, 1164:1, 1165:1, 1166:1, 1167:1, 1168:1, 1169:1, 1170:1, 1171:1, 1172:1, 1173:1, 1174:1, 1175:1, 1176:1, 1177:1, 1178:1, 1179:1, 1180:1, 1181:1, 1182:1, 1183:1, 1184:1, 1185:1, 1186:1, 1187:1, 1188:1, 1189:1, 1190:1, 1191:1, 1192:1, 1193:1, 1194:1, 1195:1, 1196:1, 1197:1, 1198:1, 1199:1, 1200:1, 1201:1, 1202:1, 1203:1, 1204:1, 1205:1, 1206:1, 1207:1, 1208:1, 1209:1, 1210:1, 1211:1, 1212:1, 1213:1, 1214:1, 1215:1, 1216:1, 1217:1, 1218:1, 1219:1, 1220:1, 1221:1, 1222:1, 1223:1, 1224:1, 1225:1, 1226:1, 1227:1, 1228:1, 1229:1, 1230:1, 1231:1, 1232:1, 1233:1, 1234:1, 1235:1, 1236:1, 1237:1, 1238:1, 1239:1, 1240:1, 1241:1, 1242:1, 1243:1, 1244:1, 1245:1, 1246:1, 1247:1, 1248:1, 1249:1, 1250:1, 1251:1, 1252:1, 1253:1, 1254:1, 1255:1, 1256:1, 1257:1, 1258:1, 1259:1, 1260:1, 1261:1, 1262:1, 1263:1, 1264:1, 1265:1, 1266:1, 1267:1, 1268:1, 1269:1, 1270:1, 1271:1, 1272:1, 1273:1, 1274:1, 1275:1, 1276:1, 1277:1, 1278:1, 1279:1, 1280:1, 1281:1, 1282:1, 1283:1, 1284:1, 1285:1, 1286:1, 1287:1, 1288:1, 1289:1, 1290:1, 1291:1, 1292:1, 1293:1, 1294:1, 1295:1, 1296:1, 1297:1, 1298:1, 1299:1, 1300:1, 1301:1, 1302:1, 1303:1, 1304:1, 1305:1, 1306:1, 1307:1, 1308:1, 1309:1, 1310:1, 1311:1, 1312:1, 1313:1, 1314:1, 1315:1, 1316:1, 1317:1, 1318:1, 1319:1, 1320:1, 1321:1, 1322:1, 1323:1, 1324:1, 1325:1, 1326:1, 1327:1, 1328:1, 1329:1, 1330:1, 1331:1, 1332:1, 1333:1, 1334:1, 1335:1, 1336:1, 1337:1, 1338:1, 1339:1, 1340:1, 1341:1, 1342:1, 1343:1, 1344:1, 1345:1, 1346:1, 1347:1, 1348:1, 1349:1, 1350:1, 1351:1, 1352:1, 1353:1, 1354:1, 1355:1, 1356:1, 1357:1, 1358:1, 1359:1, 1360:1, 1361:1, 1362:1, 1363:1, 1364:1, 1365:1, 1366:1, 1367:1, 1368:1, 1369:1, 1370:1, 1371:1, 1372:1, 1373:1, 1374:1, 1375:1, 1376:1, 1377:1, 1378:1, 1379:1, 1380:1, 1381:1, 1382:1, 1383:1, 1384:1, 1385:1, 1386:1, 1387:1, 1388:1, 1389:1, 1390:1, 1391:1, 1392:1, 1393:1, 1394:1, 1395:1, 1396:1, 1397:1, 1398:1, 1399:1, 1400:1, 1401:1, 1402:1, 1403:1, 1404:1, 1405:1, 1406:1, 1407:1, 1408:1, 1409:1, 1410:1, 1411:1, 1412:1, 1413:1, 1414:1, 1415:1, 1416:1, 1417:1, 1418:1, 1419:1, 1420:1, 1421:1, 1422:1, 1423:1, 1424:1, 1425:1, 1426:1, 1427:1, 1428:1, 1429:1, 1430:1, 1431:1, 1432:1, 1433:1, 1434:1, 1435:1, 1436:1, 1437:1, 1438:1, 1439:1, 1440:1, 1441:1, 1442:1, 1443:1, 1444:1, 1445:1, 1446:1, 1447:1, 1448:1, 1449:1, 1450:1, 1451:1, 1452:1, 1453:1, 1454:1, 1455:1, 1456:1, 1457:1, 1458:1, 1459:1, 1460:1, 1461:1, 1462:1, 1463:1, 1464:1, 1465:1, 1466:1, 1467:1, 1468:1, 1469:1, 1470:1, 1471:1, 1472:1, 1473:1, 1474:1, 1475:1, 1476:1, 1477:1, 1478:1, 1479:1, 1480:1, 1481:1, 1482:1, 1483:1, 1484:1, 1485:1, 1486:1, 1487:1, 1488:1, 1489:1, 1490:1, 1491:1, 1492:1, 1493:1, 1494:1, 1495:1, 1496:1, 1497:1, 1498:1, 1499:1, 1500:1, 1501:1, 1502:1, 1503:1, 1504:1, 1505:1, 1506:1, 1507:1, 1508:1, 1509:1, 1510:1, 1511:1, 1512:1, 1513:1, 1514:1, 1515:1, 1516:1, 1517:1, 1518:1, 1519:1, 1520:1, 1521:1, 1522:1, 1523:1, 1524:1, 1525:1, 1526:1, 1527:1, 1528:1, 1529:1, 1530:1, 1531:1, 1532:1, 1533:1, 1534:1, 1535:1, 1536:1, 1537:1, 1538:1, 1539:1, 1540:1, 1541:1, 1542:1, 1543:1, 1544:1, 1545:1, 1546:1, 1547:1, 1548:1, 1549:1, 1550:1, 1551:1, 1552:1, 1553:1, 1554:1, 1555:1, 1556:1, 1557:1, 1558:1, 1559:1, 1560:1, 1561:1, 1562:1, 1563:1, 1564:1, 1565:1, 1566:1, 1567:1, 1568:1, 1569:1, 1570:1, 1571:1					

Schedule of Quantity

NAME OF WORK:- (i) A/R & M/O link road Bharmath Majhoga Kalasi km. 2/00 to 4/00 (ii) A/R & M/O link road Majhoga Gela to Sial km. 0/0 to 1/500 (iii) A/R & M/O link road Nakher Sauran km. 0/00 to 1/00 (SH- Repair of pot holes.).

NAME OF WORK:- (i) A/R & M/O link road Bharmath Maiphog Kailasi km. 2/00 to 4/00 (ii) A/R & M/O link road Maiphog Kaila to Sial km. 0/0 to 1/500 (iii) A/R & M/O link road Makher Sauran km. 0/00 to 1/00.(SHT- Repair of pot holes).						
Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Repair to patch/pot holes (any depth) in connection with repairing including sweeping free from dust and mud, securing sunkeda in road, patches etc. cutting around edges to at least 25mm (twenty five millimeters) in depth and removal of loose material, trimming of sides, clearing of surface and making good by providing tack coat with emulsion bitumen @ 0.30kg/sqm. (zero point three zero kilogram per square metre) and then providing 20mm (twenty millimeter) thick prunx carpet using VG-10 bitumen @ 1.40kg/sqm (one point four six kilogram per square metre) and seal coat type-B with VG-10 bitumen @ 0.68kg/sqm (zero point six eight kilogram per square metre) as per technical specification clause 1904.2.503 and 508.2 as per the direction of the Engineer-in-charge including entire carriage of material within all loads and fix and other incidentals.	1442.84			Per Square metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specifications.

2. The bill/extension will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

Executive Engineer,
Tauni Devi Division,
HPPWD, Tauni Devi

NAME OF WORK: A/R M/M/O link road - Hamirpur to Rupa km. 0/00 to 10/615.(5H):- Repair of pot holes at RD. 0/00 to 4/00).

Schedule of Quantity

Sr No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Earliest Money:-	Rate		
			Time:-	In Words		
1	Repair to patch/pot holes (any depth) in connection with repairing including sweeping free from dust and mud, scoring sunkeds in road, patches etc. cutting around edges to at least 25mm (twenty five millimeters) in depth and removal of loose material, trimming of sides, clearing of surface and making good by providing tack coat with emulsion bitumen @ 0.30kg/sqm. (zero point three zero zero kilogramme per square metre) and then providing 20mm (twenty millimeter) thick premix carpet using VG-10 bitumen @ 1.45kg/sqm (one point four six kilogramme per square metre) and seal coat (type-B with VG-10 bitumen @ 0.65kg/sqm (zero point six eight kilogramme per square metre) as per technical specification clause 1904.2.503 and 508.2 as per the direction of the Engineer-in-charge including entire carriage of material within all loads and its and other incidentals.	1449.24			Per Square metre	
Terms and Condition						
1. Work shall be executed as per PWD specification.						
2. The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.						
Total						

Executive Engineer:
Tamil Desai Division
HPPWD, Tamil Desai

Schedule of Quantity

NAME OF WORK: A/R & M/O link road Hamirpur to Ropa kun, 0/00 to 10/615, (Slt:- Repair of pot holes at RD. 4/00 to 10/615).

Estimated Cost:- Rs. 491459.00
 Earnest Money:- Rs. 10000.00
 Time:- Two Months

Sr No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Repair to patch/pot holes (any depth) in connection with repaving including sweeping free from dust and mud, scoring surface in road, patching etc. cutting around edges to at least 25mm (twenty five millimeters) in depth and removal of loose material, trimming of sides, clearing of surface and making good by providing tack coat with emulsion bitumen @ 0.300kg/sqm. (zero point three zero zero kilogramme per square metre) and then providing 20mm (twenty millimeter) thick premix carpet using VG-10 bitumen @ 1.45kg/sqm (one point four six kilogramme per square metre) and seal coat type-B with VG-10 bitumen @ 0.68kg/sqm (zero point six eight kilogramme per square metre) as per technical specification clause 1904.2.503 and 508.2 as per the direction of the Engineer-in-charge including entire carriage of material within all loads and its and other incidentals.	1424.52			Per Square metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.

2. The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

Am CCR
 Executive Engineer,
 Tarnai Devi Division,
 HPPPWD, Tarnai Devi

Schedule of Quantity

NAME OF WORK: C/O link road Kalluvu to Marthian East Naduvana Sathana km. 0/00 to 1/00 (5th P/L roller compacted concrete pavement from RD. 0/115 to 0/210). **(Under Survey MMSY)**

Sr No.	Description of Items	Qty.	Rate		Estimated Cost:	Rs. 4910750.00
			In Fig.	In Words	Earnest Money:	Rs. 90000.00
					Time:	Two Months
1	Construction of roller compacted concrete pavement (RCCP) with coarse and fine aggregates conforming to IS 383, Bag size of coarse aggregate not exceeding 25mm (Twenty five millimeters) with maximum aggregate percent ratio of 5.1 mm (five : one) minimum and with maximum content of 120 kg. (Three hundred fifty kilogram) per cubic metre aggregate gradation to be as per table 602.2 after blending, rising in concrete mixer at optimum moisture content, transporting to site, laying with wheel barrows or steel pans or with mechanical pans, compacting with 80-100 kN smooth wheel tandem vibratory roller, to achieve, the designed flexural strength, finishing and curing as per drawings and technical specification clause 1502, as per direction of Engineer in Charge, including entire carriage of material within all limits and this and other materials. The rates are inclusive of cart, royalty, labour, all tax, GST or other taxes imposed by the Government.	70.15				Per Cubic metre
Total						

Terms and Conditions
1. Work shall be executed as per PWD specifications.

A. S. Ravi
Executive Engineer,
Tamil Nadu District
MPPWD, Tamil Nadu

Schedule of Quantity

NAME OF WORK:- C/O link road Kakkra to Marrian West Madhava Sathana km. 0/00 to 1/00 (SH- 7/A roller compacted concrete pavement from RD. 0/00 to 0/115). (tender ~~2007~~ **2008-09**)

Schedule of Quantity						
NAME OF WORK:- C/A link road Kakra to Hartana Road Naalana Sadhana km. 0/00 to 1/00 (SH- P/L roller compacted concrete pavement from RD. 0/00 to 0/113). (Under SSP <i>minor</i> <i>SSY</i>)						
Sr.No.	Description of Items	Qty.	Rate		Estimated Cost:-	Rs. 491070.00
			In Fig.	In Words	Earnest Money:-	Rs. 9000.00
					Time:-	Two Months
1	Construction of roller compacted concrete pavement (RCCP) with coarse and fine aggregates conforming to IS-383, the size of coarse aggregate not exceeding 25mm (twenty five millimetre) with maximum aggregate content ratio of 5:1 (five : one) minimum and with minimum cement content of 350 kg. (Three hundred fifty kilograms) per cubic metre. Aggregate gradation to be as per table 602.2 after blending, mixing to concrete mixer at optimum moisture content, transporting to site, laying with wheel barrows or steel pans or with mechanical pans, compacting with 80-100 kN smooth wheel tandem vibratory roller to achieve, the designed bearing strength, finishing and curing as per drawings and technical specification clause 1502, as per direction of Engineer-in-Charge, including entire carriage of material within all loads and this and other accessories. The rates are inclusive of all, royalty, Mahasabai tax, GST or other taxes imposed by the Government.	70.15			Per Cubic metre	
					Total	

Terms and Condition
1. Work shall be executed as per PWD specification.

Executive Engineer,
Tamil Desai Division,
HPPWD, Tamil Desai


Schedule of Quantity

NAME OF WORK:- Construction of link road to village Sh. Panel Km 0/00 to 1/300 (SH:- Providing and laying wet mix macadam as correction layer at RD 0/050 to 0/500, Construction of breast wall at RD 0/610 to 0/650 and parapets from RD 0/00 to 1/300) **under contract M.M.Q.S.Y.**

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Providing - laying, spreading and compacting graded stone aggregates in wet mix macadam specification including providing the material with water at 0.4M in mechanical mixer (Pug Mill), carriage of mixed material by lorry to site, laying in uniform layers in sub base/base course on a well prepared sub base and compacting with smooth wheel roller of 80-100 KN weight to achieve the desired density including lighting, barricading and maintenance of diversion etc as per Tables 400.11 & 400.12 and technical specification clause 406 and as per direction of Engineer in charge including entire carriage of material within all leads and lifts and other incidents.	85.05			Per cubic metre	
2.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive of net, royalty, Mahasana tax, GST or other taxes imposed by the Government.	37.20			Per cubic metre	
3.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement : four coarse sand : eight graded stone aggregate 40 mm(dirty millimetre) nominal size) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of net, royalty, Mahasana tax, GST or other taxes imposed by the Government.	61.07			Per cubic metre	
4.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimetre) dia PVC pipe. The pipes /timber/sectors having pressure 4kg per sqm (four kilogram) per square meter extending through the full width of the structures with slopes of (1V: 20H)(twenty) towards drawing face complete as per drawing and technical specifications clauses 61.6, 70.9, 120.3.7 as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of net, royalty, Mahasana tax, GST or other taxes imposed by the Government.	24.60			Each	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devl Division,
 H.P.W.D. Tauni Devl

Schedule of Quantity

NAMH OF WORK: Construction of link road from Village Kangri to (Shay) Khalapur in Km 0/0 to 0/765. (SH-1)
 Construction of breast wall, D/Shape drains and paver block at RD 0/508 to 0/536 (Under OTMSP)

Sr. No.	Description of Items	Qty.	Time:-		Two Months Unit	Amount
			In Fig.	Rate In Words		
1.00	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.50/one point five metre) in width or 10 (ten) square metre) on (plan) including dressing of sides with running of bottoms, for upto 1.5 (one point five metre), including putting out the excavated soil and disposal of surplus excavated soils as directed, within all limits (Ordinary rock) as per the direction of Engineer-in-Charge including entire cartage of material within all limits and lifts and other incidents. The rates are inclusive of petrol, royalty, Mahasaul tax, GST or other taxes imposed by the Government.	27.16			Per cubic metre	
2.00	Providing, laying, spreading and compacting graded stone aggregate (same range S3 mm/fifty three millimetre) to 0.075 mm/gross joint area seven (five millimetre) to wet mix macadam (WMM) specification including premixing the material with water at CMCC or for all beds & lifts, laying in uniform layers with mechanical power/rollers (10 sub-base / base course on well prepared surface and compacting with vibratory roller of (height) to 10 (ten) tonnes capacity to achieve the desired density, complete as per technical specifications clause 302.3 direction of Engineer-in-Charge including entire cartage of material within all limits and lifts and other incidents. The rates are inclusive of petrol, royalty, Mahasaul tax, GST or other taxes imposed by the Government.	12.04			Per cubic metre	
3.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : three coarse sand: six graded stone aggregate 40 mm (forty millimetre) nominal size) as per the direction of Engineer-in-Charge including all incidents. The rates are inclusive of petrol, royalty, mahasaul tax, sale tax, GST or other taxes imposed by the Government.	53.90			Per cubic metre	
4.00	Providing and laying heavy duty precast cement concrete interlocking paver blocks where compacted upto M-50 (M-fifty) grade including binder or burnt brick grey or coloured over sub base of concrete with 25mm (twenty millimetre) thick average thickness of cement 1:4 (one cement: four sand) laid (over and jointed with neat cement slurry mixed with pigment or match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 10mm (ten millimetre) thick interlocking blocks (ITC) and as per the direction of Engineer-in-Charge including entire cartage of material within all limits and lifts and other incidents. The rates are inclusive of petrol, royalty, Mahasaul tax, GST or other taxes imposed by the Government.	120.40			Per Square metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Town Dev. Division,
 HPPWD, Jammu City

Schedule of Quantity


NAME OF WORK:- Restoration of rain damages on Ural to Bagehira via landroo road km. 0/00 to 27/00 (5th Imp. Of curves & ROAD, At RD. 11/945 to 12/075).

NAME OF WORK:- Restoration of rain damages on Uhal to Baghetra via Jandree road km. 0/00 to 27/00 (SH- Imp. Of curves & ROFD. At RD. 11/945 to 12/075).

Sr.No.	Description of Items	Qty.	Estimated Cost:-		Rs. 480682.00	
			Earnest Money:-		Rs. 9600.00	
			Time:-		Two Months	
			Rate	In Words	Unit	Amount
1	Excavation in bity areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /knocking out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades with cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1603.1,1603.2 sorting out useful material and stacking the same in all loads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its twining fine dressing and cartage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including cartage of material within all loads and lifts.(Recovery of useful stone i.e.267.12-cubic metre shall be made from the contractor @ Rs. 300/- (three hundred only per cubic metre) amounting to Rs.80,136/- only.	1335.00			Per cubic metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


Executive Engineer,
Tandi Devi Division,
Hyderabad Tandi Rd.

NAME OF WORK: Restoration of rain damages on Ural to Bagehra via Jandiro road km. 0/00 to 27/00 (SH- Imp. Of curves & HOPTD. At RD. 17/705 to 17/810).

Schedule of Quantity

Sr.No.		Description of Items	Qty.	Rate		Unit	Amount
				In Fig.	In Words		
1		Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1603.1,1603.2 setting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, cutback, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling fine dressing and cartage of machines materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including cartage of material within all leads and lifts. (Recovery of useful stone i.e. 249.42-cubic metre shall be made from the contractor @ Rs. 300/- (three hundred only per cubic metre) amounting to Rs. 74,826/- only.	1247.11			Per cubic metre	
Total							

Work shall be executed as per the

HO/PD, M/ RD, 17/705 to 17/810).

of works, restoration of rain damages on Ural to Bagelbra via Jandiroo road km. 0/00 to 27/00 (SH- Imp. Of curves &

Estimated Cost:-

Rs. 448835.00

Earliest Money:-

Rs. 9000.00

Time:-

Two Months

Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tamil Nadu Division,
PWD, Tamil Nadu.

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Tandi Devi Uthai Kakhar Bajrol Jungle belt km. 0/0 to 30/915. (SIH- P/L patch work at RD. 7/300 to 8/500).

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Earliest Money:-	Time:-		
				Rate	In Words		
1	Providing, laying and rolling of built up spray grout layer over prepared base consisting of a two layer composite construction of crushed coarse aggregates using motor grader for aggregates. Key stone chips spreader may be use with application of bituminous binder after each layer and with key aggregates placed on top of the second layer to serve as a base conforming to the fine grades and cross section specified the compacted layer thickness being 75mm (seventy five millimeter) as per technical specification clause 505 as per the direction of the Engineer-in-Charge including entire cartage of material within all loads and its and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	106.75				Per cubic metre	
2	Repair to pot holes and removal of loose material, trimming of sides, clearing of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-10 (ten) as per MORD specification clause 1904.2.503 and 508.1 including entire cartage of material within all loads and lifts and as per entire satisfaction and direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST, labour cost or other taxes imposed by the Government.	1319.40				Per square metre	
Total							

Terms and Condition

1. Work shall be executed as per PWD specification.
2. The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

Executive Engineer,
Tandi Devi Division,
HPPWD, Tandi Devi

Schedule of Quantity

NAME OF WORK: Restoration of rain damages on Tamsil Devi Ethal Kalkar Rajrol Jangle bent from 0/0 to 30/915. (SH:- P/L patch work at RD, 10/00 to 12/00).

Estimated Cost:- Rs. 49,4199.00

Estimated Money:- Rs.9900.00


Time:- Two Months

Sr. No.	Description of Items	Qty.	Time:-		Two Months	
			Rate	In Words	Unit	Amount
1	Providing, laying and rolling of built up spray grout layer over prepared base consisting of a two layer composite construction of crushed coarse aggregates using motor gradie for aggregates. Key stone chips spreader may be use with application of bituminous binder after each layer and with key aggregates placed on top of the second layer to serve as a base conforming to the line grades and cross section specified the compacted layer thickness being 75mm (seventy five millimeter) as per technical specification clause 505 as per the direction of the Engineer-in-charge including entire carriage of material within all loads and its and other incidentals. The rates are inclusive octroi, royalty, Mahanulot tax, GST or other taxes imposed by the Government.	102.12			Per cubic metre	
2	Repair to pot holes and removal of loose material, trimming of sides, clearing of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-10 (ten) as per MORD specification clause 1904.2.503 and 508.1 including entire carriage of material within all loads and its and as per entire satisfaction and direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Mahanulot tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1322.33			Per square metre	
Totals and Condition					Total	

Terms and Condition

1. Work shall be executed as per PWD specification.

2. The bid/contract/consent will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.



Executive Engineer,
 Tamsil Devi Division,
 HPPWD- Tamsil Devi

Schedule of Quantity

NAME OF WORK: Restoration of rain damages on link road from to Garbholi via Badvana road Km 0/00 to 2/700. (SH- Construction of R/wall at RD 0/211.25 to 0/217.25)

Construction of R/W/Seal at RD 0/21.1.25 to 0/21.7.25)									
Sr. No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount			
			Earnest Money:-						
			Rs.8800.00	Two Months					
		In Fig.	Rate	In Words					
1.00	Earthwork in excavation for structure as per drawing and technical specifications: Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other obstructions material and disposal upon a haul of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all loads, lifts and other incidents. The rates are inclusive of cart, royalty, Mahanazoli tax, GST or other taxes imposed by the Government.	20.92			Per cubic metre				
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand; ten graded stone aggregate 40 mm(forty millimetre) nominal size) as per the direction of Engineer-in-Charge including entire carriage of material within all loads and lifts and other incidents. The rates are inclusive of cart, royalty, Mahanazoli tax, GST or other taxes imposed by the Government.	102.24			Per cubic metre				
3.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 100mm (one hundred millimetre) dia PVC pipe the plaster /mosaic/verres having pressure 4kg per sqm (four kilogram) per square meter extending through the full width of the structures with slopes of (1V): 20(H)(twenty) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.1.7 as per the direction of Engineer-in-Charge including entire carriage of material within all loads and lifts and other incidents. The rates are inclusive of cart, royalty, Mahanazoli tax, GST or other taxes imposed by the Government.	17.80			Each				
Terms and Condition		Total							

Terms and Condition
1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tappu Dev Division,
 H.P.W.D. Taun Dab

श्रीगंगाराम

Schedule of Quantity

NAME OF WORK: Restoration of rain & Kalokhar Bahal Swahal road km 0/00 to 3/00. (Sft. Construction of breast wall at RD 2/785 to 2/797)

Sr. No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			In Fig.	In Words		
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of sheeting and bracing, removal of dumps and other obstructions, material and disposal upto a head of 50m (50 metre) dressing of sides and bottom and backfilling in trucks with excavated suitable material (ordinary soil upto 3m (three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all heads, lifts and other incidents. The rates are inclusive of cart, royalty, Mahasaul tax, GST or other taxes imposed by the Government.	12.48			Per cubic metre	
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering. All work up to plinth level 1:5:10 (one centimetre five coarse sand) ten graded stone aggregate 40 mm (forty millimetre) nominal size for the direction of Engineer-in-Charge including entire carriage of material within all heads and lifts and other incidents. The rates are inclusive of cart, royalty, Mahasaul tax, GST or other taxes imposed by the Government.	22.72			Per cubic metre	
3.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 100mm (one hundred millimetre) dia PVC pipe. The plain/finishes/sectors having pressure 4kg per sqm (four kilogram) per square meter extending through the full width of the structures with slopes of (1V): 20(H) (twenty) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.1.7 as per the direction of Engineer-in-Charge including entire carriage of material within all heads and lifts and other incidents. The rates are inclusive of cart, royalty, Mahasaul tax, GST or other taxes imposed by the Government.	19.00			Each	
	Total					

Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tauri Devi Division,
HP PWD - Jammu Division