




Office of  
Executive Engineer Baijnath Division HP.PWD, Baijnath  
Himachal Pradesh Public works Department Baijnath-176125  
Phone No. 01894-263035 Fax 262704 e-mail:- [ee-baij-hp@nic.in](mailto:ee-baij-hp@nic.in)

## CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS, AS  
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2023-24/-  
2215-2265 DATED 28-06-2024 ARE URGENT NATURE  
AND PUBLIC INTEREST.

  
Executive Engineer,  
Baijnath Division,  
HP.PWD, Baijnath.



**Office of**  
**Executive Engineer Baijnath Division HP.PWD, Baijnath**  
**Himachal Pradesh Public works Department Baijnath-176125**  
**Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in**

**"NOTICE INVITING TENDER"**

Sealed item rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before 11.07.2024 up to 11.30 A.M and will be opened on the same day at 12.00 Noon in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on 10.07.2024 between 2.00 PM up to 4.30 P.M and the application for issue of tender forms shall be received on 09.07.2024 up to 12.00 Noon.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	R/D on Various roads under Bir Sub-Division Deol Section (SH: Hiring of Hydraulic Excavator) (JCB)	Rs.4,95,000/-	Rs.10,000/-	Rs.350/-	Two Months
2	A/R & M/O Various road under Baijnath Sub-Division (SH: Hiring of Tipper)	Rs.2,77,875/-	Rs.5,600/-	Rs.350/-	One Month
3	C/O Bahi Rangehar via Chobu Nagher Road (SH: C/O R/Wall at RD 1/500 to 1/517 and 1/592 to 1/596 (R.Side)	Rs.4,96,646/-	Rs.9,900/-	Rs.350/-	One Month
4	C/O Link road from Chadhar to Doli Khurad km 0/0 to 2/300 (SH: P/L C.C Pavement & WBM G-II at km 0/00 to 0/140)	Rs.4,84,814/-	Rs.9,700/-	Rs.350/-	Two Months

**Terms and conditions:-**

1. The contractor should be registered as dealer under H.P. GST Tax Act, 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
3. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
4. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
5. Only two tenders form will be issued to the contractor/firm which may be noted.
6. The contractor will also have to attach the labour employer license from the labour office with the application.
7. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
8. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
9. The contractor shall have all required machinery such as Truck/ Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
10. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
11. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
12. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,  
Baijnath Division.,  
H.P.PWD., Baijnath.


For & On behalf of the governor of H.P.  
Dated:- 28.06.2024

NO:-PWD/BD/TA/NIT/2024-25/-

2215-2265

*E.E.*

- 1 Copy to the F.C. cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- 2 The Engineer-in-chief, HPPWD, Shimla.
- 3 The Chief Engineer (MZ), HPPWD, Mandi.
- 4 The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- 5 All the Assistant Engineer working under this Division.
- 6 Drawing Branch in this office.
- 7 Notice Board.
- 8 The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

  
Executive Engineer,  
Bajjnath Division.,  
H.P.PWD., Bajjnath.

1

# DNIT/SCHEDULE OF QUANTITY

Estimated Cost:-4,95,000.00

Earnest Money:-4,95,000.00 (0,000) - 42

Time Limit:- Two Month

Name of work:- R/D on Various roads under Bir Sub Division Deol Section.

(SH: Hiring of Hydraulic Excavator) (JCB)

Sr. No.	Description of items	Quantity	Rates (in Rupees)		Unit	Amount (in Rupees)
			In Figure	In words		
1	2	3	4	5	6	7
1	Hiring of Hydraulic Excavator having capacity of 0.9 Cum (zero point nine) in working condition per day basis with 8 (eight) hours per day excluding Sunday Holiday. The operational and maintenance charges POI charges and other miscellaneous supply replacement required for smooth running of vehicle will be borne by the owner of the Hydraulic Excavator).				Per Hour	

Total

Executive Engineer  
Bajnath Division,  
H.P.P.W.D. Bajjnath (H.P.)

2

## DNIT/SCHEDULE OF QUANTITY

Estimated Cost:- 2,77,875.00

Earnest Money:- 5,600.00

Time Limit:- One Month

Name of work:- A/R & M/O various road under Baijnath Sub Division  
(SH: Hiring of Tipper)

Sr. No.	Description of items	Quantity	Rates (in Rupees)		Unit	Amount (in Rupees)
			In Figure	In words		
1	2	3	4	5	6	7
1.	Hiring of Tipper having capacity of 5.5 Cum (five point five)/10 (ten) tonne in working condition per hour basis with excluding Sunday Holiday. The operational and maintenance charges POL charges and other miscellaneous supply/replacement required for smooth running of vehicle will be borne by the owner of the tipper.				Per Hour	
<b>Total</b>						

Executive Engineer  
Baijnath Division,  
H.P.P.W.D. Baijnath (H.P.)

# DNIT/DRAFT SCHEDULE OF QUANTITY

9

Name of work: C/O Bafu Rangchar Via Chohn Nagher Road (Side: C/O Road at RD 1/500 to 1/517 and 1/592 to 1/596 (R side) i.e.				Estimate Cost: 4,96,646.00 Earnest Money: 9,93,292.00 Time Limit: One Month		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P.
				Figures	Words	
1	Earth work in excavation for all type of road structure and wall type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling (wedging out rocks) (Where Blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness, including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	21.00	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth as per drawing and Month technical specification section 800, 900 & 1200 for nominal mix 1:3:6 (one cement, five sand, ten graded stone age 10mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and handling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	85.21	Per Cum			
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204 & 8 granular material including entire carriage of materials within all leads and lifts and other incidental including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	10.38	Per Cum			
Total						

Executive Engineer  
Bafnath Division  
H.B.P.W.D. Bafnath

(4)

**DNIT/DRAFT SCHEDULE OF QUANTITY**

Name of Work : C/O Link Road from Chadhiar to Doli Khurad km 0/00 to 2/300 .

(SH:-P/L C. C Pavement & W B M G-II at km 0/00 to 0/140 )


Estimate Cost: 4,84,814.00/-

Earnest Money: 9,700.00/-

Time Limit : Two Months

**SCHEDULE OF WORKS**

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
					Words	Rs.	P
1	Providing laying spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber. applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cubic metre (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 cubic metre (zero decimal zero six) cubic metre per ten square metre to fill up the intersitices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.42	Per Cubic Metre				
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Milimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and M.O.R.D. technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	68.35	Per Cubic metre				
<b>Total</b>							

  
 Executive Engineer  
 Bajjnath Division,  
 H.P.P.W.D. Bajjnath (H.P.)