




Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS, AS
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2023-24/-
2270-2320 DATED 29-06-2024 ARE URGENT NATURE
AND PUBLIC INTEREST.


Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **12.07.2024 up to 11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **11.07.2024 between 2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **10.07.2024 up to 12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	Special Repair to S.D.P.O office cum Residence Building at Baijnath (SH: P/F Vitrous China Pedestal. P/F Mirror, P/F Gyser, P/F Aluminum work, G1 Pipe etc.)	Rs.1,41,749/-	Rs.2,800/-	Rs.350/-	Fifteen Days
2	C/O A.E office Cum Residence at Bir (P/L 60 mm Thick paver block & Painting on boundary wall.	Rs.4,92,733/-	Rs.9,900/-	Rs.350/-	Two Months
3	C/O Tashijong to Jhikli Beth Ghorpith Averi Road Km 0/0 to 8/915 (SH: Providing and Laying Premix Surface 20mm thick in various RD 0/0 to 8/915)	Rs.4,99,397/-	Rs.10,000/-	Rs.350/-	Two Months
4	C/O Road from Sabji Mandi to Village Sangrehar Near Sarman Km 0/0 to 4/0 (Portion Link road to village Sarman (SH: Cutting in earth work Km 2/450 to 2/675)	Rs.4,99,526/-	Rs.10,000/-	Rs.350/-	One Month

Terms and conditions:-

- The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
- The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
- The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
- In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
- Only two tenders form will be issued to the contractor/firm which may be noted.
- The contractor will also have to attach the labour employer license from the labour office with the application.
- Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
- The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
- The contractor shall have all required machinery such as Truck/ Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
- The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
- All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
- The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Baijnath Division.,
H.P.PWD..Baijnath.

For & On behalf of the governor of H.P.


Dated:- 29.06.2024

NO:-PWD/BD/TA/NIT/2024-25/-

2270-2320

E.E.

- 1 Copy to the F.C. cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- 2 The Engineer-in-chief, HPPWD, Shimla.
- 3 The Chief Engineer (MZ), HPPWD, Mandi.
- 4 The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- 5 All the Assistant Engineer working under this Division.
- 6 Drawing Branch in this office.
- 7 Notice Board.
- 8 The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.


Executive Engineer,
Bajinath Division.,
H.P.PWD..Bajinath.

D.N.I.T/ SCHEDULE OF QUANTITY

Name of work :- Special Repair to S.D.P.O office cum Residence Building at Baijnath.

Estimated Cost: Rs. 141749.00

(Sh:- P/F Vitrous China Pedestal, P/F Mirror, P/F Gyser, P/F Aluminium work, GI pipe etc).

Earnest Money: Rs. 2,800.00

Time Limit: Fifteen Days

SCHEDULE OF WORKS

Sr No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Providing and fixing 25 liters Gyser in toilet bath with all fitting in complete in all respect. The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Government.	1.00	Each			
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections, appropriate Z sections and other sections of approved make conforming to IS- 733 and IS- 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle. Aluminium snap beading for glazing, paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Government.	162.56	Kg			
3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with PVC / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (cost of aluminium snap beading shall be paid in basic item.) glazing with glass panes of 4mm thickness (weight not less than 10kg /sqm. The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Government.	14.11	Sqm			
4	Providing and fixing GI pipes complete with GI fitting and clamps i/c cutting and making good the walls etc 15mm dia. The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Government.	25.00	Rm			
TOTAL						

Executive Engineer
Baijnath Division,
H.P.P.W.D. Baijnath (H.P.)

DNIL DRAFT SCHEDULE OF QUANTITY

Name of Work : Construction of A/E office Cum Residence at Bir
(SHE: P/L 60 mm thick paver block & Painting on boundary wall)

Estimate Cost:4,92,733.00
Earnest Money:9,900.00
Time Limit : Two Months

Sr. n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, and rock chiseling, wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 5-8.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any fill including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge including cartage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana tolltax or other taxes imposed by the government.	14.62	Per Cum	290.10	Rupees Two Hundred & Ninety - Parse Ten Only	4,241.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level (1:8:16 Cement : 4 coarse sand) : 8 graded stone aggregate (40mm nominal size) The rate including of octroi, royalty, Malkana tolltax, Sale Tax or other taxes imposed by the government.	14.62	Cum	4,850.00	Rupees Four thousand Eight Hundred Fifty Only	70,907.00
3	Providing and laying factory made unglazed edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic park etc. of required strength, thickness & size, shape made by table & honox method using P/L mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedment by inter locking paver blocks into the sand bedding layer through vibratory compaction by using vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in-Charge 60mm (sixty millimeter) thick cement concrete paver block of M-35 grade with approved colour, design & pattern The rate including of octroi, royalty, Malkana tolltax, Sale Tax or other taxes imposed by the government.	195.00	Sqm	1880.00	Rupees One thousand Eight Hundred Eighty Only	366,600.00
4	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equivalent on undecorated wall surfaces two coats to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete. The rate including of octroi, royalty, Malkana tolltax, Sale Tax or other taxes imposed by the government.	396.00	Sqm	128.75	Rupees One Hundred Twenty Eight And Parse Seventy Five Only	50,985.00
						492,733.00

D.S.I.I. Checked and approved for Rs. 492,733.00 only
Rupees Four Lakh(s) Ninety Two Thousand Seven Hundred Thirty Three Only

Executive Engineer
Baranath Division
THPPWD Baranath

SCHEDULE OF QUANTITY						
Name of Work: C/O Tashijong to Jhikli Beth Ghorpith Averi Road Km 0/0 to 8/915 (SH: Providing and Laying Premix Surface 20mm thick in various RD 0/0 to 8/915).				Estimated Cost: Rs. 499397/- Earnest Money: Rs. 10000/- Time Limit : Two Months		
SCHEDULE OF WORKS						
S No.	Description of work	No or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the Rate of 0.25- 0.30 kg per sqm on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503.The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government including GST.	1495.20	Per Square metre			
2	Providing, laying and rolling of open-graded premix carpet of 20 mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN static roller capacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508. Taking Qty. from item No 1 The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government including GST.	1495.20	Per Square metre			
3	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type A, Type B and Type C as per Technical Specification Clause 510. Taking Qty. from item No 1 The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government including GST.	1495.20	Per Square metre			


 Executive Engineer
 Bajinath Division,
 H.P.P.W.D. Bajinath (H.P.)


SCHEDULE OF QUANTITY

Name of Work: C/O Road from Sabji Mandi to Village Sangrehar Near Sarman Km 0/0 to 4/0 (Portion Link road to village Sarman
(SH: Cutting in earth work Km 2/450 to 2/675)

Estimated Cost: Rs. 499526/-
Earnest Money: Rs. 10000/-
Time Limit : One Month

SCHEDULE OF WORKS

S No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Excavation in earthwork in hilly areas in all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and levels as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification clause 1603.1 and 1603.2 to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, up to all leads & lift and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. The recovery @ Rs. 300.00 per cubic metre for 127.71 cubic metre useful stones shall be made from the contractor on pro-rata basis in each running bill. The rate including of octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the government.	2187.45	Per Cubic Meter			


 Executive Engineer
 Baijnath Division,
 H.P.P.W.D. Baijnath (H.P.)