



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

SHORT TERM NOTICE INVITING TENDERS"

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **29/06/2024** up to 11.00 AM. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on **28/06/2024** up to 4.00 P.M and the application for issue of tender form shall be received on **27/06/2024** up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	Up-gradation of link road from Panyali to Jhunga Devi Mandir via Dhalera, Kholi & Bhadrol Km. 0/0 to 7/0 in Distt. Kangra (HP) (SW:- Balance work of C/o Edge wall with Drain Bed between RD 6/477 TO 6/877 RHS) (under NABARD)	3,74,400/-	7500/-	Three Months	350/-
2	C/o Parour Dheera Naura road Km. 0/0 to 17/0 (SW:- C/o 1.00 mtr span culvert at Rd 9/985)	2,63,773/-	5300/-	Two Months	350/-
3	Restoration of rain damages on Dadh Malan Massal Rajhoon road in Km. 8/0 to 24/0 (SW:- C/o Unlined drain & Maintenance of Earthen Shoulder Between Km.8/000 to 10/0)	2,67,750/-	5400/-	Two Months	350/-
4	C/o Nagni Gharana road Km. 0/0 to 10/00 (SW:- C/o R/Wall in Km. 7/320 to 7/334.50 LHS))	4,08,175/-	8200/-	Three Months	350/-
5	C/o Lahar Thakrain Sadun Bargaran road in Km. 0/0 to 4/630 (SW:- P/L CC work in Km. 4/020 to 4/070 & 4/230 to 4/310)	4,67,610/-	9300/-	Two Months	350/-
6	Upgradation of Alampur to Thakurdwara road Km. 45/175 to 9/675) (SW:- Preparation of Detailed project report)	4,85,750/-	9700/-	Three Months	350/-
7	C/o Rada Rarouth road (SW:- Providing and laying CC Pavement in Km. 0/185 to 0/255, 0/435 to 0/452)	3,18,604/-	6300/-	Three Months	350/-
8	Restoration of Rain Damages link road from Main road Dedha Village Nanaon (SW:- Breast wall in Km. 0/037 to 0/050 LHS) (Deposit work)	1,45,295/-	2900/-	Two Months	350/-
9	C/o link road Chellian Dholta Dharot road Km. 0/0 to 2/100 (SW:- C/o R/Wall at RD 0/330 to 0/350 & 0/355 to 0/371) (under SCSP)	4,86,518/-	9700/-	Two Months	350/-
10	Restoration of rain damages on Santoshi Mata Malandher Garthoon road Km. 0/0 to 7/0 (SW:- Providing and Fixing of W-Metal crash Berrier in Km. 0/350 to 0/450)	4,00,000/-	8000/-	Three Months	350/-
11	C/o Duhak Tikkri Rakha Basti to Dhabi road Km. 0/0 to 4/389 in Distt. Kangra (HP) (SW:- Providing and laying Thermoplastic Paint in Km. 0/0 to 3/250)	4,87,500/-	9800/-	One Month	350/-
12	C/o Retaining wall at Govt. High School at Arla Tehsil Palampur Distt. Kangra (HP) (SW:- C/o B/Wall in School Campus) (Deposit work)	1,99,790/-	4000/-	One Month	350/-
13	C/o link road from Baskhehar to Khabli road Km. 0/0 to 1/0 (SW:- C/o Retaining wall in Km. 0/820 to 0/838)	4,02,212/-	8000/-	Two Months	350/-
14	Restoration of rain damages on Parour to Balla road Km. 0/00 to 3/700(SW:- C/o Unlined drain & Maintenance of Earthen Shoulder Between Km. 0/000 to 3/300)	2,78,100/-	5500/-	Two Months	350/-
15	C/o link road to village Galluin GP Panaper (SW:- C/o Edge wall in Km. 0/510 to 0/535)	1,34,688/-	2700/-	Two Months	350/-
16	C/o Gadiara Khateen road (SW:- C/o 900 mm dia Hume pipe culvert at Rd 2/150 and approaches in Km. 2/145.50 to 2/148.50 & 2/151.50 to 2/155.50 (LHS)	2,62,435/-	5200/-	Two Months	350/-



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

17	C/o Naura Kiarwan road Km.0/0 to 3/345 (SW:- C/o retaining wall in Km. 1/180 to 1/193.50)	3,94,197/-	7900/-	Two Months	350/-
18	C/o Bharath to Tillu Mata Mandir via Narah Basti Km. 0/000 to 2/000 (SW:- P/L Premix Carpet with Seal coat in Km. 0/000 to 0/300)	3,63,909/-	7200/-	Three Months	350/-
19	C/o Addl. Acc. Govt. Sen. School at Gharana Teh. Dheera Distt. Kangra (HP) (SW:- C/o Protection wall with Drain Length=36.00 mtr & C/o Boundary wall Length=64.00mtr) (Deposit)	4,76,199/-	9500/-	Three Months	350/-
20	C/o Rud Panyali Lahar Chhalaina Chowki Parmar Nagar road Km. 0/0 to 10/00 (SW:- C/o R/Wall at Rd 8/184 to 8/200)	3,28,020/-	6600/-	Two Months	350/-
21	C/o Naura Kiarwan road Km. 0/00 to 3/35 (SW:- P/L CC work in Km. 1/180 to 1/240 & C/o V-shape drain in Km. 1/120 to 1/260)	4,28,160/-	8600/-	Two Months	350/-
22	C/o Newly Up- Graded 50 Beded Hospital at Bhawarna Distt. Kangra (HP) (SW:- P/L Vitrified tiles for ramp)	4,98,187/-	9900/-	Two Months	350/-
23	C/o Newly Up- Graded 50 Beded Hospital at Bhawarna Distt. Kangra (HP) (SW:- Providing edge moulding to granite)	4,96,461/-	9900/-	Two Months	350/-
24	Special Repair of Bridge on Hamirpur Sujampur Thural Maranda road at Rd 37/950 (SW:- C/o RCC crass baeier Railing on existing bridge tat Rd 37/950)	4,50,160/-	9000/-	Three Months	350/-

Terms & Conditions:-

7. The contractor/firm should be registered as or dealer GST No.
8. The intending contractor/firm have to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
9. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
10. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.
11. The contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
12. Next tender will be issued only after completion of previous works in hand.

HIM SUCHANA AVM JAN SAMPARK


Executive Engineer
Bhawarna Division
HPPWD Bhawarna
(On behalf of Governor of Himachal Pradesh)

No. PWD/BWD/Tender/NIT/2024-25/-

2296-2355

Dated:- 21-6-2024

Copy to following for information and necessary action:-

13. The Principal Secy.(PW) to the Govt. of H.P. Shimla.
14. The Engineer-in-Chief, HPPWD. Shimla.
15. The Chief Engineer (KZ), HPPWD, Dharamshala.
16. The Director, Information & Publications Department, HP Shimla.
17. The Executive Engineer (IT), Nigam Vihar Shimla. He is requested to upload the same on the department website.
18. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
19. The Deputy Commissioner, Kangra at Dharamshala.
20. The Sub-Divisional Officer(Civil) Palampur.
21. All the S.E.s/E.E.s under Kangra Zone.
22. All the Assistant Engineers under this Division.
23. The Drawing /Accounts Branch in this office.
24. Notice Board.


Executive Engineer
Bhawarna Division
HPPWD Bhawarna

Schedule of Quantity

Name of Work:- Up-gradation of link road from Panyali to Jhunga Devi Mandir via Dhalera, Kholi & Bhadrol Km 0/0 to 7/0 in District Kangra (HP).

Estimate Cost :- Rs. 3,74,400/-
Earnest Money :- Rs. 7500/-

Time Limit :- Three Month

(SH:- Balance Work of C/o Edge Wall With Drain Bed Between RD. 6/477 to 6/877 RHS) (Under NABARD)

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, GST or other taxes imposed by the Government.	180.00			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, GST or other taxes imposed by the Government.	73.20			Per Cubic metre	
Total:-						


 Executive Engineer
 Bhawana Division
 HP PWD Bhawana

Schedule of Quantity

Name of work:- C/o Parour Dheera Naura road Km 0/0 to 17/0 (SW):- C/o 1.00 mtr span culvert at RD 9/985).

Estimate Cost :- Rs. 2,63,773/-
Earnest Money :- Rs. 5300/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	2.89			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub-structure for all type of structure complete nominal mix 1: 2 ½ :5 (One cement : two point five sand : five graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size) on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths in abutments, parapet etcetera and the like including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	11.56			Per Cubic metre	
3	Supplying, fitting and placing HYSD bar reinforcement in super structure complete with straightening, bending, binding of bars including the cost of binding wire in all heights / depths as per drawing and MORD technical specification section 1000 and 1400 and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the government.	178.860			Per Kilogram	
4	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimeter) nominal size in bed block & dirt wall as per drawing and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203, including the cost of form work, curing complete and hauling of materials in all kinds of leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.35			Per Cubic metre	

5	Steel work welded in built up sections trusses and frame work including cutting hoisting and fixing in position and applying a primer coat of red lead paint in single stanchions composed of rolled steel joists or channels with caps, bases splices, angles brackets etc. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1309.16			Per Kilogram
6	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	2.82			Per Cubic metre
7	Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade- M-25 (M-Twenty Five) in open foundation design mix with cement contents not less than 400 kg (Four hundred kilogram) per cubic metre using graded crushed stone aggregate 20mm (twenty millimetre) nominal size complete as per drawings and MORD technical specification section 800, 900 and 1400, including the cost of form work and curing complete including hauling of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.20			Per Cubic metre
Total:-					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Dadh Malan Massal Rajhoon road in Km 8/0 to 24/0. (SW:- C/o Unlined drain & Maintenance of Earthen Shoulder Between Km 8/000 to 10/0).

Estimate Cost :-Rs. 2,67,750/-
Earnest Money :-Rs. 5400/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Consruction of un lined surface drain of average cross sectional area 0.40 Sqm. In soil to specified lines, grades, level and dimension excavated materials to be used in embankment with a lift upto 3 m and lead of 50m (Average lead 25m) as per technical specification clause 307. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1500.00			Per Running metre	
2	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipemnt at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	5850.00			Per Square metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP-PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain Damages on Nagni Gharana Road Km. 0/000 to 10/000.

Estimate Cost :-Rs 4,08,175/-
Earnest Money :- Rs 8200/-

Time Limit :- Three Months

(SH:- C/o R/Wall in Km 7/320 to 7/334.50 LHS).

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	31.03			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	94.40			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	20.00			Each	
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	27.41			Per Cubic metre	
Total :-						


 Executive Engineer,
 Bhawarna Division,
 HPPWD Bhawarna

Schedule of Quantity

Name of work:- Construction of Lahar Thakra in Sadun Bargaran road in Km 0/00 to 4/630 (SH:- P/L CC work in Km 4/020 to 4/070 & 4/230 to 4/310).


Estimate Cost :- Rs. 4,67,610/-
Earnest Money :- 9300/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing, laying, Soling 90 to 45mm (Ninety to forty five milimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	42.90			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimeter) nominal size in open foundation as per drawing and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203, including the cost of form work, curing complete and hauling of materials in all kinds of leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	64.35			Per Cubic metre	
Total:-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

SCHEDULE OF QUANTITY						
NAME OF WORK:-UPGRADATION OF ALAMPUR TO THAKURDWARA ROAD KM 45/175 TO 59/675.			Estimated cost:-		4,85,750.00	
			Earnest Money		9700.00	
			Time:-		Three Months	
SUB HEAD : PREPARATION OF DETAILED PROJECT REPORT						
SR. NO.	DESCRIPTION OF ITEMS	QTY	RATES		UNIT	AMOUNT
			In Figure	In Words		
1	Preparation of detailed project report soil investigation detailed total station survey,Bankel Beam Deflection Test for preparation of manuscript copy of detailed estimate and drawings complete including Plan, cross-sections, L-Sections, cross drainage work, Retaining wall , Breast walls & other necessary provisions taken in the estimate preparation of detailed estimate Topography survey by digital total staion /dual frequency dgps with two second accuracy, showing all offsets such as trees bridges culverts electric poles, hand pumps , school, habitants village etc. In the shape of manuscript to be fair out after approval from the circle office, Chief office, preparation of approved copies of detailed estimate alongwith relevent working drawings (Five sets of DPRs complete) and soft copies in the form of compact Disc(CD) if any correction/amendment is desired by the Head office the same may be corrected as desired and directed by the Engineer-In-Charge complete in all respects.	14.50			Per Kilometer	
2	CBR-value & pavement design of crust as per IRC:37-2012/SP:72-2015	29.00			Each	
3	Bankel man Beam Deflection test for pavement design of IRC81-1997	14.50			Per Kilometer	
		TOTAL				



 EXECUTIVE ENGINEER
 DIVISION-BHAWARNA
 HP.PWD BHAWARNA

Schedule of Quantity

Name of work:- Construction of Rada Rarouth Road. (SW:- Providing and Laying CC Pavement I Km 0/185 to 0/255, 0/435 to 0/452).

Estimate Cost :-Rs. 3,18,604/-
Earnest Money :- Rs. 6300/-
Time Limit :- Three Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, stone, screening type-B of size 11.2mm (eleven point two millimetre) nominal size at the rate of 0.20 cum. (Zero point two zero cubic metre) per ten square metre and binding materials at the rate of 0.06 cum. (Zero point zero six cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -II, 63mm to 45mm (sixty three millimeters to forty five millimeters)size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer -in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.00			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in sub structure nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boiling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	50.42			Per Cubic metre	
				Total :-		


Executive Engineer,
Bhawarna Divsion,
HP PWD Bhawarna.

Schedule of Quantity

Name of Work :- Restoration of Rain Damages Link Road from Main Road Bedha n Village Nanaon. (SH:- C/o Breast Wall in Km. 0/037 to 0/050 LHS). (Deposit work)

Estimate Cost :- Rs. 1,45,295/-
Earnest Money :- Rs. 2900/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	25.22			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	34.06			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	11			Each	
Total :-						


 Executive Engineer
 Bhawana Division
 HP PWD Bhawana

Schedule of Quantity

Name of Work :- Construction of link road Chellian Dholta Gadiara Dharot road Km 0/0 to 2/100 (SH:- C/o R/wall at RD 0/330 to 0/350 & 0/355 to 0/371) (under SCDP)

Estimated Cost :- Rs. 4,86,518/-
Earnest Money :- Rs. 9700/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	42.60			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	110.16			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	50			Each	
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	37.88			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawana Division
 HP PWD Bhawana

Schedule of Quantity

Name of Work :- Restoration of rain Damages on Santoshi Mata Malandher Garthoon road Km 0/0 to 7/0. (SH:- Provinding and Fixing of W-Metal crash Berrier in Km 0/350 to 0/450).

Estimated Cost :-Rs. 4,00,000/-
Earnest Money :- Rs. 8000/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and erecting a "W" metal beam crash barrier comprising of 3mm (Three millimetre) thick corrugated sheet metal beam rail 70cm (Seventy centimetre) above road/ ground level channel vertical post 150x75x5mm (One hundred fifty into seventy five into five millimetre) space 2m (two metre) Centre to centre 1.80m (One decimal eight zero metre) high 1.10 m (One decimal one zero metre) below ground/road level all steel parts and fitments to be galvanized by hot dip process all fitting to confirmed to IS 1367 and IS 1364 metal beam rail to be fixed on the vertical post with a excavation on work and cement concrete 1:2.5:5 (One isto two decimal five isto five) in foundation having size of pit / hole 0.45x0.45x1.10 m (zero decimal four five into zero decimal four five into one decimal one zero) as per the entire satisfaction and direction of Engineer-in-charge. Including hauling of materials in all leads and lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	100.00			Per Running metre	
Total :-						


Executive Engineer,
Bhawana Division,
HPPWD Bhawana

Schedule of Quantity

Name of Work :- Construction of Duhak Tikkri Rakha Basti to Dhabi road Km 0/0 to 4/389 in District Kangra (HP) . (SW:- Providing and laying Thermoplastic Paint in Km 0/0 to 3/250).

Estimated Cost :-Rs. 4,87,500/-
Earnest Money :- Rs. 9800/-
Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and Laying hot applied thermoplastic compound 2.5mm (Two decimal five millimetre) thick including reflectorising glass beads at the rate of 250 (Two hundred fifty) grams per square metre area, thickness of 2.5mm (Two decimal five millimetre) is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes as per MORTH technical specification clause 803 complete in all respect including carriage of material within all leads, lifts and other incidentals . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	650.00			Per Square metre	
			Total :-			


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Construction of Retaining wall at Govt. High School at Arla Tehsil Palampur Distt. Kangra (HP) (SH:- C/o B/wall in School Campus) (Deposit work).

Estimated Cost :- Rs. 1,99,790/-
Earnest Money :- Rs. 4,000/-
Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	19.08			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	47.88			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	14			Each	
Total :-						



 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Construction of Link road from Baskehar to Khabli road Km 0/0 to 1/0. (SH:- Construction of Retaining wall in Km 0/820 to 0/838).

Estimate Cost :- Rs. 4,02,212/-
Earnest Money :- Rs. 8000/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	42.12			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	90.54			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	44			Each	
19	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	26.46			Per Cubic metre	
Total :-						


Executive Engineer
Bhawana Division
HP PWD Bhawana

Schedule of Quantity

Name of Work :- Restoration of rain damages on Parour to Balla road Km 0/000 to 3/700. (SW:- C/o Unlined drain & Maintenance of Earthen Shoulder Between Km 0/000 to 3/300).

Estimate Cost :-Rs. 2,78,100/-
Earnest Money :-5500 /-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Construction of un lined surface drain of average cross sectional area 0.40 Sqm. In soil to specified lines, grades, level and dimension excavated materials to be used in embankment with a lift upto 3 m and lead of 50m (Average lead 25m) as per technical specification clause 307. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1800.00			Per Running metre	
2	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	4950.00			Per Square metre	
Total :-						


 Executive Engineer
 Bhawana Division
 HP PWD Bhawana

Schedule of Quantity

Name of Work :- Construction of link road to village Galluin GP Panaper. (SH:- Construction of Edge wall in Km 0/510 to 0/535).

Estimated Cost :- Rs. 1,34,600/-
Earnest Money :- Rs. 2700/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	11.25			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	28.25			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	19			Each	
Total :-						


 Executive Engineer
 Bhawana Division
 HP PWD Bhawana

Schedule of Quantity

Name of Work: - Construction of Gadiara Khateen road. (SH:- C/o 900 mm dia hume pipe culvert at RD 2/150 and approaches in Km 2/145.50 to 2/148.50 & 2/151.50 to 2/155.50 (LHS)).

Estimate Cost :-Rs. 2,62,435/-
Earnest Money :- Rs. 5200/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	45.84			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge. Including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	3.42			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub-structure for all type of structure complete of plain cement concrete nominal mix 1: 2 ½ :5 (One cement : two point five sand : five graded crushed/ broken stone aggregate 20mm (Twenty millimetre) nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths in abutments etcetera and the like including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and as per direction of Engineer-in-Charge Including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	13.29			Per Cubic metre	
4	Providing and laying (to level or slope) 900mm dia (Nine hundred millimetre) diameter reinforced cement concrete non pressure pipes IS Class NP-2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications section 1100 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.50			Per Running Metre	

5	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	32.63			Per Cubic metre
6	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	12			Each
7	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.51			Per Cubic metre
		Total :-			


 Executive Engineer
 Bhawarna-Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Construction of Naura Kiarwan road km 0/0 to 3/345. (SH):- Construction of retaining wall in Km 1/180 to 1/193.50)

Estimated Cost :- Rs. 3,94,197/-
Earnest Money :- Rs. 7900/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable compacted material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	33.21			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	90.32			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	27			Each	
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	25.52			Per Cubic metre	
Total :-						


Executive Engineer
Bhawana Division
HP PWD Bhawana

Schedule of Quantity

Name of Work :- Construction of Bharath to Tillu Mata Mandir Via Narah Basti Km. 0/000 to 2/000. (SH:- P/L Premix Carpet with Seal coat in Km 0/000 to 0/300).

Estimated Cost :- Rs. 3,63,909/-
Earnest Money :- Rs. 7200-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing, laying, spreading and compacting stone aggregates of size 53mm to 22.4mm (Fifty three millimetre to Twenty two point four millimetre) Grading -III, 75mm (Seventy five millimetre consolidated thick) to water bound macadam specification including spreading in uniform thickness, using template hand packing, rolling with Three wheel 80-100 KN static roller to stages to proper grade and camber, applying and brooming, stone screening Type B of size 11.2mm (Eleven point two millimetre) nominal size at the rate of 0.18 Cum. (Zero point one Eight Cubicmetre) per ten square metre and to fill up the interstices of coarse aggregate watering and compacting to the required density as per technical Specification Clause 405 as per entire satisfaction and direction of the Engineer -in-Charge. The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	10.00			Per Cubic metre	
2	Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface with hydraulic broom and spraying primer at the rate of 0.85 Kg. (Zero decimal eight five Kilogram) per Square metres using mechanical means as per technical specification clause 502, and as per the directions of Engineer-in-charge including carriage of materials within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana toll tax, sale tax or any other taxes imposed by the Government.	960.75			Per Square metre	
3	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion pressure distributor at the rate of 0.275 Kg. (Zero decimal two seven five Kilogramme) per Square metres on the prepared granular surface treated with primer and cleaned with Hydraulic broom as per technical specification clause 503, as per directions of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana toll tax, sale tax or any other taxes imposed by the Government.	960.75			Per Square metre	
4	Providing, laying and rolling of open-graded premix carpet of 20 mm (Twenty millimetre) compacted thickness composed of Type-A 13.2 mm (Thirteen decimal two millimetre) to 5.6 mm (Five decimal six millimetre) aggregates at rate of 0.27 Cum. (Zero point two seven Cubicmetres) mixed with penetration grade V.G-10 (VG-Ten) Bitumen at the rate 14.6 Kg. (Fourteen point six Kilogramme) per ten Square metres of road surface to required line, grade and level to serve as wearing course on a previously prepared base, including mixing and heating binder and aggregate in Hot mix Plant 30/40 (Thirty / Forty) Tonne per hour capacity, transporting mixed material with tipper any laying with paver finisher to the required grade and camber and rolling with a three wheel 80-100 (Eighty - Hundred)KN static road roller, finished to required level and grades to be followed by seal coat as per Technical Specification Clause 508 and 511 of MORD specification.	960.75			Per Square metre	

5	Providing and laying seal coat for sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per technical specification Clause 510 using Bitumen grade V.G. 10 (Viscosity Grade Ten) at the rate of 6.8 kg (Six point eight kilogramme premixed with 0.06 (Zero point Zero six cubic meter of fine aggregate per ten square metre heated in hot mix plant and laying manually of mixed material and rolling with power road roller 8 - 10 tonne (eight to ten) tonnes capacity as per the direction of Engineer-in-Charge.	960.75				Per Square metre	
Total :-							


 Executive Engineer
 Bhawana Division
 HP PWD Bhawana

Schedule of Quantity

Name of Work :- Construction of Addl. Acc. Govt. Sen. School at Gharana Teh.Dheera Distt. Kangra (HP). (SH:- Construction of Protection Wall with Drain Length =36.00 mtr.& C/o Boundary Wall Length =64.00 mtr). (Deposit

Estimate Cost :- Rs. 4,76,199/-
Earnest Money :- Rs. 9500/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	68.31			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D. technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	47.16			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	29			Each	

4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	4.68			Per Cubic metre
6	Providing form work with steel plates of 3.15mm (three decimal one five millimeter) thick, welded with angle iron in frames of 30x30x5mm (thirty into thirty into five millimeter) so as to give a fair finish including centring, shuttering strutting and propping etc, with wooden battens and ballies for all heights/depths of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in foundation,. Footings bases of columns and mass concrete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.Rate inclusive toll tax, GST and any other taxes imposed by the government.	63.60			Per Square metre
6	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer –in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octrai, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	11.43			Per Cubic metre
7	Second class brick work using common burnt clay building bricks in cement mortar 1:6 (one cement isto six sand) in super structure upto all floor levels as per PWD specification drawing and design and curing complete including scaffolding. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	2.78			Per Cubic metre
8	Second class half brick work using common burnt clay building bricks with hoop iron in cement mortar 1:4 (one cement isto four sand) in super structure as per PWD specification, drawing and design and curing complete including scaffolding. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	86.25			Per Square metre

9	15mm (fifteen millimeters) thick cement plaster in single coat on the rough side of brick/concrete/stone walls for interior plastering upto any floor level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (eighty millimeters) in girth, in rough side with cement mortar 1:6 (one cement isto six sand) complete including curing as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	247.22			Per Square metre	
10	Rate inclusive toll tax, GST and any other taxes imposed by the government. Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	247.22			Per Square metre	
11	Finishing walls with water proofing cement paint of new work (Two or more coats applied @ 3.84 kg/10 sqm) required shade. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	247.22			Per Square metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Construction of Rud Panyali Lahar Chhalaina Chowki Parmar Nagar road Km 0/00 to 10/00 (SH:- C/o R/wall at RD 8/184 to 8/200).

Estimated Cost :- Rs. 3,28,020/-
Earnest Money :- Rs. 6600/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved thickness of each original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	27.36			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D. technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	74.72			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	22			Each	
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.00			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawana Division
 HP PWD Bhawana

Schedule of Quantity

Name of work:- Construction of Naura Kiarwan road Km 0/00 to 3/345 (SH:- P/L CC work in Km 1/180 to 1/240 & C/o V-shape drain in Km 1/120 to 1/260).

Estimate Cost :- Rs. 4,28,160/-
Earnest Money :- 8600/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, stone, screening type-B of size 11.2mm (eleven point two millimetre) nominal size at the rate of 0.20 cum. (Zero point two zero cubic metre) per ten square metre and binding materials at the rate of 0.06 cum. (Zero point zero six cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -II, 63mm to 45mm (sixty three millimeters to forty five millimeters)size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer -in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	5.00			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimeter) nominal size in open foundation as per drawing and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203, including the cost of form work, curing complete and hauling of materials in all kinds of leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	60.00			Per Cubic metre	
3	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	15.40			Per Cubic metre	

4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	12.18			Per Cubic metre
Total:-					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of work:- Construction of Newly Up-Graded 50 Bedded Hospital at Bhawarna Distt. Kangra H.P. (SH:- P/L Vitrified tiles for ramp).

Estimate Cost :- Rs. 4,98,187/-
Earnest Money :- 9900/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and laying 400x400 mm (Four hundred into four hundred millimetre) outdoor heavy duty vitrified tiles of restile/ Nitco/ Rak/ Simpolo/ Kajaria/ Johnson as per approved shade in flooring laid over 12 mm (twelve millimetre) thick cement mortar 1:3 (one cement isto three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as per approved specification, drawing and design complete including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	296.54			Per Square metre	
Total:-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of work:- Construction of Newly Up-Graded 50 Bedded Hospital at Bhawarna Distt. Kangra H.P.(SH:- Providing edge moulding to granite).

Estimate Cost :- Rs. 4,96,461/-
Earnest Money :- 9900/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing edge moulding to 18 mm thick marble stone counters, Vanities etcetra including machine polishing to edge to give high gloss finish etc. complete as per design approved, entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	1337.45			Per Running metre	
Total:-						


Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of work:- Special Repair of Bridge on Hamirpur Sujjanpur Thural Maranda road at RD 37/950 (Sw:- C/o RCC crass barrier Railing on existing bridge at RD 37/950).

Estimate Cost :- Rs. 4,50,160/-
Earnest Money :- Rs. 9000/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Supplying, fitting and placing HYSD bar reinforcement in super structure complete with straightening, bending, binding of bars including the cost of binding wire in all heights / depths as per drawing and MORD technical specification section 1000 and 1400 and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the government.	2648.000			Per Kilogram	
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete of grade M-30 (M- Thirty) designed mix with minimum cement contents of 430 kg (Four hundred thirty kilogram) per cubic meter with 20 mm (Twenty millimeter) nominal size graded crushed stone aggregate and curing complete in crash barrier railing including reinforcement for reinforced concrete work and form work as per drawing and technical specifications clause 800 & 1206.3 and as per the directions of the Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax or other taxes imposed by the Government.	26.48			Per Cubic metre	
Total:-						


 Executive Engineer
 Bhawana Division
 HP PWD Bhawana