




Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS, AS
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2023-24/-
2884-92 DATED 08-07-2024 ARE URGENT NATURE
AND PUBLIC INTEREST.


Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before 23.07.2024 up to 11.30 A.M and will be opened on the same day at 12.00 Noon in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on 22.07.2024 between 2.00 PM up to 4.30 P.M and the application for issue of tender forms shall be received on 20.07.2024 up to 12.00 Noon.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	Restoration of rain damages on various Roads under Bir Sub-Division (SH: Hiring of Hydraulic Excavator/JCB for Removal of Slips & cleaning of slush from catch pit of culverts)	Rs.97,900/-	Rs.2,000/-	Rs.350/-	One Month
2	Restoration of rain damages on various Roads under Baijnath Sub-Division (SH: Hiring of Hydraulic Excavator/JCB for Removal of Slips & Cleaning of Slush from catch pit of culverts)	Rs.97,900/-	Rs.2,000/-	Rs.350/-	One Month
3	R/D Baijnath Sub-Division HPPWD Baijnath (Andreta Section) (SH: Hiring of Hydraulic Excavator cum Loader/JCB) in Land Sliding and Removal of Slips)	Rs.2,64,000/-	Rs.5,300/-	Rs.350/-	Two Months
4	R/D Baijnath Sub-Division HPPWD Baijnath (Chadhiar Section) (SH: Hiring of Hydraulic Excavator cum Loader/JCB) in Land Sliding and Removal of Slips)	Rs.2,69,500/-	Rs.5,400/-	Rs.350/-	Two Months
5	Restoration of rain damages on various Roads under Baijnath Sub-Division (SH: Hiring of Hydraulic Excavator cum Loader/JCB) for Removal of Slips & cleaning of slush from catch pit of culverts)	Rs.4,97,200/-	Rs.10,000/-	Rs.350/-	One Month
6	Construction of Link road from chobu Bhullana 0/00 to 8/00 (SH: Construction of 3.00 mtr. R.C.C. Slab culvert at RD 2/640) (Sub structure)	Rs.4,99,842/-	Rs.10,000/-	Rs.350/-	Two Months

- The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
- The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
- The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
- In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
- Only two tenders form will be issued to the contractor/firm which may be noted.
- The contractor will also have to attach the labour employer license from the labour office with the application.
- Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
- The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
- The contractor shall have all required machinery such as Truck/ Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
- The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
- All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
- The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Baijnath Division.,
H.P.PWD..Baijnath.

For & On behalf of the governor of H.P.
Dated:- 08.07.2024

NO:-PWD/BD/TA/NIT/2024-25/-

2884-92

- Copy to the F.C. cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-chief, HPPWD, Shimla.
- The Chief Engineer (MZ), HPPWD, Mandi.
- The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Baijnath Division.,
H.P.PWD..Baijnath.

①

DNIT/SCHEDULE OF QUANTITY

Estimated Cost:- 97,900.00

Earnest Money:- 2000.00

Time Limit:- One Month

Name of work:- : Restoration of rain damages on various Roads under Bir Sub Division
(SH: Hiring of Hydraulic Excavator/JCB for Removal of Slips & cleaning of slush from catchpit of culverts)

Sr. No.	Description of items	Quantity	Rates (in Rupees)		Unit	Amount (in Rupees)
			In Figure	In words		
1	2	3	4	5	6	7
1.	Hiring of Hydraulic Excavator having capacity of 0.9 Cum (zero point nine) in working condition per day basis with 8 (eight) hours per day excluding Sunday Holiday, for rainy seasons as and when required. The operational and maintenance charges POI charges and other miscellaneous supply/replacement required for smooth running of vehicle will be borne by the owner of the Hydraulic Excavator.	89.00 Hours			Per Hour	
Total						

Executive Engineer
Bajjnath Division,
H.P.P.W.D. Bajjnath (H.P.)

②

DNIT/SCHEDULE OF QUANTITY

Estimated Cost:- 97,900.00

Earnest Money:- 2000.00

Time Limit:- One Month

Name of work:- : Restoration of rain damages on various Roads under Baijnath Sub Division
(SH: Hiring of Hydraulic Excavator/JCB for Removal of Slips & cleaning of slush from catchpit of culverts)

Sr. No.	Description of items	Quantity	Rates (in Rupees)		Unit	Amount (in Rupees)
			In Figure	In words		
1	2	3	4	5	6	7
1.	Hiring of Hydraulic Excavator having capacity of 0.9 Cum (zero point nine) in working condition per day basis with 8 (eight) hours per day excluding Sunday Holiday, for rainy seasons as and when required. The operational and maintenance charges POL charges and other miscellaneous supply/replacement required for smooth running of vehicle will be borne by the owner of the Hydraulic Excavator.	89.00	Hours		Per Hour	
Total						

Executive Engineer
Baijnath Division,
H.P.P.W.D. Baijnath (H.P.)

(3)

SCHEDULE OF QUANTITY

Name of Work: R/D Baijnath Sub Division HPPWD Baijnath (Andreta Section)

(SH: Hiring of Hydraulic Excavator cum Loader / JCB). In Land Sliding and Removal of Slips

Estimated Cost: Rs. 264000/-

Earnest Money: Rs. 5300/-

Time Limit : Two Months

SCHEDULE OF WORKS

S No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Hiring of Hydraulic Excavator cum front end loader One Cum bucket capacity @ 45 Cum /Hour in working condition per hour basis including Sunday / Holiday, for rainy seasons as and when required (i.e. need basis). The patrolling charges will be paid half from destination to working site. Operational and maintenance charges POL charges and other miscellaneous supply/replacement required for smooth running of vehicle will be borne by the owner of the Hydraulic Excavator. The rate is including Royalty, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government including GST.	240.00	Per Hour			

Executive Engineer
Baijnath Division,
H.P.P.W.D. Baijnath (H.P.)

4

SCHEDULE OF QUANTITY

Name of Work: R/D Baijnath Sub Division HPPWD Baijnath (Chadhiar Section)

(SH: Hiring of Hydraulic Excavator cum Loader / JCB). In Land Sliding and Removal of Slips

Estimated Cost: Rs. 269500/-

Earnest Money: Rs. 5400/-

Time Limit : Two Months

SCHEDULE OF WORKS

S No.	Description of work	No.or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Hiring of Hydraulic Excavator cum front end loader One Cum bucket capacity @ 45 Cum Hour in working condition per hour basis including Sunday / Holiday, for rainy seasons as and when required (i.e. need basis). The patrolling charges will be paid half from destination to working site. Operational and maintenance charges POI charges and other miscellaneous supply/replacement required for smooth running of vehicle will be borne by the owner of the Hydraulic Excavator. The rate is including Royalty, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government including GST.	245.00	Per Hour			

Executive Engineer
Baijnath Division,
H.P.P.W.D. Baijnath (H.P.)

SCHEDULE OF QUANTITY						
Name of Work: Restoration of rain damages on various roads under Baijnath Sub Division (SH: Hiring of Hydraulic Excavator cum Loader / JCB). For removal of slips & cleaning of slush from catchpit of culverts).				Estimated Cost: Rs. 497200/- Earnest Money: Rs. 10000/- Time Limit : One Months		
SCHEDULE OF WORKS						
S No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Hiring of Hydraulic Excavator cum front end loader One Cum bucket capacity @ 45 Cum /Hour in working condition per hour basis including Sunday / Holiday, for rainy seasons as and when required (i.e. need basis). The patrolling charges will be paid half from destination to working site. Operational and maintenance charges POI charges and other miscellaneous supply/replacement required for smooth running of vehicle will be borne by the owner of the Hydraulic Excavator. The rate is including Royalty, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government including GST	452.00	Per Hour			

Executive Engineer
Baijnath Division,
H.P.P.W.D. Baijnath (H.P.)

DNIT/DRAFT SCHEDULE OF QUANTITY

Estimate Cost: 4,99,842.00/-

Earnest Money: 10,000.00/-

Time Limit : Two Months

Name of work : Construction of Link Road from Chobu Bhullana 0/00 to 8/00 . (SH: Construction of 3.00 mtr R C C Slab culvert at RD 2/640) (Sub structure)					
Sr. No.	Description of work	No. or Qty.	Unit	Rate	
				Figures	Words
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost.	57.46	Per Cubic metre		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect	7.08	Per Cubic metre		
3	Providing and laying mechanically mixed and vibrated plain/ cement concrete in sub structure for all type of structure complete using plain cement concrete grade M-15 (M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilogram) per cubic metre in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800,900 & 1200 and curing complete including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect	72.00	Per Cubic metre		
Total					

Executive Engineer

Bajnath Division,

H.P.P.W.D. Bajnath (H.P.)