

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Sealed item rate tender on form No. 6 & 8 are hereby invited by the **Executive Engineer, HP Dehra Division HP PWD Dehra** on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **22.07.2024** up to **11:00 A.M.** And the same shall be opened on the same day at **04:00 P.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **20.07.2024** up to **4:00 P.M** and the application for issue of tender form shall be received on **19.07.2024** up to **12:00 noon**. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of **Executive Engineer, HP Dehra Division HP PWD Dehra**


The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1	Construction of Aluha Jasehar Road Km 0/0 to 3/00 (SH:- Construction of PCC Retaining wall at RD. 2/415 to 2/443)	Rs.490154/-	10000/-	Three months
2	Construction of Link road to village Bagg in Km. 0/0 to 1/500 (SH:-P/L Interlocking Paver Block 80mm thick at RD. 0/0 to 0/060)	Rs.498855/-	10000/-	Three months
3	Construction of Link road to village Bagg in Km. 0/0 to 1/500 (SH:-P/L Interlocking Paver Block 80mm thick at RD. 0/065 to 0/124)	Rs.490850/-	10000/-	Three months
4	Construction of Link road to village Bagg in Km. 0/0 to 1/500 (SH:-P/L Interlocking Paver Block 80mm thick at RD. 0/127 to 0/188)	Rs 497498/-	10000/-	Three months
5	Construction of Link road Pihri to Jujpur via Bhadrol GP Pihri in Km. 0/0 to 1/200 (SH:-Construction of R/wall at RD 0/330 to 0/341)	Rs 219255/-	10000/-	Three months
6	Construction of Link Road Dola Jamuli Road to Harizan Basti via G.S.S.S Dolla Khariyana Km. 0/0 to 1/500 (SH:-Construction of PCC R/wall at RD. 0/725 to 0/745.50)	Rs 490829/-	10000/-	Three months
7	Restoration of rain damages on Sapraloo Tihri road Km. 0/0 to 10/00 (SH:- Construction of PCC R/wall at RD. 7/180 to 7/198)	Rs 499459/-	10000/-	Three months
8	Restoration of rain damages on Dharti to Kural Road Km. 0/0 to 4/00 (SH:- C/o PCC R/wall at RD. 2/400 to 2/420.25)	Rs.499459/-	10000/-	Three months
9	Construction of Ambulance road from NH-88/303 Shiv Mandir to Gujar Basti via Saleter ward No.2 Km. 0/00 to 1/00 (SH:-C/o Embankment filling at RD. 0/0 to 0/040 & Cement concrete pavement at RD 0/0 to 0/050)	Rs 499695/-	10000/-	Three months
10	Construction of Ambulance road from NH-88/303 Shiv Mandir to Gujar Basti via Saleter ward No.2 Km. 0/00 to 1/00 (SH:-C/o Cement Concrete Pavement at RD 0/052 to 0/113.50)	Rs 497482/-	10000/-	Three months

11	Construction of Ambulance road from NH-88/303 Shiv Mandir to Gujjar Basti via Saleter ward No.2 Km. 0/00 to 1/00 (SH:-C/o Cement concrete pavement at RD 0/115.50 to 0/177.20)	Rs 499083/-	10000/-	Three months
12	Construction of Ambulance road from NH-88/303 Shiv Mandir to Gujjar Basti via Saleter ward No.2 Km. 0/00 to 1/00 (SH:-C/o Cement concrete pavement at RD 0/178.20 to 0/240)	Rs.499904/-	10000/-	Three months
13	Construction of Ambulance road from NH-88/303 Shiv Mandir to Gujjar Basti via Saleter ward No.2 Km. 0/00 to 1/00 (SH:-C/o Cement concrete pavement at RD 0/242 to 0/307)	Rs.499138/-	10000/-	Three months
14	A/R & M/O on various road under Dehra Division (SH:- Supply and Stacking road bond (Ready mix pot seal) for patch work.	Rs.499800/-	10000/-	Three months

Terms & Conditions:-)

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
3. If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.


Executive Engineer
Dehra Division
HP PWD Dehra

HIMSUCHANA AVAM & JAN SAMPARK


(On behalf of Governor of Himachal Pradesh)

No.PW/NBD/TA/Tender/NIT/2023-24- **1687-1716**

Dated/ **11/7/2024**

Copy to the following for information and necessary action:-

1. The Principal Secy. (PW) to the Govt. of H.P. Shimla.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (KZ), HPPWD, Dharamshala.
4. The Director, Information & Publications Department, H.P. Shimla
5. The Executive Engineer (IT), Nigam Vihar Shimla 2 for information. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
7. The Principal, Dr. RPGMC, Tanda.
8. The Deputy Commissioner, Kangra at Dharamshala.
9. All the S.E.s/E.E.s under North Zone.
10. The Sub-Divisional Officer(C) Nagrota Bagwan.
11. The Block Development Office Nagrota Bagwan
12. All the Assistant Engineer under this Division.
13. The Drawing /Accounts Branch in this office.
14. The Contractors concerned.
15. Notice Board.


Executive Engineer
Dehra Division
HP PWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.4,90,154.00
 Earnest Money :-Rs. 10000.00
 Time Limit :- Three Months.

Name of work:- Construction of Aluha Jasehar Road Km 0/0 to 3/00 (SH:-Construction of PCC Retaining wall at RD. 2/415 to 2/443)

Sr. No.	Description of Item	Quantity	Rate In		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	40.98 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	11,884.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	105.23 Cubic meter	4050.00	Rupees Four Thousand Fifty Only	Per Cubic meter	4,26,182.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	43.09 Cubic metre	750.00	Rupees Seven Hundred Fifty Only	Per Cubic metre	32,318.00
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	49.00 Number	230.00	Rupees Two Hundred Thirty Only	Each	11,270.00
5	Providing and fixing dual directional delineator made of dia 16 (sixteen) gauge M.S rectangular pipe of size 25x68mm (twenty five into sixty eight millimeter) and of length 600mm (six hundred millimeter) pipe stove enameled and baket to 120 c or powder coated. Head made pf ABS plastic rectangular moulded with flat face provided with high Intensity. Prismatic reflectors of colour (Yellow) of size 100x125mm (one hundred into one hundred twenty five millimeter) with additional to reflective strips of 25mm (twenty millimeter) wide Cat-Part No.GPL-UBPH-11-56:make greens/lite including carriage of material within all leads and lifts as per direction of the Engineer-in-Charge and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	10.00 Number	850.00	Rupees Eight Hundred Fifty Only	Each	8,500.00
Total						4,90,154.00
% Above/below						
Quoted Amount in Figures						
Quoted Amount in Words						

Executive Engineer
Dehra Division
PPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.498855.00
 Earnest Money :-Rs. 10000.00
 Time Limit :- Three Months.

Name of work:- Construction of Link road to village Bagg in Km. 0/0 to 1/500 (SH:-P/L Interlocking Paver Block 80mm thick at RD. 0/0 to 0/060)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	24.60 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	99,630.00
2	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 80 mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	246.00 Square metre	1130.00	Rupees One Thousand One Hundred Thirty Only	Per Square metre	2,77,980.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty Five) Nominal mix 1:1.5:3(one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	17.70 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	1,21,245.00
	Total					4,98,855.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					


 Executive Engineer,
 Dehra Division,
 JPPWD Dehra

36


PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.490850.00
 Earnest Money :-Rs. 10000.00
 Time Limit :- Three Months.

Name of work:- Construction of Link road to village Bagg in Km. 0/0 to 1/500 (SH:-P/L Interlocking Paver Block 80mm thick at RD. 0/065 to 0/124)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ devatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	24.19 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	97,970.00
2	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 80 mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax ,GST or any other taxes imposed by the Government.	241.90 Square metre	1130.00	Rupees One Thousand One Hundred Thirty Only	Per Square metre	2,73,347.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3(one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer in-Charge, including cartage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government	17.45 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	1,19,533.00
	Total					4,90,850.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					


 Executive Engineer,
 Debra Division,
 PWD Debra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.497498.00
 Earnest Money :-Rs. 10000.00
 Time Limit :- Three Months.

Name of work:- Construction of Link road to village Bagg in Km. 0/0 to 1/500 (SH:-P/L Interlocking Paver Block 80mm thick at RD. 0/127 to 0/188)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	24.40 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	98,820.00
2	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 80 mm of M-30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick, compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax ,GST or any other taxes imposed by the Government.	244.00 Square metre	1130.00	Rupees One Thousand One Hundred Thirty Only	Per Square metre	2,75,720.00

Sr. No.	Description of Item	Quantity	Rate In		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3(one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer In-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	17.95 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	1,22,958.00
	Total					4,97,498.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Executive Engineer,
Dehra Division,
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.219255.00
 Earnest Money :-Rs. 4000.00
 Time Limit :- Three Months.

Name of work:- Construction of Link road Pihri to Juipur via Bhadrol GP Pihri in Km. 0/0 to 1/200 (SH:-Construction of R/wall at RD 0/330 to 0/341)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	16.90 Cubic meter	250.00	Rupees Two Hundred Fifty Only	Per Cubic meter	4,225.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	49.48 Cubic meter	4000.00	Rupees Four Thousand Only	Per Cubic meter	1,97,920.00

Sr. No.	Description of Item	Quantity	Rate In		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	17.00 Number	230.00	Rupees Two Hundred Thirty Only	Each	3,910.00
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	17.60 Cubic meter	750.00	Rupees Seven Hundred Fifty Only	Per Cubic meter	13,200.00
	Total					2,19,255.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

2,19,255.00


 Executive Engineer,
 Dehra Division,
 SHPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.4,50,829.00


Earnest Money :-Rs. 10000.00

Time Limit :- Three Months.

Name of work:- Construction of Link Road Dola Jamuli Road To Harizan Basti via G.S.S Dolla Khariyana Km. 0/0 to 1/500 (SH:-Construction of PCC R/wall at RD. 0/725 to 0/745.50)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including cartage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	40.41 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	11,719.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:5:10 (One cement isto five sand isto ten graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including cartage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, toll tax, sales tax, GST or any other taxes imposed by the Government.	108.49 Cubic meter	4050.00	Rupees Four Thousand Fifty Only	Per Cubic meter	4,39,355.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	52.00 Number	230.00	Rupees Two Hundred Thirty Only	Each	11,960.00
4	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	37.02 Cubic meter	750.00	Rupees Seven Hundred Fifty Only	Per Cubic meter	27,765.00
	Total					4,90,829.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					


 Executive Engineer,
 Dehra Division,
 HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.4,99,459.00
 Earnest Money :-Rs. 10000.00
 Time Limit :- Three Months.

Name of work:- Restoration of Rain damages on Sapraloo Tihri road Km. 0/0 to 10/00 (SH:-Construction of PCC R/wall at RD. 7/180 to 7/198)

Sr. No.	Description of Item	Quantity	Rate In		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	25.37 Cubic meter	275.00	Rupees Two Hundred Seventy Five Only	Per Cubic meter	6,977.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	112.53 Cubic meter	4050.00	Rupees Four Thousand Fifty Only	Per Cubic meter	4,55,747.00

Sr. No.	Description of Item	Quantity	Rate In		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	27.00 Number	220.00	Rupees Two Hundred Twenty Only	Each	5,940.00
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	41.06 Cubic meter	750.00	Rupees Seven Hundred Fifty Only	Per Cubic meter	30,795.00
Total						4,99,459.00
		% Above/below:				
		Quoted Amount in Figures				
		Quoted Amount in Words				

Executive Engineer,
Dehra Division,
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.4,99,459.00
 Earnest Money :-Rs. 10000.00
 Time Limit :- Three Months.

Name of work:- Restoration of rain damages Dhatti to Kural Road Km. 0/0 to 4/00 (SH:- C/o PCC R/wall at RD. 2/400 to 2/420.25)

Sr. No.	Description of Item	Quantity	Rate In		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, levelling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	41.31 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	11,980.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	110.97 Cubic meter	4050.00	Rupees Four Thousand Fifty Only	Per Cubic meter	4,49,429.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	38.00 Number	230.00	Rupees Two Hundred Thirty Only	Each	8,740.00
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	39.08 Cubic meter	750.00	Rupees Seven Hundred Fifty Only	Per Cubic meter	29,310.00
	Total					4,99,459.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Executive Engineer,
Dehra Division,
R.P.W.D. Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.499695.00
 Earnest Money :-Rs. 10000.00
 Time Limit :- Three Months.

Name of work:- Construction of Ambulance road from NH-88/303 Shree Mandir to Gujjar Basti via Saleter ward No.2 Km. 0/00 to 1/00 (SH:-C/o Embankment filling at RD. 0/0 to 0/040 & Cement concrete pavement at RD 0/0 to 0/050)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Construction of embankment with approved materials deposited at site obtained from approved source or roadway cutting and excavation from drains and other structures, graded and completed to meet requirement, including setting out, true to the lines, grades, width and side slopes in accordance with drawings, pumping or bailing out water (surface/sub-soil water) up to any depth or any quantum of water, including spreading the embankment material with motor -Grader in successive layers of 20mm (twenty millimeter) uniform thickness, compacting with vibratory roller 8-10 (eight to ten) Tonne static weight to meet the requirements of table 300.1 & 300.2 of MORD technical specification clause 301.5 and as per the entire satisfactions and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sales tax or any other taxes imposed by the Government.	352.80 Cubic meter	270.00	Rupees Two Hundred Seventy Only	Per Cubic meter	95,256.00
2	Granular sub-base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	43.31 Cubic meter	850.00	Rupees Eight Hundred Fifty Only	Per Cubic meter	36,814.00
3	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	28.88 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	1,16,964.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
4	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3(one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	27.56 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	1,88,788.00
5	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	12.50 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	61,875.00
	Total					4,99,695.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Executive Engineer,
Dehra Division,
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.497482.00
 Earnest Money :-Rs. 100000.00
 Time Limit :- Three Months.

Name of work:- Construction of Ambulance road from NH-88/303 Shree Mandir to Gujjar Basti via Saleter ward No.2 Km. 0/00 to 1/00 (SH:-C/o Cement Concrete Pavement at RD 0/052 to 0/113.50)

Sr. No.	Description of item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Granular sub-base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	53.27 Cubic meter	850.00	Rupees Eight Hundred Fifty Only	Per Cubic meter	45,280.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	35.52 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	1,43,856.00
3	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3(one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	33.90 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	2,32,215.00

Sr. No.	Description of Item	Quantity	Rate In		Unit	Amount
			Figures	Words		
4	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	15.38 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	76,131.00
	Total					4,97,482.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					


 Executive Engineer,
 Dehra Division,
 HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.499083.00
 Earnest Money :-Rs. 10000.00
 Time Limit :- Three Months.

Name of work:- Construction of Ambulance road from NH-88/303 Shree Mandir to Gujjar Basti via Satefer ward No.2 Km. 0/00 to 1/00 (SH:-C/o Cement Concrete Pavement at RD 0/115.50 to 0/177.20)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Granular sub-base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	53.45 Cubic meter	850.00	Rupees Eight Hundred Fifty Only	Per Cubic meter	45,433.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	35.63 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	1,44,302.00
3	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3(one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	34.01 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	2,32,969.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
4	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M Ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	15.43 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	76,379.00
	Total					4,99,083.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Executive Engineer,
Dehra Division,
UP PWD Dehra

45


PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.499904.00
Earnest Money :-Rs. 10000.00
Time Limit :- Three Months.

Name of work:- Construction of Ambulance road from NH-88/303 Shree Mandir to Guljar Basti via Saleter ward No.2 Km. 0/00 to 1/00 (SH:-C/o Cement Concrete Pavement at RD 0/178.20 to 0/240)

Sr. No.	Description of Item	Quantity	Rate In		Unit	Amount
			Figures	Words		
1	Granular sub-base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	53.53 Cubic meter	850.00	Rupees Eight Hundred Fifty Only	Per Cubic meter	45,501.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	35.69 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	1,44,545.00
3	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3(one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government	34.07 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	2,33,380.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
4	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	15.45 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	76,478.00
	Total					4,99,904.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					


 Executive Engineer,
 Dehra Division,
 HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.499138.00
 Earnest Money :-Rs. 10000.00
 Time Limit :- Three Months.

Name of work:- Construction of Ambulance road from NH-88/303 Shree Mandir to Gujjar Basti via Saleter ward No.2 Km. 0/00 to 1/00 (SH:-C/o Cement Concrete Pavement at RD 0/242 to 0/307)

Sr. No.	Description of Item	Quantity	Rate In		Unit	Amount
			Figures	Words		
1	Granular sub-base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	53.75 Cubic meter	850.00	Rupees Eight Hundred Fifty Only	Per Cubic meter	45,688.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	35.83 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	1,45,112.00
3	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3(one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	33.27 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	2,27,900.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
4	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	16.25 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	80,438.00
	Total					4,99,138.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Executive Engineer,
Dehra Division,
HPPWD Dehra