HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PWI/CB/2nd C/Tender case/2023-24-_____ Dated:_____

To

The Executive Engineer,
HP.PWD. Nirman Bhawan, Nigam Vihar,
Shimla.

Subject:- Publication of tender Notice on departmental site.

Sir,

In this context, it is submitted that the tender notice is being enclosed herewith for up loading on Department web-site as per Notification of the Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A-9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and in public intrest.

DA/As above.

Executive Engineer,
Indora Division, HPPWD,
Indora.

Copy forwarded for information to following for information please:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur.
2. All the Assistant Engineers working under this Division.
3. All the Contractors.
4. Notice Board.

DA/As above.

Executive Engineer,
Indora Division, HPPWD, Indora
Telephone No. 01893-242336
e-mail- eepwd-indora-hp@gov.in

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

(2)

Sealed item rate tenders on the form 6 & 8 are hereby invited by the Executive Engineer, Indora Division HPPWD., Indora on behalf of the worthy Governor of Himachal Pradesh for the following works from the approved and eligible contractor or in presence of the contractor or their authorized representatives who may like to be present. The schedule date of the tender is being given below please:-

1.	Date and time of receipt of application for tender form.	26.07.2024 upto 12.00 Noon.
2.	Date and time of Sale/ issue of tender form:-	26.07.2024 from 3.00 PM to 5.00 PM.
3.	Date and time of receipt of tenders:-	27.07.2024 at 11.00 A.M.
4.	Date and time of opening of tenders:-	27.07.2024 AT 11.30 A.M.

The Earnest Money in shape of National Saving Certificate/ time deposit account/saving account in any nationalized bank in HP duly pledged in favour of the Executive Engineer, Indora division, HPPWD., Indora will be received along with application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders will be kept open for 90 days from the date of opening of tender. The Executive Engineer, Indora Division, HP.PWD. Indora reserves the right to reject any or all tenders without assigning any reason. The contractor should append their Enlistment/ Renewed Certificate/ Sale Registration Number with the application for issue of tender form. If any of the mentioned above date happens to be holiday the same should be processed on next working day.

Sr. No	Name of work.	Estimated cost (Rs.)	Earnest money (Rs)	Time limit.	Cost of form	Eligible class of Contractor.
1.	Balance work for the C/O HP.PWD. Division office building at Indora (HP) (SH:- P/F Glass Pans, Aluminium Grill, Handle etc).	497823	10000	Six Month.	350/-	Class D & C
2.	Balance work for the C/O HP.PWD. Division office building at Indora (HP) (SH:- P/F S.S. Rail, Primer & Painting).	494603	10000	Two Month.	350/-	Class D & C
	Balance work for the C/O HP.PWD. Division office building at Indora (HP) (SH:- Wall Paining, wire guage shutter.).	499585	10000	Two Month.	350/-	Class D & C

TERMS AND CONDITIONS:-

1. The contractor/Firm shall have his GST No. & copy of the same be attached with the application.
2. The intending Contractors/firm should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender for The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender form. In this regard, the contractor has submitted an affidavit that he is not having more than two work
5. The intending contractors are required to see the site of the work before submitting the tender.
6. The offer of the tender shall remain valid upto 75 days after the opening of tender.
7. The Executive Engineer reserves the right to reject/accept any or all tenders without assigning any reasons.

Executive Engineer,
Indora Division, HPPWD,
Indora.

Copy to the following for inforamion and necessary action :-

1. The Superintending Engineer, 9th Circle, HP.PWD. Nurpur.
2. All Assistant Engineer working under this office.
3. Notice Board.

Executive Engineer,
Indora Division, HPPWD, Indora,
elephone No. 01893-2241233
e-mail- eepwd-indora-hp@gov.in
On behalf of Governor.

BILL OF QUANTITY

Name of Work:- Balance work for the C/o HPPWD Division Office building at Indora. (SH:- Providing and Fixing Glass Pans, Aluminium Grill, handles etc)

Estimated Cost :-Rs. 497823/-

Earnest Money:- Rs 10000/-

Time Limit :- Two Months

Sr.No.	Description of Items	Quantity	Units	Rate in fig.	Words	Amount
1	Providing and fixing glazing with glass pans of 5.00 mm (five millimetre) thickness weight not less than 12.50 kg (twelve point fifty kilograme) per square metre (Modi Guard/Saint Gobain) in aluminium door, window,ventilator shutters and partition etc with PVC/neoprene gasket etcetera complete as per the architectural drawings, design, specification (cost of aluminium snap beading shall be paid in basic item) and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including of octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	208.08	Per Square Meter	1100.00	Rupees One thousand One hundred only.	228888.00
2	Providing and fixing aluminium (Zindal/ Hindalco make) anodized powder coated grill of 8mm (Eight Millimeter) thick Providing and fixing anodised aluminium grill (anodised transparent or dyed to required shade according to IS: 1868 with minimum anodic coating of grade AC 15) of approved design/pattern, with approved standard section and fixed to the existing window frame with C.P. brass/ stainless steel screws @ 200 mm centre to centre, including cutting the grill to proper opening size for fixing and operation of handles and fixing approved anodised aluminium standard section around the opening, all complete as per requirement and direction of Engineer in-charge. (Only weight of grill to be measured for payment) complete as per approved design, specification and as per the direction of Engineer-in-Charge including carriage of material within all leads , lifts and other incidentals. The rate is including of octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	144.41	Per Kilogramme	500.00	Rupees Five Hundred Only.	72206.00
3	Providing and fixing aluminium handles, ISI marked,anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etcetera complete as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.					
	(i) 125mm (One Hundred Twenty Five Millimeter)	118.00	Each	70.00	Rupees Seventy Only	8260.00
	(ii) 100mm (One Hundred Millimeter)	380.00	Each	60.00	Rupees Sixty Only.	22800.00
4	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etcetera complete as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.					
	(i) 300x16mm (Three Hundred into Sixteen Millimeter)	32.00	Each	260.00	Rupees Two Hundred Sixty Only.	8320.00

5	Providing and fixing bright finished brass ball catcher 10mm (Ten Millimeter) dia complete as per directions and entire satisfaction of engineer in charge including carriage of material within all leads , lift and other incidentals . The rate is inclusive of octroi , royality , malkhana , toll tax , sale tax , Gst and any taxes imposed by Government.	170.00	Each	52.00	Rupees Fifty Two Only.	8840.00
6	Providing and fixing 150mm (One hundred Fifty Millimeter) aluminium eyes and hooks ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etcetera complete as per directions and entire satisfaction of engineer in charge including carriage of material within all leads , lift and other incidentals . The rate is inclusive of octroi , royality , malkhana , toll tax , sale tax , Gst and any taxes imposed by Government.	115.00	Each	60.00	Rupees Sixty Only.	6900.00
7	Providing and fixing 25mm (twenty five millimetre) dia stainless steel curtain rod having well thickness of 1.25mm (One Point Twenty Five Millimeter) with two stainless steel brackets fixed with C.P Brass screws and P.V.C sheeves etcetera wherever necessary complete as per directions and entire satisfaction of engineer in charge including carriage of material within all leads , lift and other incidentals . The rate is inclusive of octroi , royality , malkhana , toll tax , sale tax , Gst and any taxes imposed by Government.	138.40	Per Running Meter	560.00	Rupees Five Hundred Sixty Only.	77504.00
8	Providing and Fixing 65x35mm (Sixty Five into Thirty Five Millimeter) special quality bright finished CB locks with six leverse complete as per directions and entire satisfaction of engineer in charge including carriage of material within all leads , lift and other incidentals . The rate is inclusive of octroi , royality , malkhana , toll tax , sale tax , Gst and any taxes imposed by Government.	30.00	Each	250.00	Rupees Two Hundred Fifty Only.	7500.00
9	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etcetera complete as per directions and entire satisfaction of engineer in charge including carriage of material within all leads , lift and other incidentals . The rate is inclusive of octroi , royality , malkhana , toll tax , sale tax , Gst and any taxes imposed by Government.	38.00	Each	60.00	Rupees Sixty Only.	2280.00
10	Providing and laying Doctor fixited Tourch Shield (P3160-3mm) shall be used for water proofing treatment Doctor fixited Tourch Shield on terrace/depressed portion membrences are made from high grade bitumen and selector polymers the APP/SBS modified bitumen than coated to non woven polyster inovemply reinforcement to give high tear and puncture resistance. The application shall be done as per approved drawing, design and specifications complete as per the direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including of octroi, royality, Malkana, toll tax, sales tax,GST and any other taxes imposed by the Government.	91.37	Per Square Meter	350.00	Rupees Three Hundred Fifty Only.	31980.00
11	Providing and fixing 8 mm (Eight Millimeter) dia C.P. / S.S. Jet of Continental series of Jaquar / Classik series of Hindware /Ocean series of Cera / Vintage series of Kerovite & Hindon series of Jal with flexible tube upto 1 (One) metre long with S.S. triangular plate to Eureopean type W.C. of quality and make as approved by Engineer - in - charge including carriage of material with in all leads, lifts and other incidentals. The rate is including of octroi, royality, Malkana, toll tax, sales tax,GST and any other taxes imposed by the Government.	15.00	Each	600.00	Rupees Six Hundred Only.	9000.00

12	Providing and fixing Mixer for kitchen sink and wash basin with casted swinging spout at top of mixure hindware /cera /Jaquar make as per approved design, specification and as per the direction of Engineer-in-Charge including carriage of material with in all leads, lifts and other incidentals. The rate is including of octroi, royality, Malkana, toll tax, sales tax,GST and any other taxes imposed by the Government.	2.00	Each	4350.00	Rupees Four thousand Three Hundred Fifty Only.	8700.00
13	Providing and fixing 32 mm (Thirty Two Millimeter) dia P.V.C.flexible waste pipe of Finolex , Relpipe (Reliance) , Vectus for sink or wash basin including P.V.C. waste fittings complete as per approved drawing, design, specification and as per the direction of Engineer-in-Charge including carriage of material with in all leads , lifts and other incidentals. The rate is including of octroi, royality, Malkana, toll tax, sales tax,GST and any other taxes imposed by the Government.	30.00	Each	155.00	Rupees One Hundred fifty Five Only.	4650.00
		Total:-				**497823.00**

Executive Engineer
Indora Division
HP.PWD Indora.

BILL OF QUANTITY

Name of Work:- Balance work for the C/o HPPWD Division Office building at Indora. (SH:- Providing and Fixing SS Rail, Primer and Painting

Estimated Cost :-Rs. 494603/-
Earnest Money:- Rs 10000/-
Time Limit :- Two Months

Sr.No.	Description of Items	Quantity	Units	Rate in fig.	Words	Amount
1	Providing and fixing 40 mm/50 mm (Forty Millimeter/Fifty Millimeter) dia SST Pipe Grab bars fixed with wall and floor as per detail and specificationincluding welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete as per approved drawing, design, specification and as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	10.00	Per Running Meter	1096.10	Rupees One thousand One hundred only.	10961.00
2	Applying primingcoats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content with water thinnable cement primer on wall surface having VOC content less then 50 grams/litre complete as per approved drawing, design, specification and as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	3643.38	Per Sqaure Meter	50.00	Rupees Five Hundred Only.	182169.00
3	Finishing wall with Apex weather proof exterior grade emulsion of (ASIAN/NEROLAC/SURAKSHA of Nerolac paint BERGER/DULUX) paints of approved shade having VOC less then 50gm/litre and UV reistance as per IS 15489:2004, Alkali and fungal resistance, dirt resistance exterior paint of required shade with silicon additives two or more coats applied @ 1.43 litre/10sqm over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm with in all leads, lifts and other incidential as per approved drawing, design, specification and direction by the Engineer-in-charge including carriage of materials . The rate is including of octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	2109.27	Per Sqaure Meter	110.00	Rupees One Hundred Ten Only.	232019.00
4	Applying priming two or more coats with ready mixed paint brushing with white lead of Asian/Dulux/Nerolac make for priming coat over new wood and wood based surfaces after and including preparing the surface by thoroughly cleaning oil, grease, dirt, dust and other foreign matter sand papering and knotting complete up to any floor level as per approved drawing, design,specification and as per the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including of octroi, royality, Malkana, toll tax, sales tax,GST and any other taxes imposed by the Government.	450.90	Per Sqaure Meter	40.00	Rupees Fourty Only.	18036.00
5	Painting two or more coats (excluding priming coat) on new wood and wood based surfaces with rady mixed paint brushing to give an even shade including cleaning of all dirt, dust and other foreign matter sand papering and stopping with ready mixed paint white of Asian/Dulux and Nerolac make complete up to any floor level as per approved drawing, design, specification and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royality, Malkana, toll tax, sales tax,GSTand any other taxes imposed by the Government.	450.90	Per Sqaure Meter	75.00	Rupees Seventy Five Only.	33818.00

6	Providing and fixing double action hydraulic floor spring of approved brand and manufacture conforming to IS : 6315, having brand logo embossed on the body / plate with double spring mechanism and door weight upto 125 kg (One hundred Twenty five kilogramme) for doors, including cost of cutting floors, embedding in floors as required and making good the same matching to the existing floor finishing and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etcetera complete as per approved drawing, design, specification and direction of Engineer-in-charge including carriage of material within all leads, lifts and other incidentials With stainless steel cover plate minimum 1.25 mm (One Point Twenty five millimeter) thickness. The rate is including of octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	8.00	Each	2200.00	Rupees Two Thousand Two Hundred Only.	17600.00
		Total:-				**494603.00**

Executive Engineer
Indora Division
HP.PWD Indora.

BILL OF QUANTITY

Name of Work:- Balance work for the C/o HPPWD Division Office building at Indora. (SH:- Wall Painting, wire guage shutter)

Estimated Cost :-Rs. 499585/-
Earnest Money:- Rs 10000/-
Time Limit :- Two Months

Sr.No.	Description of Items	Quantity	Units	Rate in fig.	Words	Amount
1	Wall finishing two or more coats with Acrylic washable Emulsion of Asian Paints/ Nerolac Paints / Berger Paints / Dulux Paints Above Dado / skirting as per Approved from this office complete as per approved drawing, design, specification and direction by the Engineer-in-charge including carriage of material within all leads , lift and other incidentals . The rate is including of octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	3643.38	Per Sqaure Meter	80.00	Rupees Eighty only.	291470.00
2	Painting on G.S sheet with Synthetic enamel paint of approved and manufacture of required colour to give an even shade: New work (Two or more coats) including a coat of approved steel primer but excluding a coat of mordant solution complete as per approved drawing, design, specification and direction by the , Engineer-in-charge including carriage of material within all leads , lift and other incidentals . The rate is including of octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	313.92	Per Sqaure Meter	118.00	Rupees One Hundred Eighteen Only.	37043.00
3	Providing and fixing wire fly proof stainless steel (Grade 304) wire guage of 0.5mm (Zero point five millimeter) dia wire and 1.4mm aperture on both side in windows, clerestory windows and doors with S.S Flat 15x3mm (Fifteen into Three millimeter) and bolts complete and as per the direction of Engineer-in-Charge including carriage of materials within all leads , lifts and other incidentals. The rate is including of octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	65.88	Per Sqaure Meter	1200.00	Rupees One thousand Two Hundred Only.	79056.00
4	Providing and fixing 12 mm (twelve millimetre) thick door shutter in fill panel both side prelaminated water proof particle board with decorative lamination on both sides of Action Tessa/Centuary/Kitlam/Kitply, Green ply three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etceter complete as per architectural drawings ,design,specification and directions of engineer- in-charge with in all leads , lifts and other incidentals.The rate is including of octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	30.64	Per Sqaure Meter	1400.00	Rupees One thousand Four Hundred Only.	42896.00
5	Providing and fixing aluminium tower bolts, ISI marked,anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etcetera complete as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.					
	(i) 200x10mm (Two Hundred into Ten Millimeter)	80.00	Each	82.00	Rupees Eighty Two Only.	6560.00
	(ii) 150x10mm (One Hundred Fifty into Ten Millimeter)	532.00	Each	80.00	Rupees Eighty Only.	42560.00
					Total:-	**499585.00**

Executive Engineer
Indora Division HPPWD
Indora

BILL OF QUANTITY

Name of Work:- Balance work for the C/o HPPWD Division Office building at Indora. (SH:- Providing and Fixing Glass Pans, Aluminium Grill, handles etc)

Estimated Cost :-Rs. 497823/-
Earnest Money:- Rs 10000/-
Time Limit :- Two Months

Sr.No.	Description of Items	Quantity	Units	Rate in fig.	Words	Amount
1	Providing and fixing glazing with glass pans of 5.00 mm (five millimetre) thickness weight not less than 12.50 kg (twelve point fifty kilograme) per square metre (Modi Guard/Saint Gobain) in aluminium door, window,ventilator shutters and partition etc with PVC/neoprene gasket etcetera complete as per the architectural drawings, design, specification (cost of aluminium snap beading shall be paid in basic item) and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including of octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	208.08	Per Square Meter			
2	Providing and fixing aluminium (Zindal/ Hindalco make) anodized powder coated grill of 8mm (Eight Millimeter) thick Providing and fixing anodised aluminium grill (anodised transparent or dyed to required shade according to IS: 1868 with minimum anodic coating of grade AC 15) of approved design/pattern, with approved standard section and fixed to the existing window frame with C.P. brass/ stainless steel screws @ 200 mm centre to centre, including cutting the grill to proper opening size for fixing and operation of handles and fixing approved anodised aluminium standard section around the opening, all complete as per requirement and direction of Engineer in-charge. (Only weight of grill to be measured for payment) complete as per approved design, specification and as per the direction of Engineer-in-Charge including carriage of material within all leads , lifts and other incidentals. The rate is including of octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	144.41	Per Kilogramme			
3	Providing and fixing aluminium handles, ISI marked,anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etcetera complete as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.					
	(i) 125mm (One Hundred Twenty Five Millimeter)	118.00	Each			
	(ii) 100mm (One Hundred Millimeter)	380.00	Each			
4	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etcetera complete as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.					
	(i) 300x16mm (Three Hundred into Sixteen Millimeter)	32.00	Each			

5	Providing and fixing bright finished brass ball catcher 10mm (Ten Millimeter) dia complete as per directions and entire satisfaction of engineer in charge including carriage of material within all leads , lift and other incidentals . The rate is inclusive of octroi , royality , malkhana , toll tax , sale tax , Gst and any taxes imposed by Government.	170.00	Each			
6	Providing and fixing 150mm (One hundred Fifty Millimeter) aluminium eyes and hooks ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etcetera complete as per directions and entire satisfaction of engineer in charge including carriage of material within all leads , lift and other incidentals . The rate is inclusive of octroi , royality , malkhana , toll tax , sale tax , Gst and any taxes imposed by Government.	115.00	Each			
7	Providing and fixing 25mm (twenty five millimetre) dia stainless steel curtain rod having well thickness of 1.25mm (One Point Twenty Five Millimeter) with two stainless steel brackets fixed with C.P Brass screws and P.V.C sheeves etcetera wherever necessary complete as per directions and entire satisfaction of engineer in charge including carriage of material within all leads , lift and other incidentals . The rate is inclusive of octroi , royality , malkhana , toll tax , sale tax , Gst and any taxes imposed by Government.	138.40	Per Running Meter			
8	Providing and Fixing 65x35mm (Sixty Five into Thirty Five Millimeter) special quality bright finished CB locks with six leverse complete as per directions and entire satisfaction of engineer in charge including carriage of material within all leads , lift and other incidentals . The rate is inclusive of octroi , royality , malkhana , toll tax , sale tax , Gst and any taxes imposed by Government.	30.00	Each			
9	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etcetera complete as per directions and entire satisfaction of engineer in charge including carriage of material within all leads , lift and other incidentals . The rate is inclusive of octroi , royality , malkhana , toll tax , sale tax , Gst and any taxes imposed by Government.	38.00	Each			
10	Providing and laying Doctor fixited Tourch Shield (P3160-3mm) shall be used for water proofing treatment Doctor fixited Tourch Shield on terrace/depressed portion membrences are made from high grade bitumen and selector polymers the APP/SBS modified bitumen than coated to non woven polyster inovemply reinforcement to give high tear and puncture resistance. The application shall be done as per approved drawing, design and specifications complete as per the direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including of octroi, royality, Malkana, toll tax, sales tax,GST and any other taxes imposed by the Government.	91.37	Per Square Meter			
11	Providing and fixing 8 mm (Eight Millimeter) dia C.P. / S.S. Jet of Continental series of Jaquar / Classik series of Hindware /Ocean series of Cera / Vintage series of Kerovite & Hindon series of Jal with flexible tube upto 1 (One) metre long with S.S. triangular plate to Eureopean type W.C. of quality and make as approved by Engineer - in - charge including carriage of material with in all leads, lifts and other incidentals. The rate is including of octroi, royality, Malkana, toll tax, sales tax,GST and any other taxes imposed by the Government.	15.00	Each			

12	Providing and fixing Mixer for kitchen sink and wash basin with casted swinging spout at top of mixure hindware /cera /Jaquar make as per approved design, specification and as per the direction of Engineer-in-Charge including carriage of material with in all leads, lifts and other incidentals. The rate is including of octroi, royality, Malkana, toll tax, sales tax,GST and any other taxes imposed by the Government.	2.00	Each			
13	Providing and fixing 32 mm (Thirty Two Millimeter) dia P.V.C.flexible waste pipe of Finolex , Relpipe (Reliance) , Vectus for sink or wash basin including P.V.C. waste fittings complete as per approved drawing, design, specification and as per the direction of Engineer-in-Charge including carriage of material with in all leads , lifts and other incidentals. The rate is including of octroi, royality, Malkana, toll tax, sales tax,GST and any other taxes imposed by the Government.	30.00	Each			
		Total:-				

Executive Engineer
Indora Division
HP.PWD Indora.

BILL OF QUANTITY

Name of Work:- Balance work for the C/o HPPWD Division Office building at Indora. (SH:- Providing and Fixing SS Rail, Primer and Painting

Estimated Cost :-Rs. 494603/-
Earnest Money:- Rs 10000/-
Time Limit :- Two Months

Sr.No.	Description of Items	Quantity	Units	Rate in fig.	Words	Amount
1	Providing and fixing 40 mm/50 mm (Forty Millimeter/Fifty Millimeter) dia SST Pipe Grab bars fixed with wall and floor as per detail and specificationincluding welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete as per approved drawing, design, specification and as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	10.00	Per Running Meter			
2	Applying primingcoats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content with water thinnable cement primer on wall surface having VOC content less then 50 grams/litre complete as per approved drawing, design, specification and as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	3643.38	Per Sqaure Meter			
3	Finishing wall with Apex weather proof exterior grade emulsion of (ASIAN/NEROLAC/SURAKSHA of Nerolac paint BERGER/DULUX) paints of approved shade having VOC less then 50gm/litre and UV reistance as per IS 15489:2004, Alkali and fungal resistance, dirt resistance exterior paint of required shade with silicon additives two or more coats applied @ 1.43 litre/10sqm over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm with in all leads, lifts and other incidential as per approved drawing, design, specification and direction by the Engineer-in-charge including carriage of materials . The rate is including of octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	2109.27	Per Sqaure Meter			
4	Applying priming two or more coats with ready mixed paint brushing with white lead of Asian/Dulux/Nerolac make for priming coat over new wood and wood based surfaces after and including preparing the surface by thoroughly cleaning oil, grease, dirt, dust and other foreign matter sand papering and knotting complete up to any floor level as per approved drawing, design,specification and as per the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including of octroi, royality, Malkana, toll tax, sales tax,GST and any other taxes imposed by the Government.	450.90	Per Sqaure Meter			
5	Painting two or more coats (excluding priming coat) on new wood and wood based surfaces with rady mixed paint brushing to give an even shade including cleaning of all dirt, dust and other foreign matter sand papering and stopping with ready mixed paint white of Asian/Dulux and Nerolac make complete up to any floor level as per approved drawing, design, specification and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royality, Malkana, toll tax, sales tax,GSTand any other taxes imposed by the Government.	450.90	Per Sqaure Meter			

6	Providing and fixing double action hydraulic floor spring of approved brand and manufacture conforming to IS : 6315, having brand logo embossed on the body / plate with double spring mechanism and door weight upto 125 kg (One hundred Twenty five kilogramme) for doors, including cost of cutting floors, embedding in floors as required and making good the same matching to the existing floor finishing and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etcetera complete as per approved drawing, design, specification and direction of Engineer-in-charge including carriage of material within all leads, lifts and other incidentials With stainless steel cover plate minimum 1.25 mm (One Point Twenty five millimeter) thickness. The rate is including of octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	8.00	Each			
		Total:-				

Executive Engineer
Indora Division
HP.PWD Indora.

BILL OF QUANTITY

Name of Work:- Balance work for the C/o HPPWD Division Office building at Indora. (SH:- Wall Painting, wire guage shutter)

Estimated Cost :-Rs. 499585/-
Earnest Money:- Rs 10000/-
Time Limit :- Two Months

Sr.No.	Description of Items	Quantity	Units	Rate in fig.	Words	Amount
1	Wall finishing two or more coats with Acrylic washable Emulsion of Asian Paints/ Nerolac Paints / Berger Paints / Dulux Paints Above Dado / skirting as per Approved from this office complete as per approved drawing, design, specification and direction by the Engineer-in-charge including carriage of material within all leads , lift and other incidentals . The rate is including of octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	3643.38	Per Sqaure Meter			
2	Painting on G.S sheet with Synthetic enamel paint of approved and manufacture of required colour to give an even shade: New work (Two or more coats) including a coat of approved steel primer but excluding a coat of mordant solution complete as per approved drawing, design, specification and direction by the Engineer-in-charge including carriage of material within all leads , lift and other incidentals . The rate is including of octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	313.92	Per Sqaure Meter			
3	Providing and fixing wire fly proof stainless steel (Grade 304) wire guage of 0.5mm (Zero point five millimeter) dia wire and 1.4mm aperture on both side in windows, clerestory windows and doors with S.S Flat 15x3mm (Fifteen into Three millimeter) and bolts complete and as per the direction of Engineer-in-Charge including carriage of materials within all leads , lifts and other incidentals. The rate is including of octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	65.88	Per Sqaure Meter			
4	Providing and fixing 12 mm (twelve millimetre) thick door shutter in fill panel both side prelaminated water proof particle board with decorative lamination on both sides of Action Tessa/Centuary/Kitlam/Kitply, Green ply three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etceter complete as per architectural drawings ,design,specification and directions of engineer- in-charge with in all leads , lifts and other incidentals.The rate is including of octroi, royality, Malkana, toll tax, GST and any other taxes imposed by the Government.	30.64	Per Sqaure Meter			
5	Providing and fixing aluminium tower bolts, ISI marked,anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etcetera complete as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.					
	(i) 200x10mm (Two Hundred into Ten Millimeter)	80.00	Each			
	(ii) 150x10mm (One Hundred Fifty into Ten Millimeter)	532.00	Each			
					Total:-	

Executive Engineer
Indora Division HPPWD
Indora