



Office of
Executive Engineer B&R Division HP.PWD, Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P.) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 21-08-2024 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 19-08-2024 up to 10:00 A.M. to 12:30 P.M. and tender form can be had from this office on 20-08-2024 from 2:00 P.M. to 5:00 P.M. The earnest money as shown against each in the shape of F.O.R. of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost tender form	Eligible Class of Contractor	Time
1	Construction of LPG Gas Office cum show room at Joginder Nagar District Mandi (H.P.) (SH:- Construction of Room with Varendah).	Rs.4,14,771/-	Rs.8,300/-	Rs.350/-	Class "D"	Three Months
2	Construction of Bridge on Gugli Khad near Vill. Tatanka & C/o bridge over Neri Khad on Joginder Nagar Arthi road to join with Syuri Majharnoo road (Preparation of Hydraulic Data of bridges).	Rs. 4,98,500/-	Rs.10,000/-	Rs.350/-	Class "D"	Three months
3	Construction of Junior Engineer & Work Inspector Residence Building at Lad Bharol Tehsil Lad Bhrol District Mandi (H.P.) Construction of Additional Accommodation in PWD Rest House at Lad Bhrol in Tehsil Lad Bharol District Mandi (H.P.), Construction of Combined office/ Mini Sectt. Building at Lad Bharol in Tehsil Lad Bharol District Mandi (H.P.), & Construction of I.T.I. Building at Lad Bharol Tehsil Lad Bharol District Mandi (H.P.) (SH:- Preparation of Countour Site Plan and Cross Section).	Rs. 2,08,000/-	Rs.4,200/-	Rs.350/-	Class "D"	Three Months
4	Construction of Bridge over Sukkad Khad Between Sukhar & Sarohli village at km. 0/105 & Construction of bridge over Bajgar Khad on Chauntra Chakli Mahrehar Dohag road at km. 2/450 (SH:- Preparation of Hydraulic Data of bridges).	Rs. 4,98,500/-	Rs.10,000/-	Rs.350/-	Class "D"	Three Months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

- The contractor should produce a copy of enlistment / renewal letter at time of application.
- Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
- The contractor/Firm shall have his registration and GST No. the copy of same be attached with the application.
- The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
- No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
- The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
- The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP.PWD.,
Joginder Nagar,
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-INITI/Press/2023-24- 5540-89

Dated:- 10/07/2024

- Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-Chief, HPPWD, Shimla.
- The Chief Engineer (MZ), HPPWD, Mandi.
- The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- All the Contractor working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP.PWD.,
Joginder

① SCHEDULE OF QUANTITY

Name of work : Construction of LPG Gas Office cum Show room at Joginder Nagar District Mandi (H.P.)
(SH: Construction of Room with Varendah)

Name of work : Construction of LPG Gas Office cum Show room at Joginder Nagar District Mandi (H.P.) (SH: Construction of Room with Varendah)							Estimate Cost: Earnest Money: Time Limit :	4,14,771.00 8,300.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P		
				Figures	Words			
1	Excavation in foundation, trenches etcetera in earth work involving all classification of soil such as pick work, pick jumper work, blasting work, soft or hard rocks including chiseling/wedging out of rocks where blasting work is prohibited or any other mixed variety of intermediate soil, dewatering and removal of slush if arisen during course of construction and lifts upto all heights including stacking the excavated soil not more than three meters clear from the edge of the excavation and then returning the stacked soil in 15 cm (fifteen centimeters) thick layers when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus excavation earth within all leads/lifts by any mode of transportation and other incidental, as per the direction and entire satisfaction of Engineer-In-Charge. Any loss to the private and public property during course of construction shall be absolute responsibility of the contractor. The rate is inclusive all taxes levy by the government time to time excluding GST.	17.13	Per cubic metre					
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (one Cement isto four coarse sand) isto eight graded stone aggregate 40 mm (fourty millimeter) nominal size). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.64	Per Cubic Meter					
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:6:12 (one Cement isto six coarse sand) isto twelve graded stone aggregate 40 mm (fourty millimeter) nominal size). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.37	Per Cubic Meter					
4	Boulder filling of selected hard dry stone hand packed tightly under floor as per the direction of Engineer-In-Charge including carriage of materials within all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.94	Per cubic metre					
5	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:6 (one cement isto six coarse sand) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	10.21	Per cubic metre					

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
6	Supplying and fixing rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm (twenty seven point five centimeter) long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS-4454 - part I and M.S. top cover of required thickness for rolling shutters 80x125 mm (eighty by one point two five millimeter) M.S. laths with 1.25 mm (one point two five millimeter) thick work in single section, fixed with or top cover. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.10	Per square metre			
7	Providing corrugated G.S. sheet 0.63 mm (zero point six three millimeter) thick with zinc coating not less than 275 gm/ m ² (two hundred seventy five gramme per square meter) for roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. Impet washers or with G.I. Impet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal / vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	75.18	Per Square Meter			
8	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1440.50	Per Kilogramme			
9	Providing and fixing 12 mm (twelve millimeter) thick White face insulating board ceiling of approved quality with necessary nails etc. complete (frame work to be paid separately). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	36.90	Per Square Meter			
	Total					


 Executive Engineer
 B & R Division HP, PWD,
 Jalandhar Nagar

Schedule of Quantity

Name of work:- Construction of bridge on Gugli khad near vill. Tatanka & C/O bridge over Neri Khad on Joginder Nagar Arthi road to join with Syuri Majharnoo road. **(SH: Preparation of Hydraulic Data of bridges)**

Estimated Cost:- 498500.00

Earnest Money:- 10000.00

Time:- Three months

Sr. No.	Description of item	Qty.	Rate	In words	Unit	Amount
1	Preparation of Hydraulic data such as contour site plan, L-section of nallah and approaches, Cross-section 7 (seven) numbers upto 500 metre up stream and 500 metre down stream, Index plan, catchment area as per survey sheet, proforma of hydraulic data duly filled properly and necessary discharge calculation sheet as required by the Engineer-in-Charge. The Hydraulic data in triplicate copy get approved from the Circle office as well as Chief office with relevant drawings and to attend all observations raised by design office till the approval of GAD which is evolved at circle/ zonal office and soft copy in the form of Compact Disc (C.D.) of above mentioned Hydrauluc data including all formats and other incidental charges complete in all respect. The rate is included all taxes levy by the Govt. time to time excluding GST.	2.00			Per Job	
2	Geotechnical Investigation in manuscript form and submission of the same to higher office for approval. If any correction/ amendment has desired by the head office the same may be corrected as desired and directed by the Engineer - In -charge complete in all respect. After approval the same should be submitted in 3 copies as per conditions of TOR. (Borehole 2 nos. depth upto 15 mtr. each for Gugli khad near vill. Tatanka) The rate is inclusive all taxes levy by the government time to time excluding GST.	30.00			Per Running meter	
	Total					


 Executive Engineer,
 B & R Division
 HP, PWD, Joginder Nagar

Schedule of Quantity

Estimated Cost:- 208000.00
 Earnest Money:- 4200.00
 Time:- Two months

Name of work:- Construction of Junior Engineer & Work Inspector Residence Building at Ladbharol Tehsil Lad Bharol District Mandi (H.P.), Construction of Additional Accommodation in PWD Rest House at Lad Bharol in Tehsil Lad Bharol District Mandi (H.P.), Construction of Combined office/ Mini Sectt. building at Lad Bharol in Tehsil Lad Bharol District Mandi (H.P.), & Construction of I.T.I. Building at Lad Bharol Tehsil Lad Bharol District Mandi (H.P).

Sub Head: Preparation of Contour Site Plan and Cross Section.

Sr. No.	Description of item	Qty.	Unit	Rate		Amount
				In Figure	In Words	
1	Site Survey using total station/DGPS and preparation of Survey and contour plan at desired intervals. The Survey will be carried out to show all boundary points compound walls, roads, trees, building structures stream electric pole, telephone pole and any other man made structure with in survey permanent structure including supply of 3 sets of drawing along with soft copy of entire survey work and approval of contour plan from heigher authority as per direction of Engineer-in-Charge including other incidentals and soft copy. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.00	Per Job			
	Total.					

Executive Engineer,
 B & R Division, HP.PWD
 Joginder Nagar

Schedule of Quantity

Name of work:- Construction of Bridge over Sukkad Khad between Sukhar & Sarohli Village at KM 0/105 & Construction of ridge over Bajgar Khad on Chauntra Chakli Mahrehar Dohg Road at KM 2/450. (SH: Preparation of Hydraulic Data of bridges)

Estimated Cost:- 498500.00
 Earnest Money:- 10000.00
 Time:- Three months

Sr. No.	Description of item	Qty.	Rate	In words	Unit	Amount
1	Preparation of Hydraulic data such as contour site plan, L-section of nallah and approaches, Cross-section 7 (seven) numbers upto 500 metre up stream and 500 metre down stream, Index plan, catchment area as per survey sheet, proforma of hydraulic data duly filled properly and necessary discharge calculation sheet as required by the Engineer-in-Charge. The Hydraulic data in triplicate copy get approved from the Circle office as well as Chief office with relevant drawings and to attend all observations raised by design office till the approval of GAD which is evolved at circle/ zonal office and soft copy in the form of Compact Disc (C.D.) of above mentioned Hydrayulic data including all formats and other incidental charges complete in all respect. The rate is included all taxes levy by the Govt. time to time excluding GST.	2.00			Per Job	
2	Geotechnical Investigation in manuscript form and submission of the same to higher office for approval. If any correction/ amendment has desired by the head office the same may be corrected as desired and directed by the Engineer - In -charge complete in all respect. After approval the same should be submitted in 3 copies as per conditions of TOR. (Borehole 2 nos. depth upto 15 mtr. each for Sukkad Khad) The rate is inclusive all taxes levy by the government time to time excluding GST.	30.00			Per Running meter	
	Total					

Executive Engineer,
 B & R Division
 HP.PWD, Jalandhar Nagar