

**O/o the Executive Engineer, Karchham Division, HP.PWD., Bhabanagar-172115.**

Web: [www.hppwd.gov.in](http://www.hppwd.gov.in), e-mail: [ee-karc-hp@nic.in](mailto:ee-karc-hp@nic.in) DDO KNR04-651 Phone No-01786-292897

**Registered**

**No:- PW- BHNH-B&R-EA-I-NIT/2024-25- 2495-2500**

**Dated:- 18-7-2024**

To

The Executive Engineer (IT Cell),  
Nigam Bihar, Himachal Pradesh Shimla-2.


**Subject:- Publication of Notice Inviting Tender.**

Sir,

I am enclosing herewith the “**Notice Inviting Tender**” alongwith  
“**Schedule of Quantity**” for favour of information and necessary action. The work attached in list  
is very urgent nature. It is requested that the same may kindly be got published .

**DA: - Notice Inviting Tender/Schedule of Quantity.**


Yours Faithfully

  
**Executive Engineer,**  
**Karchham Division,**  
**HP.PWD., Bhabanagar.**

Copy forwarded to for information please:-

1. The Chief Engineer (SZ), Nirman Bhawan, Nigam Vihar Shimla-II .
2. The Superintending Engineer, 11<sup>th</sup> Circle, HP.PWD, Rampur Bushahr.
3. All the Assistant Engineers, working under this Division.
4. Drawing Branch/ Accounts Branch.
5. Notice Board in this office.

DA: - 1 No.

  
**Executive Engineer,**  
**Karchham Division,**  
**HP.PWD., Bhabanagar.**



O/o the Executive Engineer, Karchham Division, HP.PWD. Bhabanagar

Web: [www.hppwd.gov.in](http://www.hppwd.gov.in), Email: [ee-karc-hp@nic.in](mailto:ee-karc-hp@nic.in)

Phone No.-01786-292897

**NOTICE INVITING TENDER**

Sealed item rate tenders on PWD form No. 6&8 are invited by the **Executive Engineer, Karchham Division, HP.PWD., Bhabanagar** on behalf of the Governor H.P. for the following works reach in the office of the Executive Engineer, Karchham Division, HP.PWD., Bhabanagar on **26.07.2024** upto **10:30 A.M.** and will be opened on the same day at **3:00 P.M.** in the presence of the intending Contractors or their authorized representatives. The tender form can be had from the office of the **Executive Engineer, Karchham Division, HP.PWD., Bhabanagar** against cash payment (Non refundable) on **25.07.2024** during office hours **2:00 PM. to 5:00.** The application for obtaining the tender forms will be received on **25.07.2024** upto **1:00 P.M.** The earnest money in the shape of fresh FDR/NSC, duly **printed pledged** in favour of undersigned must be submitted with the application for issue of tender form. **The earnest money should be submitted separately for each work.** The copy of **valid enlistment / renewal certificate** shall be attached with application form. The ambiguous/telegraphic/conditional/fax/e-mail or by post tender will also not be entertained/considered in any case. The offer of the tender shall remain open 90 days from the date of opening of the tenders, the undersigned reserves to reject/cancel the tenders without assigning any reason:-

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Cost of Form	Eligible class of contractor	Time Period
1	R/R damages on Rangle Miroo road Km. 0/00 to 4/705 (SH:- C/o B/Wall at R.D. 4/190 to 4/217)	4,22,670/-	8500/-	350/-	Class-D	Two Month
2	R/R damages on Rangle Miroo road Km. 0/00 to 4/705 (SH:- C/o B/Wall in wire crate at R.D. 0/050 to 0/060)	3,64,195/-	7300/-	350/-	Class-D	Two Month
3	C/o Link road Rakchham to Barda Km. 0/0 to 5/00. (SH:- C/o Sub grade at R.D. 0/200 to 2/000).	4,69,800/-	9400/-	350/-	Class-D	Three Month
4	R/R damages on Rangle Miroo road Km. 0/00 to 4/705 (SH:- C/o B/Wall in wire crate with C.C. toe wall at R.D. 0/005 to 0/013)	4,93,285/-	9900/-	350/-	Class-D	Two Month
5	R/R damages on Rangle Miroo road Km. 0/00 to 4/705 (SH:- C/o B/Wall at R.D. 4/162 to 4/189)	4,10,446/-	8300/-	350/-	Class-D	Two Month
6	C/o link road to Village Yukto Km. 0/00 to 1/00 (SH:- C/o R/Wall at R.D. 0/350 to 0/365)	4,90,537/-	10,000/-	350/-	Class-D	Three Month
7	R/R damages on Rangle Miroo road Km. 0/00 to 4/705 (SH:- C/o B/Wall in wire crate with C.C. toe wall at R.D. 0/014 to 0/022)	4,95,681/-	10,000/-	350/-	Class-D	Two Month


**GENERAL TERMS AND CONDITION:-**

1. In case office happens to closed on any of the above mentioned dates, the tenders will be opened on the next working day at same time and venue.
2. The contractor/firms are required to quote their rates clearly both in words as well as in figures, failing which tenders are likely to be rejected.
3. No person/persons shall be allowed to give the documents with regard to tender unless he/she/they/hold/holds the power of attorney duly registered under law.
4. The tender of those Contractors who are registered under HP Central Sale Tax Act 1969, G.S.T. and who have been cleared all the dues on account of tax will be entertained.
5. The competent authority on behalf of Governor of HP reserves the right to reject any or all the tenders received without assigning any reason.



6. Authorized Firms/Contractors approved by HP.PWD., Civil will participate in specialized Job only.
7. Permanent Account Number (PAN).
8. EPF No. & G.S.T. No.
9. Exemption letter for payment of earnest money from competent authority if any.

The contractor enlisted in a particulars class shall be eligible to tender for his/her own class and one step below. The conditional tenders or the tenders without earnest money shall be rejected.

  
(Er. Pramod Kumar Upreti),  
Executive Engineer,  
Karchham Division,  
HP.PWD, Bhabanagar.  
For and On behalf of Governor of H.P.



Job No - 1

Draft Schedule of Quantity

Estimated Cost:- 422670.00  
 Earnest Money:- 8500/-  
 Time:- Two Months

Name of work:- R/R damages on Rangle Mirroo road Km 0/00 to 4/705  
 Sub Head:-C/O B/wall at RD 4/190 to 4/217)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Excavation in earthwork in hilly area all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited) as per technical specification clause 1603.1 including carriage and stacking of useful material for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in-charge.	68.85	199.60	Rupees one hundred ninety nine and sixty paise only	Per cubic metre	13742.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	17.01	285.00	Rupees two hundred eighty five and zero paise only	Per cubic metre	4848.00
3	Providing and laying concrete for plain/reinforced cement concrete 1:4:8 (One cement isto four sand isto eight graded stone aggregate 25mm. (twenty five millimetre) nominal size) in open foundation and curing complete including cost of form work in retaining walls/breast walls, as per HPPWD specification clause 802, 803, 1202 & 1203 within all leads and lifts and as per the direction of Engineer-in-charge.	76.95	5251.20	Rupees five thousand two hundred fifty one and twenty paise only	Per cubic metre	404080.00
Total:-						422670.00

*Draft schedule of quantity approved for Rs 422670.00*

Executive Engineer  
 Karchham Division,  
 HPPWD at Bhaba Nagar.



# Draft Schedule of Quantity

Name of work:- R/R damages on Rangle Miroo road Km 0/00 to 4/705  
Sub Head:-C/O B/wall in wire crate at RD 0/050 to 0/060

Estimated Cost:- 364195.00  
Earnest Money:- 7300/-  
Time:- Two Months

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Excavation in earthwork in hilly area all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited) as per technical specification clause 1603.1 including carriage and stacking of useful material for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge.	83.25	199.60	Rupees one hundred ninety nine and sixty paise only	Per cubic metre	16617.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	13.80	285.00	Rupees two hundred eighty five and zero paise only	Per cubic metre	3933.00
3	Providing and laying boulder apron laid in wire crates with 4 mm diameter G.I. wire confirming to IS:280 and IS:4826 in 100mmx 100mm (one hundred into one hundred millimetre) mesh (woven diagonally) including 10 % (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	108	3181.90	Rupees three thousand one hundred eighty one and ninety paise only	Per cubic metre	343645.00
Total:-						364195.00

*Draft schedule of quantity approved for 364195/-*

Executive Engineer,  
Karchham Division,  
HPPWD, at Bhaba Nagar.

*Job No-29*

lealant

For No-3

### Draft Schedule of Quantity

Name of work:- C/O link road Rakchham to Barda Km 0/0 to 5/00  
Sub Head:- C/O sub grade at RD. 0/200 to 2/200 )

Estimated Cost:- 469800.00  
Earnest Money:- 9400/-  
Time:- Three Months

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In figer	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	1620.00	290.00	Rupees two hundred ninety and nil paise only	Per cubic metre	469800.00
Total:-						469800.00

*Draft schedule of quantity approved for ₹ 469800/-*

Executive Engineer,  
Karchham Division,  
HPPW at Bhaba Nagar.



# Draft Schedule of Quantity

Job No-6

Estimated Cost:- 493285.00  
Earnest Money:- 9900/-  
Time:- Two Months

Name of work:- R/R damages on Rangle Mirroo road Km 0/00 to 4/705

Sub Head:- C/O B/wall in wire crate with CC toe wall at RD 0/005 to 0/013

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Excavation in earthwork in hilly area all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited) as per technical specification clause 1603.1 including carriage and stacking of useful material for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in-charge.	84	199.60	Rupees one hundred ninety nine and sixty paise only	Per cubic metre	16766.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	14.40	285.00	Rupees two hundred eighty five and zero paise only	Per cubic metre	4104.00
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete 1:3:6 (one cement : three sand : six graded/crushed stone aggregate 40mm (forty millimetre) nominal mix curing complete within all leads, lifts carriage of material and other incidentals.	45.12	6002.00	Rupees six thousand two and nil paise only	Per cubic metre	270810.00
4	Providing and laying boulder apron laid in wire crates with 4 mm diameter G.I. wire conforming to IS:280 and IS:4826 in 100mmx100mm (one hundred millimetre) mesh (woven diagonally) including 10 % (ten percent) extra for laps and joints laid with stones boulders weighing not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	63.36	3181.90	Rupees three thousand one hundred eighty one and ninety paise only	Per cubic metre	201605.00
<b>Total:-</b>						<b>493285.00</b>

*Draft schedule of quantity approved for 493285/-*

Executive Engineer,  
Karchham Division,  
HPPWD at Bhaba Nagar.



Job No-5

# Draft Schedule of Quantity

Estimated Cost:- 410446.00  
 Earnest Money:- 8300/-  
 Time:- Two Months

Name of work:- R/R damages on Rangle Mirro road Km 0/00 to 4/705  
 Sub Head:-C/O B/wall at RD 4/162 to 4/189)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Excavation in earthwork in hilly area all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited) as per technical specification clause 1603.1 including carriage and stacking of useful material for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in-charge.	60.75	199.60	Rupees one hundred ninety nine and sixty paise only	Per cubic metre	12126.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	17.01	285.00	Rupees two hundred eighty five and zero paise only	Per cubic metre	4848.00
3	Providing and laying concrete for plain/reinforced cement concrete 1:4:8 (One cement isto four sand isto eight graded stone aggregate 25mm. (twenty five millimetre) nominal size) in open foundation and curing complete including cost of form work in retaining walls/breast walls, as per HPPWD specification clause 802, 803, 1202 & 1203 within all leads and lifts and as per the direction of Engineer-in-charge.	74.93	5251.20	Rupees five thousand two hundred fifty one and twenty paise only	Per cubic metre	393472.00
Total:-						410446.00

*Draft schedule of quantity approved of Rs 410446/-*

Executive Engineer,  
 Karcham Division,  
 HPPWD, at Bhaba Nagar.



# Draft Schedule of Quantity

Estimated Cost:-  
Earnest Money:-  
Time:-

490537.00  
10000/-  
Three Months

Name of work:- C/O link road to village Yukto Km. 0/00 to 1/00  
Sub Head:- C/O R/wall at RD 0/350 to 0/365)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	45.00	285.00	Rupees two hundred eighty five and nil paise only	Per cubic metre	12825.00
2	Providing and laying ceent 1:6:12 (one cement : six sand: twelve graded stone aggregate 40mm (forty millimeter) nominal size for plain /reinforced concrete in open foundations complete as per drawings and technical specification clauses 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of materials in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	9.00	4198.00	Rupees four thousand one hundred ninety eight and zero paise only	Per cubic metre	37782.00
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for structure like retaining walls, breast walls wing walls, toe walls, abutment and similar works etc. in all heights complete as per drawing and technical specification clauses 702, 704, 1202 & 1204 and curing complete including carriage of materials in all leads lifts as per the entire satisfaction and direction of Engineer-in-Charge.	80.33	5148.20	Rupees five thousand one hundred forty eight and twenty paise only	Per cubic metre	413555.00
4	Providing weep holes in brick masonry/stone masonry/plain/ reinforced concrete abutment wing wall, return wall with 100mm.(One hundred millimetre) dia PVC pipe extneiding through the full with of the structures with slope of 1 (v) : 20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 12.04, 3.7 within all leads and lifts and as per direction of Engineer-in-charge.	20.00	250.00	Rupees two hundred fifty and nil paise only	Each	5000.00
5	Back filling behind abutment, wing wall and return wall/breast wall and retaining walls complete as per drawing and technical specification within all leads and lifts and as per the direction of Engineer-in-charge.	22.50	950.00	Rupees nine hundred fifty and nil paise only	Per cubic metre	21375.00
					Total	490537.00

*Draft Schedule of Quantity approved for Rs 490537.00*

Executive Engineer  
Karcham Division,  
HPPWD, at Bhaba Nagar.

*26846-6*

# Draft Schedule of Quantity

Name of work:- R/R damages on Rangle Miroo road Km 0/00 to 4/705  
Sub Head:-C/O B/wall in wire cratwith CC toe wall at RD 0/014 to 0/022)

Estimated Cost:- 495681.00  
Earnest Money:- 10000/-  
Time:- Two Months

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Excavation in earthwork in hilly area all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited) as per technical specification clause 1603.1 including carriage and stacking of useful material for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge.	96.00	199.60	Rupees one hundred ninety nine and sixty paise only	Per cubic metre	19162.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidentals.	14.40	285.00	Rupees two hundred eighty five and zero paise only	Per cubic metre	4104.00
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete 1:3:6 (one cement : three sand : six graded/crushed stone aggregate 40mm (forty millimetre) nominal mix curing complete within all leads, lifts carriage of material and other incidentals.	45.12	6002.00	Rupees six thousand two hundred and nil paise only	Per cubic metre	270810.00
4	Providing and laying boulder apron laid in wire crates with 4 mm diameter G.I. wire confirming to IS:280 and IS:4826 in 100mmx 100mm (one hundred into one hundred millimetre) mesh (woven diagonally) including 10 % (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	63.36	3181.90	Rupees three thousand one hundred eighty one and ninety paise only	Per cubic metre	201605.00
<b>Total:-</b>						<b>495681.00</b>

*Draft schedule of quantity approved for 495681.00*

Executive Engineer,  
Karchham Division,  
HPPWD, at Bhaba Nagar.

*Vol No-7*