OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG
PH: 01907-222229 Fax: 222229 , e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2023- 1649 Dated:- 1.7.2024

To

The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.

Subject :- Regarding publication of Tender on departmental site.

Enclosed please find herewith the copies of Notice Inviting Tender for the loading on departmental web-site before 01.07.2024 per notification issued by the Pr. Secy.(PW) to the Govt. of HP vide letter No. PBW(B)A(3)1/2020 dated 16th July, 2021. As the works mentioned in the Tender Notice are urgent in nature.

Encl:- As above.

Executive Engineer,
B&R Division,
HP PWD Karsog

OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG
PH: 01907-222229 Fax: 222229 , E-mail : ee-kar-hp@nic.in

Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **12.07.2024 upto 11.00** AM and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 10.07.2024** for which the application should reach in this office **upto 1.00 PM 10.07.2024**.

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/R damages on Seri Shout Km. 0/00 to 14/00 (SH:- Deployment/Hiring of Excavator-cum loader with breaker for removal of slips at various RDs)	2,64,700/-	5,300/-	One month	350/-
2	C/o link road from Johad Thandapani to Sanohal road Km. 0/00 to 2/00 (SH:- C/o 900mm dia hume pipe culvert at RD 0/540) Computer code 2022-307-4307 Page-221)	3,25,096/-	6,600/-	Two months	350/-
3	C/o link road from Johad Thandapani to Sanohal road Km. 0/00 to 2/00 (SH:- C/o 900mm dia hume pipe culvert at RD 0/465) Computer code 2022-307-4307 Page-221)	3,24,350/-	6,500/-	Two months	350/-
4	C/o road from Shakelar to Mahog road via Navidhar Km. 0/00 to 10/500 (SH:- 900mm dia NP2 Hume Pipe Culvert at RD 8/090)	4,98,660/-	10,000/-	One month	350/-
5	M/T on link road to village Dachhain Km. 0/00 to 2/500 (SH:- C/o 900mm dia NP2 Hume pipe culvert at RD 0/690)	3,38,068/-	6,800/-	One month	350/-
6	M/T on link road to village Dachhain Km. 0/00 to 2/500 (SH:- C/o 900mm dia NP2 Hume pipe culvert at RD 0/380)	2,97,224/-	6,000/-	One month	350/-
7	C/o Govt. High School Building at Kanda Sorta Tehsil Karsog Distt. Mandi H.P. (SH:- C/o R/wall & B/wall)	4,96,800/-	10,000/-	Two months	350/-
8	C/o Jingal Mod to Ghanufri via Kotla katachhi link road Km. 0/00 to 1/300(SH:- Providing and laying Granular Sub Base in Km. 0/000 to 0/318)	4,97,229/-	10,000/-	Three months	350/-
9	C/o Jingal Mod to Ghanufri via Kotla Katachhi link road Km. 0/00 to 1/300(SH:- Providing and laying Granular Sub Base in Km. 0/318 to 0/637)	4,98,799/-	10,000/-	Three months	350/-
10	Construction of Ambulance road from Kahulu to Mahroo Bia Km. 0/00 to 1/00 (SH:- F/C 3/5 mtr wide in Km. 0/00 to 0/135) D.C. Deposit vide BSP/2023/110	1,99,441/-	4,000/-	Two months	350/-

11	C/o Bhanera to Kotlu road Km. 0/00 to 2/400 (SH:- C/o 900mm dia NP2 hume pipe culvert at RD 1/980)	3,54,803/-	7,100/-	One month	350/-
12	C/o Gagaun Nalla to Mamail road in Km. 0/00 to 3/00 (SH:- C/o 900mm dia NP2 hume pipe culvert at RD 2/540)	3,31,229/-	6,700/-	One month	350/-
13	C/o Kao to Kanndha via Narol road Km. 0/00 to 5/00 (SH:- C/o 900 mm dia NP2 hume pipe culvert at RD 1/345)	4,99,890/-	10,000/-	One month	350/-
14	C/o Karsog to Kanndha road Km. 0/00 to 12/500 (SH:- C/o 900 mm dia NP2 hume pipe culvert at RD 6/225)	3,30,242/-	6,700/-	One month	350/-

TERMS & CONDITIONS:-

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification **PW/CTR/32-20Genl Inst-CPWD/2020-37996-38095 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.**

Executive Engineer
B&R Division
HPPWD Karsog,

No. PW-E-Tender-NIT/23 1442-48 Dated:- 1-7-2024

1. Copy to the Superintending Engineer,1st Circle, HP,PWD, Mandi for information please.
2. The Sub-Divisional Officer (Civil) Karsog, tehsil Karsog Distt. Mandi HP.
3. The Block Development Officer Karsog , tehsil Karsog Distt. Mandi HP.
4. All the Assistant Engineers, working under this Division.
5. Copy to Drawing & Account Branch.
6. Notice board of this office.

Executive Engineer,
B&R Division,
HP PWD Karsog
Distt. Mandi H.P.

Percentage Schedule of Quantity

Estimated Cost 264700
Earnest Money 5300
Time One Month

Name of Work:- R/R Damages on Seri Shout road Km. 0/00 to 14/00 (SH:- Deployment/Hiring of Excavator-cum loader with breaker for removal of slips at various RDs).

Sr.No.	Sub-Head and items of works.	Qty	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of earth cutting/excavating machinary of 0.75 cubic meter bucket capacity @ 45 cubic meter per hour loading capacity to be deployed for earth cutting/excavation/ filling/slips and clearance of blocked side drain etc. including cost of fuel oil lubricant and wages of operating staff. any repair/ breakage during operation will be absolute responsibility of contractor/owner at his own risk. Shifting of machinary from one place to other place will be absolute responsibility of the contractor and no payment will be made for the same. Only actual working hours will be accounted for the payment. Cutting in earth work/removal of slips in all kinds of soil including loading in tipper/ truck, removal/disposal of the same in all leads and lifts to the entire satisfactions and directions of Engineer-in-Charge.					
A	With Bucket	88.00	Per Hours	1150.00	101200.00	Rupees One Lakh One Thousand Two Hundred and Paise Zero Only
B	With Breaker	109.00	Per Hours	1500.00	163500.00	Rupees One Lakh Sixty Three Thousand Five Hundred and Paise
Total in Figures					**264700.00**	
Quoted Rate in Figures			Select		**0.00**	
Quoted Rate in Words				#VALUE!		

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 325096
Earnest Money 6600
Time Two Months

Name of Work:- C/O link road from Johad Thandapani to Sanohal road km. 0/00 to 2/00 (SH:- C/O 900 mm dia hume pipe culvert at RD 0/540) Computer code 2022-307-4307 Page-221

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount with all taxes	Toatal Amount with all taxes including GST In
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	43.11	Per Cubic Metre	559.05	24101.00	Rupees Twenty Four Thousand One Hundred One and Paise Zero Only
2	Providing and laying concrete for pain/reinforced concrete 1:3:6 (one cement : three sand : six graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	10.04	Per Cubic Metre	6306.30	63315.00	Rupees Sixty Three Thousand Three Hundred Fifteen and Paise Zero Only
3	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class beeding of granular material in double row including fixing collar with cement morter 1:2 but excluding excavation, protection works, backfilling, concrete and masonary works in head walls and parapets as per clause 1106 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	7.50	Per Running Metre	5445.95	40845.00	Rupees Forty Thousand Eight Hundred Forty Five and Paise Zero Only
4	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	31.94	Per Cubic Metre	5546.80	177165.00	Rupees One Lakh Seventy Seven Thousand One Hundred Sixty Five and Paise Zero Only
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	10.36	Per Cubic Metre	1322.40	13700.00	Rupees Thirteen Thousand Seven Hundred and Paise Zero Only
6	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drewing face complete as per drawing and technical specification clause 614,709,1204.3.7 As per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	16.00	Each	373.15	5970.00	Rupees Five Thousand Nine Hundred Seventy and Paise Zero Only
Total in Figures					325096.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	324350
Earnest Money	6500
Time	Two Months

Name of Work:- C/O link road from Johad Thandapani to Sanohal road km. 0/00 to 2/00 (SH:- C/O 900 mm dia hume pipe culvert at RD 0/465) Computer code 2022-307-4307 Page-221

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount with all taxes	Toatal Amount with all taxes including GST In
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	43.11	Per Cubic Metre	559.05	24101.00	Rupees Twenty Four Thousand One Hundred One and Paise Zero Only
2	Providing and laying concrete for pain/reinforced concrete 1:3:6 (one cement : three sand : six graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	10.04	Per Cubic Metre	6306.30	63315.00	Rupees Sixty Three Thousand Three Hundred Fifteen and Paise Zero Only
3	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class beeding of granular material in double row including fixing collar with cement morter 1:2 but excluding excavation, protection works, backfilling, concrete and masonary works in head walls and parapets as per clause 1106 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	7.50	Per Running Metre	5445.95	40845.00	Rupees Forty Thousand Eight Hundred Forty Five and Paise Zero Only
4	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	31.94	Per Cubic Metre	5546.80	177165.00	Rupees One Lakh Seventy Seven Thousand One Hundred Sixty Five and Paise Zero Only
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	10.36	Per Cubic Metre	1322.40	13700.00	Rupees Thirteen Thousand Seven Hundred and Paise Zero Only
6	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drewing face complete as per drawing and technical specification clause 614,709,1204.3.7 As per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	14.00	Each	373.15	5224.00	Rupees Five Thousand Two Hundred Twenty Four and Paise Zero Only
Total in Figures					324350.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 498660
Earnest Money 10000
Time One Month

ame of Work:- C/O road from shakelar to Mahog road via Navidhar km 0/00 to 10/500 (SH:- 900 mm dia NP2 Hume Pipe culvert at Rd 8/090)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount with all taxes	Toatal Amount with all taxes including GST In
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	63.11	Per Cubic Metre	559.05	35282.00	thirty-five thousand two hundred eighty-two and zero peise only
2	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.45	Per Cubic Metre	4837.65	7015.00	seven thousand fifteen and zero peise only
3	Providing and laying concrete for pain/reinforced concrete 1:3:6 (one cement : three sand : six graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	71.80	Per Cubic Metre	5546.80	398260.00	three lacs ninety-eight thousand two hundred sixty and zero peise only
4	Providing and laying (to level and slopes) and jointing reanforcemednt concrete light duty no pressure pipe Is class NP2 of flowing dia meter with colure and butts ends prepare for colur joints inculding testing of joints complete 900 mm dia as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	7.50	Per Running Metre	5445.95	40845.00	forty thousand eight hundred forty-five and zero peise only
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	9.10	Per Cubic Metre	1322.40	12034.00	twelve thousand thirty-four zero peise only
6	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drewing face complete as per drawing and technical specification clause 614,709,1204.3.7 As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	14.00	Each	373.15	5224.00	five thousand two hundred twenty-four and zero peise only
Total in Figures					498660.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	338068
Earnest Money	6800
Time	One Month

Name of Work:- M/T on link road to Village Dachhain Km. 0/00 to 2/500 (SH:- C/O 900 mm dia NP2 Hume pipe culvert at RD 0/690)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount with all taxes	Toatal Amount with all taxes including GST In
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	39.75	Per Cubic Metre	559.05	22222.00	Rupees Twenty Two Thousand Two Hundred Twenty Two and Paise Zero Only
2	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	25.14	Per Cubic Metre	5546.80	139447.00	Rupees One Lakh Thirty Nine Thousand Four Hundred Forty Seven and Paise Zero Only
3	Providing and laying concrete for pain/reinforced concrete 1:3:6 (one cement : three sand : six graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	13.14	Per Cubic Metre	6306.30	82865.00	Rupees Eighty Two Thousand Eight Hundred Sixty Five and Paise Zero Only
4	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class beeding of granular material in double row including fixing collar with cement morter 1:2 but excluding excavation, protection works, backfilling, concrete and masonary works in head walls and parapets as per clause 1106 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	15.00	Per Running Metre	5445.95	81689.00	Rupees Eighty One Thousand Six Hundred Eighty Nine and Paise Zero Only
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	6.70	Per Cubic Metre	1322.40	8860.00	Rupees Eight Thousand Eight Hundred Sixty and Paise Zero Only
6	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drewing face complete as per drawing and technical specification clause 614,709,1204.3.7 As per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	8.00	Each	373.15	2985.00	Rupees Two Thousand Nine Hundred Eighty Five and Paise Zero Only
Total in Figures					338068.00	
Quoted Rate in Figures	-		Select	-	0.00	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost	297224
Earnest Money	6000
Time	One Month

Name of Work:- M/T on link road to Village Dachhain Km. 0/00 to 2/500 (SH:- 900 mm dia NP2 Hume Pipe culvert at Rd 0/380)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount with all taxes	Toatal Amount with all taxes including GST In
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	39.75	Per Cubic Metre	559.05	22222.00	twenty-two thousand, two hundred twenty-two and zero peise only
2	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	25.14	Per Cubic Metre	5546.80	139447.00	one lacs thirty-nine thousand, four hundred forty-seven and zero peise only
3	Providing and laying concrete for pain/reinforced concrete 1:3:6 (one cement : three sand : six graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	13.14	Per Cubic Metre	6306.30	82865.00	eighty-two thousand, eight hundred sixty-five and zero peise only
4	Providing and laying (to level and slopes) and jointing reanforcemednt concrete light duty no pressure pipe Is class NP2 of flowing dia meter with colure and butts ends prepare for colur joints inculding testing of joints complete 900 mm dia as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	7.50	Per Running Metre	5445.95	40845.00	forty thousand, eight hundred forty-five and zero peise only
6	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	6.70	Per Cubic Metre	1322.40	8860.00	eight thousand, eight hundred sixty and zero peise only
7	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drewing face complete as per drawing and technical specification clause 614,709,1204.3.7 As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	8.00	Each	373.15	2985.00	two thousand, nine hundred eighty-five and zero peise only
Total in Figures					297224.00	
Quoted Rate in Figures			Select		**0.00**	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	496800
Earnest Money	10000
Time	Two Months

Name of Work:- C/O Govt High School Building at Kanda Sorta Tehsil Karsog Distt. Mandi H.P. (SH:- C/O R/Wall & B/Wall)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount with all taxes	Toatal Amount with all taxes including GST In
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	66.52	Per Cubic Metre	559.05	37188.00	Rupees Thirty Seven Thousand One Hundred Eighty Eight and Paise Zero Only
2	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	79.66	Per Cubic Metre	5546.80	441858.00	Rupees Four Lakhs Forty One Thousand Eight Hundred Fifty Eight and Paise Zero Only
3	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drewing face complete as per drawing and technical specification clause 614,709,1204.3.7 As per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	21.00	Each	373.15	7836.00	Rupees Seven Thousand Eight Hundred Thirty Six and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	7.50	Per Cubic Metre	1322.40	9918.00	Rupees Nine Thousand Nine Hundred Eighteen and Paise Zero Only
Total in Figures					496800.00	
Quoted Rate in Figures			Select		**0.00**	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 497229
Earnest Money 10000
Time Three months

Name of Work:- C/O Jingal Mod to Ghanufri via Kotla Katchhi link road Km. 0/00 to 1/300 (SH:- Providing and laying Granular Sub Base in Km. 0/00 to 0/318)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount with all taxes	Toatal Amount with all taxes including GST In
1	Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	167.79	Per Cubic Metre	2963.40	497229.00	Rupees Four Lakhs Ninety Seven Thousand Two Hundred Twenty Nine and Paise Zero Only
Total in Figures					497229.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words		#VALUE!				

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 498799
Earnest Money 10000
Time Three months

Name of Work:- C/O Jingal Mod to Ghanufri via Kotla Katchhi link road Km. 0/00 to 1/300 (SH:- Providing and laying Granular Sub Base in Km. 0/318 to 0/637)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount with all taxes	Toatal Amount with all taxes including GST In
1	Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	168.32	Per Cubic Metre	2963.40	498799.00	Rupees Four Lakhs Ninety Eight Thousand Seven Hundred Ninety Nine and Paise Zero Only
Total in Figures					498799.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words		#VALUE!				

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 199441
Earnest Money 4000
Time Two Months

Name of Work:- Construction of Ambulance road from Kahulu to Mahroo Bia Km. 0/00 to 1/00 (SH:-F/C3/5 Mtr. wide in Km. 0/00 to 0/135) D.C. Deposit vide BSP/2023/110

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount with all taxes	Toatal Amount with all taxes including GST In
1	Excavation in earth work in hilly area by mechanical means all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification for Rural Roads August 2004 and Clause 16.2 of general condition for contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery of **76.93 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 23079/- only,** shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases. as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	811.43	Per Cubic Metre	245.79	199441.00	Rupees One Lakh Ninety Nine Thousand Four Hundred Forty One and Paise Zero Only
Total in Figures					199441.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	354803
Earnest Money	7100
Time	One Month

Name of Work:- C/O Bhanera to Kotlu road Km. 0/00 to 2/400 (SH:- C/O 900 mm dia NP2 Hume pipe culvert at RD 1/980)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount with all taxes	Toatal Amount with all taxes including GST In
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	42.42	Per Cubic Metre	559.05	23715.00	Rupees Twenty Three Thousand Seven Hundred Fifteen and Paise Zero Only
2	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	33.68	Per Cubic Metre	5546.80	186816.00	Rupees One Lakh Eighty Six Thousand Eight Hundred Sixteen and Paise Zero Only
3	Providing and laying concrete for pain/reinforced concrete 1:3:6 (one cement : three sand : six graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	14.04	Per Cubic Metre	6306.30	88540.00	Rupees Eighty Eight Thousand Five Hundred Forty and Paise Zero Only
4	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class beeding of granular material in double row including fixing collar with cement morter 1:2 but excluding excavation, protection works, backfilling, concrete and masonary works in head walls and parapets as per clause 1106 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	7.50	Per Running Metre	5445.95	40845.00	Rupees Forty Thousand Eight Hundred Forty Five and Paise Zero Only
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	9.00	Per Cubic Metre	1322.40	11902.00	Rupees Eleven Thousand Nine Hundred Two and Paise Zero Only
6	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drewing face complete as per drawing and technical specification clause 614,709,1204.3.7 As per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	8.00	Each	373.15	2985.00	Rupees Two Thousand Nine Hundred Eighty Five and Paise Zero Only
					354803.00	
Total in Figures			Select		0.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	331229
Earnest Money	6700
Time	One Month

Name of Work:- C/O Gagaun Nalla to Mamail road In Km. 0/00 to 3/00 (SH:- C/O 900 mm dia NP2 Hume pipe culvert at RD 2/540)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount with all taxes	Toatal Amount with all taxes including GST In
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	42.42	Per Cubic Metre	559.05	23715.00	Rupees Twenty Three Thousand Seven Hundred Fifteen and Paise Zero Only
2	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	29.43	Per Cubic Metre	5546.80	163242.00	Rupees One Lakh Sixty Three Thousand Two Hundred Forty Two and Paise Zero Only
3	Providing and laying concrete for pain/reinforced concrete 1:3:6 (one cement : three sand : six graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	14.04	Per Cubic Metre	6306.30	88540.00	Rupees Eighty Eight Thousand Five Hundred Forty and Paise Zero Only
4	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class beeding of granular material in double row including fixing collar with cement morter 1:2 but excluding excavation, protection works, backfilling, concrete and masonary works in head walls and parapets as per clause 1106 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	7.50	Per Running Metre	5445.95	40845.00	Rupees Forty Thousand Eight Hundred Forty Five and Paise Zero Only
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	9.00	Per Cubic Metre	1322.40	11902.00	Rupees Eleven Thousand Nine Hundred Two and Paise Zero Only
6	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drewing face complete as per drawing and technical specification clause 614,709,1204.3.7 As per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	8.00	Each	373.15	2985.00	Rupees Two Thousand Nine Hundred Eighty Five and Paise Zero Only
Total in Figures					331229.00	
Quoted Rate in Figures			Select	-	0.00	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 499890
Earnest Money 10000
Time One Month

Name of Work:- C/O Kao to Kandha via Narol road Km. 0/00 to 5/00 (SH:- C/O 900 mm dia NP2 Hume pipe culvert at RD 1/345)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount with all taxes	Toatal Amount with all taxes including GST In
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	46.47	Per Cubic Metre	559.05	25979.00	Rupees Twenty Five Thousand Nine Hundred Seventy Nine and Paise Zero Only
2	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	55.14	Per Cubic Metre	5546.80	305851.00	Rupees Three Lakhs Five Thousand Eight Hundred Fifty One and Paise Zero Only
3	Providing and laying concrete for pain/reinforced concrete 1:3:6 (one cement : three sand : six graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	16.32	Per Cubic Metre	6306.30	102919.00	Rupees One Lakh Two Thousand Nine Hundred Nineteen and Paise Zero Only
4	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class beeding of granular material in double row including fixing collar with cement morter 1:2 but excluding excavation, protection works, backfilling, concrete and masonary works in head walls and parapets as per clause 1106 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	7.50	Per Running Metre	5445.95	40845.00	Rupees Forty Thousand Eight Hundred Forty Five and Paise Zero Only
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	11.60	Per Cubic Metre	1322.40	15340.00	Rupees Fifteen Thousand Three Hundred Forty and Paise Zero Only
6	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drewing face complete as per drawing and technical specification clause 614,709,1204.3.7 As per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	24.00	Each	373.15	8956.00	Rupees Eight Thousand Nine Hundred Fifty Six and Paise Zero Only
Total in Figures					499890.00	
Quoted Rate in Figures	-	-	Select		0.00	-
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 330242
Earnest Money 6700
Time One Month

Name of Work:- C/O Karsog to Kandha road km 0/00 to 12/500 (SH:- 900 mm dia NP2 Hume Pipe culvert at Rd 6/225)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount with all taxes	Toatal Amount with all taxes including GST In
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	42.36	Per Cubic Metre	559.05	23681.00	twenty-three thousand, six hundred eighty-one and zero peise only
2	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	29.43	Per Cubic Metre	5546.80	163242.00	one lacs sixty-three thousand, two hundred forty-two and zero peise only
3	Providing and laying concrete for pain/reinforced concrete 1:3:6 (one cement : three sand : six graded stone aggregte) in open foundations complete as per drawing and technical specification clauses 802,803.1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	14.04	Per Cubic Metre	6306.30	88540.00	eighty-eight thousand five hundred forty and zero peise only
4	Providing and laying (to level and slopes) and jointing reanforcemednt concrete light duty no pressure pipe Is class NP2 of flowing dia meter with colure and butts ends prepare for colur joints inculding testing of joints complete 900 mm dia as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	7.50	Per Running Metre	5445.95	40845.00	forty thousand, eight hundred forty-five and zero Pesie only
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	8.28	Per Cubic Metre	1322.40	10949.00	ten thousand nine hundred forty-nine and zero Pesie only
6	Providing weepholes in bricks masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drewing face complete as per drawing and technical specification clause 614,709,1204.3.7 As per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	8.00	Each	373.15	2985.00	two thousand, nine hundred eighty-five and zero Pesie only
Total in Figures					330242.00	
Quoted Rate in Figures			Select		**0.00**	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.