

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No.PW-MDI(Padhar)E-Tender-NIT/2024-25- 3935-37 Dated:- 5/7/24

To

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.


Executive Engineer,
Mandi Division No.I,
HP. PWD at Padhar

Copy forwarded the Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and further necessary action please.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed percentage rate tender on form No. 6&8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 16.07.2024 up to 12:00 Noon and the same shall be opened on the same day at 12:30 P.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 15.07.2024 upto 1.00 P.M.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.

Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Annual repair & maintenance of Cheli to Silhikhad road Km 0/0 to 10/800. (SH:- Providing and laying premix carpet in Km 0/00 to 1/500)	3,42,056.98	6,800/-	350/-	One month
2	Annual repair & maintenance of Cheli to Silhikhad road Km 0/0 to 10/800. (SH:- Providing and laying premix carpet in Km 1/500 to 3/00)	3,32,768.80	6,700/-	350/-	One month
3	Restoration of rain damages on NH-154 to link road GDC Narla road in Km 0/00 to 1/365 (SH:- Construction of Retaining wall at R.D. 0/05 to 0/09.25) (Above Toe wall)	4,64,782.44	9,300/-	350/-	One month
4	Restoration of rain damages on NH-154 to link road GDC Narla road in Km 0/00 to 1/365 (SH:- Construction of Retaining wall at R.D. 0/09.25 to 0/013.50) (Above Toe wall)	4,65,268.57	9,300/-	350/-	One month
5	Restoration of rain damages on NH-154 to link road GDC Narla road in Km 0/00 to 1/365 (SH:- Construction of Retaining wall at R.D. 0/013.50 to 0/016.75) (Above Toe wall)	2,59,470.50	5,200/-	350/-	One month
6	Restoration of rain damages on NH-154 to link road GDC Narla road in Km 0/00 to 1/365 (SH:- Construction of Retaining wall at R.D. 0/016.75 to 0/020) (Above Toe wall)	2,59,470.50	5,200/-	350/-	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.


4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.
5. The intending Contractors are requested to see the site of the work before submitting the tender.
6. The offer of the tender shall remain valid upto 75 days after the opening of tender.
7. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
8. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


Executive Engineer,
Mandi Division No. I,
HPPWD., at Padhar Distt. Mandi (H.P.)
on behalf of Governor of Himachal Pradesh


PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 342056.98
Earnest Money Rs:- 6800.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP. PWD. at Padhar.						
Name of work :- Annual repair & maintenance of Cheli to Silhikhad road Km. 0/0 to 10/800. (Sub Head:- Providing and laying Premix carpet in km. 0/00 to 1/500.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	1646.88	Per square metre	207.70	342056.98	Rupees Three Lakh Forty Two Thousand Fifty Six and Paise Ninety Eight Only
Total in figure :					342056.98	Rupees Three Lakh Forty Two Thousand Fifty Six and Paise Ninety Eight Only
Total in Words :		Rupees Three Lakh Forty Two Thousand Fifty Six and Paise Ninety Eight Only				


Executive Engineer,
Mandi Division No-I,
HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 332768.80
Earnest Money Rs:- 6700.00
Time One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Annual repair & maintenance of Cheli to Silhikhad road Km. 0/0 to 10/800. (Sub Head:- Providing and laying Premix carpet in km. 1/500 to 3/00.)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	1599.85	Per square metre	208.00	332768.80	Rupees Three Lakh Thirty Two Thousand Seven Hundred Sixty Eight and Paise Eighty Only
Total in figure :					332768.80	Rupees Three Lakh Thirty Two Thousand Seven Hundred Sixty Eight and Paise Eighty Only
Total in Words :		Rupees Three Lakh Thirty Two Thousand Seven Hundred Sixty Eight and Paise Eighty Only				


Executive Engineer,
Mandi Division No-I,
HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 464782.44
 Earnest Money Rs:- 9300.00
 Time :- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP. PWD. at Padhar.

Name of work :- Restoration of rain Damages on NH-154 to Link Road GDC Narla road in Km. 0/00 to 1/365. (Sub Head:- Construction of Retaining wall at R.D. 0/05 to 0/09. 25). (Above Toe wall)

Contract No. :

Bidder Name :

SCHEDULE OF WORKS


Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with taxes excluding GST in words.
1	Excavation in soil in hilly area by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	51.09	Per cubic metre	159.90	8169.29	Rupees Eight Thousand One Hundred Sixty Nine and Paise Twenty Nine Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803, 1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	91.04	Per cubic metre	4692.80	427232.51	Rupees Four Lakh Twenty Seven Thousand Two Hundred Thirty Two and Paise Fifty One Only
3	Providing weep hole in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	273.70	3284.40	Rupees Three Thousand Two Hundred Eighty Four and Paise Forty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	17.72	Per cubic metre	1472.70	26096.24	Rupees Twenty Six Thousand Ninety Six and Paise Twenty Four Only
Total in figure :					464782.44	Rupees Four Lakh Sixty Four Thousand Seven Hundred Eighty Two and Paise Forty Four Only
Total in Words :						Rupees Four Lakh Sixty Four Thousand Seven Hundred Eighty Two and Paise Forty Four Only


 Executive Engineer,
 Mandi Division No.1,
 HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 465268.57
 Earnest Money Rs:- 9300.00
 Time :- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP. PWD. at Padhar.						
Name of work :- Restoration of rain Damages on NH-154 to Link Road GDC Narla road in Km. 0/00 to 1/365 (Sub Head:- Construction of Retaining wall at R.D. 0/09.25 to 0/013.50). (Above Toe wall)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Excavation in soil in hilly area by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	57.63	Per cubic metre	159.90	9215.04	Rupees Nine Thousand Two Hundred Fifteen and Paise Four Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	91.04	Per cubic metre	4692.80	427232.51	Rupees Four Lakh Twenty Seven Thousand Two Hundred Thirty Two and Paise Fifty One Only
3	Providing weep hole in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	273.70	3284.40	Rupees Three Thousand Two Hundred Eighty Four and Paise Forty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	17.34	Per cubic metre	1472.70	25536.62	Rupees Twenty Five Hundred Thirty Six and Paise Sixty Two
Total in figure :					465268.57	Rupees Four Lakh Sixty Five Thousand Two Hundred Sixty Eight and Paise Fifty Seven Only
Total in Words :		Rupees Four Lakh Sixty Five Thousand Two Hundred Sixty Eight and Paise Fifty Seven Only				


 Executive Engineer,
 Mandi Division No.I,
 HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 259470.50
Earnest Money Rs:- 5200.00
Time :- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP. PWD. at Padhar.						
Name of work :- Restoration of rain Damages on NH-154 to Link Road GDC Narla road in Km. 0/00 to 1/365 (Sub Head:- Construction of Retaining wall at R.D. 0/013.50 to 0/016.75). (Above Toe wall)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Excavation in soil in hilly area by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	30.23	Per cubic metre	159.90	4833.78	Rupees Four Thousand Eight Hundred Thirty Three and Paise Seventy Eight Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	49.40	Per cubic metre	4692.80	231824.32	Rupees Two Lakh Thirty One Thousand Eight Hundred Twenty Four and Paise Thirty Two Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	273.70	3284.40	Rupees Three Thousand Two Hundred Eighty Four and Paise Forty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	13.26	Per cubic metre	1472.70	19528.00	Rupees Nineteen Thousand Five Hundred Twenty Eight Only
Total in figure :					259470.50	Rupees Two Lakh Fifty Nine Thousand Four Hundred and Paise Fifty Only
Total in Words :		Rupees Two Lakh Fifty Nine Thousand Four Hundred and Paise Fifty Only				

Executive Engineer,
Mandi Division No. I,
HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 259470.50
 Earnest Money Rs:- 52000.00
 Time :- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of rain Damages on NH-154 to Link Road GDC Narla road in Km. 0/00 to 1/365, (Sub Head:- Construction of Retaining wall at R.D. 0/016.75 to 0/020). (Above Toe wall)						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Excavation in soil in hilly area by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	30.23	Per cubic metre	159.90	4833.78	Rupees Four Thousand Eight Hundred Thirty Three and Paise Seventy Eight Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	49.40	Per cubic metre	4692.80	231824.32	Rupees Two Lakh Thirty One Thousand Eight Hundred Twenty Four and Paise Thirty Two Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	273.70	3284.40	Rupees Three Thousand Two Hundred Eighty Four and Paise Forty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	13.26	Per cubic metre	1472.70	19528.00	Rupees Nineteen Thousand Five Hundred Twenty Eight Only
Total in figure :					259470.50	Rupees Two Lakh Fifty Nine Thousand Four Hundred and Paise Fifty Only
Total in Words :		Rupees Two Lakh Fifty Nine Thousand Four Hundred Seventy and Paise Fifty Only				


 Executive Engineer,
 Mandi Division No.I,
 HP. PWD. at Padhar