

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT.
NOTICE INVITING TENDER

Sealed percentage rate tenders are hereby invited on Form No.7 &8 by the undersigned on behalf of the Governor of Himachal Pradesh for the following works 10-07-2024 upto 11:00 A.M and shall be opened on the same day on 11:30 A.M. in the presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (Non- refundable) during the working hours.

The earnest money in the shape of National Saving Certificate, FDRs/TDRs/ Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Sarahan must accompany with each applications/tender. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 75 days. The undersigned reserves the right to reject the any or all tender without assigning any reason.

S N	Tender Schedule				
1	Last date for tender receipt of application for tender form	08-07-2024 up to 4:00 PM			
2	Last date of sale of tender forms	09-07-2024 up to 4:00 PM			
3	Date of receipt of tender forms	10-07-2024 up to 11:00 A.M			
4	Date of opening of tenders	10-07-2024 at 11:30 A.M			
Sr. No	Name of Work	Estimat ed cost	Earnest Money	Time Limit	Cost of Form
1	C/O Naina Tikker Dagothar road via Kanchi Mod Km 0/0 to 2/800 (SH:- C/O 900 mm dia Hume pipe culvert alongwith wing wall at Rd 0/900) SCSP	288901	6000	Two Month	350/-
2	C/O Mari ghat Kerry Shutiya road Km 0/0 to 10/300 (SH:- C/O 900 mm dia Hume Pipe Culvert alongwith wing wall at Rd 3/200 to 6/450) MNP	458140	9200	Two Month	350/-
3	C/O Dungaghat Kila Klanch road Km 0/0 to 22/00 (SH:- C/O 900 mm dia Hume Pipe Culvert alongwith wing wall of 3.05 mtr Height at Rd 4/100, 4/245) MNP	458029	9200	Two Month	350/-
4	C/O Kalaghat Banona road Km 0/00 to 5/00 (SH:- C/o 900 mm dia Hume Pipe culvert alongwith wing wall at Rd 3/100 (MNP)	232722	4700	Two Month	350/-
5	C/O Naina Tikker Dhangyar road Km 0/00 to 12/00 (SH:- C/O 900 mm dia Hume Pipe culvert alongwith wing wall at Rd 10/480 MNP	302254	6000/-	Two Month	350/-
6	C/o Link road to village Gandhal Km 0/00 to 7/00 (SH:- C/O 900 mm dia Hume Pipe Culvert alongwith wing wall of 3.05 mtr Height at Rd 3/00) MNP	228953	4600	Two Month	350/-
7	C/O Rister Panwa road in Km 0/00 to 2/100 (SH:- P/L Soling G-I between Km 1/025 to 1/500) MNP	490581	10000	Two Month	350/-
8	C/O Prem Nagar Chandog road Km 0/00 to 15/00 (SH:- C/O Boundary wall of Bal Niketan Ashram at Rd 10/030 to 10/8038) Under De[post work.	499760	10000	One Month	350/-
9	C/O Link road to Y. S Parmar Birth Place at Chanalag in Km 0/0 to 0/560 (SH:- ROFD in Km 0/130 to 0/525) MNP	491655	10000	Two Month	350/-
10	C/O Shakol to Bagula road Km 0/00 to 1/270 (SH:- C/O V-shape drain at RD 0/10 to 0/270 Height 2.5 mtr MNP	136150	2800	Two Month	350/-
11	C/O Shakol to Bagula road Km 0/00 to 1/270 (SH:- ROFD i.e, C/O wire crate at RD 0/150 to 0/180 Height 2.5 mtr MNP.	312281	6500	Two Month	350/-
12	C/O Jaman Ki Ser Harkaghat road in Km 0/0 to 11/200 (SH:- C/O wire crate at Rd 2/630 to 2/640 height 2.5 mtr MNP	83532	1700	Two Month	350/-
13	C/O Dinger Khal Dhawal road Km 0/0 to 5/630 (SH:- ROFD in Km 1/900 to 2/060) MNP	265172	5500	Two Month	350/-
14	C/O Dinger Khal Dhawal road Km 0/0 to 5/630 (SH:- ROFD in Km 1/720 to 1/900) MNP	458233	9200	Two Month	350/-

15	C/O Ghargaon to Dagothar via Ganyana road Km 0/0 to 5/0 (SH:- C/O 900 mm Hume Pipe culvert at Rd 2/410) SCSP	228720	4600	One Month	350/-
16	R/R damages on Marighat Sulatanpur road (Portion Devol Tikkeri to Kangarghat) Km 16/0 to 21/0 (SH:- Removal of slips Debris etc.)	495977	10000	One Month	350/-
17	C/O of HPPWD Division office Building at Sarahan (SH:- Felling of Trees involved in Site development works for construction of HPPWD Divisional office building at Sarahan)	48020	1000	15 days	350/-
18	R/R Damages on Dungaghat Bagthan road Km 0/0 to 12/450 (SH:- C/O R/wall in G.I wire crate between RD 2/505 to 2/520 & 5/750 to 5/765)	492767	10000	Three Month	350/-
19	R/R damages on Dalag ka Ghat Sher Shog road Km 0/0 to 9/0 (SH:- Removal of slips)	339334	7000	One month	350/-

Certificate:- It is certified that the tender of above work are exigency/emergent nature and in public interest.

Terms & conditions:-

1. The contractors/Bidders must submit their Permanent Income Tax Account Number/GST number on the tender along with copy of the same be attached with the application.
2. The contractor/Firms should attached copy of the Registration/Renewal with the application.
3. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. Before quoting the bid/tender.
4. Conditional and telegraphic tender will not be accepted and rejected straightway. Tender received after due date and time shall not entertained.
5. The contractor/firm should have to produce the detail of work in hand in HPPWD and its position therefore along with application.
6. The tender document shall be issued to only those contractors who does not have more than two works in hand in HPPWD Circle/ Division.
7. The contractor shall have to establish testing laboratory at site for the day to day testing of material.
8. The Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reason.

sd
Executive Engineer
Sarahan B&R Division.
HP.PWD, Sarahan.

Dated:- 1/7/2024

No.PW/SRN/Estt-Tender/2022-23-

Copy forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD, Shimla-171002.
2. The Chief Engineer (South) HP.PWD, Shimla-171002.
3. The Superintending Engineer, 12th Circle HPPWD Nahan.
4. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD Shimla-2 for uploaded of Notice Inviting Tenders on Departmental website please.
5. All the Assistant Engineers working under this Division.
6. 7. All Intending Bidders/Contractors.
8. Notice Board.

[Signature]
Executive Engineer
Sarahan B&R Division.
HP.PWD, Sarahan.

SCHEDULE OF QUANTITY

Name of Work:- C/O Naina Tikker Dagother Via Kenchi More in km 0/00 to 2/800(SH):- C/O 900 mm dia Hume Pipe Culvert along with wing wall at RD 0/900(SCSP)

Estimated cost:-Rs. 288901/-✓

Earnest money:- Rs. 6000/✓

Time Limit:- Two Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	51.535✓	Per Cubic Metre.	261.00✓	Rupees two hundred sixty one and paise nil only✓	13451.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	29.690✓	Per Cubic Metre.	5166.45✓	Rupees five thousand one hundred sixty six and paise fourty five only✓	153392.00
3	Providing and laying Plain Cement Concrete 1:3:6(one cement: three sand: six graded hard stone aggregate 20mm(twenty) millimeter)nominal size} and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	12.284✓	Per cubic metre	6029.00✓	Rupees six thousand twenty nine and paise nil only✓	74060.00
4	Providing and laying cement concrete 1:6:12 {One cement: Six sand: twelve graded crushed stone aggregate 40(Forty) millimeter nominal size} in open foundation and curing complete excluding cost of form work complete as per drawing and technical specification clause 802,803,1202 and 1203 including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge	1.95✓	Per cubic meter.	4601.50✓	Rupees four thousand six hundred one and paise fifty only✓	8973.00

5	Laying reinforced cement concrete 900 mm (Nine Hundred millimeter) diameter pipe class NP-2 (Non Pressure-Two), including jointing for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) including back filling but excluding excavations, protection works, concrete and masonry works in head walls and parapets as per drawings and technical specifications C - 1108. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,	7.500 ✓	Per Running Metre.	4167.64 ✓	Rupees four thousand one hundred sixty seven and paise sixty four only ✓	31257.00 ✓
6	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)), including hauling / carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	6.000 ✓	Each	280.00 ✓	Rupees two hundred eighty and paise nil only ✓	1680.00 ✓
7	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in- Charge.	7.710 ✓	Per Cubic Metre.	789.60 ✓	Rupees seven hundred eighty nine and paise sixty only ✓	6088.00 ✓
					Total	288901.00 ✓


 Executive Engineer
 Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of Work:- C/O Marighat Kerry Shutiy Road in km 0/0 to 10/300(SH:- C/O 900 mm dia Hume Pipe Culvert along with wing wall at RD 3/200 and 6/450(MNP)

Estimated cost:-Rs. 458140/- ✓

Earnest money:- Rs. 9200/- ✓

Time Limit:- Two Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	94.72 ✓	Per Cubic Metre.	261.00 ✓	Rupees two hundred sixty one and paise nil only ✓	24722.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	43.54 ✓	Per Cubic Metre.	5166.45 ✓	Rupees five thousand one hundred sixty six and paise forty five only ✓	224947.00
3	Providing and laying Plain Cement Concrete 1:3:6(one cement: three sand: six graded hard stone aggregate 20mm(twenty) millimeter)nominal size} and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	20.36 ✓	Per cubic metre	6029.00 ✓	Rupees six thousand twenty nine and paise nil only ✓	122750.00
4	Providing and laying cement concrete 1:6:12 {One cement: Six sand: twelve graded crushed stone aggregate 40(Forty) millimeter nominal size} in open foundation and curing complete excluding cost of form work complete as per drawing and technical specification clause 802,803,1202 and 1203 including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge	2.97 ✓	Per cubic meter.	4601.50 ✓	Rupees four thousand six hundred one and paise fifty only ✓	13666.00

Laying reinforced cement concrete 900 mm (Nine Hundred millimeter)diameter pipe class NP-2(Non Presseure-Two), including jointing for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2(one cement: two sand) including back filling but excluding excavations, protection works, concrete and masonry works in head walls and parapets as per drawings and technical specifications C - 1108. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,	15.000 ✓	Per Running Metre.	4167.64 ✓	Rupees four thousand one hundred sixty seven and paise sixty four only ✓	62515.00 ✓
6 Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	7.000 ✓	Each	280.00 ✓	Rupees two hundred eighty and paise nil only ✓	1960.00 ✓
7 Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in Charge.	9.600 ✓	Per Cubic Metre.	789.60 ✓	Rupees seven hundred eighty nine and paise sixty only ✓	7580.00 ✓
				Total	458140.00 ✓


 Executive Engineer
 Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of Work:- C/O of Dungaghat Kilakalanch Road km 0/00 to 22/00 (SH:- C/O 900 mm dia Hume Pipe Culvert along with wing wall of 3.05 mtr Hieght at RD 4/100,4/245 (MNP)

Estimated cost:-Rs. 458029/-

Earnest money:- Rs. 9,200/-

Time Limit:- Two Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	94.72	Per Cubic Metre.	261.00	Rupees two hundred sixty one and paise nil only	24722.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	43.53	Per Cubic Metre.	5166.45	Rupees five thousand one hundred sixty six and paise forty five only	224896.00
3	Providing and laying Plain Cement Concrete 1:3:6 (one cement: three sand: six graded hard stone aggregate 20mm (twenty millimeter) nominal size) and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	20.35	Per cubic metre	6029.00	Rupees six thousand twenty nine and paise nil only	122690.00
4	Providing and laying cement concrete 1:6:12 {One cement: Six sand: twelve graded crushed stone aggregate 40 (Forty) millimeter nominal size} in open foundation and curing complete excluding cost of form work complete as per drawing and technical specification clause 802,803,1202 and 1203 including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge	2.97	Per cubic meter.	4601.50	Rupees four thousand six hundred one and paise fifty only	13666.00

	Laying reinforced cement concrete 900 mm (Nine Hundred millimeter) diameter pipe class NP-2 (Non Presseure-Two), including jointing for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) including back filling but excluding excavations, protection works, concrete and masonry works in head walls and parapets as per drawings and technical specifications C - 1108. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,	15.00 ✓	Per Running Metre.	4167.64 ✓	Rupees four thousand one hundred sixty seven and paise sixty four only ✓	62515.00 ✓
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	7.000 ✓	Each	280.00 ✓	Rupees two hundred eighty and paise nil only ✓	1960.00 ✓
7	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in Charge.	9.60 ✓	Per Cubic Metre.	789.60 ✓	Rupees seven hundred eighty nine and paise sixty only ✓	7580.00 ✓
					Total	458029.00 ✓


 Executive Engineer
 K. Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of Work:- C/O Kalaghat Banana Road in km 0/00 to 5/00(SH:- C/O 900 mm dia Hume Pipe Culvert along with wing wall at RD 3/100(MNP)

Estimated cost:-Rs. 232722/-

Earnest money:- Rs. 4700/-

Time Limit:- Two Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	47.36 ✓	Per Cubic Metre.	261.00 ✓	Rupees two hundred sixty one and paise nil only ✓	12361.00 ✓
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	21.770 ✓	Per Cubic Metre.	5166.45 ✓	Rupees five thousand one hundred sixty six and paise forty five only ✓	112474.00 ✓
3	Providing and laying Plain Cement Concrete 1:3:6 (one cement: three sand: six graded hard stone aggregate 20mm (twenty millimeter) nominal size) and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	10.480 ✓	Per cubic metre	6029.00 ✓	Rupees six thousand twenty nine and paise nil only ✓	63184.00 ✓
4	Providing and laying cement concrete 1:6:12 {One cement: Six sand: twelve graded crushed stone aggregate 40 (Forty) millimeter nominal size} in open foundation and curing complete excluding cost of form work complete as per drawing and technical specification clause 802, 803, 1202 and 1203 including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge	1.49 ✓	Per cubic meter.	4601.50 ✓	Rupees four thousand six hundred one and paise fifty only ✓	6856.00 ✓

3	Laying reinforced cement concrete 900 mm (Nine Hundred millimeter) diameter pipe class NP-2 (Non Presseure-Two), including jointing for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) including back filling but excluding excavations, protection works, concrete and masonry works in head walls and parapets as per drawings and technical specifications C - 1108. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,	7.500 ✓	Per Running Metre.	4167.64 ✓	Rupees four thousand one hundred sixty seven and paise sixty four only ✓	31257.00 ✓
6	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)), including hauling / carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	10.000 ✓	Each	280.00 ✓	Rupees two hundred eighty and paise nil only ✓	2800.00 ✓
7	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	4.800 ✓	Per Cubic Metre.	789.60 ✓	Rupees seven hundred eighty nine and paise sixty only ✓	3790.00 ✓
					Total	232722.00 ✓


 Executive Engineer
 KS Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of Work:- C/O Naina Tikker Dhangyar Road in km 0/00 to 12/00 (SH:- C/O 900 mm dia Hume Pipe Culvert along with wing wall at RD 10/480(MNP))

Estimated cost:-Rs. 302254/-

Earnest money:- Rs. 6,000/-

Time Limit:- Two Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	52.12	Per Cubic Metre.	261.00	Rupees two hundred sixty one and paise nil only	13603.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8, (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	31.971	Per Cubic Metre.	5166.45	Rupees five thousand one hundred sixty six and paise fourty five only	165177.00
3	Providing and laying Plain Cement Concrete 1:3:6 (one cement: three sand: six graded hard stone aggregate 20mm (twenty) millimeter) nominal size} and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	12.359	Per cubic metre	6029.00	Rupees six thousand twenty nine and paise nil only	74512.00
4	Providing and laying cement concrete 1:6:12 {One cement: Six sand: twelve graded crushed stone aggregate 40 (Forty) millimeter nominal size} in open foundation and curing complete excluding cost of form work complete as per drawing and technical specification clause 802, 803, 1202 and 1203 including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge	1.69	Per cubic meter.	4601.50	Rupees four thousand six hundred one and paise fifty only	7777.00

Laying reinforced cement concrete 900 mm (Nine Hundred millimeter) diameter pipe class NP-2 (Non Presseure-Two), including jointing for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) including back filling but excluding excavations, protection works, concrete and masonry works in head walls and parapets as per drawings and technical specifications C - 1108. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,	7.500 ✓	Per Running Metre.	4167.64 ✓	Rupees four thousand one hundred sixty seven and paise sixty four only ✓	31257.00 ✓
6 Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)), including hauling / carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	6.000 ✓	Each	280.00 ✓	Rupees two hundred eighty and paise nil only ✓	1680.00 ✓
7 Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	10.446 ✓	Per Cubic Metre.	789.60 ✓	Rupees seven hundred eighty nine and paise sixty only ✓	8248.00 ✓
				Total	302254.00 ✓


 Executive Engineer
 KSSarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of Work:- C/O Link road to village Gandal km 0/00 to 7/00 (SH:- C/O 900 mm dia Hume Pipe Culvert along with wing wall of 3.05 mtr Height at RD 3/00 (MNP)

Estimated cost:-Rs. 228953/-

Earnest money:- Rs. 4,600/-

Time Limit:- Two Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	47.36 ✓	Per Cubic Metre.	261.00 ✓	Rupees two hundred sixty one and paise nil only ✓	12361.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	21.77 ✓	Per Cubic Metre.	5166.45 ✓	Rupees five thousand one hundred sixty six and paise forty five only ✓	112474.00
3	Providing and laying Plain Cement Concrete 1:3:6 (one cement: three sand: six graded hard stone aggregate 20mm (twenty millimeter) nominal size) and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	10.18 ✓	Per cubic metre	6029.00 ✓	Rupees six thousand twenty nine and paise nil only ✓	61375.00
4	Providing and laying cement concrete 1:6:12 {One cement: Six sand: twelve graded crushed stone aggregate 40 (Forty) millimeter nominal size} in open foundation and curing complete excluding cost of form work complete as per drawing and technical specification clause 802, 803, 1202 and 1203 including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge	1.49 ✓	Per cubic meter.	4601.50 ✓	Rupees four thousand six hundred one and paise fifty only ✓	6856.00

Laying reinforced cement concrete 900 mm (Nine Hundred millimeter) diameter pipe class NP-2 (Non Presseure-Two), including jointing for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) including back filling but excluding excavations, protection works, concrete and masonry works in head walls and parapets as per drawings and technical specifications C - 1108. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,	7.50 ✓	Per Running Metre.	4167.64 ✓	Rupees four thousand one hundred sixty seven and paise sixty four only ✓	31257.00 ✓
6 Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)), including hauling / carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	3.000 ✓	Each	280.00 ✓	Rupees two hundred eighty and paise nil only ✓	840.00 ✓
7 Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in Charge.	4.80 ✓	Per Cubic Metre.	789.60 ✓	Rupees seven hundred eighty nine and paise sixty only ✓	3790.00 ✓
				Total	228953.00 ✓


 Executive Engineer
 KS Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of Work:- C/O Rister Panwa Road in km 0/00 to 2/100 (SH:- P/L Soling G-I between km 1/025 to 1/500 (MNP)

Estimated cost:-Rs. 490581/-

Earnest money:- Rs. 1,0000/-

Time Limit:- Two Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Loosening Levelling, Compacting original ground supporting embankment to facilitate placement of layer for embankment scarified to a depth of 150 mm mixed with water at OMC and then compacted by rolling so as to achieve minimum dry density as given in the table 300.0 and 300.2 for embankment construction as per technical specification.	175.04	Per Cubic Metre.	30.58	Rupees thirty and paise fifty eight only	5353.00
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 1 as per Technical Specification Clause 405.	175.040	Per Cubic Metre.	2772.10	Rupees two thousand seven hundred seventy two and paise ten only	485228.00
					Total	490581.00

Executive Engineer
K3 Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- C/O Prem Nagar Chandog Road in km 0/00 to 15/00 (SH:- C/O Boundary Wall of Bal Niketen Ashram at RD 10/030 to 10/038) under Deposit work

Estimated cost:-Rs.499760/-

Earnest money:- Rs. 10,000/-

Time Limit:- One Months.

Sr. No	Description Items of work	Qty.	Unit	in figures.	Rate		Amount
					in words		
1	2	3	4	5	6	7	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	33.12	Per Cubic Metre.	261.00	Rupees two hundred sixty one and paise zero only	8644.00	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	92.88	Per Cubic Metre.	5166.45	Rupees five thousand one hundred sixty six and paise forty five only	479860.00	
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)).including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	12.00	Each	280.00	Rupees. Two Hundred eighty and paise nil only	3360.00	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	10.00	Per Cubic Metre.	789.60	Rupees seven Hundred eighty nine and paise sixty Only	7896.00	
						499760.00	

Executive Engineer
KS Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- C/O link Road to Dr. Y.S Parmar Birth Place at Chanalag in km 0/0 to 0/560 (SH:- ROFD in km 0/130 to 0/525 MNP

Estimated cost:-Rs.491655/-

Earnest money:- Rs. 10,000/-

Time Limit:- Two Months.

Sr. No	Description Items of work	Unit	QTY	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Excavation in hilly area in soft blast requiring blasting by mechanical means including cutting and trimming of side slopes and disposing of excavated earth within a lift up to 1.5 m and a lead upto 20 m as per technical specification clause 1603.2 Soft Blast	Cum	1863.74	263.80	Rupees two hundred sixty three and paise eighty only	491655.00
2	Recovery for usefull stones SW, =1863.74 m3/6=310.62m3@Rs.170/-	Cum	310.62	170.00	Rupees one hundred seventy and paise nil only	
						491655.00

Executive Engineer

K. Sarahan Division

HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- C/O Shakol to Bagula Road in km 0/00 to 1/270(SH:-C/O V-shape drain at RD 0/10 to 0/270 Height 2.5 mtr
MNP

Estimated cost:-Rs.136150/-

Earnest money:- Rs. 2800/-

Time Limit:- Two Months.

Sr. No	Description Items of work	Unit	QTY	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	Cum	26.16 ✓	261.00 ✓	Rupees two hundred sixty one and paise nil only ✓	6828.00 ✓
2	Providing and laying Plain Cement Concrete 1:3:6(one cement: three sand: six graded hard stone aggregate 20mm(twenty) millimeter)nominal size} and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	Cum	21.45 ✓	6029.00 ✓	Rupees Six thousand twenty nine and paise nil only ✓	129322.00 ✓
						136150.00 ✓


Executive Engineer
Sarhan Division
HP, PWD, Sarhan

SCHEDULE OF QUANTITY

Name of work:- C/O Shakol to Bagula Road in km 0/00 to 1/270(SH:-C/O wire crate at RD 0/150 to 0/180 Height 2.5 mtr MNP Earnest money:- Rs. 6500/-

Estimated cost:-Rs.312281/-
Time Limit:- Two Months.

Sr. No	Description Items of work	Unit	QTY	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	Cum	33.75	261.00	Rupees two hundred sixty one and paise nil only	8809.00
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	Cum	103.12	2942.90	Rupees two thousand nine hundred forty two and paise ninety only	303472.00
						312281.00

Executive Engineer
KS Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work: - C/O Jaman ki ser Harkaghat Road in km 0/00 to 11/200(SH:- ROFD in 0.300 km C/O wire crate at RD 2/630 to 2/640 Height 2.5 mtr MNP

Estimated cost:-Rs.83532/-

Earnest money: - Rs. 1700/-

Time Limit: - One Months.

Sr. No	Description Items of work	Unit	QTY	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	Cum	9.36 ✓	261.00 ✓	Rupees two hundred sixty one and paise nil only ✓	2443.00 ✓
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	Cum	26.80 ✓	2942.90 ✓	Rupees two thousand nine hundred forty two and paise ninety only ✓	78870.00 ✓
	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	Cum	2.81 ✓	789.60 ✓	Rupees seven hundred eighty nine and paise sixty only ✓	2219.00 ✓
						83532.00 ✓


 Executive Engineer
 K.S. Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- C/O Dinger Kinner Khal Dhawal Road in km 0/0 to 5/630 (SH:- ROFD in km 1/900 to 2/060 MNP

Estimated cost:-Rs.265172/-

Earnest money:- Rs. 5500/-

Time Limit:- Two Months.

Sr. No	Description Items of work	Unit	QTY	in figures.	Rate in words	Amount
				5	6	
1	2	3	4			7
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 137.50 cum (two hundred eighty two point	Cum	205.90	172.00	Rupees one hundred seventy two and paise nil only ✓	35415.00
2	Excavation in hilly area in soft blast requiring blasting by mechanical means including cutting and trimming of side slopes and disposing of excavated earth within a lift up to 1.5 m and a lead upto 20 m as per technical specification clause 1603.2 Soft Blast	Cum	823.50	279.00	Rupees two hundred seventy nine and paise nil only ✓	229757.00
	Recovery for usefull stones, =823.08 m3/6=137.50m3@Rs.170/-	Cum	137.25	170.00	Rupees one hundred seventy and paise nil only	
						265172.00


 Executive Engineer
 Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- C/O Dinger Kinner Khal Dhawal Road in km 0/0 to 5/630 (SH:- ROFD in km 1/720 to 1/900 MNP

Estimated cost:-Rs.458233/-

Earnest money:- Rs. 9200/-

Time Limit:- Two Months.

Sr. No	Description Items of work	Unit	QTY	in figures.	Rate		Amount
					in words.	6	
1	2	3	4	5	6	7	
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 237.18 cum (two hundred eighty two point forty one) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases. Bick work	Cum	355.78	172.00	Rupees one hundred seventy two and paise nil only	✓	61194.00
2	Excavation in hilly area in soft blast requiring blasting by mechanical means including cutting and trimming of side slopes and disposing of excavated earth within a lift up to 1.5 m and a lead upto 20 m as per technical specification clause 1603.2 Soft Blast	Cum	1423.08	279.00	Rupees two hundred seventy nine and paise nil only	✓	397039.00
	Recovery for usefull stones, =1423.08 m ³ /6=237.18m ³ @Rs.170/-	Cum	237.18	170.00	Rupees one hundred seventy and paise nil only	✓	458233.00


Executive Engineer
K. Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of Work:- C/O Ghargon to Dagother via Ganyana Road in km 0/0 to 5/0 (SH:- C/O 900mm HPC culvert at RD 2/410) SCS

Estimated cost:-Rs. 228720-

Earnest money:- Rs. 4600/-

Time Limit:- One Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	47.36 ✓	Cum	261.00 ✓	Rupees two hundred sixty one and paise nil only ✓	12361.00 ✓
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	21.76 ✓	Cum	5166.45 ✓	Rupees five thousand one hundred sixty six and paise fourty five only ✓	112422.00 ✓
3	Providing and laying Plain Cement Concrete 1:3:6 (one cement: three sand: six graded hard stone aggregate 20mm (twenty) millimeter) nominal size} and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	10.15 ✓	Cum	6029.00 ✓	Rupees six thousand twenty nine and paise nil only ✓	61194.00 ✓
4	Providing and laying cement concrete 1:6:12 {One cement: Six sand: twelve graded crushed stone aggregate 40(Forty) millimeter nominal size} in open foundation and curing complete excluding cost of form work complete as per drawing and technical specification clause 802,803,1202 and 1203 including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge	1.49 ✓	Cum	4601.50 ✓	Rupees four thousand six hundred one and paise fifty only ✓	6856.00 ✓
5	Laying reinforced cement concrete 900 mm (Nine Hundred millimeter) diameter pipe class NP-2(Non Presseure- Two), including jointing for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) including back filling but excluding excavations, protection works, concrete and masonry works in head walls and parapets as per drawings and technical specifications C - 1108. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	7.50 ✓	Rmt	4167.64 ✓	Rupees four thousand one hundred sixty seven and paise sixty four only ✓	31257.00 ✓
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)).including hauling /carriage of all labour equipments and materials to various	3.00 ✓	each	280.00 ✓	Rupees two hundred eighty and paise nil only ✓	840.00 ✓

7	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	4.80	Cum	789.60	Rupees seven hundred eighty nine and paise sixty only	3790.00
					Total	228720.00


 Executive Engineer
 KS Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Marighat Sultanpur road (portion Devol Tikkri to Kangarghat) km 16/0 to 21/0
(SH:- Removal of slips. Debris etc.)

Estimated cost:-Rs. 495977/-

Earnest money: - Rs 10000

Time Limit: - one Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Removal of landslides /slip clearance. clearance of drain ,Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	5450.30	Per Cubic Metre.	91.00	Rupees ninety one and paise nil only	495977.00
						495977.00

Executive Engineer
KS Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of Work:- Construction of HPPWD Division office Building at Sarahan((SH:-Felling of Trees involved in Site Development works for construction of HPPWD Divisional office building at Sarahan.)

Estimated cost:-Rs. 48020/-

Earnest money:- Rs. 1000/-

Time Limit:- (15 Days

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Felling of trees involved in Site development works for construction of Divisional office Building at sarahan comprised in Khasra No. 91 to 111. including cutting the trees in proper and specified sizes of 6' 8' and 10' logs and stacking the same in separate stacks at site as per the directions of the Engineer -in Charges	49.00	each	980.00	Rupees Nine Hundred Eighty and paise nil only ✓	48020.00 ✓
					Total	48020.00 ✓

Executive Engineer
KS Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work: R/R Damages on Dungaghat Bagthan Road km 0/0 to 12/450 (SH:- C/o R/Wall in G.I wire crate


between RD 2/505 to 2/520 & 5/750 to 5/765)

Estimated cost:- Rs. 4,92,767/- ✓

Earnest money:- Rs 10,000/- ✓

Time Limit:- Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	45.18 ✓	Per Cubic Metre.	261.00 ✓	Rupees two hundred sixty one and paise nil only	11792.00
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	159.25 ✓	Per Cubic Metre.	2942.90 ✓	Rupees two thousand nine hundred forty two and paise ninety only	468657.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	15.60 ✓	Per Cubic Metre.	789.60 ✓	Rupees seven hundred eighty nine and paise sixty only ✓	12318.00
						492767.00 ✓


KS Sarahan
Executive Engineer
HP, PWD, Sarahan

SCHEDULE OF QUANTITY


Name of work: - R/R Damages on Dalag ka ghat Sher shog road km 0/0 to 9/0 (SH:- Removal of slips)

Estimated cost:-Rs. 3,39,334/- ✓

Earnest money: - Rs 7,000 ✓

Time Limit: - one Month. ✓

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Removal of landslides /slip clearance. clearance of drain ,Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	3728.94 ✓	Per Cubic Metre.	91.00 ✓	Rupees ninety one and paise nil only ✓	339334.00 ✓
						339334.00 ✓


Executive Engineer
KS Sarahan Division
HP, PWD, Sarahan