

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT.
NOTICE INVITING TENDER

Sealed percentage rate tenders are hereby invited on Form No.7 &8 by the undersigned on behalf of the Governor of Himachal Pradesh for the following works 29-07-2024 upto 11:00 A.M and shall be opened on the same day on 11:30 A.M. in the presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (Non- refundable) during the working hours.

The earnest money in the shape of National Saving Certificate, FDRs/TDRs/ Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Sarahan must accompany with each applications/tender. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 75 days. The undersigned reserves the right to reject the any or all tender without assigning any reason.

S N	Tender Schedule				
1	Last date for tender receipt of application for tender form	26-07-2024 up to 4:00 PM			
2	Last date of sale of tender forms	27-07-2024 up to 4:00 PM			
3	Date of receipt of tender forms	29-07-2024 up to 11:00 A.M			
4	Date of opening of tenders	29-07-2024 at 11:30 A.M			
Sr. No	Name of Work	Estimat ed cost	Earnest Money	Time Limit	Cost of Form
1	C/O Motorable Bridges at Giri River between Chabyoga (Pachhad) to Shalamu (Rajgarh) District Sirmour (SH:- Geo-Tech investigation for safe bearing capacity of bridge	480000	10000	Three Month	350/-
2	C/O Motorable Bridges at Giri River between Chabyoga (Pachhad) to Shalamu (Rajgarh) District Sirmour (SH:- Preparation of Hydraulic Data, GAD (General arrangement of drawing) and detailed project report Bridge-I)	300000	6000	Three month	350/-
3	Construction of Sarahan Chadech road Km 0/0 to 7/0 (SH:- C/O R/wall at RD 1/115 to 1/135) balance work	175342	4000	Three month	350/-
4	R/R damages on Banethi Bagthan Chandol road Km 7/0 to 28/0 (SH:- C/O PCC R/wall at RD 16/307 to 16/316)	305196	7000	Three Month	350/-
5	Preparation of Drawings of existing Building /Structure of State of Art Model De-addiction rehabilitation Centre situated at village Kotla Barog tehsil Pachhad Distt. Sirmour H.P	270928	6000	One month	350/-
6	C/O R/wall in wire create to protect the school playground at GSSS Naya Gaon Tehsil Pachhad Distt Sirmour	268147	6000	Two Month	350/-

Certificate:-It is certified that the tender of above work are exigency/emergent nature and in public interest.

Terms & conditions:-

1. The contractors/Bidders must submit their Permanent Income Tax Account Number/GST number on the tender along with copy of the same be attached with the application.
2. The contractor/Firms should attached copy of the Registration/Renewal with the application.
3. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. Before quoting the bid/tender.
4. Conditional and telegraphic tender will not be accepted and rejected straightway. Tender received after due date and time shall not entertained.
5. The contractor/firm should have to produce the detail of work in hand in HPPWD and its position therefore along with application.
6. The tender document shall be issued to only those contractors who does not have more than two works in hand in HPPWD Circle/ Division.
7. The contractor shall have to establish testing laboratory at site for the day to day testing of material.
8. The Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reason.

Sd/-
Executive Engineer
Sarahan Division,
H.P.PWD., Sarahan

P.T.O

No.PW/SRN/Estt-Tender/2022-23-

1651-1700

Dated:-

18 7
2024

Copy forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD, Shimla-171002.
2. The Chief Engineer (South) HP.PWD, Shimla-171002.
3. The Superintending Engineer, 12th Circle HPPWD Nahan.
4. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD Shimla-2 for uploaded of Notice Inviting Tenders on Departmental website please.
5. All the Assistant Engineers working under this Division.
6. 7. All Intending Bidders/Contractors.
8. Notice Board.


Executive Engineer
Sarhan B&R Division.
P.PWD, Sarhan.

SCHEDULE OF QUANTITY

Name of work:- Construction of Motorable Bridges at Giri River between chabyoga (Pachhad) to Shalamu (Rajgarh) Distt

Estimated cost:-Rs.4,80,000/-

Earnest money:- Rs. 9,600/-

Sirmour (SH):- Geo-tech Investigation for safe bearing capacity of bridge

Time Limit:- Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Geo-Tech Investigation for safe bearing capacity by conducting SPT up to 20m as per IS:1892 by core drilling, at 2 No. Bore hole location (Quantity =3x20=60m) 1. Mobilization of necessary equipments, men and materials for geotechnical investigation from one test location to another and remobilizing the same including provision of casing pipe. 2. Collecting undisturbed soil samples at including waxing, labeling, handling and transportation etc. 3. Determination of standard penetration Test (SPT) in all the bore holes at regular intervals and collection of the disturbed soil samples from SPT spoon. 4. Presentation of data as per IRC:78 and work out the Bearing Capacity of the soil for design of the	60.00	Per Running Meter	8000	Rupees eight thousand and paise zero only	480000.00
						480000.00


 Executive Engineer
 Ks Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- Construction of Motorable Bridges at Giri River between chabyoga (Pachhad) to Shalamu (Raigarh) Distt. Sirmour (SH):- Preparation of Hydraulic Data, GAD (General arrangement of drawings) and Detailed project report Bridge.]

Estimated cost:-Rs.3,00,000/-

Earnest money:- Rs. 6,000/-

Time Limit:- Three Months.

Sr. No	Description Items of work	Qty.	Unit	in figures.	Rate		Amount
					in words		
1	2	3	4	5	6	7	
1	Preparation of Hydraulic data i.e Topography survey by total station equipment for preparation of survey plan, cross section at bridge site, 50 m, 150 m, 300 m, 500 m upstream and down stream of river, L-section of road and river.	1.00 ✓	Per Job	90000 ✓	Rupees ninety thousand and paise zero only ✓	90000.00	
2	Preparation of General arrangement of drawings according to the existing site conditions and submit the same in the form of two hard copies .The consultant will get the GAD approved from the HPPWD Chief Office Shimla. The Work will be carried in accordance with latest design specification and to satisfaction of Engineer -in - charge.	1.00 ✓	Per Job	80000.00 ✓	Rupees eighty thousand and paise zero only ✓	80000.00	
3	Preparation of Detailed project report on NABARD guideline on market rate, submitted in the form of five hard copy and approval of the same from HPPWD chief office Shimla.	1.00 ✓	Per Job	130000.00 ✓	Rupees one lakhs thirty thousand and paise nil only ✓	130000.00	
						300000.00	


 Executive Engineer
 K.S. Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work: ~~Balance estimate for the Construction of Sarahan Chadech road km 0/0 to 7/0 (SH:- C/O~~

~~R/wall at RD 1/15 to 1/135) Balance extra work .~~

Estimated cost:- Rs. 1,75,342/-

Earnest money: - Rs 3,500

Time Limit: - Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	33.66 ✓	Per Cubic Metre.	4717.20	Rupees four thousand seven hundred seventeen and paise twenty only ✓	158781.00
2	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	22.44 ✓	Per Cubic Metre.	738.00 ✓	Rupees seven hundred thirty eight and paise nil only ✓	16561.00
						175342.00

Executive Engineer
KS Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:-R/R Damages on Banethi Bagthan Rajgarh Chandol road km 7/0 to 28/0 (SH:- C/O PCC R/Wall at RD 16/307 to 16/316)


Estimated cost:-Rs. 3,05,196/-

Earnest money: - Rs 6,500

Time Limit:- Three Months.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	15.30	Per Cubic Metre.	261.00	Rupees two hundred sixty one and paise nil only	3993.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	55.78	Per Cubic Metre.	5166.45	Rupees five thousand one hundred sixty six and paise forty five only	288185.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	21.000	Each	280.00	Rs. Two Hundred eighty and paise nil only	5880.00

4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	9.04 ✓	Per Cubic Metre.	789.60 ✓	Rupees seven hundred eighty nine and paise sixty only ✓	7138.00 ✓
						305196.00 ✓


 Executive Engineer
 Sarahan Division
 HP, PWD, Sarahan

(5)

SCHEDULE OF QUANTITY

Name of work :- Preparation of Drawings of existing Building/Structures of State of Art Model De-addition and rehabilitation Center Situated at Village Kotla Barog Tehsil Pachhad Distt. Sirmour H.P

Estimated cost:-Rs. 2,70,928/-

Earnest money:- Rs. 6000/-

Time Limit:- One month

Sr N	Description Items of work	Qty.	Unit	Rate		Amount
				in figures	in words	
1	2	3	4	5	6	7
1	Detailed Topographical Survey work with Total Electronic Station to detect the topography of load and every feature on the ground true to their position and preparation of contour plan at appropriate Contour interval depending upon the topography of the terrain. Fixing of temporary benchmark and marketing them on ground with paint as required. Calculation of area with standard surveying software program and preparation of drawing on computer using auto CAD.	128.000	Per Bigha	1416.00	Rupees one thousand four hundred sixteen and paise nil only	181248.00
2i)	Preparation of As Built Drawings of Existing Buildings / Structures. GIRL'S HOSTEL AND BOYS HOSTEL BLOCK TOTAL 4 FLOORS	4.000	Per Floor	7080.00	Rupees seven thousand eighty and paise nil only	28320.00
ii)	ALL 9 NOS SINGLE STOREY AND 2 NOS DOUBLE STOREY STRUCTURES TOTAL 13 FLOORS	13.000	Per Floor	4720.00	Rupees four thousand seven hundred twenty and paise nil only	61360.00
						270928.00

Executive Engineer

Sarhan Division

HP, PWD, Sarhan

SCHEDULE OF QUANTITY

Estimated cost:-Rs. 2,86,147/-

Name of work:- C/O Wire crate to protect the school play ground at GSSS Naya Gaon Tehsil Pachhad Distt. Sirmour H.P

Earnest money:- Rs. 5,800

Time Limit:- Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	29.72	Per Cubic Metre.	194.00	Rupees one hundred ninety four and paise zero only	5766.00
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	93.23	Per Cubic Metre.	2846.40	Rupees two thousand eight hundred forty six and paise forty only	265370.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge	20.34	Per Cubic Metre.	738.00	Rs. seven hundred thirty eight and paise nil only	15011.00
						286147.00


 Executive Engineer
 Sarahan Division
 HP, PWD, Sarahan