



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in

CERTIFICATE

**CERTIFIED THAT THE TENDERS OF WORKS, AS
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2024-25/-
16445-84 DATED 15-01-2025 ARE URGENT NATURE
AND PUBLIC INTEREST.**


**Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.**



**Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in**

"NOTICE INVITING TENDER"

Sealed item rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **27.01.2025** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **24.01.2025 between 2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **23.01.2025 up to 12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	A/R & M/O under Baijnath Division (SH: Supply and fixing Printer, Biometric System and Metal casing in HPPWD Division Baijnath.	Rs.92,000/-	Rs.1,900/-	Rs.350/-	One Month
2	Special Repair of Rest House Baijnath (SH: Applying Painting, Putty work etc.)	Rs.99,860/-	Rs.2,000/-	Rs.350/-	Two Months
3	Special Repair of Rest House Baijnath (SH: Painting, Distemping, Aluminium door Shutter etc.)	Rs.99,989/-	Rs.2,000/-	Rs.350/-	Two Months
4	C/O Baijnath Deol Phatar Road Km 0/00 to 10/180 (SH: C/O Damaged protection wall of slab culvert at RD 7/425 R.H.S approach)	Rs.99,972/-	Rs.2,000/-	Rs.350/-	Two Months
5	C/O R/R Damages on Bir Palampur Road Km 0/00 to 40/00 (SH: C/O R/wall at RD 1/140 to 1/146.50)	Rs.98,649/-	Rs.2,000/-	Rs.350/-	Two Months
6	C/O Main Road from Shri Sarwan Kumar House to Sh. Jufi Ram House Deposit work SDP/2024/828 (SH: P/L 40mm thick Paver Block)	Rs.99,020/-	Rs.2,000/-	Rs.350/-	Two Months
7	C/O Road from Shri Pami Kumar House to Sh. Gyan Chand Hose Mohal (SH: P/L C.C. Pavement & Kharnja Soling) (Deposit work SDP/2024/838)	Rs.98,562/-	Rs.2,000/-	Rs.350/-	Two Months
8	C/O Pucca Path from Sh. Payar Chand House to SC Basti-Nagehar Mohal (SH: P/L C.C. Pavement & Kharnja Soling) (Deposit work SDP/2024/835)	Rs.98,912/-	Rs.2,000/-	Rs.350/-	Two Months
9	C/O ambulance Road from Chaniyara to Mehta Basti Mohal (SDP/2024/832) (Under Deposit) (SH: P/L C.C. Pavement & Kharnja Soling)	Rs.99,001/-	Rs.2,000/-	Rs.350/-	One Month
10	C/O Pucca Path from Jaswant Lagwal to Ishwar Dass House (SH: P/L 40mm thick Paver Block at Km 0/00 to 0/055) SDP/2024/829	Rs.98,970/-	Rs.2,000/-	Rs.350/-	Two Months
11	C/O Link Road from Behru to Majhera Railway Station via Desh raj House Km 0/00 to 0/500 (SH: P/L C.C. Pavement & Kharnja Stone Soling at Km 0/135 to 0/161) (Deposit work SDP/2024/811)	Rs.99,529/-	Rs.2,000/-	Rs.350/-	Two Months
12	Construction of Pucca Path alongwith Pully Panchyat MahalPatt (SH: Construction of 1.00 mtr span RCC Slab culvert at RD 0/007 & P/L Kharnja Stone soling & C.C. Pavement at RD 0/007 to 0/0038 & Edge wall at RD 0/000 to 0/006) (Deposit work) SDP/2024/837	Rs.99,992/-	Rs.2,000/-	Rs.350/-	Two Months
13	C/O Jeepable Road along with Paver Block Post Office to Deep Raj/Tilak House ward No.3 (SH: P/L 60mm thick Paver Block) Deposit work- SDP/2024/811	Rs.98,957/-	Rs.2,000/-	Rs.350/-	Two Months
14	C/O Community Shed Near SDPO at Baijnath (SH: Extension of slab) back side (Deposit work) SDP/2023-748	Rs.99,451/-	Rs.2,000/-	Rs.350/-	Two Months
15	C/O Holta Chadhar Road (SW: Diversion Portion Between Portion Between 62/900 to 63/300 (SH: P/L C.C. Pavement & Kharnja Soling at RD 0/250 to 0/274.50)	Rs.98,649/-	Rs.2,000/-	Rs.350/-	Two Months
16	C/O Bhullana to Simbal Road Km 0/00 to 6/220 (SH: C/O E/Wall at RD 0/011.50 to 0/023)	Rs.64,114/-	Rs.1,300/-	Rs.350/-	One Month
17	C/O Lohardi to Andarli Mahan Road Km 0/00 to 2/500 (SH: Providing and laying Kharnja Soling at Km 0/830 to 0/900)	Rs.64,830/-	Rs.1,300/-	Rs.350/-	One Month

1. The contractor should be registered as dealer under H.P. GST Tax Act 2018.

2. The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
3. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
4. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
5. Only two tenders form will be issued to the contractor/firm which may be noted.
6. The contractor will also have to attach the labour employer license from the labour office with the application.
7. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
8. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
9. The contractor shall have all required machinery such as Truck/Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
10. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
11. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
12. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Bajjnath Division.,
H.P.PWD..Bajjnath.

For & On behalf of the governor of H.P.

Dated:-15.01.2025

NO:-PWD/BD/TA/NIT/2025/- 16475-84

- 1 Copy to the F.C.Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- 2 The Engineer-in-chief, HPPWD, Shimla.
- 3 The Chief Engineer (MZ), HPPWD, Mandi.
- 4 The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- 5 All the Assistant Engineer working under this Division.
- 6 Drawing Branch in this office.
- 7 Notice Board.
- 8 The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Bajjnath Division.,
H.P.PWD..Bajjnath.

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: - A/R & M/O Under Baijnath Division
(SH: Supply and fixing Printer, Biometric System and Metal Casing in HPPWD Division Baijnath)

Estimate Cost: 92,000.00
Earnest Money: 1900.00
Time Limit : One Month

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Rate to be entered by the Bidder in		AMC Rs.
				Figures	Words	
1	Providing and installation Canon image CLASS MF275dw 4-in-1 (Print, Scan, Copy, Fax) Monochrome Wi-Fi Laser Printer with Auto Duplex Printing for Home/Office Printer type: Laser ; Functions: Print, Scan, Copy, FAX ; Printer output: Monochrome ; Connectivity: USB 2.0, Wi-Fi ; Scanner: Yes ; Scanner resolution: 600 x 600 dpi, Driver enhanced- Up to 9600 x 9600 dpi; Print Language: UFR II Page size :A4, B5, A5, A6, Letter, Legal, Statement, Executive, Government Letter, Government Legal, Foolscap, Indian Legal, Index Card, Envelope; Max paper thickness: 64 to 275 GSM ; Maximum Input Sheet Capacity: 150 sheets (A4) Compatible Toner: CRT 071 - 1200 prints; Power wattage of printer, Operation: Avg :530W (Max-1300W); Avg (Standby)-5.8 W; Avg (Sleep)-1 W with one year onsite warranty. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	1.00	Each			
2	Providing and installation Aadhaar Enabled Secureye S-SAB3000 Biometric System, 4G AADHAAR BASED TIME ATTENDANCE SYSTEM The contemporary aesthetic that blends perfectly with modern architecture Inbuilt battery backup to ensure 99.9% up time 1:1 or 1: N Fingerprint Matching functions Support STQC/Aadhaar Certified fingerprint reader Data retention in case of power failure, no loss of data. Online/offline software makes individual operation easy to manage. Wifi means cable-less installations. Dual SIM Card Support 4G Enabled The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	1.00	Each			
3	Providing and installation Metal Casing Enclosure Compatible for All Brands Long Range Face Attendance Machines Designed for quick and hassle-free installation, allowing for seamless integration with existing systems Includes ventilation holes or fans to prevent overheating and maintain optimal performance, even in extended operation periods The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	1.00	Each			

Executive Engineer
Baijnath Division
H.P.P.W.D., Baijnath

DNIT/DRAFT SCHEDULE OF QUANTITY

2

Name of work :- Special Repair of Rest House Baijnath
(SH:- Applying Painting, putty work Etc)

Estimate Cost: 99,860.00
Earnest Money: 2,000.00
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	554.82	Per square metre			
2	Disempering with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	500.00	Per square metre			

Executive Engineer
Baijnath Division
HPPWD Baijnath

DNT/DRAFT SCHEDULE OF QUANTITY

**Name of work :- Special Repair of Rest House Bajinath
(SH:- Painting , Distemping, Aluminium door Shutter Etc)**

**Estimate Cost:99,989 .00
Earnest Money: 2,000.00
Time Limit : Two Months**

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Wall painting with acrylic exterior emulsion paint of approved brand and manufacture to give an even shade as per entire satisfaction and direction of Engineer - In-Charge including hauling/carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect:the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	16.42	Sqm			
2	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer:as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	85.00	Per square metre			
3	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	301.80	sqm			
4	Providing and fixing anodised aluminium work for door, window, ventilators and partitions with extruded built up standard tubular and other sections of approval make conforming to IS 733 and IS 1285 anodised transparent or dyed to required shade according to IS 1868.)Minimum anodic coating of grade AC 15) fixed with rawlplugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junction, at top- bottom and sides with required PVC/neoprene felt etc. Aluminium sections shall be smooth,rustfree, straight mitred and jointed mechanically where ever required including cleast angle, aluminium,snap beading for glazing/panelling C.P. brass/stainless steel screws. All complete as per architectural drawings and the directions of Engineer-in-Charge. For doors windows and ventilations and glazed partitions frames,as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.30	Per mt			
5	Providing and fixing factory made shutters of Pre laminated particle board flat pressed three layer graded wood particle board with one side decorative finish and other side balancing lamination conforming to IS: 12823 Grade I Type II, of approved design, and edges sealed with water resistant paint and lipped with aluminium 'U' type edge beading all- round the shutter, including fixing with angle cleat, grip strip, cadmitu plated steel screws, including fixing of aluminium hinges 100x63x4 mm etc. complete as per architectural drawing and direction of Engineer-in-Charge (Cost of 'U' beading and hinges will be paid for separately).	15.41	Per square metre			

6	Supplying and fixing glass panes with putty and nails including removal of broken glass panes wherever necessary plain glass 4mm thick The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	0.78	Sqm				
7	Providing and fixing G.I. pipes complete with G.I. Fittings including trenching and refilling etc. :20 mm (Twenty Millimeter) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	12.00	Rmt				
8	Providing and Fixing Composite End Seal Compression Fitting of approved brand ISI Mark as per IS-15450-2004 for Cold Water Supply Reducer 2025 * 1216 as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.00	Each				
9	Providing and fixing 32mm (Thirty two millimetres) nominal size diameters M.I. union for wash basin sink, within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.00	Each				
10	Providing and fixing composite end seal compression fittings Female elbows 1216 X 15 mm (fifteen millimeter) thread Size as per IS-15450-2004 for cold water supply e.g. tees, elbows, reducers, connectors, couplers and clamps with jointing testing and fittings complete including cutting and making good the walls etc. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.00	Each				
11	Providing and fixing female socket including entire carriage of materials within all leads and lifts as per directions of Engineer-In-Charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.00	Each				
12	Providing and fixing 10 mm nipple including entire carriage of materials within all leads and lifts as per directions of Engineer-In-Charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.00	Each				
13	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 lit/10 sqm (one point six seven lit per ten square meter) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (two point two zero kilogram per ten square meter). Clause 13.46.1 The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	97.82	sqm				
14	Providing and fixing Exhaust fan complete in all respect Make Havel or equivalent as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each				

15	Providing and fixing water purifier complete in all respect of Kent or equivalent as per entire satisfaction and direction of Engineer - In-Charge including hauling/carrriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	1.00	Each				
16	Providing and fixing anodized aluminium handle anodized transparent or dyed to required shade or colour with necessary screws etcetra complete. 125mm (one hundred twenty five millimeter) size. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	10.00	Each				
17	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete :250x16 mm (two fifty into sixteen millimetre) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1.00	Each				
18	Providing and fixing anodized aluminium tower bolts (barrel type) anodized transparent or dyed to required shade and colour with screws etcetra complete 150x10mm (One hundred fifty into ten millimeter) size. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	16.00	Each				
19	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :200x10 mm (two hundred into ten millimeter) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1.00	Each				
20	Providing and fixing aluminium hanger for cloths, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete two hundred into ten millimeter) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1.00	Each				
21	Providing and fixing Door Closer anodized colour and shade with bolts and nuts screws etc. complete and technical specifications Including carriage of materials within all leads and lifts and other incidental The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	1.00	Each				

Executive Engineer
Bajnath Division
H.P.W.D., Bajnath

Name of work : C/O Bajinath Deol Phatar Road km 0/00 to 10/180

DNI/DRAFT SCHEDULE OF QUANTITY

(SH: C/O Damaged protection wall of slab culvert at RD 7/425 R.H.S approach)

Estimate Cost: 99,972.00/-
Earnest Money: 2,000.00/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	9.26	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone aggr. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	18.77	Per Cum			
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals, including entire carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.30	Per Cum			
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.00	Each			
Total						

Executive Engineer
Bajinath Division
H.P.P.W.D., Bajinath

Name of work : C/O R/R Damages on Bir Palampur Road km 0/00 to 40/00
(SH: C/O R/Wall at RD 1/140 to 1/146.50)

DNIIT/DRAFT SCHEDULE OF QUANTITY

Estimate Cost: 98,649.00/-
Earnest Money: 2,000.00/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	5.72	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Moth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	19.05	Per Cum			
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.00	Each			
Total						

Executive Engineer
Bajinath Division
H.P.W.D., Bajinath

D.N.1/ SCHEDULE OF QUANTITY

Name of work :- C/O Main Road from Shri Sarwan Kumar House to Sh. Jufi Ram House Deposit Work
SDP/2024/828
(Sh:- P/L 40mm thick Paver Block).

Estimated Cost: Rs. 9902
Earnest Money: Rs. 9,000
Time Limit : Two M

Sr No.	Description of work	SCHEDULE OF WORKS				AMOUNT Rs. P
		No. or Qty.	Unit	Figure	Estimated Rate Words	
1	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:4:8 stone age, 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	1.86	Cum			
2	Providing concrete for plain / reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC Grade M-20 Nominal Mix 1:2:4 (one cement : two sand; four aggregate) per the direction of Engineer-in-charge including entire carriage of materials within all leads and lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	0.85	Cum			
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in Chage 40mm (forty millimeter) thick cement concrete paver block of M-35 grade with approved colour, design & pattern. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	59.60	Sqm			
TOTAL						

Executive Engineer
Bajinath Division
HPP WD Bajinath

Name of work :- C/O Road from Shri Parvi Kumar House to Shri Gyan Chand House Mohal
(SH:- P/L C. C Pavement & Kharanja Soling X Deposit work SDP/2024/838)

DNT/DRAFT SCHEDULE OF QUANTITY

Estimate Cost: 98,56,200/-
Earnest Money: 2000,00/-
Time Limit : Two months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying hard stone Soling properly hand packed intersects with kharanja stone and consolidating with power / hand roller to requested gradient and camber including spreading watering and rolling of binding mortum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	11.25	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	11.25	Per Cubic metre			
Total						

Executive Engineer
Bajnath Division
HPPWD Bajnath

Name of work :- C/O Pucca Path from Sh. Pyar Chand house to SC Basti Nagehar Mohal
(SH:- P/L C C Pavement & Kharrja Soiling) Deposit work SDP/2024/833)

DNT/DRAFT SCHEDULE OF QUANTITY

Estimate Cost: 98,912,00/-
Earnest Money: 2000,00/-
Time Limit : Two months

SCHEDULE OF WORKS						
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying hard stone Soiling properly hand packed intersects with Kharrja staone and consolidating with power / hand roller to requested gradient and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals . The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	3.96	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with minimum (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803,1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	13.20	Per Cubic metre			
Total						

Executive Engineer
Bajinath Division
HPPWD Bajinath

Estimate Cost: 99,001.00/-
Earnest Money: 2000.00/-
Time Limit :One Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying hard stone Soling properly hand packed intersects with kharanja stone and consolidating with power / hand roller to requested gradient and camber including spreading watering and rolling of binding mortar or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals . The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	11.25	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals . The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	11.25	Per Cubic metre			
Total						

Executive Engineer
Bajnath Division,
H.P.P.W.D. Bajinath (H.P.)

D.N.I.T/ SCHEDULE OF QUANTITY

Name of work :- C/O Pucca Path from Jaswant Lagwal to Ishwar Das House
(Sh:- P/L 40mm thick Paver Block at Km 0/00 TO 0/055). SDEP/2024/829

Estimated Cost: Rs. 9897
Earnest Money: Rs. 2,000

Time Limit: Two Months

SCHEDULE OF WORKS

Sr No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:4:8 stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	2.52	Cum			
2	Providing concrete for plain / reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC Grade M-20 Nominal Mix 1:2:4 (one cement : two sand; four aggregate) per the direction of Engineer-in-charge including entire carriage of materials within all leads and lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	0.88	Cum			
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in-Charge 40mm thick cement concrete paver block of M-35 grade with approved colour, design & pattern. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	55.00	Sqm			
TOTAL						

Executive Engineer
Bajinath Division,
H.P.P.W.D. Bajinath (H.P.)

DNT/DRAFT SCHEDULE OF QUANTITY
Name of work :-C/O Link Road From Behru to Majhera Railway Station via Desh raj House km 0/00 to 0/500
(SH.-P/L C. C Pavement & Kharanja Stone Soling at km 0/135 to 0/161) Deposit Work SDP/2024/811)

Estimate Cost: 99,529.00/-
Earnest Money: 2,000.00/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying hard stone Soling properly hand packed intersects with kharanja stone and consolidating with power / hand roller to requested gradient and camber including spreading watering and rolling of binding mortum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	11.31	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	11.31	Per Cubic metre			
Total						

Executive Engineer
Bajnath Division
H.P.P.W.D., Bajnath

DNT/DRAFT SCHEDULE OF QUANTITY

12 (a)

Name of Work: - Construction of Pucca path along with Pully Panchyat Mahal Patt
(SH:- Construction of 1.00 mtr span RCC slab culvert at RD 0/007 & P/L Kharnia stone soling & C C pavement at RD 0/007 to 0/0038 & Edge wall at RD 0/000 to 0/006) (Deposit work) SDP/2024/837 .

Estimate Cost: 99,992.00
Earnest Money: 2,000.00
Time Limit : Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Rate to be entered by the		AMOUNT Rs. P
				Figures	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.(Ordinary rock and hard rock) as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.67	Cum			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (P.C.C M-10- 1:3:6 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.91	Cum			
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 804, 805 ,806,807,1202 and 1204 M-15 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.83	Cum			
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 804, 805 ,806,807,1202 and 1205 RCC M-20 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.98	Cum			

5	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 800, 1205.4 and 1205.5 RCC M-25 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	0.48	Cum					
6	Supplying, fitting, and placing HYSD bar reinforcement in structure complete as per drawing and technical specifications Clauses 1002, 1005, 1010 and 1202 all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	72.00	Kg					
7	Providing and laying hard stone Soiling properly hand packed intersects with kharanja stone and consolidating with power / hand roller to requested gradient and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	6.98	Per Cubic metre					


 Executive Engineer
 Bajinath Division
 H.P.P.W.D. Bajinath

D.N.I.T/SCHEDULE OF QUANTITY

Name of work :- C/O Jeepable Road along with Paver Block Post office to Deep raj /Tilak House ward no. 3 .
(Sh:- P/L 60mm thick Paver Block). DEPOSIT WORK - S.D.P/2024/811

Estimated Cost: Rs. 989
Earnest Money: Rs. 2,000
Time Limit: Two Months

Sr No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Providing concrete for plain / reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC Grade M-20 Nominal Mix 1:2:4 (one cement : two sand; four aggregate) per the direction of Engineer-in-charge including entire carriage of materials within all leads and lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	0.46	Cum			
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge 60mm (sixty millimeter) thick cement concrete paver block of M-35 grade with approved colour, design & pattern. The rate including of octroi, royalty, Malkhana, tolltax, Sale Tax or other taxes imposed by the government	59.85	Sqm			
TOTAL						

Executive Engineer
Bajinath Division,
H.P.P.W.D. Bajinath (H.P.)

Name of work :- C/O Community Shed Near S D P O at Baijnath
(Sh:- Extension of slab) back side . (Deposit work) SDP/2023/748 .

DNIT/DRAFT SCHEDULE OF QUANTITY

Estimate Cost: 99,451.00
Earnest Money: 2,000.00
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling (wedging out rocks) (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	0.32	Per Cum			
2.a	Providing form work with steel plates 3.15mm(three point fifteen) thick welded with angle iron in frame 30x30x5mm (thirty into thirty into five) . so as to give a fair finish including centring, shuttering, strutting and propping etc. with wooden battens and ballies, height of propping and centring below supporting floor to ceiling not exceeding 4 (four) Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in Square, rectangular or polygonal in plan column pillar posts and sturts The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	14.64	Sqm			
2 b	Providing form work with steel plates of 3.15mm (three decimal one five millimeter) thick, welded with angle iron in frames of 30x30x5mm (thirty into thirty into five millimeter) so as to give a fair finish including centring, shuttering strutting and propping etc. with wooden battens and ballies for all heights/depts of propping and Centering and shuttering including strutting, propping etc. and removal of form work for Beams Cantilever girder etc The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	10.56	sqm			
2.c	Providing form work with steel plates of 3.15mm (three decimal one five millimeter) thick, welded with angle iron in frames of 30x30x5mm (thirty into thirty into five millimeter) so as to give a fair finish including centring, shuttering strutting and propping etc. with wooden battens and ballies for all heights/depts of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in flat surfaces such as soffits of suspended floors roofs, landings and the like floor etc. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	17.13	Per square metre			

3	Demolition above G.L. up to floor two level including disposal of unserviceable material within 20 m (Twenty metres) lead and including cutting the necessary reinforcement and separating out from RCC R.B. works. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	0.62	cum					
4.a	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size) in foundation Footings and Basis of columns. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	0.32	Per cubic metre					
4.b	Providing and laying mechanically mixed and vibrated reinforced cement concrete work grade M-20 design mix to obtain the minimum compressive strength of M-20 N/mm ² with cement contents not less than of 320kg/m ³ (three hundred twenty kilogramme per cubic metre) excluding cost of form work and reinforcement for reinforced concrete work in suspended floor, roofs, landing and shelves and their support balconies beams girders bressumers and cantilevers upto floor all level and curing complete including carriage of material within all leads, lifts and other incidental charges complete in all respect as per the direction of Engineer-in-Charge.	4.03	Per cubic metre					
4.c	Providing and laying cement concrete work 1:2:4 (1 Cement:2 Sand:4 graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and Coulmn Pillar Posts & sturrs and the like and mass concrete reinforcement for reinforced concrete work in : The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.10	Per cubic metre					
5	Providing for steel reinforcement for reinforced cement concrete work including bending, binding and placing in position complete in all respects as per drawing and design in all floor levels including the cost of binding wire as per PWD specification and approved design. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	436.00	Per kilo gram					

Executive Engr
Baili Division
H.P.D., W.D., Bajna

(15)

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Holta Chadhar Road

(SW:-Diversion Portion Between 62/900 to 63/300)
(SH:- P/L C. C Pavement & Kharrja Soling at RD 0/250 TO 0/274.50)Estimate Cost: 98,649.00/-
Earnest Money: 2,000.00/-
Time Limit : Two months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying hard stone Soling properly hand packed intersects with Kharrja staone and consolidating with power / hand roller to requested gradient and camber including spreading watering and rolling of binding mortum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	11.21	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	11.21	Per Cubic metre			
Total						

Executive Engineer
Bajnath Division,
H.P.P.W.D. Bajnath (H.P.)

Name of work: C/O Bhulana to Simbal Road km 0/00 to 6/220.
(Sh:- C/O E/wall at RD 0/011.50 TO 0/023).

DNT/DRAFT SCHEDULE OF QUANTITY

Estimate Cost: 64,114.00/-
Earnest Money: 1,300.00/-
Time Limit: One Month

Sr. No.	Description of work	No. or Qty.	Unit	Figures		AMOUNT Rs. p
				Rate	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-In-Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including cartiage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	3.42	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone age 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling cartiage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	11.62	Per cubic metre			
3	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling cartiage of machineries, materials, tools equipments and safety measures. shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	10.50	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire cartiage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	9.00	Each			
Total						

16

Security Engineer
Sajmal Division
HPPWD, Baitmat.
HPPWD

DNT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Lohardi to Andarti Malhan Road km 0/00 to 2/500
(SH.-Providing and laying Kharanja Soling at km 0/830 to 0/900)

Estimate Cost: 64,830,00/-
Earnest Money: 1,300,00/-
Time Limit : One Month

SCHEDULE OF WORKS									Time Limit :One Month	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT				
				Figures	Words	Rs.	P			
1	Preparation of sub grade by dressing to camber (Earth work for the cutting involved for sub grade to be paid for separately depending upon the classification of soil) complete as per HP.PWD specifications and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	231.53	Per square metre							
2	Providing and laying hard stone Soling properly hand packed intersects with kharanja stone and consolidating with power / hand roller to requested gradient and camber including spreading watering and rolling of binding mortum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	34.73	Per Cubic metre							
Total										

Executive Engineer
Bajnath Division,
H.P.P.W.D. Bajinath (H.P.)