



"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 22/01/2025 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 21/01/2025 up to 10.00 A.M. to 12:30 P.M. and tender form can be had from this office on 23/01/2025 from 2.00 P.M. to 5.00 Pm. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	A/R&M/O various roads under Joginder Nagar, Sub Division HP.PWD, Joginder Nagar (Chaurtra Section) (SH:- Hiring of tractor with trolley for carriage/shifting of patch work materials etc.)	Rs. 98,880/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
2	Special repair of State Level Revenue Training Institute at Joginder Nagar District Mandi (HP) (SH:- Providing & fixing steel work, fencing etc. for roofing over water tank for 6 Nos. type-III qtrs.)	Rs. 87,686/-	Rs. 1,800/-	Rs. 350/-	Class "D"	Two months
3	Restoration of rain damages on various roads under Lad-Bharol Sub Division HPPWD, Lad-Bharol (Neri Section) (SH:- Hiring of breaker machineries for breaking of Boulder along road side).	Rs. 99,000/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
4	Restoration of rain damages on Pihari Bedhlu Suan Roparu road Km. 0/0 to 3/0 (SH:- Construction of Breast wall at Km. 1/750 to 1/757	Rs. 88,055/-	Rs. 1,800/-	Rs. 350/-	Class "D"	Two months
5	Restoration of rain damages various road under Lad-Bharol Sub Division HPPWD, Lad-Bharol (Neri Section) (SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains and construction of road side katcha drains).	Rs. 99,060/-	Rs. 2,000/-	Rs. 350/-	Class "D"	One month
6	Restoration of rain damages on various roads under Joginder Nagar Sub Division HPPWD, Joginder Nagar (Local Section) (SH:- Hiring of Tipper for shifting and carriage / disposal of Muck, debris).	Rs. 99,000/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
7	Special repair of State Level Revenue Training Institute at Joginder Nagar District Mandi (HP) (SH:- Providing & fixing pre-painted sheet & rain water pipe etc. for roofing over water tank for 6 Nos. type-III qtrs.)	Rs. 79,321/-	Rs. 1,600/-	Rs. 350/-	Class "D"	Two months
8	Stock & Storage under Joginder Nagar sub Division HPPWD, Joginder Nagar (SH:- Supplying and Stacking of dual directional rectangular delinators for road side with plastic head unbreakable at neck.	Rs. 99,000/-	Rs. 2,000/-	Rs. 350/-	Class "D"	One month
9	A/R&M/O various road under Joginder Nagar, Sub Division HP.PWD, Joginder Nagar (Makreri Section) (SH:- Hiring of Tipper for shifting and carriage of land slide materials and other various type of materials etc.).	Rs. 99,000/-	Rs. 2,000/-	Rs. 350/-	Class "D"	One month
10	Restoration of rain damages on various roads under Joginder Nagar Sub Division HPPWD, Joginder Nagar (Ladruhin Section) (SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/o road side katcha drains etc.)	Rs. 99,060/-	Rs. 2,000/-	Rs. 350/-	Class "D"	One month
11	Construction of 40 mtr. Span single Lane bridge over Bajgar Khad on Chaurtra Chakli Marehar Dohag road Km. 2/450 (SH:- Preparation of Detailed estimate of Bridge) (Sub Structure & Super Structure only).	Rs. 99,500/-	Rs. 2,000/-	Rs. 350/-	Class "D"	One month
12	Restoration of rain damages on Drubbal Kunkar Nagan road Km. 0/0 to 3/0 (SH:- Construction of retaining wall at RD. 2/233 to 2/240).	Rs. 93,089/-	Rs. 1,900/-	Rs. 350/-	Class "D"	Three months
13	Restoration of rain damages on Joginder Nagar Sarkaghat Ghumarwin road Km. 21/500 to 34/0 (Neri Section) (SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/o road side katcha drains etc.).	Rs. 99,060/-	Rs. 2,000/-	Rs. 350/-	Class "D"	One month
14	A/R&M/O various roads under Joginder Nagar, Sub Division HP.PWD, Joginder Nagar (Chaurtra Section) (SH:- Hiring of tractor with trolley for carriage/shifting of patch work materials etc.)	Rs. 98,880/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
15	A/R&M/O various road under Joginder Nagar, Sub Division HP.PWD, Joginder Nagar (Makreri Section) (Makreri Section) (SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/o road side katcha drains etc.).	Rs. 99,060/-	Rs. 2,000/-	Rs. 350/-	Class "D"	One month

16	Restoration of rain damages on various roads under Lad-Bharol Sub Division HPPWD, Lad-Bharol (Neri Section) (SH:- Hiring of breaker machineries for breaking of Boulder along road side).	Rs. 99,000/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
17	Restoration of rain damages on Baijnath Lad-Bharol Kandapattan road km 0/00 to 46/00 (SH:- Removal of Formation Deficiency in km 36/210 to 36/270).	Rs. 77,335/-	Rs. 15,00/-	Rs. 350/-	Class "D"	Two months
18	Special repair of State Level Revenue Training Institute at Joginder Nagar District Mandi (HP) (SH:- Providing & fixing steel work, fencing etc. for roofing over water tank for 6 Nos. type-III qtrs.)	Rs. 87,686/-	Rs. 1,800/-	Rs. 350/-	Class "D"	Two months
19	A/R & M/O Batohlu to Kharon road Km. 0/0 to 3/0 (SH:- Removal of formation deficiency in Km. 0/240 to 0/273)	Rs. 98,168/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
20	Stock & Storage under Joginder Nagar sub Division HPPWD, Joginder Nagar (SH:- Supplying and Stacking of dual directional rectangular delinators for road side with plastic head unbreakable at neck.	Rs. 99,000/-	Rs. 2,000/-	Rs. 350/-	Class "D"	One month
21	Restoration of rain damages on Drubbal Kunkar Nagan road Km. 0/0 to 3/0 (SH:- Construction of retaining wall at RD. 2/225 to 2/232).	Rs. 93,037/-	Rs. 1,900/-	Rs. 350/-	Class "D"	Three months
22	Construction of 19.75 mtr. Span single Lane bridge over Sukar Khad at Km. 0/105 between Sukar & Sarohli village (SH:- Preparation of Detailed estimate of Bridge including approaches both side).	Rs. 99,500/-	Rs. 2,000/-	Rs. 350/-	Class "D"	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-/NIT/Press/2023-24-21183-232

Dated: 10-01-2025

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Notice Board.
9. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.

Job - 1

Schedule of Quantity

Estimated Cost:- 98800.00
 Earnest Money:- 2000.00
 Time:- Two months

Name of work:- A/R & M/O various roads under Joginder Nagar Sub Division No.II, HP.PWD, Joginder Nagar (Chauntra Section)
 Sub Head:- Hiring of tractor with trolley for carriage/shifting of various type of materials etc.).

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Tractor with trolley in working condition per day basis (eight working hour per day) with including Sunday/ Holiday for carriage of various type of materials etc. The operational , maintenance and P.O.L charges and other miscellaneous supply / replacement required for smooth running of vehicle will be borne by the owner of the tractor within all leads and lifts to the entire satisfaction of Engineer-in-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	38.00			Per day	
Total:-						


 Executive Engineer,
 B&R Division HP.PWD,
 Joginder Nagar

Job - 2

SCHEDULE OF QUANTITY

Name of work : Special repair to State Level Revenue Training Institute at Joginder Nagar Distt. Mandi (HP) (Sh:- Providing & fixing steel work, fencing etc. for roofing over water tank for 6Nos. type -III qtrs.)					Estimate Cost: 87,686.00			Earnest Money: 1,800.00		Two Months	
					Time Limit :			AMOUNT			
					Rate		Unit	Words		Rs. P	
					Figures						
Sr. No.	Description of work	No. or Qty.	Unit								
1	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	267.54	Per Kilogramme								
2	Providing & fixing G.I. chain link made of G.I wire of dia 4mm (four millimetres) fabric facing of required width in mesh size 50x50mm (fifty millimetres x fifty millimetre including strengthening with 2mm (two millimetres dia) wire of nuts and washers as required complete as per the direction of Engineer in-charge including carriage of material within all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	66.00	Per Square Meter								
3	Providing and fixing 250x16mm (two hundred fifty by sixteen millimeter) Size anodized aluminium sliding door bolt anodized colour and shade with bolts and nuts screws etc. complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each								
4	Cement concrete flooring 40mm thick (forty millimeter) with 20mm nominal size aggregate (twenty millimetre) with cement concrete 1:2:4 (one cement :two sand:four aggregate) finished with a floating coat of neat cement. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer -In- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	33.50	Per Square Meter								
Total											

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job-3

Schedule of Quantity

Estimated Cost:- 99000.00
Earnest Money:- 2000.00
Time:- Two months
Name of work:- Restoration of rain damages on various roads under Lad-Bharol Sub Division HP PWD, Lad-Bharol (Neri Section) (Sub Head:-Hiring of breaker machineries for breaking of Boulder along road side).

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of hydraulic excavator/breaker machineries to be deployed for breaking of stone/boulder along road side etc. i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/owner at his own risk, shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	45.00			Per working hour	
				Total:-		


 Executive Engineer
 B&R Division HP.PWD,
 Jodhinder Nagar

Job-4

Name of Work : Restoration of Damages on Pihar Bedhlu Suan Roparu Road km 0/00 to 3/00 (SH: Construction of Breast wall at km 1/750 to 1/757)

Sr. No.	Description of work	No. or Qty.	Unit	Estimate Cost: Earnest Money: Time Limit :		
				Rate	Words	AMOUNT Rs. P
				Figures		
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost.The rate is inclusive all taxes levy by the government time to time excluding GST.	11.65	Per cubic metre			
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to entering seepage rain and other	8.16	Per cubic metre			
3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	16.45	Per cubic metre			

Job-4

4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	6.00	Each			
Total						


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar



Job - 5

Schedule of Quantity

Estimated Cost:- 99060.00
 Earnest Money:- 2000.00
 Time One month

Name of work:- Restoration of rain damages on various roads under Lad-Bharol Sub Division HP.PWD, Lad-Bharol (Neri Section)
Sub Head:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic Excavator having capacity of 1.00 (one point zero) cubic meter loader capacity for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc. i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out bt the contractor/owner at his own risk, shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	78.00			Per working hours	
Total:-						


 Executive Engineer
 B&R Division HP.PWD,
 Jodhpur Nagar

Job-6

SCHEDULE OF QUANTITY

Name of Work: Restoration of Damages Various Roads Under Joginder Nagar Sub Division HPPWD Joginder Nagar (Local Section) (SH:- Hiring of Tipper for Shifting of Carriage/disposal of Muck, debris.)					Estimate Cost: Earnest Money: Time Limit :			99,000.00 2,000.00 Two Months
Sr. No.	Description of work	No. or Qty.	Unit		Rate		AMOUNT	
					Figures	Words		
1	Hire charges of tipper for carriage/shifting of soling stone earth, moorume, premix material, seal coat etc. having capacity of 5.50 (five point five zero) cubic metre per trip and covering 70 (seventy) kilometers per day (9AM to 5PM), the contractor/ owner of tipper shall bear the expensive of POL charges, repair of machineries including driver and helper wages. Any accident and other damages to private and Govt property occur during the working hours in the work shall be the responsibility of the contractor and disposal of excavated material/ slips debris with in all leads and lifts as per the direction of Engineer-in-Charge. The rates are inclusive of all taxes including GST levy by the Govt. time to time.	22.00	Per Working Day					
Total								

~~Executive Engineer~~
B & R Division HP.PWD,
Joginder Nagar

[Signature]

SCHEDULE OF QUANTITY

Name of work : Special repair to State Level Revenue Training Institute at Joginder Nagar Distt. Mandi (HP) (Sh:- Providing & fixing pre-painted sheet & rain water pipe etc. for roofing over water tank for 6Nos. type -III qtrs.)

Name of work : Special repair to State Level Revenue Training Institute at Joginder Nagar Distt. Mandi (HP) (Sh:- Providing & fixing prepainted sheet & rain water pipe etc. for roofing over water tank for 6Nos. type -III qtrs.)							Estimate Cost: Earnest Money: Time Limit :		Two Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P				
				Figures	Words					
1	Providing and fixing 0.60mm (zero point six zero millimetre) thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (twenty) microns over 5 (five) microns primer coating to back coat of polyester 5 (five) microns over 5 (five) microns primer coating including fixing with screws prepainted iron J or L hooks, bolts and nuts 6mm (six millimetre) diameter with prepainted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-In-Charge including carriage of material within all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	39.36	Per Square Meter							
2	Providing and fixing ridges or hips 60cm (sixty centimetre) overall with 0.63mm (zero point six three millimetre) thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 (twenty) microns over 5 (five) microns primer coating plus back coat of polyester of 5 (five) microns over 5 (five) microns primer coating including fixing with screws prepainted iron J or L hooks, bolts and nuts 6mm (six millimetre) diameter with prepainted GI limpet and bitumen washers complete with all accessories as required as per the direction of Engineer In-Charge including carriage of material within all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.90	Per Running Meter							
3	Providing and fixing valley 90cm (ninty centimetre) overall with 0.60mm (zero point six millimetre) thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 (twenty) microns over 5 (five) microns primer coating plus back coat of polyester of 5 (five) microns over 5 (five) microns primer coating including fixing with screws prepainted iron J or L hooks, bolts and nuts 6mm (six millimetre) diameter with prepainted GI limpet and bitumen washers complete with all accessories as required as per the direction of Engineer-In-Charge including carriage of material within all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	13.60	Per Running Meter							
4	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes 110 mm (one hundred ten millimeter diameter) diameter conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm (ten milimeter) gap for thermal expansion, (i) Single socketed pipes. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	25.80	Per running metre							

Job - 7

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
5	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. Bend 87.5° 110 mm (One hundred ten millimeter) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.00	Each			
	Total					

~~Executive Engineer~~
 B & R Division HP.PWD,
 Jodhpur Nagar

Draft Schedule of Quantity

Estimated Cost:- 99000.00
 Earnest Money:- 2000.00
 Time:- One Month

Name of work:- Stock Storage under Joginder Nagar sub division HPPWD Joginder Nagar.
Sub Head:- Supplying and Stacking of dual directional rectangular delinators for road side with plastic head unbreakable at neck

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stcking dual directional delinators made out of 18 gauge (eighteen) MS rectangular pipe of size 25x68mm (twenty five into sixty eight millimetre) and of length 600 mm (six hundred millimetre) pipe to be enamelled and baked to 120 (one hundred twenty) degree celcious / powder coated. Head made out ABC plastic rectangular moulded with flat face provided with high tensity prismatic reflectors of clolour white/yellow/red of size 100x125mm (one hundred into one hucdred twenty five millietre) with additional 2 (two) reflective strips of 25mm (twenty five millietre) wide greens/greenlite including carriage of mateiral with in all leads lifts as per the direction of Engineer-In-Charge. The rate is included of all taxes levy by the Govt. time to time excluding GST.	120.00				

Executive Engineer
 B & R Division H.P.P.W.D.
 Joginder Nagar (H.P.)

Job - 9

Schedule of Quantity

Estimated Cost:- 99000.00
 Earnest Money:- 2000.00
 Time:- One month

Name of work:- A/R&M/O various roads under Joginder Nagar Sub Division No. II, HPPWD, Joginder Nagar (Makriri Section) (SH: Hiring of tipper for shifting and carriage of land slide materials and other various type of materials etc.).

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hire charges of tipper for carriage/shifting of patch work material like premix material, seal coat etc. having capacity of 5.50 (five point five zero) cubic metre per trip and covering 70 (seventy) kilometers per day (9AM to 5PM), the contractor/ owner of tipper shall bear the expensive of POL charges, repair of machineries including driver and helper wages. Any accident and other damages to private and Govt property occur during the working hours in the work shall be the responsibility of the contractor and disposal of excavated material/ slips debris with in all leads and lifts as per the direction of Engineer-in-Charge. The rates are inclusive of all taxes including GST levy by the Govt. time to time.	22.00			Per day	
Total:-						


 Executive Engineer,
 B&R Division HP.PWD,
 Joginder Nagar

Schedule of Quantity

Estimated Cost:- 99060.00
 Earnest Money:- 2000.00
 Time:- Two months

Name of work:- Restoration of rain damages on various roads under Joginder Nagar Sub-Division HPPWD, Joginder Nagar (Ladruhin Section) (SH: Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/o road side katcha drains etc.)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic Excavator having capacity of 1.00 (one point zero) cubic meter loader capacity for removal of slips, dressing of berms, clearing of road side drains, debris and C/o road side katcha drains etc. i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out bt the contractor/owner at his own risk, shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	78.00			Per working hours	
Total:-						


 Executive Engineer
 B&R Division HP.PWD,
 HR.PWD, Joginder Nagar

Job- (11)

SCHEDULE OF QUANTITY

Rs. 99500 00
Rs. 2000 00
One month

Estimated Cost:
Earns Money:
Time:

Name of work:- Construction of 40.00 mtr. span single Lane bridge over Bajgar Khad on Chauntra Chakli Marehar Dohag road at Km. 2/450. (SH-1)
Preparation of Detailed estimate of Bridge (Sub Structure & Super Structure only)

S.N o.	Description	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Preparation of detailed estimate of bridge as per approved GAD complete in all respect and its approval from the competent authority and checking of whole estimate from circle office and chief officer/ Engineer-in-Chief office as required by the Engineer-in-Charge including hauling of materials all modes of transportation with in all leads and lifts of material and other incidentals If any correction/amendment has desired by the head office the same shall be corrected as per requirement and as per direction of Engineer-in-charge. The DPR should be submitted in 3 (three) hard copies along with soft copy as per condition of TOR. The rate is included all taxes levy by the Govt. time to time excluding GST.	1.00			Job	
					Total	


Executive Engineer,
B&R Division, HP PWD.,
Joginder nagar

206-12

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Drubbal Kunkar Nagan road km. 0/0 to 3/0 (SH:-Construction of retaining wall at RD 2/233 to 2/240)				Estimate Cost: Earnest Money: Time Limit :		93,089.00 1,900.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	5.60	Per cubic metre			
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	16.45	Per cubic metre			
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	8.19	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	7.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

Job-13

Schedule of Quantity

Estimated Cost:- 99060.00
 Earnest Money:- 2000.00
 Time:- Two months

Name of work:- Restoration of rain damages on Joginder Nagar Sarkaghat Ghumanwin road Km. 21/500 to 34/0 (Neri Section) (SH: Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/o road side katcha drains etc.)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic Excavator having capacity of 1.00 (one point zero) cubic meter loader capacity for removal of slips, dressing of berms, clearing of road side drains, debris and C/o road side katcha drains etc. i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/owner at his own risk, shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	78.00			Per working hours	
Total:-						


 Executive Engineer
 B&R Division HP.PWD,
 HP.PWD, Joginder Nagar

Job-14

Schedule of Quantity

Estimated Cost:- 98800 00
 Earnest Money:- 2000 00
 Time:- Two months

Name of work:- A/R & M/O various roads under Joginder Nagar Sub Division No.II, HP.PWD, Joginder Nagar (Chauntra Section)
 Sub Head:- Hiring of tractor with trolley for carriage/shifting of various type of materials etc.);

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Tractor with trolley in working condition per day basis (eight working hour per day) with including Sunday/ Holiday for carriage of various type of materials etc. The operational , maintenance and P.O.L charges and other miscellaneous supply / replacement required for smooth running of vehicle will be borne by the owner of the tractor within all leads and lifts to the entire satisfaction of Engineer-in-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	38.00			Per day	
Total:-						


 B.R. Engineer,
 B&R Division HP.PWD,
 Joginder Nagar

Job - 15

Schedule of Quantity

Estimated Cost:- 99060.00
 Earnest Money:- 2000.00
 Time:- One Month

Name of work:- A/R & M/O various road under Joginder Nagar Sub-Division No.II HPPWD Joginder Nagar (Makriri Section)
 Sub Head:-Hiring of excavator cum Loader for removal of slips, dressing of berms, clearing of road side drains and construction of road side katcha drains.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of hydraulic excavator cum loader of 1.00(one point Zero) cubic metre loader capacity for formation cutting having out put not less than 40(Forty) cubic metre per hour i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/owner at his own risk, shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment . Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-In-Charge.	78.00			Per working hour	
			Total:-			

 Executive Engineer,
 B&R Division HPPWD,
 Joginder Nagar

Job 16

Schedule of Quantity

Estimated Cost:- 99000.00
 Earnest Money:- 2000.00
 Time:- Two months

Name of work:- Restoration of rain damages on various roads under Lad-Bharol Sub Division HP.PWD, Lad-Bharol (Neri Section) (Sub Head:-Hiring of breaker machineries for breaking of Boulder along road side).

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of hydraulic excavator/breaker machineries to be deployed for breaking of stone/boulder along road side etc. i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out bt the contractor/owner at his own risk,shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge.The rate is inclusive of all taxes including GST levy by the Govt. time to time.	45.00			Per working hour	
				Total:-		


 Executive Engineer
 B&R Division HP.PWD,
 Jodhpur Nagar

Job-17

SCHEDULE OF QUANTITY

Name of Work: Restoration of Rain Damages on Baijnath Lad Bharol Kandapattan Road km 0/00 to 46/00 (SH: Removal of Formation Deficiency in km 36/210 to 36/270)				Estimate Cost: Earnest Money: Time Limit :			77,335.00 1,500.00 Two Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		Words	AMOUNT	
				Figures			Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 28.97 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	334.64	Per cubic metre					
Total								

[Signature]
Executive Engineer
B & R Division HP.PWD,
Jodhpur Nagar

Job - 18

SCHEDULE OF QUANTITY

Name of work : Special repair to State Level Revenue Training Institute at Joginder Nagar Distt. Mandi (HP) (Sh:- Providing & fixing structural steel for roofing over water tank for 6Nos. type -III qtrs.)					Estimate Cost: Earnest Money: Time Limit :			86,993.00 1,700.00 Two Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate	Words		AMOUNT		
					Figures	Words	Rs.	P	
1	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	741.00	Per Kilogramme						
	Total								


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar



Job - 19

SCHEDULE OF QUANTITY

Name of Work: A/R & M/O Batohlu to Kharon road km.0/0 to 3/0 (SH:-Removal of formation deficiency in km.0/240 to 0/0/273)					Estimate Cost: Earnest Money: Time Limit :			98,168.00 2,000.00 Two Months
Sr. No.	Description of work	No. or Qty.	Unit		Rate		AMOUNT Rs. P	
					Figures	Words		
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 19.19 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	479.78	Per cubic metre					
Total								

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job - 20

Draft Schedule of Quantity

Estimated Cost:- 99000.00
Earnest Money:- 2000.00
Time:- One Month

Name of work:- Stock Storage under Joginder Nagar sub division HPPWD Joginder Nagar.
Sub Head:- Supplying and Stacking of dual directional rectangular delinators for road side with plastic head unbreakable at neck

Sr. No.	Description of item	Qty.	Rate	Unit	Amount
1	Supplying and stacking dual directional delinators made out of 18 gauge (eighteen) MS rectangular pipe of size 25x68mm (twenty five into sixty eight millimetre) and of length 600 mm (six hundred millimetre) pipe to be enamelled and baked to 120 (one hundred twenty) degree celcius / powder coated. Head made out ABC plastic rectangular moulded with flat face provided with high tensity prismatic reflectors of colour white/yellow/red of size 100x125mm (one hundred into one hundred twenty five millimetre) with additional 2 (two) reflective strips of 25mm (twenty five millimetre) wide greens/greenlite including carriage of material with in all leads lifts as per the direction of Engineer-In-Charge. The rate is included of all taxes levy by the Govt. time to time excluding GST.	120.00			

Executive Engineer
B & R Division H.P.P.W.D.
Joginder Nagar (H.P.)

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Drubbal Kunkar Nagan road km. 0/0 to 3/0 (SH:-Construction of retaining wall at RD 2/225 to 2/232)

Estimate Cost: Earnest Money: Time Limit :				AMOUNT Rs. P	
Rate				Figures	Words
Sr. No.	Description of work	No. or Qty.	Unit		
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	5.50	Per cubic metre		
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	16.45	Per cubic metre		
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	8.19	Per cubic metre		

93,037.00
1,900.00
Three Months

206-21

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	7.00	Each			
Total						

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar



Name of work:- Construction of 19.75 mtr. span single Lane bridge over Sukar Khad at Km. 0/105 between Sukar & Sarohli village. (SH. Preparation of Detailed estimate of Bridge including approaches both side)

Estimated Cost Rs. 99500.00
 Earnes Money: Rs. 2000.00
 Time: One month

S.N O.	Description	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Preparation of detailed estimate of bridge as per approved GAD including both side approaches with drawings complete in all respect and its approval from the competent authority and checking of whole estimate from circle office and chief officer/Engineer-in-Chief office as required by the Engineer-in-Charge including hauling of materials all modes of transportation with in all leads and lifts of material and other incidentals. If any correction/amendment has desired by the head office the same shall be corrected as per requirement and as per direction of Engineer-in-charge. The DPR should be submitted in 3 (three) hard copies along with soft copy as per condition of TOR. The rate is included all taxes levy by the Govt. time to time excluding GST.	1.00			Job	
					Total	

~~Executive Engineer,~~
 B&R Division, HP PWD.,
 Jalandhar nagar.