HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDERS"

Sealed item/ percentage rate tender on form NO. 6&8 are hereby invited by the Executive Engineer, Bilaspur Division No. I, HP.PWD., Bilaspur on behalf of Governor of Himachal Pradesh from the approved and eligible contractors enlisted in PWD Department so as to reach in this office on or before **05/03/2025** up to 10.30 A.M. and will be opened on the same day at 11.00 A.M. in the presence of the intending contractors or their authorized representatives who may like to be present. If it happens to be holiday on that day tenders will be opened on next working day. The application for obtaining the tender forms will be received up to **03/03/2025** up to 5.00 PM and the tender form can be had from this office on **04/03/2025** during the office hours.

The Earnest money in the shape of National Saving Certificate Time deposit Accounts/FDR of any Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, Division No. I., HP.PWD., Bilaspur must be accompanied with each application for obtaining the tenders. The tender application received without earnest money /cost of tender forms will similarly be rejected. The undersigned reserves the right to reject the tenders without assigning any reason.

Sr. No	Name of work	Estimated cost (In Rs.)	Earnest Money (In Rs.)	Cost of form (In Rs.)	Time limit
1	A/R & M/O residential building at Changer sector Bilaspur (H.P.). (SH:- P/F wood work, water tank & W.S. & S.I. work etc. F-28 S/S).	97,754	2000	350	One month
2	A/R & M/O residential building at Changer sector Bilaspur. (SH:- White washing, painting wood work, tile work etc. Qtr No. F-22 S/S).	97,535	2000	350	One month
3	Preparation of detailed estimate for the construction of Community Health Centre Kuthera Distt. Bilaspur (H.P.).	99,650	2000	350	Fiftee n days
4	Restoration of rain damages on Joginder Nagar Sarkaghat Ghumarwin road Km. 91/00 to 95/00. (SH:- Removal of slips at various RD's).	98,883	2000	350	One month
5	Restoration of rain damages on Harlog Hawan Trifalghat road Km. 0/00 to 20/00. (SH:- C/o R/wall at RD. 8/670 to 8/674.40).	95,776	2000	350	One month
6	Restoration of rain damages on Harlog Hawan Trifalghat road Km. 0/00 to 20/00. (SH:- C/o B/wall and U-shape drain at RD. 8/630 to 8/637.25).	96,205	2000	350	One month
7	Propsed regeneration of water resource at village Badsour (Bandla road) Tehsil Sadar Distt. Bilaspur.	74,410	2000	350	One month
8	Proposed Gate in Champa Park at Main Market Tehsil Sadar Distt. Bilaspur.	68,737	2000	350	One month
9	A/R & M/O on link road from Kasol to Balh road Km. 0/00 to 1/00. (SH:- Preparation of Digital Map, Topo Sheet of project and CA site with collecting data from site under HPPWD Division-I Bilaspur for preparation of FCA Case).	95,000	2000	350	One month
10	A/R & M/O various road under Beri Sub-Divison (Under Panjgain section-I).(SH:- Maintenance of earthen shoulder).	99,376	2000	350	One month
11	A/R & M/O residential building in Roura Sector Bilaspur. (SH:- P/L water proofing treatment in Qtr. No. T-81 and T-82).	95,586	2000	350	One month

12	Construction of Dhoun Kothi to Pandha Palgiri road Km. 0/00 to 3/867. (sH:- Preparation of Forest Diversion case and Digital Plan maps under HPPWD Sub-Division Beri.	99,500	2000	350	Sixmonths
13	Construction of Multilevel Parking and Library (Distt. Attorney) near D.C. office Bilaspur Distt. Bilaspur (H.P.). (SH:- Preparation of detailed estimate as per Drg. No. 39 to 42 Job No. 4523-A)/	`95,000	2000	350	One month
14	Prepration of detailed estimate for the C/o 10Nos type-III quarter at Police Line Bilaspur.	97,000	2000	350	One month
15	Prepration of detailed estimate for the C/o 20Nos type-III quarter at Police Line Bilaspur.	99,000	2000	350	One month
16	Restoration of rain damages on various road under Beri Sub-Division. (SH:- Removal of slips at various RD's).	99,846	2000	350	One month
17	A/R & M/O residential building Changer sector Bilaspur. (sH:- Earth filling & Providing and fixing expanded metal Distt. And Session Judge residence Bilaspur).	83,296	2000	350	One month
18	A/R & M/O non residential building HPPWD Bilaspur. (SH:- P/L 20mm G.I. pipe for Circuit house suit No. 1,2 & 3 HPPWD Bilaspur.	77,352	2000	350	One month

TERMS & CONDITIONS: -

1. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
2. The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactorily including adherence to quality future work will be awarded to him. All undertaking that he is not having more than two works in hand must be recorded in the application, failing which application of such contractor shall be rejected without any notice to him.
3. Earnest money should be accompanied with application. Application without earnest money will not be entertained.
4. The photo copy of Pan Number/renewal should be attached with the application otherwise tender form will not be issued.

Executive Engineer,
Bilaspur, Division No.I
HP.PWD, Bilaspur.
Dated :- 25/02/2025

NO.PW-BLP-I-CB-EA-I-Tender/ 2024- 1845-55

Copy forwarded to the following for information please.

1. The Engineer-in-Chief, HP.PWD; Shimla-I.
2. The Chief Engineer (HZ) HP.PWD, Hamirpur.
3. The Superintending Engineer, 10th Circle, HP.PWD, Bilaspur .
4. The Executive Engineer (IT) O/o the Engineer-i-Chief, HP.PWD, Shimla through email:- cc-pwd-hp@nic.in alongwith copies of Schedule of quantities for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. All the contractors as per record of this office.
7. Accounts Branch/ Drawing Branch/Supdt. in this office.
8. Notice Board.

Executive Engineer,
Bilaspur, Division No.I,
HP.PWD, Bilaspur.

Job No. 1

Schedule of quantity

Estimated cost Rs. 97,754/-only
Earnest Money Rs. 2,000/- only.
Time Limit. = One month

ame of work:- A/R & M/O residential building at Changer Sector Bilaspur (H.P). (SH:- P/F wood work, water tank & W.S & S.I work etc. F- S/S).

No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	2	3	5	6	7	8
1	Providng and fixing 40mm (Forty milimetere) thick panalled glazed or panalled and glazed shutter for doors windows and clorestary windows, including block enamelled iron bult hinges with necessary screws in second class deodar wood. including carriage of materials in all leads and lifts as directed by the Engineer-in-charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.23			Per Square Metre	
2	Providing and fixing wire guage shutters for doors windows using galvanised M.S. wire guage designation 85 (Eighty five) G with wire of dia 0.56 mm (Zero point fifty six) millimeter) 40 mm (Forty millimeter) thick in 2nd class deodar wood including carriage of materials within all leads, lifts and other incidentals. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.23			Per Square Meter	
3	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. 15 mm dia nominal bore. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20			Per Runung Metre	
4	Providing and fixing C.P. Brass shower rose 15 mm dia (Fifteen millimeter)intel . 100 mm (One hundred milimeter) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	

5	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931. 15 mm nominal bore. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00			Each	
6	Providing and fixing PVC floor trap D-plast or equivalent make approved by the Bureau of Indian Standard of self cleaning design including fixing with approved adhesive etc. complete . including cost of cutting making good in the walls and floors complete . 110x90 mm (One hundered ten into ninety millimetre) . including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00			Each	
7	Providing and fixing 100 mm (one hundred millimeter) dia chromium plated grating of superior quality for floor, gully/Nahini trap. including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00			Each	
8	Providing and fixing rectangular high density polyethylene water storage loft tank with cover, conforming to ISI : 12701, colour of opaque white or as approved by Engineer-in-charge. The rate includes making necessary holes for inlet, outlet & over flow pipes. The base support i/c fittings & fixtures for tank shall be paid separately. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1000			Per Litre	
9	Providing and fixing C.P.brass bib tap with capstan head 15mm (Fifteen millimetre) dia. including carriage of materials ,within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00			Each.	

10	Structural steel work in single section, fixed with or without connecting plate,including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	68.40			Per Kilograme	
	TOTAL					

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Job No. 2

Schedule of Quantity

Estimated cost Rs. = 97,535/- only
Earnest Money Rs. = 2,000/- only
Time = One Month.

Name of work:- A/R & M/O residential building Changer Sector Bilaspur. (SH:- White washing , painting wood work, tile work etc. qtr No. F-22 S/S).

Sr No.	Description of items.	Qty.	Rate		Unit	Amount
			In Figure	In words		
1	2	3	4	5	6	7
1	Removing dry oil bound distemper, water proofing cement paint and like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	225.75			Per Square Metre	
2	Applying Birla white putty wall care putty over plaster surfaces after thoroughly brushing the surface fre mortar drops,duist,loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.58			Per Square Meter	
3	Distempering (two coat) with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give and even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth. Priming coat with distemper primer. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	225.75			Per Square Metre	

4	Painting two coats (excluding priming coat) on new wood and wood based surfaces with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter, sand papering and stopping with white enamel paint. as per HP.PWD Specification clause 16. including carriage of materials ,within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	75.28			Per Square Meter	
5	Repair to plaster in patches of 2.50 (Two point fifty) Square meter and under and 10 (Ten) to 15mm (Fifteen millimetre) thick including cutting the patch in proper shape and replastering the surface of the wall including dispoal of rubbish to the dumping ground upto 20m (twenty metre) lead with cement mortor 1:5 (One Cement : five approved Sand) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.52			Per Square Meter	
6	Providing and fixing 1st quality ceramic glazed floor tile conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm (Twelve milimetre) thick bed of cement Mortar 1:3 (One cement: Three coarse sand) and jointing with grey cement slurry @ 3.3kg (Three point three kilograme) per sqm including pointing in white cement mixed with pigment of matching shade complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.79			Per Square Metre	
7	Tile work in skirting, risers of steps and dado up to 2 m height over 12 mm thick bed of cement mortar 1:3 (1 cement :3 coarse sand) and jointed with grey cement slurry @ 3.3 kg/sqm, including pointing in white cement mixed with pigment of matching shade complete. 8 mm (Eight milimetre) thick. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.51			Per Square Metre	

8	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (Twenty milimetre) (average) thick base of cement mortar 1:4 (One cement : Four coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.32			Per Square Metre	
9	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge. Granite work including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.20			Per Square Metre	
10	Providng and fixing 40mm (Forty milimetere) thick panalled glazed or panalled and glazed shutter for doors windows and clorestary windows, including block enamelled iron bult hinges with necessary screws in second class deodar wood. including carriage of materials in all leads and lifts as directed by the Engineer-in-charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.44			Per Square Metre	
11	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm (One point four milimetre) in both directions with wire of dia 0.56 mm, (Zero point fifty six milimetre) for doors, windows and clerestory windows with hinges and necessary screws : 30 cm (Thirty centemetre) thick shutters with ISI marked M.S. pressed butt hinges bright finished of required size Second class teak wood. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.20			Per Square Metre	

12	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Nos	
13	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. 15 mm (Fifteen milimetre)dia nominal bore. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.00			Per Runing Metre	
14	Providing and fixing C.P. Brass shower rose 150 mm dia (Fifteen millimeter). including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
15	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931. 15 mm nominal bore. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00			Each	
16	Providing and fixing PVC floor trap FINOLEX of self cleaning design including fixing with approved adhesive etc. complete . including cost of cutting making good in the walls and floors complete . 110x90 mm (One hundered ten into ninety millimetre) . including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	

17	Providing and fixing 100 mm (one hundred millimeter) dia chromium plated grating of superior quality for floor, gully/Nahini trap. including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
18	Structural steel work in single section, fixed with or without connecting plate,including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.00			Per Kilograme	
	TOTAL					

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Job No. 3

Schedule of quantity

Estimated cost Rs. 99,650/-only
Earnest Money Rs. 2,000/- only.
Time Limit. = 15 Days.

Name of work:- Preparation of detailed estimate for the construction of Community Health Centre Kuthera Distt. Bilaspur (H.P).

Sr No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	2	3	5	6	7	8
1	Prepration of detailed estimate for as per Arch. Drg. No. 33, 34 & 35 Job No. 3390 based on HPSR 2020 with all item analysis of rates as per market rate & present labour wages being application in HP.PWD estimate for technical sanction in all respect complete. 4 set of estimates with spiral binding may be supplied to this office as per the direction of Enginer-in-Charge.	1.00			Job	
	TOTAL					

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Job No. 4

Schedule of Quantity

Estimated Cost:- 98,883/-
Earnest Money :- 2,000/-
Time :- One month

Name of Work:- Resoration of rain damages on Joginder Nagar Sarkaghat Ghumarwin road Km. 91/00 to 95/00. (SH:- Removal of slips at various RD's).

Sr No	Description of items.	Quantity		Rate		Amount
				in figure	In word	
1	2	3		4	5	7
1	Removal of land slides in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift up to 1.50 metre and lead upto 1000 metre as per technical specification 302.3.5 and 1611 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	726.82	Cubic Metre			
					Total.	

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Job No. 5

	SCHEDULE OF QUANTITY.	Estimated cost Rs. = 95,776/-only Earnest Money Rs. = 2,000/- only. Time Limit. = One Month

Name of work:- Restoration of rain damaged on Harlog Hawan Trifalghat road Km. 0/00 to 20/00. (SH:- C/O R/Wall at RD. 8/670 to 8/674.40).

Sr No	Description of items.	Qty.		Rates		Amount
				In Figure	In words	
1	2	3	4	5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.56	Cubic Metre			
2	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.40	Square Metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty milimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.26	Cubic Metre			
4	Providng weepholes in brick masonary/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.00	Nos.			-

5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.50	Per Cubic metre			

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Job No. 6

	SCHEDULE OF QUANTITY.	Estimated cost Rs. = 96,205/-only Earnest Money Rs. = 2,000/- only. Time Limit. = One Month

Name of work:- Restoration of rain damaged on Harlog Hawan Trifalghat road Km. 0/00 to 20/00. (SH:- C/O B/Wall and U-shape drain at RD. 8/630 to 8/637.25)

Sr No	Description of items.	Qty.		Rates		Amount
				In Figure	In words	
1	2	3	4	5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.57	Cubic Metre			
2	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.60	Square Metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty milimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.11	Cubic Metre			
4	Providng weepholes in brick masonary/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.00	Nos.			

5	Providing and laying mechanically mixed and vibrated plain/reinforced concrete 1:3:6 (One cement : three sand :six graded crushed stone aggregate 40 mm (forty milimetre) in open foundations complete as per drawings and technical specifications clause 802,803,1202 & 1203 . plain cement concrete grade M-10 (M-ten) Nominal mix including cost of form work and curing complete and including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.72	Cubic Meter			
		TOTAL				

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Job No. 7

Schedule of Quantity	Estimated cost Rs. = 74,410/- only
	Earnest Money Rs. = 2,000/- only
	Time = One Month.

Name of work : Proposed regeneration of water resource at village Badsour (Bandla road) Tehsil Sadar Distt. Bilaspur.

Sr No.	Description of items.	Qty.	Rate		Unit	Amount
			In Figure	In words		
1	2	3	4	5	6	7
1	Excavation in foundations, trenches by (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-incharge. All Kind of Soil. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.77			Per Cubic Metre	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty milimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.87			Per Cubic Metre	
3	Coursed rubble masonry (first sort) with hard stone in foundation and plinth with : Cement mortar 1:6 (1 cement : 6 coarse sand) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.56			Per Cubic Metre	

	Providing and laying autoclaved aerated cement blocks masonry with 150mm/230mm/300 mm thick AAC blocks in super structure above plinth level up to floor V level with RCC band at sill level and lintel level with approved block laying polymer modified adhesive mortar all complete as per direction of Engineer-in-Charge. (The payment of RCC band and reinforcement shall be made for seperately). including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.47			Per Cubic Metre	
4	Stone tile work for wall lining upto 10 m height with special adhesive over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand), including pointing in white cement with an admixture of pigment to match the stone shade 8mm thick (mirror polished and machine cut edge) Granite stone of any colour and shade. including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.36			Per Square Metre	
5	Providing and fixing wooden plank ceiling with tongued and grooved jointing and wood screws (frame work and cover fillets to be measured and paid for separately) 1st class deodar wood. 20 mm (Twenty milimetre) thick. including carriage of materials ,within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.40			Per Square Meter	
6	Providing and fixing 0.60mm (Zero point sixty millimeter) thick pre-painted steel sheet of TATA / DURO SHINE in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RNP) organic coating of 20 (Twenty) micron over 5 (Five) miocrons primer coating to back coat of polyster of 5 (Five) microns over 5 (Five) microns primer coating including fixing with pre-painted iron J opr L hooks, bolts and nuts , 6mm diametre with prepainted limpet and rubber washers complete with all accessories. as per HP.PWD Specification . including carriage of materials ,within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.63			Per Square Meter	

7	Providing ridges or hips of width 60 cm (Sixty centemetre) overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete. 0.80 mm (Zero point eighty milimetre) thick with zinc coating not less than 275 gm/m².(Two hundred seventy five gramme / Per Square Metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.75			Per Runing Metre	
8	Structural steel work in single section, fixed with or without connecting plate,including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	138.98			Per Kilograme	
9	Providing and fixing 50 mm thick extruded polystyrene rigid insulation board of required size underdeck on ceiling surface, complying with ISO 4898:2008 & ASTM C 578-08b - type VI, having thermal conductivity of 0.0289 W/m K as per ASTM C 578 (measured as per IS 3346), compressive strength of > 350 kPa listed as per ASTM D 1621, density of 34-36 kg/cum as per ASTM D 1622, water absorptions < 1% by volume as per ASTM D 2842, oxygen index of 24.1 to 28.1 listed as per ASTM D 2863, cell size 0.4 mm of dia (max) as per ASTM D 3576. Fire retardent property as per DIN 4102, Part 1 of class B2 and as per ASTM E84 class A, fixed with suitable water based adhesive and fastener, complete in all respect as per the direction of Engineerin-Charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.84			Per Square Metre	
10	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. 15 mm (Fifteen milimetre)dia nominal bore. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Per Runing Metre	

11	Providing and fixing C.P. brass bib tap of approved quality conforming to IS:8931 : 15 mm (Fifteen milimetre) nominal bore including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00			Each	

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Job No. 8

Schedule of Quantity

Estimated cost Rs. = 68,737/- only
Earnest Money Rs. = 2,000/- only
Time = One Month.

Name of work :- Proposed Gate in Champa Park at main Market Tehsil Sadar Distt. Bilaspur.

Sr No.	Description of items.	Qty.	Rate		Unit	Amount
			In Figure	In words		
1	2	3	4	5	6	7
1	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (One cement : One point five coarse sand): 3 (Three) graded stone aggregate 20 mm (twenty milimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.17			Per Cubic Metre	
2	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.27			Per Square Metre	
3	Providing and fixing 0.60mm (Zero point sixty millimeter) thick pre-painted steel sheet of TATA / DURO SHINE in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RNP) organic coating of 20 (Twenty) micron over 5 (Five) miocrons primer coating to back coat of polyster of 5 (Five) microns over 5 (Five) microns primer coating including fixing with pre-painted iron J opr L hooks, bolts and nuts , 6mm diametre with prepainted limpet and rubber washers complete with all accessories. as per HP.PWD Specification . including carriage of materials ,within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.65			Per Square Meter	

4	Providing ridges or hips of width 60 cm (Sixty centemetre) overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete. 0.80 mm (Zero point eighty milimetre) thick with zinc coating not less than 275 gm/m².(Two hundred seventy five gramme / Per Square Metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.05			Per Runing Metre	
5	Structural steel work in single section, fixed with or without connecting plate,including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	438.92			Per Kilograme	
6	Providing and fixing 50 mm thick extruded polystyrene rigid insulation board of required size underdeck on ceiling surface, complying with ISO 4898:2008 & ASTM C 578-08b - type VI, having thermal conductivity of 0.0289 W/m K as per ASTM C 578 (measured as per IS 3346), compressive strength of > 350 kPa listed as per ASTM D 1621, density of 34-36 kg/cum as per ASTM D 1622, water absorptions < 1% by volume as per ASTM D 2842, oxygen index of 24.1 to 28.1 listed as per ASTM D 2863, cell size 0.4 mm of dia (max) as per ASTM D 3576. Fire retardent property as per DIN 4102, Part 1 of class B2 and as per ASTM E84 class A, fixed with suitable water based adhesive and fastener, complete in all respect as per the direction of Engineerin-Charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.32			Per Square Metre	
		TOTAL				

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Job No. 9

	SCHEDULE OF QUANTITY.	Estimated cost Rs. = 95,000/-only Earnest Money Rs. = 2,000/- only. Time Limit. = One Month				
Name of Work : A/R & M/O on link road from Kasol to Balh road Km. 0/00 to 1/00. (SH:- Preparation of Digital Map, Topo Sheet of project and CA site with collecting data from site under HPPWD Division-1 Bilaspur for Preparation of FCA Case)						
Sr No	**Description of items.**	**Qty.**		**Rates**		**Amount**
				In Figure	**In words**	
1	**2**	**3**	**4**	**5**	**6**	**8**
1	Preparation and processing of FCA case of the Project with collection of data from site as per FCA guidelines with G.P.S. Coordinates. CA Site with preparation of the proposal folder of Project as per the Guidelines of MoEF with online uploading data on MoEF Portal and monitoring of the Proposal till final approval. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00	Per case			
		TOTAL				

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Job No. 10

Schedule of Quantity

Estimated cost Rs. = 99,376/-only	
Earnest Money Rs. = 2,000/ only.	
Time Limit. = One Month	

Name of work:- A/R & M/O various road under Beri Sub Division (under Panjgain section-I). (SH;- Maintenance of earthen shoulder).

Sr No	Description of items.	Qty.		Rates		Amount
				In Figure	In words	
1	Maintenance of Earthen shoulder (filling with fresh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment as per technical specification Clause 1903, including carriage of materials, within all leads and lifts as per direction of Engineer-in - Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2151.00	Square Meter			

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Job No. 11

Schedule of quantity

Estimated cost Rs. 95,586/-only	
Earnest Money Rs. 2,000/- only.	
Time Limit. = One month	

Name of work:- A/R & M/O residential building in Roura Sector Bilaspur. (SH:- P/L water proofing treatment in Qtr. No. T-81 and T-82).

Sr No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	2	3	5	6	7	8
1	Providing and laying clexo silver -SBS self-adhesive sheet membaren comprising of a tropical grade polymer modified bitumen membrane and solar reflective bituminous compund with 45 gsm glass fiber / 160gsm plymer line and topped with 30 microne colored aluminum foil surfacing with UV rays reflections tempraures should be between 5 degree to 50 degree depending on site condition. Membrane thickness 2mm not less then 2.1 kg per square metre and clexo dam primer 2.05 -3.05 square metre per litre. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	68.43			Per Square Metre	
	TOTAL					

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Job No. 12

	Schedule of Quantity	Estimated cost Rs. = 99,500/-only Earnest Money Rs. = 2,000/ only. Time Limit. = One Month

Name of work:- Construction of Dhoun Kothi to Pandha Palgiri road Km. 0/00 to 3/867. (SH:- Preparation of Forest Diversion case and Digital Plan Maps under HPPWD Sub Division Beri).

Sr No	Description of items.	Qty.		Rates		Amount
				In Figure	In words	
1	Preparation of forest Diversion case under Forest rights Act, 2006" including preparation of all essential papers of land falling on the proposed site. To prepare & submit the forest diversion application as per "Scheduled Tribes and other Traditional Forest Dwellers (Recognition of Forest Rights) Act, 2006" and scope of work encomasses up to obtaining Forest clearance from Forest Department by submitting necessary document ation including DGPS survey map of forest plots, compensatory Afforestation site or any other required survey map to the concerned authorities. If any any, expeding & follow-up with forest Department and furnish clarification, additional documentation, presenttation to RO & DFO, provide all technical and logistic support to forest Department etc. in obtaining forest clearance. The consultant will have to undertake all necessary studies as may be required as per the notificaton issued by the MoEF&CC during the execution of the assignment. The rate is excluding GST levy by the Govt. time to time.	1.00	Job			

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Job No. 13

Schedule of quantity

Estimated cost Rs. 95,000/-only
Earnest Money Rs. 2,000/- only.
Time Limit. = One month

Name of work:- Construction of Multilevel Parking and Library (Distt. Attorney) near D.C Office Bilaspur Distt. Bilaspur (H.P). (SH:- Preparation of detailed estimate as per Drg. No. 39 to 42 Job No. 4523-A).

Sr No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	2	3	5	6	7	8
1	Prepration of detailed estimate as per Architectural Drawing No. 39 to 42 and Job No. 4523-A on detail analysis of rate based on HPSR 2020with latest market rates and as per guidlines issued by HPPWD and CPWD in quadruplicate with a soft copy and also got it approved from competent authority complete in all respect and entire satisfaction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Job	
	TOTAL					

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Job No. 14.

	Schedule of Quantity			Estimated cost Rs. = 97,000/- Earnest Money Rs. = 2,000/ only. Time Limit. = One Month		
Name of work:- Prepration of detailed estimate for the C/O 10 Nos. type-III Qtrs at Police line Bilaspur.						
Sr No	**Description of items.**	**Qty.**		**Rates**		**Amount**
				In Figure	**In words**	
1	Prepration of detailed estimate for the C/O 10 Nos. type-III Qtrs at Police line Bilaspur in all respect in fairout form and submission of the same to higher office for approval. If any amendment / correction as desired by the head office, the same may be corrected as desired and directed by the Engineer-in-charge complete in all respect. After approval the same should be sumbitted in five copies as per condition. After approval of estimate the DNIT and justification of tender in fair manner be prepared and approved of same competent authority, as per direction of Engineer-in-Charge.	1.00	Job			

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Job No. 15/15

	Draft Schedule of Quantity			Estimated cost Rs. = 99,800/-only Earnest Money Rs. = 2,000/ only. Time Limit. = One Month		
Name of work:- Prepration of detailed estimate for the C/O 20 Nos. type-II Qtrs at Police line Bilaspur.						
Sr No	**Description of items.**	**Qty.**		**Rates**		**Amount**
				In Figure	**In words**	
1	Prepration of detailed estimate for the C/O 20 Nos. type-II Qtrs at Police line Bilaspur in all respect in fairout form and submission of the same to higher office for approval. If any amendment / correction as desired by the head office, the same may be corrected as desired and directed by the Engineer-in-charge complete in all respect. After approval the same should be sumbitted in five copies as per condition. After approval of estimate the DNIT and justification of tender in fair manner be prepared and approved of same competent authority, as per direction of Engineer-in-Charge.	1.00	Job			

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Job No. 16

Schedule of Quantity

Estimated Cost:- 99,846/-
Earnest Money :- 2,000/-
Time :- One month

Name of Work:- Restoration of rain damages on various road under Beri Sub Division. (SH:- Removal of slips at various RD's).

Sr No	Description of items.	Quantity		Rate		Amount
				in figure	In word	
1	2	3		4	5	7
1	Removal of land slides in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift up to 1.50 metre and lead upto 1000 metre as per technical specification 302.3.5 and 1611 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	733.89	Cubic Metre			
	total					

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Job No. 17

	SCHEDULE OF QUANTITY.	Estimated cost Rs. = 83,296/-only Earnest Money Rs. = 2,000/ only. Time Limit. = One Month.

NAME OF WORK:- A/R & M/O residential building Changer Sector Bilaspur. (SH;- Earth filling & Providing and fixing expanded metal Distt. and Session Judge residence Bilaspur).

Sr. No.	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In words		
1	2	3	5	6	7	8
1	Construction of Embankment with Material Obtained from Borrow Pits Construction of embankment with approved material obtained from borrow pits with all lead and lifts, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge.The rate includes octroi royality Malkhana toll tax and other taxes imposed by the Government.	72.19			Per Cubic metre	
2	Excavation in foundation trenches etc in earth work in all kinds of soil , such as pick work, pick jumper work, jumper work , jumper blasting work, chiseling wedging out rocks including pumping or bailing out water upto all lifts, stacking the excavated soil not more than three metres clear from the edge of excavation and then returning the stacked soil in 15 cm (fifteen centimetres) layers when required in to plinth side of foundation etcetra consolidating each deposited layer by ramming and watering and then disposing of all surplus excavated earthincluding carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.19			Per Cubic Metre	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (One Cement : Three coarse sand) : Six graded stone aggregate 20 mm(Twenty milimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.19			Per Cubic Metre	

4	Structural steel work in single section, fixed with or without connecting plate,including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	257.74			Per Kilograme	
5	Providing and fixing expanded metal 20x60 mm strands 3.25 mm wide and 1.6 mm thick for windows etc. with approved steel primer all complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	25.50			Per Square Metre	
6	Painting with synthetic enamel paint of approved brand and manufacture togive an even shade Two or more coats on new work,Two or more coats on new work. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	51.00			Per Square Metre	
		TOTAL				

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Job No. 19

	SCHEDULE OF QUANTITY.	Estimated cost Rs. = 77,352/-only Earnest Money Rs. = 2,000/ only. Time Limit. = One Month.

NAME OF WORK:- A/R & M/O non residential building HP.PWD Bilaspur. (SH;- P/L 20mm G.I pipr for circuit house suit No. 1, 2 & 3 HP.PWD Bilaspur).

Sr. No.	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In words		
1	2	3	5	6	7	8
1	Excavation in foundation trenches etc in earth work in all kinds of soil , such as pick work, pick jumper work, jumper work , jumper blasting work, chiseling wedging out rocks including pumping or bailing out water upto all lifts, stacking the excavated soil not more than three metres clear from the edge of excavation and then returning the stacked soil in 15 cm (fifteen centimetres) layers when required in to plinth side of foundation etcetra consolidating each deposited layer by ramming and watering and then disposing of all surplus excavated earthincluding carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.60			Per Cubic Metre	
2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50m (Fifty metres) lead as per direction of Engineer - in - charge Nominal concrete 1:3:6 (One:Three:Six)or richer mix (i/c equivalent design mix) . including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.15			Per Cubic Metre	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (One Cement : Three coarse sand) : Six graded stone aggregate 20 mm(Twenty milimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.58			Per Cubic Metre	

4	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
4.1	20 mm (twenty milimetre)dia nominal bore.	75.00			Per Runing Metre	
4.2	15 mm (Fifteen milimetre)dia nominal bore.	20.00			Per Runing Metre	
5	Providing and fixing brass full way valve with wheel ISI marked including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00			Each	
6	Providing and fixing PTMT Ball cock of approved quality colour and make complete with epoxy coated aluminium rod with LP/HPHD plastic ball with in all leads and lifts as directed by the ENgineer-in-Charge. including carriage of material. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Per Square Metre	
7	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
8	Providing and fixing C.P.brass bib tap (superior and heavy type) 15mm (Fifteen millimetre) dia. including carriage of materials ,within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00			Each.	

9	Providing and fixing PTMT jet spray of approved quality and colour with one metre tube. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00			Nos	
10	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Flexible pipe 32 mm (Thirty two milimetre) dia including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00			Each	
11	Providing and fixing unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour. 15 mm nominal bore with 30cm length. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00			Each	
12	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm (Forty milimetre), including painting of fittings and brackets, cutting and making good the walls wherever required : 470x420 mm (Four hundred seventy into four hundred twenty milimetre) bowl depth 178 mm (One hundred seventy eight milimetre). including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
13	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes FINOLEX including fixing with approved adhesive etc. complete including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royality, malkhana, toll tax, Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
13.1	110 mm (one hundred ten millimetre) diametre .	18.00			Per Runing Metre	

13.2	75 mm (Seventy five millimetre) diametre .	18.00			Per Runing Metre	
14	Providing and fixing PVC plain bend of D-plast FINOLEX. including carriage of materials within all leads, lifts and other incidentals. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constrcution worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
14.1	110 mm (one hundred Ten millimetre) dia	3.00			Each	
14.2	75 mm (Seventy five millimetre) diametre .	3.00			Each	
		TOTAL				

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Exigency certificate

It is certified that these works are of urgent nature and the tenders are to be required called immediately. So keeping in view the exigency of work these tenders are being called.

Executive Engineer,
Bilaspur, Division No.I,
HP.PWD, Bilaspur.