

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Offline

No. PWD-Dal/TA/Tender /2024-25 **5961-63**
To

Dated: - **05.02.2025**

The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject: - Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as given in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.


Copy forwarded to the Superintending Engineer, 7th Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie


Certificate

Certified that the tenders called vide this office letter No. PWD-/TA/Tender /2024-25:-5964-6014 dated. 05.02.2025 is emergent nature and in Public interest.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

Certificate

Certified that the tenders called vide this office letter No. PWD-/TA/Tender /2024-25:-5964-6014 dated. 05.02.2025 is emergent nature and in Public interest.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Sealed Item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Dalhousie Division, HPPWD, Dalhousie on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

- 5 Date of receipt of application for the tender Form a/w requisite documents:- 05.02.2025 onward (between 2:00 p.m.to 4:30.p.m.)
- 6 Date of issued/sale of tender form against Cash payment (non refundable).

The tender shall be received up to 3:00 PM on 15.02.2025 and will be opened on the same day at 3:30 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Non refundable) during the working hours on 13.02.2025

The Earnest Money in the shape of National Saving Certificate/FDR of any Bank in HP duly pledged in favour of Executive Engineer, Dalhousie Division, HPPWD, Dalhousie must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1.	A/R M/O Residential Quarters at Banikhet (SH:-Painting work of 02 Nos Type-III and 01 No Type-II Quarter at Banikhet	99941.00	2000.00	350.00	One Month	D & C
2.	Restoration of rain damage on Banikhet Dalhousie Khajjar road k.m. 15/600 to 27/00 (SH:- Removal of Slips at various RDs)	96285.00	2000.00	350.00	One Month	D & C
3	A/R M/O Residential Quarters at Banikhet (SH:- Painting work of 01 No. Type-II. AE Quarter Building outer portion and rppf truss)	99988.00	2000.00	350.00	One Month	D & C
4	A/R M/O Residential Building at Type-III & II (Rose villa) Quarters at Dalhousie (SH:- Dismantling, Plastering , Painting and Plinth Protection etc.)	99653.00	2000.00	350.00	Two Months	D & C
5	A/R & M/O Residential Building at Type-I Quarters near Circuit House at Dalhousie (SH:- Plastering , Painting and Sanitary work etc.)	45101.00	1000.00	350.00	Two Months	D & C
6	Construction of Shed for Generator HP:PWD 7 th Circle at Dalhousie (SH:- Providing steel work, pre-painted Sheet etc.)	99931.00	2000.00	350.00	Two Months	D & C
7	A/R & M/O various road under Dalhousie Division HP:PWD Dalhousie (SH:- Painting and writing of Boards, Kilometers stone, culverts, Sign boards and Rain	96707.00	2000.00	350.00	Two Months	D & C

	shelter etc.)					
8	Restoration of Rain damage on Dalhousie Jandrigat Chamba via Kohlari road Km. 0/0 to 11/040 (SH:- Removal of Slops/Snow on Dalhousie Jandrigat Chamba via Kohlari road Km. 0/0 to 11/040	96357.00	2000.00	350.00	One Month	D & C

1. The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
2. GST No. Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.
3. Application without all documents will not be entertained.
4. Proxy application will not be entertained.

Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

No. PWD/TA/Tender /2024-25 5964-6014

Dated:- 05.02.2025

Copy forwarded to the following for information and necessary action please:-

- 1 Engineer-in-Chief, HPPWD, Shimla.
- 2 All the Chief Engineer in HPPWD.
- 3 All SEs/EE in HPPWD
- 4 All AEs/Contractor under this Division.
- 5 Deputy Commissioner, Chamba
- 6 BDO Bhattiyat
- 7 Sub Divisional Magistrate/Tehsildar Dalhousie.
- 8 Notice Board of this office.

Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie

Schedule of Qty.

Name of work :- A/R & M/O Residential Quarters at Banikhet (SH: - Painting work of 02 Nos. Type-III and 01 No. Type-II Quarter at Banikhet).

Estimated Cost: - Rs.	99941.00
Earnest Money :- Rs.	2000.00
Time Limit :-	One Month

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Fig.	In Words		
1	15mm cement plaster in single coat on fair side of brick/concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth Cement Mortar 1:5 (1 cement: 5 sand), within all leads and lift and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	24.30			Per Square Metre	
2	Providing and applying plaster of Paris Putty of 2mm (two millimeter) thickness over plastered surface to prepare the surface even and smooth complete as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	24.30			Per Square Metre	
3	Painting one coat (excluding priming coat) on previously painted concrete/masonry/plastered surface with enamel paint Asian Paints/Nerolac surksha Paints/Berger Paints /Delux of approved brand and manufacture for use on wall to give an even shade including cleaning of all dirt, dust and other foreign matter and sand papering as required as per direction of the Engineer-In-Charge including carriage of materials within all leads and lift and other incidental. The rate including of octroi, royalty, Malkana, Toll Tax, sales tax GST or any other taxes imposed by the Government.	620.06			Per Square Metre	
4	Painting one coat (excluding priming coat) of Asian paints/ Nerolac Surksha Paints/ Berger Paints/ Deluxe Paint on previously painted wood or wood based surface with enamel paint other than white to gave a even shade including cleaning of all dirt, dust other foreign matter sand papering and slopping within all leads and lift and as per direction of Engineer-In-Charge and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	320.33			Per Square Metre	
	Total: -					

Schedule of Qty.

Estimated Cost: - Rs.	96285.00
Earnest Money :- Rs.	2000.00
Time Limit :-	One Month

Name of work: - Restoration of rain damage on Banikhet Dalhousie Khajjar road Km. 15/600 to 27/00 (SH: - Removal of Slips at various RD's).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty , Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	770.90			Per Cubic Metre	
					Total:-	


 Executive Engineer
 Dalhousie Division,
 H/PV/D. Dalhousie


Schedule of Qty.

Estimated Cost :- Rs.	99988.00
Earnest Money :- Rs.	2000.00
Time Limit :-	One Month

Name of work :- A/R & M/O Residential Quarters at Banikhet (SIH :- Painting work of 01 No. Type-II, AE Quarter Building outer portion and roof truss).

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Fig.	In Words		
1	15mm cement plaster in single coat on fair side of brick/concrete/stone walls for interior plastering upto floor two level including arises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth Cement Mortar 1:5 (1 cement: 5 sand), within all leads and lift and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	7.65			Per Square Metre	
2	Providing and applying plaster of Paris Putty of 2mm (two millimeter) thickness over plastered surface to prepare the surface even and smooth complete as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	7.65			Per Square Metre	
3	Painting one coat (excluding priming coat) on previously painted concrete/masonry/plastered surface with enamel paint Asian Paints/Nerolac surksha Paints/Berger Paints /Delux of approved brand and manufacture for use on wall to give an even shade including cleaning of all dirt, dust and other foreign matter and sand papering as required as per direction of the Engineer-In-Charge including carriage of materials within all leads and lift and other incidental. The rate including of octroi, royalty, Malkana, Toll Tax, sales tax GST or any other taxes imposed by the Government.	554.90			Per Square Metre	
4	Painting one coat (excluding priming coat) of Asian paints/ Nerolac Surksha Paints/ Berger Paints/ Delux Paint on previously painted wood or wood based surface with enamel paint other than white to give a even shade including cleaning of all dirt, dust other foreign matter sand papering and slopping within all leads and lift and as per direction of Engineer-In-Charge and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	163.12			Per Square Metre	

5	Painting of G.S. Sheet (excuding Priming Coat) with synthetic enamel paint of Asian Paints/Nerolac surksha Paints/Berger Paints /Delux of approved brand and manufacture for use on wall to give an even shade including cleaning of all dirt,dust and other foreign matter and sand papering as required as per direction of the Engineer-In-Charge including carriage of materials within all leads and lift and other incidental.The rate including of octroi, royalty, Malkana, Toll Tax, sales tax GST or any other taxes imposed by the Government.	245.97				Per Square Metre	
						Total: -	


 Engineer
 Dalhousie Division,
 H.P.P.W.D. Dalhousie


Schedule of Qty.

Name of work :- A/R & M/O Residential Building at Type-III & II (Rose villa) Quarters at Dallhousie (SH: - Dismantling, Plastering, Painting and Plinth Protection etc.).

Estimated Cost: - Rs.	99653.00
Earnest Money :- Rs.	2000.00
Time Limit :-	Two Months

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Fig.	In Words		
1	Demolishing stone rubble Masonary manually/by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 (fifty) meter lead as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	6.04			Per Cubic Meter	
2	Brick work Second class common burnt clay building bricks in super structure above plinth level upto floor to all level in cement mortar 1:6 (one cement isto six sand) as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or any other taxes imposed by the Government.	2.16			Per Cubic Metre	
3	15mm cement plaster in single coat on fair side of brick/concrete/stone walls for interior plastering upto floor two level including arisies, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth Cement Mortar 1:5 (1 cement: 5 sand). within all leads and lift and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	18.92			Per Square Meter	
4	Applying Birla white/J.K. white two or more coats wall care putty over plaster surfaces after thoroughly brushing the surface free from mortar drops dust, loose material and other foreign mater sand papered smooth to give final matter finished to the surface complete upto all floor level within all leads and lifts and as per HP PWD specification and per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Toll Tax, sales tax GST or any other taxes imposed by the Government.	18.92			Per Square Metre	

5	Wall painting with two coat Acrylic emulsion of Asian Paints/Nerolac surksha Paints/Berger Paints/Delux Paint on undecorated wall having interior grade, having VOC (Volatile Organic Compound) content less than 50 (Fifty) grams / litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	351.33			Per Square Metre	
6	Painting one coat (excluding priming coat) on previously painted wood or wood based surface with enamel paint other than white to give a even shade including cleaning of all dirt, dust and other foreign matter sand papering and slopping within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax GST or any other taxes imposed by the Government.	157.15			Per Square Metre	
7	Providing plinth protection 50 mm (fifty millimetre) thick in cement concrete 1:3:6 (one cement isto three sand isto six graded stone aggregate 40 mm (Forty millimetre) nominal size) over 75mm (seventy five millimeter) thick bed of dry brick ballast 40mm (forty millimeter) size, well rammed and consolidated and grouted with fand sand including necessary excavation, lavelling and dressing and finishing the top surface of concrete smooth within all leads and lifts and as per the direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax GST or any other taxes imposed by the Government.	19.50			Per Square Metre	
					Total: -	


 Engineer
 Division,
 P.W.D. Dainousie


Schedule of Qty.

Estimated Cost: - Rs.	45101.00
Earnest Money :- Rs.	1000.00
Time Limit :- Two Months	

Name of work :- A/R & M/O Residential Building at Type-I Quarters near Circuit House at Dalhousie (SH:- Plastering, Painting and Sanitary work etc.).

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Fig.	In Words		
1	15mm cement plaster in single coat on fair side of brick/concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth Cement Mortar 1:5 (1 cement: 5 sand). within all leads and lift and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	13.34			Per Square Metre	
2	Wall painting with two coat Acrylic emulsion of Asian Paints/Nerolac surksha Paints/Berger Paints/Delux Paint on undecorated wall having interior grade, having VOC (Volatile Organic Compound) content less than 50 (Fifty) grams / litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	218.91			Per Square Metre	
3	Painting one coat (excluding priming coat) Asian Paints/Nerolac surksha Paints/Berger Paints/Delux Paint on previously painted wood or wood based surface with enamel paint other than white to give a even shade including cleaning of all dirt, dust and other foreign matter sand papering and slopping within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax GST or any other taxes imposed by the Government.	48.36			Per Square Metre	

4	Painting one coat (excluding priming coat) Asian Paints/Nerolac surksha Paints/Berger Paints/Delux Paint on previously painted steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter With white enamel paint as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	63.84			Per Square Metre	
5	Providing and fixing on wall face unplasticised Rigid Polyvinyl chloride (PVC) rain water pipes of working pressure not less than 4 kg/sqm (four killograme/square metre) conforming to IS: 13592 type A, including jointing with seal ring conforming to IS: 5382, leaving 10mm (ten millimeter) gap for thermal expansion, Single socketed pipes 110 mm (one hundred ten millimetre) dia pipes and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	12.00			Per Running Meter	
					Total: -	


 Executive Engineer
 Dalhousie Division,
 H.P.W.R. Dalhousie

Schedule of Qty.

Name of work: - Construction of Shed for Generator at HP PWD 7th Circle at Dalhousie (SH: - Providing steel work, Pre-Painted Sheet etc.).

Estimated Cost: - Rs.	99931.00
Earnest Money :- Rs.	2000.00
Time Limit :-	Two Months

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax , GST or other taxes imposed by the Government.	0.16			Per Cubic Metre	
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size) and curing complete, in or under water, including pumping or bailing out water/dewatering, removal of slush which may arise at the time of laying under water complete excluding the cost of form work in foundation and plinth in all depths/heights as per HPPWD specifications and as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts. The is rate inclusive of Malkhana, royalty, octroi, toll tax, GST or any taxes imposed by the Government.	0.16			Per Cubic Metre	
3	Structural steel work in single section fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of Asian Paints/Nerolac surksha Paints/Berger Paints /Delux approved and manufacture for use on steel including cleaning of all dirt,dust and other foreign matter and sand papering as required as per direction of the Engineer-In-Charge including carriage of materials within all leads and lift and other incidental. The rate including of octroi, royalty, Malkhana, Toll Tax, sales tax GST or any other taxes imposed by the Government.	638.72			Per Kilogram	

4	Providing and fixing 0.60mm (Zero point six millimetre) thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyester of 5 (five) microns over 5(Five) microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accessories as required within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax GST or any other taxes imposed by the Government.	6.84				Per Square Metre	
5	Providing and fixing ridges or hips 60 cm (sixty centimetre) overall with 0.60 mm (zero point six millimetre) thick prepainted steel sheets in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating + back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with prepainted iron J or L hooks, bolts and nuts 6 mm (six millimetre) dia and prepainted G.I. limpet and bitumen washers complete with all accessories as required within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax GST or any other taxes imposed by the Government.	3.80				Per Running Metre	
6	Providing and fixing mild steel black plain (BP) Sheet 1.66 mm to 2 mm (one point sixty six to two millimetre) thick in decorative eaves board / fascia / soffits / ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per HP PWD specification and as per the direction of Engineer in-charge (Base members of steel work shall be measured and paid separately) within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax or any other taxes imposed by the Government.	10.00				Per Square Metre	
7	Providing and fixing 30cm (Thirty centimetre) wide 25cm (twenty five centimeter) deep 0.60mm (zero point six zero millimeters) thick prepainted Plain Galvanized Iron(PGI) sheet gutter of Tata/Sail/Royal iron/Triveni Strips/JSW steel having dome shape grating fixed with bolts, nuts and washers etcetera including making necessary connection with rain water pipe complete within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax GST or any other taxes imposed by the Government.	3.30				Per Running Metre	
						Total:-	

Schedule of Qty.

Estimated Cost: - Rs.	96707.00
Earnest Money :- Rs.	2000.00
Time Limit :-	Two Months

Name of work :- A/R & M/O various roads under Dalhousie Division HP PWD Dalhousie (SH: - Painting and writing of Boards, Kilometers stone, culverts, Sign boards and Rain shelter etc.).

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Fig.	In Words		
1	Removal of old paint from steel other metal surfaces and making the surface even with paint remover WD-40/ Turtlewax/ Asian Paints/waveX/Waspol etcetra of approved barand and manufacture as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	46.35			Per Square Meter	
2	Painting one coat (excluding priming coat) Asian Paints/Nerolac surksha Paints/Berger Paints/Delux Paint on previously painted steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning the surface of all dirt,dust and other foreign matter With white enamel paint as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	46.35			Per Square Metre	
3	Painting two coat (excluding priming coat) on new concrete/masonry/plastered surface with readymixed paint Asian Paints/Nerolac surksha Paints/Berger Paints /Delux of approved brand brushing to give an even shade including cleaning the surface of all dirt,dust and other foreign matter and sand papering as required with paint other then white enamel paint as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	76.47			Per Square Metre	
4	Writing letters or figure on any surface with black japan paint (stops, comas, hyphens and the like not to be measured and paid separately) Indian letter/figure and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	17000.00			Each	

5	Painting index hands normal size or arrows upto 40cm (forty centimeter long) on any surface with synthetic enamel paint Burger/Asian/Nerolac/Indigo etcetra and as as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	39.00				Each	
						Total: -	



 Engineer
 Dalhousie Division,
 H.P.V.R. Dalhousie

Schedule of Qty.

Estimated Cost: - Rs.	96357.00
Earnest Money :- Rs.	2000.00
Time Limit :-	One Month

Name of work: -Restoration of rain damage on Dalhousie Jandrighat Chamba via Kohlari road Km. 0/0 to 11/040 (SH: - Removal of Slips/Snow on Dalhousie Jandrighat Chamba via Kohlari road at RD. 6/00 to 11/040).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty , Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	771.60			Per Cubic Metre	
					Total:-	


 Executive Engineer
 Dalhousie Division,
 HP PWD, Dalhousie