

Himachal Pradesh
Public Works Department.

Through mail

No. PW/HD/CB/T-I/2024-25
To

7953-55

Dated: - 15-02-2025

The Executive Engineer (IT Cell)
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject: - Publication of Notice inviting tender.

Sir,

Enclosed please find herewith copy of notice inviting tender for publishing on departmental website for favour of further necessary action please.

Encl: As above

Executive Engineer,
HPPWD Division Haroli,
Distt. Una HP).

Copy along with copy of notice inviting tender is forwarded for information and necessary action to:-

1. The Superintending Engineer, 15th Circle, HP: PWD, Una.
2. Copy to Notice board.

Executive Engineer,
HPPWD Division Haroli,
Distt. Una HP).

Certificate

Certified that the tenders for the works called vide this office letter No. PWH/HD/CB/T-1/2024-7953-55 dated 15.02.2025 are required to be carried out immediately being emergent nature of work in public interest.

Executive Engineer,
HPPWD Division Haroli,
Distt. (na HP).

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
" NOTICE INVITING TENDERS "**

Percentage rate tender on PWD Form No. 6 & 8 are hereby invited by the Executive Engineer, Haroli Division, H.P. on behalf of Governor of H.P. for the following works from the approved and eligible contractors/firms enlisted in PWD Department per latest instructions, so as to reach and open in his office as per time schedule given below. The offer of the tender will be open for 45 days from the date of opening of tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of application for the tender form a/w requisite documents: - 21.02.2025 up to 10.30 (Non).
2. Date of issue/sale of tender forms against cash payment(non-refundable): - 21.02.2025 up to 3.00 PM
3. Date of receipt of tenders: - 22.02.2025 up to 10.30 AM
4. Date of opening of tenders: - 22.02.2025 at 11.00 AM

Sr. No.	Name of work	Estimated cost	EMD	Time Limit	Cost of tender	Eligible class of contractor
1	2	3	4	5	6	7
1	Construction of link road Mehtab Singh village Nagnoli (SH: C/o CC Pavement on approach road RD 0/082 to 0/106) Deposit work	98,842/-	2000/-	One month	350/-	Class- C & D
2	A/R & M/O on link road to Harijan Basti Kuthar Beet Km 0/0 to 3/400 (SH: C/o CC pavement at RD 0/506 to 0/522)	98,666/-	2000/-	One Month	350/-	Class- C & D
3	A/R & M/O link road to village Samnal Km 0/0 to 2/180 (SH: C/o R/wall at RD 0/241 to 0/262-LHS)	99,685/-	2000/-	One Month	350/-	Class- C & D
4	Balance work for the construction of Playground under MMYKTY GSSS Nagnoli Distt.Una (SH: Foundation work, painting work of fencing etc) Deposit work (Phase-III)	53,658/-	2000/-	One month	350/-	Class- C & D
5	C/o link road from Admn and Township at Panjuana to Factory gate of Bulk Drug park at Kuthar Beet (SH: Preparation of detailed estimate for technical sanction and DNIT i/c submission of Hard and Soft copies) Deposit work	80,000/-	2000/-	One Month	350/-	Class- C & D
6	C/o Model Heath Research Centre at Haroli Distt Una (SH: Pvdg and supplying Conference Table Round type) Deposit work	85000/-	2000/-	One month	350/-	Class- C & D
7	A/R & M/O PWD Non residential bldg. at Haroli (SH: P/F All in one HP-PC with 15.12h Gen Processor 8 GB SSD with Microsoft office & window UPS 600 VA and Brother printer DCP-B75000D) in Junior Engineer room at Newly created Khad Sub Division Office)	98,300/-	2000/-	One Month	350/-	Class- C & D
8	C/o Gramin Sampark to the house of Sh.Ram Lal S/o Sh.Tarsem Lal W.No.2 GP Beetan (SH: C/o CC Pavement RD 0/052 to 0/066) under MMSY	99,678/-	2000/-	One month	350/-	Class- C & D
9	Repair of pot holes on Panjawar Bathri road to Jhikla Panjawar Km 0/0 to 34/00 (SH: Patch work at RD 1/800 to 2/550)	99,418/-	2000/-	One Month	350/-	Class- C & D
10	A/R & M/O L/R Singan to HP Bopundary Km 0/00 to 1/300 (SH: C/o Retaining wall at RD 0/391.50 to 0/394.50)	98,625/-	2000/-	One month	350/-	Class- C & D

11	A/R & M/O on Laluwal Gondpur road Km 0/0 to 6/2500 (SH: C/o R/wall at RD 3/843 to 3/854 LHS & U-shape drain at RD 3/700 to 3/735 RHS)	66,507/-	2000/-	One Month	350/-	Class- C & D
12	C/o Model Heath Research Centre at Haroli Distt Una (SH: Pvdg and supplying Conference Table Round type) Deposit work Phase-I	85,000/-	2000/-	One month	350/-	Class- C & D
13	A/R & M/O on link road to Harijan Basti Kuthar Beet Km 0/0 to 3/400 (SH: C/o CC pavement at RD 0/538 to 0/555)	98,470/-	2000/-	One Month	350/-	Class- C & D
14	A/R & M/O Panjawar Bathri road Km 0/0 to 34/00 (SH: C/o RCC slab on existing U-shape at RD 10/601 to 10/616 & edge wall RD 10/601 to 10/646)	89,287/-	2000/-	One Month	350/-	Class- C & D
15	C/o link road Baba Bharthari Mandir to Dhillwan GP Chhetran Km 0/0 to 1/00 under OTMNP (SH: P/L embankment filling for grade improvement at RD 0/525 to 0/560.50)	99,684/-	2000/-	One month	350/-	Class- C & D
16	A/R & M/O L/R Singan to HP Boundary Km 0/00 to 1/300 (SH: C/o Retaining wall at RD 0/385.50 to 0/388.50)	9,075/-	2000/-	One Month	350/-	Class- C & D
17	C/o Gramin Sampark to the house of Sh. Ram Lal S/o Sh. Tarsem Lal W.No.2 GP Beetan (SH: C/o CC Pavement RD 0/024 to 0/038) under MMSY	99,874/-	2000/-	One month	350/-	Class- C & D
18	Painting of ITI Pubowal building Tehsil Haroli Distt Una (SH: Painting work to old building) Phase-I	99,950/-	2000/-	One Month	350/-	Class- C & D
19	A/R & M/O link road to village Samnal Km 0/0 to 2/180 (SH: C/o R/wall at RD 0/220 to 0/241-LHS)	99,525/-	2000/-	One month	350/-	Class- C & D
20	Construction of link road Mehtab Singh village Nagnoli (SHL: C/o CC Pavement on approach road RD 0/058 to 0/082) Deposit work	98,726/-	2000/-	One Month	350/-	Class- C & D
21	A/R & M/O Panjawar Bathri road km 0/0 to 34/0 (SH: P/L paver block at RD 33/641 to 33/662) (Gurnam mohalla)	99,191/-	2000/-	One Month	350/-	Class- C & D
22	C/o road from Shri Gigira Sahib (Pubowal) to Shri Tahlisahib & link road from main road to Shri Baba Bharthari & road to Kinnu mohalla Panjuana (Baliwal) from Km 0/0 to 4/245 in Distt. Una (SH: Preparation of working estimate and DNIT i/c submission of Hard and soft copies) under NABARD	80,000/-	2000/-	One month	350/-	Class- C & D
23	C/o link road Baba Bharthari Mandir to Dhillwan GP Chhetran Km 0/0 to 1/00 (SH: C/o earth work cutting at RD 0/430 to 0/480 embankment filling for grade improvement at RD 0/180 to 0/222) under OTMNP	99,561/-	2000/-	One Month	350/-	Class- C & D
24	C/o Gramin Sampark to the house of Sh. Ram Lal S/o Sh. Tarsem Lal W.No.2 GP Beetan (SH: C/o CC Pavement RD 0/066 to 0/080) under MMSY	99,788/-	2000/-	One month	350/-	Class- C & D
25	Painting of ITI Pubowal building Tehsil Haroli Distt Una (SH: Painting work to old building) Phase-II	99,960/-	2000/-	One Month	350/-	Class- C & D
26	A/R & M/O on link road to Harijan Basti Kuthar Beet Km 0/0 to 3/400 (SH: C/o CC pavement at RD 0/522 to 0/538)	98,637/-	2000/-	One Month	350/-	Class- C & D

27	A/R & M/P on link road to village Dharampur road Km 0/0 to 2/250 (SH: C/o U-shape drain at RD 0/081.20 to 0/112.40)	99032/-	2000/-	One month	350/-	Class- C & D
28	A/R & M/O link road from Una Jaijon road to Gulaban da Toba Km 0/0 to 1/700 (SH: C/o B/wall at RD 1/616 to 1/632 RHS)	99508/-	2000/-	One Month	350/-	Class- C & D
29	A/R & M/O on link road to Shiv Mandir village Polian Beet Km 0/0 to 1/500 (SH: C/o R/wall at RD 0/410 to 0/419.50 RHS)	99656/-	2000/-	One Month	350/-	Class- C & D
30	A/R & M/O on link road to village Dharampur road Km 0/0 to 2/250 (SH: C/o U-shape drain at RD 0/050 to 0/081.20)	99,510/-	2000/-	One Month	350/-	Class- C & D
31	C/o link road from HB to W No.1 via Bhatti Sahib Panjavar Km 0/0 to 2/200 (SH: C/O R/wall at RD 0/705 to 0/716 LHS) under SCDP	99,896/-	2000/-	One Month	350/-	Class- C & D
32	A/R & M/O L/R Singan to HP Boundary Km 0/00 to 1/300 (SH: C/o Retaining wall at RD 0/388.50 to 0/391.50)	99,225/-	2000/-	One month	350/-	Class- C & D
33	A/R & M/O on Una Rampur Haroli Palkwah Jaijon road Km 0/0 to 23/00 (SH: C/o Police guard post near Swan bridge at RD 1/800 LHS) Phase-II	78,254/-	2000/-	One Month	350/-	Class- C & D
34	C/o L/R from H.B. to Ward No.1 via Bhatti Sahib Panjavar Km 0/0 to 2/00 (SH: C/o R/wall at RD 0/725) under SCDP	99,659/-	2000/-	One Month	350/-	Class- C & D
35	Balance work for the construction of Playground under MMYKTY GSSS Nagnoli Distt.Una (SH: Foundation work, painting work of fencing etc) Deposit work (Phase-II)	97,549/-	2000/-	One Month	350/-	Class- C & D
36	C/o Gramin Sampark to the house of Sh.Ram Lal S/o Sh. Tarsem Lal W.No.2 GP Beetan (SH: C/o CC Pavement RD 0/080 to 0/092) under MMSY	99,530/-	2000/-	One Month	350/-	Class- C & D
37	A/R & M/O Non building Rest House at Haroli (SH: P/L 60mm thick interlocking paver in back side of building)	98,757/-	2000/-	One Month	350/-	Class- C & D
38	A/R & M/O on link road to Shiv Mandir village Polian Beet Km 0/0 to 1/500 (SH: C/o R/wall at RD 0/382 to 0/394 RHS)	99441/-	2000/-	One Month	350/-	Class- C & D
39	A/R & M/O Panjavar Bathri road km 0/0 to 34/0 (SH: P/L paver block at RD 33/621 to 33/641) (Gurnam mohalla)	98,771/-	2000/-	One Month	350/-	Class- C & D
40	Painting of ITI Pubowal building Tehsil Haroli Distt Una (SH: Painting work to old building) Phase-III	99,642/-	2000/-	One Month	350/-	Class- C & D
41	Construction of link road Mehtab Singh village Nagnoli (SHL: C/p CC Pavement on approach road RD 0/034 to 0/058) Deposit work	98,496/-	2000/-	One Month	350/-	Class- C & D
42	A/R & M/O link road from Una Jaijon road to Gulaban da Toba Km 0/0 to 1/700 (SH: C/o B/wall at RD 1/600 to 1/616 RHS)	99,658/-	2000/-	One Month	350/-	Class- C & D
43	A/R & M/O on link road to village Dharampur road Km 0/0 to 2/250 (SH: C/o U-shape drain at RD 0/112.40 to 0/143.60)	98,553/-	2000/-	One Month	350/-	Class- C & D
44	C/o Model Heath Research Centre at Haroli Distt Una (SH: Pvdg and supplying Conference Table Round type) Deposit work Phase-II	92,150/-	2000/-	One Month	350/-	Class- C & D

45	A/R & M/O on link road to Harijan Basti Kuthar Beet Km 0/0 to 3/400 (SH: C/o CC pavement at RD 0/555 to 0/571)	98,535/-	2000/-	One Month	350/-	Class- C & D
46	C/o L/R from H.B. to Ward No.1 via Bhatti Sahib Panjawar Km 0/0 to 2/00 (SH: C/o R/wall at RD 0/716.50 to 0/725 LHS) under SCDP	99,839/-	2000/-	One Month	350/-	Class- C & D
47	C/o Gramin Sampark to the house of Sh.Ram Lal S/o Sh. Tarsem Lal W.No.2 GP Beetan (SH: C/o CC Pavement RD 0/038 to 0/052) under MMSY	99,798/-	2000/-	One Month	350/-	Class- C & D
48	A/R & M/O on Una Rampur Haroli Palkwah Jaijon road Km 0/0 to 23/00 (SH: C/o Police guard post near Swan bridge at RD 1/800 LHS) Phase-1	99,276/-	2000/-	One Month	350/-	Class- C & D
49	A/R & M/O on link road to Shiv Mandir village Polian Beet Km 0/0 to 1/500 (SH: C/o R/wall at RD 0/370 to 0/382 RHS)	99,291/-	2000/-	One Month	350/-	Class- C & D
50	A/R & M/O Panjawar Bathri road km 0/0 to 34/0 (SH: P/L paver block at RD 33/600 to 33/621) (Gurnam mohalla)	99,612/-	2000/-	One Month	350/-	Class- C & D
51	A/R & M/O HPPWD NR building at HPPWD Rest House at Haroli & Sub Division office bldg. Haroli HPPWD (SH: Prov & installation of water purifier water dispenser and water disperser Jar)	73,480/-	1400/-	One Month	350/-	Class- C & D
52	A/R & M/O on link road Laluwal to Dulehar Km 0/0 to 2/0 (SH: C/o Toilet block at RD 1/970) (Phase-I)	99,820/-	2000/-	One Month	350/-	Class- C & D
53	A/R & M/O on link road to Shiv Mandir village Polian Beet Km 0/0 to 1/500 (SH: C/o R/wall at RD 0/419.50 to 0/429 RHS)	99,506/-	2000/-	One Month	350/-	Class- C & D
54	A/R & M/O on link road to village Dharampur road Km 0/0 to 2/250 (SH: C/o U-shape drain at RD 0/268.40 to 0/299.60)	99,724/-	2000/-	One Month	350/-	Class- C & D
55	A/R & M/O link road from Una Jaijon road to Gulaban da Toba Km 0/0 to 1/700 (SH: C/o B/wall at RD 1/632 to 1/644 RHS)	99,238/-	2000/-	One Month	350/-	Class- C & D
56	A/R & M/O on Panjawar Bathri road Km 0/0 to 34/00 (SH: P/L 600mm dia NP2 pipes with CC chambers Near Primary school Pandoga at RD 5/310 to 5/327.50)	93,488/-	2000/-	One Month	350/-	Class- C & D
57	A/R & M/O on link road Laluwal to Dulehar Km 0/0 to 2/0 (SH: C/o Toilet block at RD 1/970) (Phase-II)	99,765/-	2000/-	One Month	350/-	Class- C & D

The earnest money in the shape of National Saving certificate/ time deposit/ saving account of any post office or FDR Nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected. The tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained. The copy of valid enlistment, GST registration No. Income Tax, Pan No. and epf no. must be attached with application.

SPECIAL CONDITION: -

1. The contractor should produce a copy of valid enlistment/renewal letter at the time of application.
2. The contractor/firm shall have his resignation and GST No. and copy of same be attached with the application.
3. The earnest money for the above work should be submitted duly pledged in favour of Executive Engineer, Haroli Division HPPWD with the application for the purchase of tender forms. The application received without earnest money shall summarily be rejected.
4. The contractor/firms are required to insert the rate in words as well as figures, failing which Executive Engineer reserves the right to accept/rejects any or all tenders. If any of the date mentioned above happens to be local/gazetted holidays, the same shall be process on next date.

5. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their application a/w proof of ownership of machinery/legal tie up arrangement).
6. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.
7. The conditional/ambiguous/telegraphic tenders by fax shall not entertained/considered in any case.

HIM SUCHANA AVAM JAN SAMPARK.


Executive Engineer
HPPWD Division Haroli
Distt.Una(HP).Pin Code-177220
Email: ee-haroli-hp@hp.gov.in
On behalf of Governor of Himachal Pradesh.

SCHEDULE OF QUANTITY

Name of work :Construction of link road Mehtab Singh village Nagnoli (SH: C/O C.C. pavement on approach road RD 0/082 to 0/106)-Deposit work

Estimated Cost 98842
Earnest Money 2000/-
Time limit One month

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	23.76	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement four sand eight graded crushed /broken stone aggregate 20mm (twenty millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	10.80	Per cubic metre			
3	Providing and laying (M-25) (M-twenty five)Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg.(four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800.1205.4 and 1205.5 as per the direction of the Engineer-in- chargeincluding carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	10.80	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)C/17/2/0212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No PBW(B)A(3)/2020 dated 22.07.20				Total:	0

Executive Engineer
Haroli Division
HPPWD

449

5-2

SCHEDULE OF QUANTITY

Name of work : A/R & M/O on link road to harijan basti Kuthar Beet Km 0/00 to 3/400 (SH: C/O C.C. pavement RD 0/506 to 0/522) Estimated Cost 98666
 Earnest Money 2000/-
 Time limit One month

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiselling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government.	2.95	Per cubic metre			
2	Construction of Granular Sub Base by providing well graded material, spreading in uniform layers with tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC and compacting with smooth wheel roller to achieve the desired density complete as per technical specification clause for grading I material including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government.	8.38	Per Cubic metre			
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement four sand eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802 803 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government..	10.82	Per cubic metre			
4	Providing and laying (M:25) (M:twenty five) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg.(four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government..	9.86	Per cubic metre			
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17J/0212 dated 7.8.2018					Total:	0
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20						

Executive Engineer
 Haroli Division

397

SCHEDULE OF QUANTITY

Name of work: A/R & M/O link road to village Sampal Km 0/00 to 2/180 (SH-C/O R/wall at RD 0/241 to 0/262- LHS)

Estimated Cost 99685

Earnest Money 2000/-

Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	13.23	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed or broken stone aggregate 20mm (Twenty Millimeter) nominal size in or under water ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.51	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709,1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.	11.00	Each			
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.	6.30	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
					Total:	0

Executive Engineer,
R.F. Division Haroli
Distt. Una (H.P.)

361

SCHEDULE OF QUANTITY									
Name of Work: Balance work for the construction of Playground under MMYKTY GSSS Nagnoli Distt.Una (HP) (SH: Foundation work painting work of fencing etc)				Estimated cost		53658			
Deposit work. (Phase-III)				Earnest money		1000			
				Time limit		One month			
S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)			
				Figures	Words				
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	6.99	Per cubic metre						
2	Providing and laying cement concrete 1:4:8 (one cement: four sand eight graded crushed stone aggregate 40mm/ forty millimeter nominal size) mechanically mixed and curing complete excluding cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	5.23	Per cubic metre						
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-Twenty) nominal mix 1:2:4 (One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	2.86	Per cubic metre						
4	Providing and laying for steel(TISCO, JINDAL PANTHER of (JSPL) /Sail/RINL/Shyam steel make) reinforcement for reinforced cement concrete work including ,bending binding, straightening and placing in position complete in all floor level/ heights including cost of binding wire complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, sale tax GST, labour cess or other taxes imposed by the Government.	146.86	Per Kilogramme						

446

5	Providing and fixing Structural steel work riveted, bolted or welded in builtup section, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of approved steel primer all complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	25.00	Per Kilogramme			
6	Finishing with deluxe multi surface paint system for interiors and exterior using Steel work with Deluxe coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	89.25	Per square metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/2/20212 dated 7.8.2018				Total	0
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Haroli Division
 HP.PWD, Haroli

446

Schedule of Quantity

Name of Work : Construction of link road from Adminstrative and Township at Panjuna to Factory gate of Bulk drug park at Kuthar Beet (SH: Preparation of detailed estimate for Technical sanctioned and DNIT including submission of Hard and soft copies)- Deposit work

Estimated cost : 80000
Earnest Money : 1600
Time Limit : 15 days

S. No.	Description of item	Qty.	Unit	Rate (Rs.)	Rate in words	Amount (Rs.)
1	Preparation and approval of working estimate from higher authority including submission of 5 (five) -set of estimate.The rate includes sale tax octori, royalty,malkhana,toll tax,GST,labour cess or other taxes imposed by the Government..	1	Number			
2	Preparation and approval of Drafts Schedule of quantity from higher authority. The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1	Number			
	1) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20				Total =	0


Executive Engineer
Haroli Division
HPPWD Haroli.

467

6

Phase-I

Draft Schedule of quantity

Name of work:- C/O Model Health Research Centre at Haroli Tehsil Haroli Distt. Una .					Estimated Cost: Rs	₹ 85,000
(SH- Providing and Supplying Conference Table Round type)-Deposit work					Time:-	One month
					Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and Supplying Conference Table Round type size 2x(14'-00" x 2'-00") make with HDMR board including carriage of material within all lead and lifts and other incidental. The rate includes sale tax octroi,royalty, malkhana, toll tax, GST,labour cess or other taxes imposed by the Government.	1.00	Each	85000.00	Rupees eighty five thousand only	85000.00
	Total					85000
	1) The Bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP Vide letter No. PBW(B) A(3) 1/2020 dated 22.07.2020 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 07.10.2021.					


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

368

Schedule of quantity

Schedule of quantity						
Name of work:- A/R & M/O PWD Non PWD Residential building at Haroli (SH: P/F All in one HP-PC with 15. 12h Gen Processor 8 GB Ram & 512 GB SSD with Microsoft office & window UPS 600 VA and Brother printer DCP-B7500D) in Junior Engineer room at Newly created Khad Sub Division Division Office)				Estimated Cost: Rs		₹ 98,300
				Time:-		One month
				Earnest Money:-		2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and fixing commercial All in one HP make computer system with inspiron 24" Intel i5.12Th Gen Processor 8 GB Ram &512TB SSD with Microsoft office & Window 11/12 Wi, fi, & Bluetooth 4.0 M.2/keyboard & optical mouse (3 year warranty provided by the manufacturer from date of purchase) including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	1.00	Each			
2	Providing and fixing Intex UPS 600 VA Gamma including entire camage of maternal within all leads and lifts and other incidentals and as per the direction by the Engineer-in charge. The rates are inclusive octroi, royalty malkana, toll tax sale tax, GST labour cess or other taxes imposed by the Government	1.00	Each			
3	Providing and fixing Brother printer DCP-B7620DW with wifi technology including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi royalty malkhana toll tax, GST, labour cess or other taxes imposed by the Government	1.00	Each			
Total						
Note:1) All Type of material shall be arranged by the contractor vide Notification No. 10 of 2024-25.						

Note:1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018
2) The rates shall be including of all types of taxes including GST etcetra)

Executive Engineer
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

HDS

SCHEDULE OF QUANTITY

3

Estimated cost 99678

Earnest money 2000

Time limit One month

(SH: C/o C.C

Name of Work: C/O Gramin Sampark to the house of Sh Ram Lal S/O Sh Tarsem Lal ward No2 GP Beetan (SH: C/o C.C

S. No.	Description of work	Quantity	Unit	Rates (in Rs.)		Amount (in Rs.)
				Figures	Words	
1	Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm(forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge . The rates are inclusive octroi, royalty, malkhana , toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.96	Per cubic metre			
2	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals . The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government..	7.96	Per cubic metre			

487-

3	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard concrete design mix of grade M-25 (M-twenty) cement contents not less than 400kg. (four hundred kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORC technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals The rate includes octroi, royalty, malikhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	11.90	Per cubic metre		
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021				
				G.Total	0


 Executive Engineer
 Haroli Division
 HP.PWD.,Haroli

487

SCHEDULE OF QUANTITY									
Name of work : Repair of Pot hole on Panjagar Bathri road to Jhikla Panjagar km.0/0 to 34/0(SH: Patch work at RD 1/800 to 2/550)									
S. No.	Description of work	Quantity	Unit	RATE IN		Estimated Cost	Earnest Money	One month	AMOUNT
				Figures	Words				
1	Providing , laying spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (pug mill) carriage of mixed material by tipper to site, laying in uniform layers in sub-base/ base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100KN (Eighty to hundred kilo newton) capacity to achieve the desired density including lighting barricading and maintenance of diversion etc. as per tables 400.11 & 400.12 and technical specification clause 406 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana , toll tax, GST, labour cess or other taxes imposed by the Government.	8.20	Per cubic metre			99419	2000		
2	Providing and applying evenly a primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg (zero point seventy kilogram to one point zero kilogram) per square metre using mechanical means as per technical specification clause 502 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts, and other incidentals. The rate including octroi royalty, malikhana toll taxes, GST, labour cess or taxes imposed by the Government	176.12	Per square metre						
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen emulsion .20mm thick premix carpet VG-30 and seal coat type B specification clause 1904 2.503 and 508.1 including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana , toll tax, GST, labour cess or other taxes imposed by the Government.	290.84	Per square metre						
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)0(17)20212 dated 7.8.2018								
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy P.W to the Govt. of HP vide letter No.PBW(B) A(3)11/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021								
						Total:		0	

Executive Engineer
Haroli Division
HP.PWD.,Haroli

402

10

Schedule of quantity

Name of Work:- A/R & M/O L/R Singan to HP Boundary km 0/00 to 1/300. (SH: C/O Retaining wall at Rd. 0/391.50 to 0/394.50).						Estimated Cost: Rs	₹ 98,625
						Time:-	One month
						Earnest Money:-	
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	14.40	Cum.				
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	27.78	Cum.				
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.00	nos				
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.08	Cum.				
Total							

NOTE: All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PAW (R) 2018/11/20/2012 dated 07.08.2018

421


Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Draft Schedule of quantity

Name of work :-A/R & M/o on Lalulwal Gondpur road Km 0/00 to 6/200 .

Name of work :-A/R & M/o on Lalulwal Gondpur road Km 0/00 to 6/200 .						Estimated Cost: Rs	₹ 66,507
(SH:- C/o Retaining wall at RD to 3/843 to 3/854 Lhs & U- shape drain at Rd. 3/700 to 3/735 Rhs)						Time:-	One month
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Earnest Money:-	
						2000	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	6.33	Cum.				
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	18.87	Cum.				
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	8.00	nos				
4	Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	5.28	Cum.				
Total							

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

465

21

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

11.
TDS 6490 744
17.11.25

12

DRAFT SCHEDULE OF QUANTITY									
Name of work : C/O Modal Health research Centre at Haroli Tehsil Haroli Ddistt Una (SH:- Providing and Supplying Conference Table Round type) D-Work				Phase-I			85000/-		
S. No.	Description	Quantity	Unit	T.Rate	RATE In		Earnest Money	Time limit	one month
					Words	AMOUNT			
1	Providing and Supplying Conference Table Round type size 2x(14'-00" x 2'-00") make with HDMR board including carriage of material within all lead and lifts and other incidental. The rate includes sale tax octroi royalty, maikhana, toll tax, GST labour cess or other taxes imposed by the Government	1.00	Each						
	Total								0
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021								

Executive Engineer
Haroli Divn.HR.PWD.,
Haroli

368

SCHEDULE OF QUANTITY

Name of work : A/R & M/O on link road to harijan basti Kuthar Beet Km 0/00 to 3/400 (SH: C/O C.C. pavement RD 0/538 to 0/555) Estimated Cost 98470
 Earnest Money 2000/-
 Time limit One month

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling (wedging out rocks) (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST labour cess or other taxes imposed by the Government.	2.95	Per cubic metre			
2	Construction of Granular Sub Base by providing well graded material, spreading in uniform layers with tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density complete as per technical specification clause for grading material including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST labour cess or other taxes imposed by the Government.	8.36	Per cubic metre			
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST labour cess or other taxes imposed by the Government.	10.80	Per cubic metre			
4	Providing and laying (M-25) (M-twenty five) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST labour cess or other taxes imposed by the Government.	9.94	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)@1712/2012 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B)A(31)/2020 dated 22.07.20					
					Total:	0

Executive Engineer
 Haroli Division
 HPPWD

433

SCHEDULE OF QUANTITY

Estimates cost:- Rs.89287/-
Earnest Money:- Rs. 1800/-
Time Limit:- One Month.

Name of work :-A/R & M/O Panjawan Bathri road Km 0/00 to 34/00 (SH:- C/O RCC slab on existing U -shape at RD 10/601 to 10/616 & edge wall RD 10/601 to 10/646)

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement three sand six graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802 803 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental The rate includes sale tax octroi, royalty,maikhana .toll tax,GST labour cess or other taxes imposed by the Government.	1772	Per Cubic metre			
2	Providing and laying (M-25) (M-twenty five)Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205 5 as per the direction of the Engineer-in-chargeincluding carriage of material with in all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,maikhana .toll tax,GST labour cess or other taxes imposed by the Government	383	Per cubic metre			
	Total					0
Note:-	1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)/6(17)/20212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)/A(31)/2020 dated 22.07.20					

Executive Engineer,
Haroli Division
HPPWD

24th

Draft Schedule of quantity

Name of work:-C/O link road Baba Bharthri Mandir to Dhiwan GP Chetran km. 0/00 to 1/00 (Under OTMNP)					Estimated Cost: Rs	₹ 99,684
(Sh: P/L Embankment filling for grade improvement at Rd. 0/525 to 0/560.50)					Time:-	One month
					Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with ~~lead~~ ^{as per} ~~1000~~ as per Technical Specification Clause 301.5 including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	415.35	cum			
Total						

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018

**Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)**

473

Schedule of quantity

Name of Work:- A/R & M/O L/R Singan to HP Boundary km 0/00 to 1/300. (SH: C/O Retaining wall at Rd. 0/385.50 to 0/388.50).					
				Estimated Cost: Rs	₹ 99,075
				Time:-	One month
				Earnest Money:-	
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width) or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other Incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	14.40	Cum.		
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth including carriage of materials within all leads and lifts and other Incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	27.78	Cum.		
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other Incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	13.00	nos		
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other Incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.08	Cum.		
Total					

Note: A) Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. 23W (B) 1171 4/02/2018 dated 07.08.2018.

419

**Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)**

SCHEDULE OF QUANTITY

Estimated cost 899574
Earnest money 2000
Time limit One month

Name of Work: C/O Gramin Sampark to the house of Sh Ram Lal S/O Sh Tarsem Lal ward No2 GP Beetan (SH: C/o C.C Pavement RD 0/024 to 0/038)- Under MMSY

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm) forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.98	Per cubic metre			
2	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.98	Per cubic metre			

485

3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard concrete design mix of grade M-25 (M-twenty) cement contents not less than 400kg (four hundred kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals The rate includes octroi, royalty, malakhana, toll tax, GST, labour cess or other taxes imposed by the Government.	11 92	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
					G.Total	0

Executive Engineer
Haroli Division
HP.PWD., Haroli


485

SCHEDULE OF QUANTITY

Name of work:- Painting of ITI Pubowal building Tehsil Haroli Distt Una (SH: Painting work to old building)- Phase-I

Estimated Cost 99950
Earnest Money 2000/-
Time limit One month

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	514.27	Per Square metre			
2	Providing and applying white cement based putty of average thickness 1 mm. of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	154.03	Per Square metre			
3	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacturer, including applying additional coats wherever required to achieve even shade and colour two coat including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	514.27	Per Square metre			
4	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacturer including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	140.82	Per Square metre			
5	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacturer including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	115.87	Per Square metre			
6	Finishing walls with Acrylic Smooth exterior paint of required shade Old work ("Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	350.07	Per Square metre			
	Total					0
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)(17)12/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					


 Executive Engineer
 Haroli Divn.HP
 Haroli

SCHEDULE OF QUANTITY

Name of work: A/R & M/O link road to village Sampal Km 0/00 to 2/180 (SH:C/O R/wall at RD 0/220 to 0/241- LHS)

Estimated Cost 99525
Earnest Money 2000/-
Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	13.23	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.51	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614, 709, 1204, 3.7 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	10.00	Each			
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	6.30	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@/(17)2/0212 dated 7.8.2018				Total:	0
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					


Executive Engineer,
H.P.P.W.D. Division Haridwar
Distt. Una (H.P.)

362

SCHEDULE OF QUANTITY

Name of work :Construction of link road Mehtab Singh village Nagnoli (SH: C/O C.C. pavement on approach road RD 0/058 to 0/082)-Deposit work

Estimated Cost 98726
Earnest Money 2000/-
Time limit One month

S. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty maikhana toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	23.04	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement four sand eight graded crushed broken stone aggregate 20mm (twenty millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, maikhana toll tax, GST labour cess or other taxes imposed by the Government.	10.80	Per cubic metre			
3	Providing and laying (M:25) (M-twenty five) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORO 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, maikhana toll tax, GST labour cess or other taxes imposed by the Government.	10.80	Per cubic metre			
					Total:	0

NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)6(17)/2012 dated 7.8.2018.
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20

Executive Engineer
Haroli Division
HPPWD

448

21

Schedule of quantity

Name of work :- A/R & M/O Panjavar Bathri road Km 0/00 to 34/00						Estimated Cost: Rs	₹ 99,191
(SH:- P/L Paver block at RD 33/641 to 33/662 Gurnam Mohalla						Time:-	One month
						Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	21.24	Cum.				
2	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.31	Cum.				
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.08	Cum.				
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	70.80	Sqm				
5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 804, 1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.83	cum				
Total							0

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) 8 (17) 2/02012 dated 07.08.2018

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

500

Schedule of Quantity

92

Name of Work : Construction of road from Shri Girgira Sahib (Pubpwal) to Shri Tahlisahib & link road from main road to Shri Baba Bharthari & road to kinnu Mohalla Panjuna (Baliwal) from km-0/0 to km-4/245 in Distt. Una (SH: Preparation of working estimate and DNIT including submission of Hard and soft copies)- under NABARD

Estimated cost : 80000
Earnest Money : 1600
Time Limit : 15 days

S. No.	Description of item	Qty.	Unit	Rate (Rs.)	Rate in words	Amount (Rs.)
1	Preparation and approval of working estimate from higher authority including submission of 5 No -set of estimate. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	1	Number			
2	Preparation and approval of Drafts Schedule of quantity from higher authority. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	1	Number			
	1) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)(A)(3)1/2020 dated 22.07.20				Total =	0


 Executive Engineer
 Haroli Division
 HPPWD Haroli.

466

Draft Schedule of quantity									
Name of work:- C/O link road Baba Bharthri Mandir to Dhiwan GP Chetran km. 0/00 to 1/00 (~~Under OTMNP~~) --									
(Sh: C/O Earthwork cutting at Rd. 0/430 to 0/480 Embankment filling for grade improvement at Rd. 0/180 to 0/222) -- ~~Under OTMNP~~									
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Earnest Money:-		Estimated Cost: Rs	One month	
					Time:-	Rate in words		2000	Amount
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1.. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	577.50	cum						
2	Construction of Embankment with Material Obtained from Roadway Cutting ~~Construction of embankment with approved materials deposited at site from roadway~~ cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5. - including carriage of materials within all leads and lifts and other incidental : The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	207.90	cum						
Total									

Note: All Type of material

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

459

SCHEDULE OF QUANTITY

Estimated cost 99788
 Earnest money 2000
 Time limit One month

(SH: C/o C.C

Name of Work: C/O Gramin Sampark to the house of Sh Ram Lal S/O Sh Tarsem Lal ward No2 GP Beetan (SH: C/o C.C					
Pavement RD 0/066 to 0/080)- Under MMSY					
S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)	
				Figures	Words
1	Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm) forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.96	Per cubic metre		
2	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading - I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.96	Per cubic metre		

488

3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard concrete design mix of grade M-25 (M-twenty) cement contents not less than 400kg (four hundred kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	11.92	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)@17/20212 dated 7.8.2018. 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No. PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 7.10.2021				G.Total	0


 Executive Engineer
 Haroli Division
 HP.PWD, Haroli

488

25

SCHEDULE OF QUANTITY

Estimated Cost 99960
Earnest Money 2000/-
Time limit One month

Name of work:- Painting of ITI Pubowal building Tehsil Haroli Distt Una (SH: Painting work to old building)- Phase-II

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete, including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	514.27	Per Square metre			
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete, including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	154.03	Per Square metre			
3	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacturer, including applying additional coats wherever required to achieve even shade and colour two coat including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	514.27	Per Square metre			
4	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacturer including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	140.82	Per Square metre			
5	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacturer including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	115.87	Per Square metre			
6	Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied @ 1.67 ltr/10 sqm) on existing cement paint surface including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	350.20	Per Square metre			
	Total					0
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)@1702/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20					

Executive Engineer
Haroli Divn. HP PWD,
Haroli

HPPWD

SCHEDULE OF QUANTITY

Name of work : A/R & M/O on link road to harijan basti Kuthar Beet Km 0/00 to 3/400 (SH: C/O C.C. pavement RD 0/522 to 0/538) Estimated Cost 98637
 Earnest Money 2000/-
 Time limit One month

S. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling/wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	2.90	Per cubic metre			
2	Construction of Granular Sub Base by providing well graded material, spreading in uniform layers with tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC and compacting with smooth wheel roller to achieve the desired density complete as per technical specification clause for grading I material including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	8.36	Per Cubic metre			
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement four sand-eight graded crushed broken stone aggregate 20mm (Twenty Millimeter) nominal size in or under water/or ground complete including pumping or bailing out water/dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	10.82	Per cubic metre			
4	Providing and laying (M-25) (M-twenty five) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	9.86	Per cubic metre			
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)/1712/0212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No PBW(B)/M(31)/2020 dated 22.07.20					Total:	0

Executive Engineer
 Haroli Division
 HPPWD

398

27
Schedule of quantity

Name of work:-A/R & M/O On link road to village Dharampur road km. 0/00 to 2/250					Estimated Cost: Rs	₹ 99,032
(SH: C/O U-Shape drain at RD. 0/081.20 to 0/112.40).					Time:-	One month
					Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	35.10	CUM.			
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	21.06	CUM.			

3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(i) nominal mix 1:1.5:3. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	0.63	CUM.		
4	Supplying, fitting and placing TMT bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	0.11	Tonne		
	Total				

Note:1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018


Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

572

Schedule of quantity

Name of work: A/R & M/O link road from Una Jajjon road to Gulaban da Toba Palkwah 0/00 to 1/700.

(C/O Breast wall at Rd. 1/616 to 1/632 Rhs)

(C/O Breast wall at Rd. 1/616 to 1/632 Rhs)							Estimated Cost: Rs	One month
							Time:-	
DESCRIPTION							Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	25.00	cum					
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (CC 1:4:8), including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	26.52	cum					
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	19.00	Each					
4	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 3 : 6 in foundation and plinth, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.68	Cum					
Total								

Note: All Type of material shall be as per specification.

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018

21

503

29

Schedule of quantity

Name of work :- A/R & M/O on link road to Shiv Mandir Village Polian Beet km 0/00 to 1/500 (SH: C/O Retaining wall at RD. 0/410 to 0/419.50 RHS).						Estimated Cost: Rs	₹ 99,656
DESCRIPTION						Time:-	One month
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:-	Rate in words	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil Upto 3 m depth, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	8.27	Cum.				
2	Providing & Laying Cement Concrete 1:4:8 (1Cement :4Sand :8Graded stone aggregate 40 mm nominal size) including cost of form work plain/reinforced concrete in retaining wall /Breast wall, as per Drawing and H.P.W.D. technical Specification, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.45	Cum.				
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	16.00	each				
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.70	Cum.				
Total							

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

507

Schedule of quantity

Name of work:-A/R & M/O On link road to village Dharampur road km. 0/00 to 2/250						Estimated Cost: Rs	₹ 99,510
(SH: C/O U-Shape drain at RD. 0/050 to 0/081.20).						Time:-	One month
						Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	35.10	CUM.				
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	21.06	CUM.				

3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(i)nominal mix 1:1.5:3. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	0.65	CUM.		
4	Supplying, fitting and placing TMT bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	0.11	Tonne		
	Total				

Note:1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

509

31

SCHEDULE OF QUANTITY

Name of work: C/O link road from harijan Basti to ward No 1 via Bhatti Sahib Panjawa Km 0/00 to 2/00 (SH:C/O R/wall at RD 0705 to 0/716- LHS)- under SCDP

Estimated Cost 99896
Earnest Money 2000/-
Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	13.53	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.60	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709, 1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	14.00	Each			
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	4.62	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B)A(3)1/2020 dated 22.07.20					
					Total:	0

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

513

32

Schedule of quantity

Name of Work:- A/R & M/O L/R Singan to HP Boundary km 0/00 to 1/300. (SH: C/O Retaining wall at Rd. 0/388.50 to 0/391.50).					
				Estimated Cost: Rs	₹ 99,225
				Time:-	One month
S.NO	DESCRIPTION	Qty	Unit	T Rate	Earnest Money:- Rate in words Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	14.40	Cum.		
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	27.78	Cum.		
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	14.00	nos		
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.08	Cum.		
Total					

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Sery to the Govt. of HP vide letter No. pgw (B) 171/2/2012 dated 07.08.2012.

L20


Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

33

SCHEDULE OF QUANTITY

33

SCHEDULE OF QUANTITY						
Name of work :A/R & M/O on Una Rampur Haroli Palkwah Jaijon road Km 0/00 to 23/00 (SH: C/O police guard post near swan bridge at RD1/800-LHS)-Phase-II						
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from MS sheets and galvanised with zinc coating of 120 gms/ sqm (both side inclusive) as per IS: 277 and consisting of angle cleats of size 25mm wide x 1.6mm thick with flanges of 27mm and 37mm, at 1200mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers 25x10x0.50mm of required length with nuts & bolts of required size and other end of angle hanger fixed fully perforated Gypsum plaster board of size 1200x2400x12.5mm having approx 15% perforated area with perforation size and pattern as approved by the Engineer-in-charge and as per manufactures specification with all 4 side tapered and backed by acoustical tissue with NRC value not less than 0.60 including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	5.84	Per Square metre			
2	Providing and fixing roofing with high performance shingles manufactured with the finished A1-Zn alloy coated steel covered with italian ceramic coated stone granules having size of 1340x420mm (per piece) and th. of 0.25-0.55mm of approved manufactured including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	13.15	13.16			
3	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	20.00	Per Square metre			
4	Providing and fixing Wall peneling with 18 mm Hi- cem remco board including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	17.54	Per Square metre			

5	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron) including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	27.10	Per Kilogramme		
6	Providing and fixing aluminium work for doors, windows,board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer- in-charge. Pre-laminated particle board with decorative lamination on both sides, including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	3.75	Per Square metre		
7	Providing and fixing aluminium 250x16 mm. sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty, malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.00	Each		

8	Providing and fixing aluminium pull bolt lock ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws bolts, nut and washers etc. complete, including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, maikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	2.00	Each			
9	Providing and fixing aluminium 250x10 mm. tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, maikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.00	Each			
10	Providing and fixing 125mm aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, maikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	6.00	Each			
			Total:			0

NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018

3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

498

SCHEDULE OF QUANTITY

Name of work: C/O link road from harijan Basti to ward No 1 via Bhatti Sahib Panjwar Km 0/00 to 2/00 (SH:C/O R/wall at RD 0/725)- under SCDP

Estimated Cost 98559
Earnest Money 2000/-

Sl. No.	Description of work	Quantity	Unit	RATE IN		Amount
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	14.50	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 20mm (Twenty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.93	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)/dia PVC pipe extending through the full width of the structures with slope of 1(v):20(h)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709, 1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.	10.00	Each			
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.	3.12	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)/0212 dated 7.8.2018				Total:	0
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

5/8

SCHEDULE OF QUANTITY

Name of Work: Balance work for the construction of Playground under MMYKTY GSSS Nagnoli Distt.Una (HP) (SH: Foundation work painting work of fencing etc)									
Deposit work. (Phase-II)									
S. No.	Description of work	Quantity	Unit	Figures	Rates (in. Rs.)	Words	Amount (in. Rs.)	Estimated cost	97549
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of direction by the Engineer-in-charge. The rates are inclusive of lifts and other incidentals and as per the tax,GST,labour cess or other taxes imposed by the Government	12.47	Per cubic metre					Earnest money	2000.00
2	Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm) (forty millimeter nominal size) mechanically mixed and curing complete excluding within all leads and lifts and other incidentals and plinth in all heights / depths including entire carriage of material rates are inclusive of octroi, royalty,maikhana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government	10.35	Per cubic metre					Time limit	One month
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,maikhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	4.64	Per cubic metre						
4	Providing and laying for steel(TISCO, JINDAL PANTHER of (JSPL) /Sail/RINL/Shyam steel make) reinforcement for reinforced cement concrete work including ,bending binding,streightening and placing in position complete in all floor level/ heights including cost of binding wire complete and entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty,maikhana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	257.01	Per Kilogramme						

445

SCHEDULE OF QUANTITY

Estimated cost 99530
 Earnest money 2000
 Time limit One month

Name of Work: C/O Gramin Sampark to the house of Sh Ram Lal S/O Sh Tarsem Lal ward No2 GP Beetan (SH: C/o C.C Pavement RD 0/080 to 0/092)- Under MMSY

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm) forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.90	Per cubic metre			
2	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading - I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.90	Per cubic metre			

4089

3	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard concrete design mix of grade M-25 (M-twenty) cement contents not less than 400kg (four hundred kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty malakhana, toll tax, GST, labour cess or other taxes imposed by the Government.	11.92	Per cubic metre		
				G.Total	0
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW(B)/@17/20212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No PBW(B) A(3) 1/2020-1 dated 7.10.2021				


 Executive Engineer
 Haroli Division
 HP.PWD.,Haroli

429

37

Page - V

Schedule of quantity

Name of work :- A/R & M/D Non Building Rest house HPPWD at Haroli

S.NO	DESCRIPTION	Qty	Unit	T. Rate	Earnest Money:-		Estimated Cost: Rs
					Rate in words	One month 2000 Amount	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, Malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	23.37	cum				₹ 98,757
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkhana toll tax, sale tax or other taxes imposed by the Government.	7.79	cum				
3	Providing and Laying of Inter-locking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504. Including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, Malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	77.90	cum				
4	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 804, 1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, Malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	1.64	som				
Total							

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. H.P. vide letter No. P&W (R) 11712/20212 dated 07.08.2016

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

427

38

Schedule of quantity

Name of work :-A/R & M/O on link road to Shiv Mandir Village Polian Beet km 0/00 to 1/500						Estimated Cost: Rs	One month
(SH: C/O Retaining wall at RD. 0/382 to 0/394 RHS).						Time:-	Amount
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Earnest Money:- Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil upto 3 m depth, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	9.36	Cum.				
2	Providing & Laying Cement Concrete 1:4:8 (1Cement :4Sand :8Graded stone aggregate 40 mm nominal size) including cost of form work plain/reinforced concrete in retaining wall /Breast wall, as per Drawing and H.P P.W.D. technical Specification. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	27.81	Cum.				
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	18.00	each				
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	10.80	Cum.				
Total							

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018

M

Executive Engineer,
H.P.P.W.D Division Haroli
Distt. Una (H.P.)

505-

Schedule of quantity

Name of work :- A/R & M/O Panjagar Bathri road Km 0/00 to 34/00

(SH:- P/L Paver block at RD 33/621 to 33/641 - (Gurnam Mohalla)

		Estimated Cost: Rs		₹ 98,771	
		Time:-		One month	
		Earnest Money:-		2000	
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Amount
1	Loosening of the ground upto a level of 300 mm below the subgrade level, watered, graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per Technical Specification Clause 303.5.2. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	21.15	Cum.		
2	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.29	Cum.		
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.05	Cum.		
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	70.50	Sqm		
5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 804, 1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.82	Cum.		
Total					

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

499

SCHEDULE OF QUANTITY

Name of work:- Painting of ITI Pubowal building Tehsil Haroli Distt Una (SH: Painting work to old building)- Phase-III

Estimated Cost 99642
Earnest Money 2000/-

S. No.	Description of work	Quantity	Unit	RATE In		One month
				Figures	Words	
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	508.20	Per Square metre			
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	154.03	Per Square metre			
3	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacturer, including applying additional coats wherever required to achieve even shade and colour two coat including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	508.20	Per Square metre			
4	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacturer including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	140.82	Per Square metre			
5	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacturer including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	115.87	Per Square metre			
6	Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	350.20	Per Square metre			
	Total					0
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)/0172/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)/A(31)/2020 dated 22.07.20					

Executive Engineer
Haroli Divn. HP
Haroli

482

SCHEDULE OF QUANTITY

Name of work :Construction of link road Mehtab Singh village Nagnoli (SH: C/O C.C. pavement on approach road RD 0/034 to 0/058)-Deposit work

Estimated Cost 98496
Earnest Money 2000/-
Time limit One month

S. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	21.60	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	10.80	Per cubic metre			
3	Providing and laying (M-25) (M-twenty five) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	10.80	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)/6(17)/2/0212 dated 7.8.2018				Total:	0
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B)/A/31/2020 dated 22.07.20					

Executive Engineer
Haroli Division
HPPWD

447

Schedule of quantity

Name of work: A/R & M/O link road from Una Jaijon road to Gulaban da Toba Palkwah km.0/00 to 1/700.
(C/O Breast wall at Rd. 1/600 to 1/616 Rhs)

(C/O Breast wall at Rd. 1/600 to 1/616 Rhs)								Estimated Cost: Rs	₹ 99,658
								Time:-	One month
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:- Rate in words	2000 Amount			
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	25.00	cum						
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (CC 1:4:8). including carriage of materials within all leads and lifts and other incidental : The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	26.52	cum						
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	20.00	Each						
4	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 3 : 6 in foundation and plinth. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.68	Cum						
Total									
Note: All Type of material shall be arranged by the contractor vide Notification by Addressee.									

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

502

43

Schedule of quantity

Name of work:-A/R & M/O On link road to village Dharampur road km. 0/00 to 2/250 (SH: C/O U-Shape drain at RD. 0/112.40 to 0/143.60).					
Estimated Cost: Rs				₹ 98,553	
Time:-				One month	
Earnest Money:-				2000	
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Amount
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	35.10	CUM.		
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	21.06	CUM.		

3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(i) nominal mix 1:1.5:3. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	0.61	CUM.			
4	Supplying, fitting and placing TMT bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	0.11	Tonne			
	Total					

Note:1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

44

Phase-II

Schedule of quantity

Name of work:- C/O Model Health Research Centre at Haroli Tehsil Haroli Distt. Una .						Estimated Cost: Rs	₹ 92,150
(SH:- Providing and Fixing Mike System in Conference Hall)- Deposit work						Time:-	One month
						Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Providing and Supplying Mike System Ahuja Delegate unit including carriage of material within all lead and lifts and other incidental. The rate includes sale tax octroi,royalty,malkhana, toll tax, GST,labour cess or other taxes imposed bythe Government.	10.00	Each				
Total							
Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018							

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

369

DRAFT SCHEDULE OF QUANTITY

Name of work : A/R & M/O on link road to harijan basti Kuthar Beet Km 0/00 to 3/400 (SH: C/O C.C. pavement RD 0/555 to 0/571) Estimated Cost 98535
 Earnest Money 2000/-

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,maikhana ,toll tax,GST labour cess or other taxes imposed by the Government.	2.95	Per cubic metre			
2	Construction of Granular Sub Base by providing well graded material, spreading in uniform layers with tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC , and compacting with smooth wheel roller to achieve the desired density complete as per technical specification clause for grading 1 material including carriage of materials within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty,maikhana ,toll tax,GST labour cess or other taxes imposed by the Government.	8.36	Per Cubic metre			
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement four sand eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water/or ground complete including pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,maikhana ,toll tax,GST labour cess or other taxes imposed by the Government.	10.82	Per cubic metre			
4	Providing and laying (M-25) (M-twenty five) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete standard concrete design mix of with cement contents not less than 400Kg (four hundred kilogram) per cubic metre and curing and form work complete in all heights complete as required at site which may arise for all heights/ depths including the cost of form work with steel plates as per drawings and technical specification MORD 2014 Clause 800, 1205.4 and 1205.5 as per the direction of the Engineer-in-charge,including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,maikhana ,toll tax,GST labour cess or other taxes imposed by the Government.	9.82	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW(B)@1712/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
					Total:	0

Executive Engineer
 Haroli Division
 HPPWD

399

SCHEDULE OF QUANTITY

Name of work: C/O link road from harijan Basti to ward No 1 via Bhatti Sahib Panjwar Km 0/00 to 2/00 (SH:C/O R/wall at RD 0/716.50 to 0/725-Earnest Money 2000/-

Estimated Cost 99839

2000/-

Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms. lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	13.08	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement : four sand : eight graded crushed / broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax, octori, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.58	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709, 1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax, octori, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	9.00	Each			
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax, octori, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	6.22	Per cubic metre			
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)(A)(31/2020 dated 22.07.20					
					Total:	0

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

514

SCHEDULE OF QUANTITY

Name of Work: C/O Gramin Sampark to the house of Sh Ram Lal S/O Sh Tarsem Lal ward No2 GP Beetan (SH: C/o C.C Pavement RD 0/038 to 0/052)- Under MMSY

Estimated cost 99798
 Earnest money 2000
 Time limit One month

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Providing and laying cement concrete 1:4:8 (one cement: four sand eight graded crushed stone aggregate 40mm(forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government	7.96	Per cubic metre			
2	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.96	Per cubic metre			

UBB

3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations upto all heights for all type structure complete of plain with cement concrete standard concrete design mix of grade M-25 (M-twenty) cement contents not less than 400kg (four hundred kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malakhana, toll tax, GST, labour cess or other taxes imposed by the Government.	11.92	Per cubic metre			
					G.Total	0
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


 Executive Engineer
 Haroli Division
 HP.PWD., Haroli

486

Doctor Quid

SCHEDULE OF QUANTITY						
Sl. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
	Name of work :A/R & M/O on Una Rampur Haroli Palkwah Jaipon road Km 0/00 to 23/00 (SH: C/O police guard post near swan bridge at RD1/800-LHS)-Phase-I				Estimated Cost	99276
					Earnest Money	2000
					Time limit	one month
1	Providig and fixing Structural steel TAT A,SAIL,RINL, JINDAL PANTHAR,SHYAM work riveted, bolted or welded in builtup section, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of approved steel primer all complete in trusses and trussed purlins in building including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	789.45	Per Kilogramme			
2	Providing and fixing M.S.B.P sheet 1.6/6mm to 2mm(one point sixty six millimeter to two millimeter) thick in eaves board/facials/soffits/ceiling including cutting,fixing and welding to steel roof members and applying a coat of red lead primer complete as per instruction of Engineer-in-charge(Base members of steel work shall be measured & paid separately) including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana toll tax, GST labour cess or other taxes imposed by the Government.	12.46	Per square metre			
3	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S sheets and galvanised with zinc coating of 120 gms/ sqm (both side inclusive) as per IS: 277 and consisting of angle cleats of size 25mm wide x 1.6mm thick with flanges of 27mm and 37mm, at 1200mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers 25x10x50mm of required length with nuts & bolts of required size and other end of angle hanger fixed fully perforated Gypsum plaster board of size 1200x2400x12.5mm having approx 15% perforated area with perforation size and pattern as approved by the Engineer-in-charge and as per manufactures specification with all 4 side tapered and backed by acoustical tissue with NRC value not less than 0.60 including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana toll tax, sale tax, GST labour cess or other taxes imposed by the Government.	2.84	Per Square metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)6(17)/20212 dated 7.8.2018				Total	0
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy P.W to the Govt of HP vide letter No PBW(B) A(3)/1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					

497

Schedule of quantity

Name of work :- A/R & M/O on link road to Shiv Mandir Village Polian Beet km 0/00 to 1/500

(SH: C/O Retaining wall at RD: 0/370 to 0/382 RHS).

Name of work :- A/R & M/O on link road to Shiv Mandir Village Polian Beet km 0/00 to 1/500					Estimated Cost: Rs	One month
(SH: C/O Retaining wall at RD: 0/370 to 0/382 RHS).						
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:- Rate in words	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil upto 3 m depth. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	9.36	Cum.			
2	Providing & Laying Cement Concrete 1:4:8 (1 Cement :4Sand :8Graded stone aggregate 40 mm nominal size) including cost of form work plain/reinforced concrete in retaining wall /Breast wall, as per Drawing and H.P.P.W.D. technical Specification including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	27.81	Cum.			
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	17.00	each			
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	10.80	Cum.			
Total						

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

506

50

Schedule of quantity

Name of work :- A/R & M/O Panjavar Bathri road Km 0/00 to 34/00						Estimated Cost: Rs	₹ 99,612
(SH:- P/L Paver block at RD 33/600 to 33/621- (Gurnam Mohalla)						Time:-	One month
DESCRIPTION						Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	21.33	Cum.				
2	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.33	Cum.				
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.11	Cum.				
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	71.10	Sqm				
5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 804, 1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.84	Cum.				
Total							

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) (17) 2/02012 dated 07.08.2018

501

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

51

Schedule of quantity						Estimated Cost: Rs	₹ 73,480
.Name of work- A/R & M/O HPPWD Non-Residential building at HPPWD Rest House Haroli and Sub Division office building Haroli HPPWD (SH: Providing and Installation of water purifier Water Dispensor and Water Dispensor Jar)						Time:-	One month
						Earnest Money:-	1400
S.NO	DESCRIPTION OF ITEM	Qty	unit	T.Rate	Rate in words	Amount	
1	Providing and installation of 7 (Seven) Litre Storage capacity Aqua guard water purifier 3 -in-1 Active Copper and water saving Technology make by eureka forves with one year warranty complete with all accessories. The rates are inclime octroi royalty, Makana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	2 00	Each				
2	Providing and installation of Voltas Water Dispensor with Hot and Cold, Normal water supply features with one year warranty with all accessories. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government	2 00	Each				
3	Providing and instalmlion of 8 (eight) litre water dispensor Jar with autocut system with one year warranty with II accessories. The retes are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government:	2 00	Each				
	Total						0
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)/A(3)/2020 dated 22.07.20						


 Executive Engineer
 Haroli Division
 HPPWD

516

SCHEDULE OF QUANTITY

Estimated cost 99820
Earnest money 2000
Time limit One month

Name of work: A/R & M/O on link road Laluwal to Dulehar Km 0/00 to 2/00 (SH: C/O toilet block at RD 1/970)- Phase-I						
S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Demolishing brick work manually/ mechanically means including stacking of serviceable material and disposal of unserviceable material including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	10.91	Per cubic metre			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	6.68	Per cubic metre			
3	Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm(forty millimeter nominal size) mechanically mixed and curing complete including cost of form work in foundation and plinth in all heights / depths including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.98	Per cubic metre			

4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) with cement contents not less than 250kg(Two hundred fifty kilogram) per cubic metre in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	8.24	Per cubic metre			
5	Providing and laying damp proof course 38mm (thirty eight millimeter)thick with cement concrete 1:2:4 (One cement:two sand:four graded crushed stone aggregate 12.5mm (twelve point five millimeter) nominal size) and curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax ,GST,labour cess or other taxes imposed by the Government.	8.60	Per square metre			
6	Applying a coat of hot bitumen (mexphalt 80/100(eighty/hundred) or equivalent using 1.70 kg. (one point seventy kilogramme)per square meter on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	8.60	Per square metre			
7	Half brick masonry with common burnt clay building bricks in cement mortar 1:4(One cement :four sand) in superstructure in all floor level/height curing complete and including entire carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge .The rate includes octroi, royalty,malkhana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	30.32	Per square metre			

8	Brick work with common burnt clay F.P.S. (Non modular) bricks of class designation 7.5 in superstructure upto all floor level /height in all shapes and size cement mortar 1:6(one cement: six sand) including curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge . The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax GST ,labour cess or other taxes imposed by the Government.	2.68	Per cubic metre	6830.00	Rupees thousand hundred only	six eight thirty	18304
9	15mm (fifteen millimetre) cement plaster in single coat on rough/ fair side of brick/concrete/stone walls for interior plastering in all floor level/any height including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm(eighty millimetre) in girth and finished even and smooth in cement mortar 1:6 (one cement : six sand) including curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge . The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	36.36	Per square metre	190.00	Rupees hundred only	one ninety	6908
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				G.Total		25212
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						



Executive Engineer

Haroli Division

HP.PWD.,Haroli

53

Schedule of quantity

Name of work :-A/R & M/O on link road to Shiv Mandir Village Polian Beet km 0/00 to 1/500 (SH: C/O Retaining wall at RD. 0/419.50 to 0/429 RHS).								Estimated Cost: Rs	₹ 99,506
								Time:-	One month
								Earnest Money:-	2000/-
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount			
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil Upto 3 m depth, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.27	Cum.						
2	Providing & Laying Cement Concrete 1:4:8 (1Cement :4Sand :8Graded stone aggregate 40 mm nominal size) including cost of form work plain/reinforced concrete in retaining wall /Breast wall, as per Drawing and H.P.P.W.D. technical Specification, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	28.45	Cum.						
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	15.00	each						
4	Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.70	Cum.						
	Total								

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

5728

54

Schedule of quantity

Name of work:-A/R & M/O On link road to village Dharampur road km. 0/00 to 2/250					Estimated Cost: Rs	₹ 99,724
(SH: C/O U-Shape drain at RD. 0/268.40 to 0/299.60).					Time:-	One month
					Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material, including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	35.10	CUM.			
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	21.06	CUM.			

510

3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(i) nominal mix 1:1.5:3. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	0.66	CUM.		
4	Supplying, fitting and placing TMT bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	0.12	Tonne		
	Total				

Note:1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

 Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

55

Schedule of quantity

Name of work: A/R & M/O link road from Una Jaijon road to Gulabani da Toba 0.000 to 1.700.					
(C/O Breast wall at Rd. 1/632 to 1/644 Rhs)					
Palkhuk					
Estimated Cost: Rs				₹ 99,238	
Time:-				One month	
Earnest Money:-					
S.NO	DESCRIPTION	Qty	Unit	T.Rate	1000 Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	18.75	cum		
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (CC 1:4:8). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	19.89	cum		
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	12.00	Each		
4	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203 P.C.C grade M 10 Nominal Mix 1 : 3 : 6 in foundation and plinth. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	4.75	Cum		
5	Providing and laying reinforced cement concrete pipe NP2 for culvert on first class bedding of granular material in SINGLE row including fixing collar with cement mortar but excluding excavation, protection work in head walls and parapets clause 1108. Hume pipe 600 mm diameter, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	5.00	Metre		
Total					

Note: All Type of material shall be arranged by the contractor.

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018

56

SCHEDULE OF QUANTITY									
				</					

WFO

7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level as the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	70.8	kg				
	The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No.PBW(B)/A(3)/1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B)/A(3)/1/2020-1 dated 7.10.2021					Total	0


 Executive Engineer
 Haroli Divn.HP.PWD.,
 Haroli

490

SCHEDULE OF QUANTITY

57

Estimated cost 99765
Earnest money 2000
Time limit One month

Name of work: A/R & M/O on link road Laluwal to Dulehar Km 0/00 to 2/00 (SH: C/O toilet block at RD 1/970)- (phase-II)

SCHEDULE OF WORK / ITEM(S)					
S.No	Description of Work / Item(s)	Qty	Unit	RATE In	
				Figures	Words
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	11.12	Per cubic metre		
2	Filling in plinth with sand under floor including watering ramming consolidating and dressing complete for all heights including entire carriage of material and disposal all surplus excavated/bored out earth within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.62	Per cubic metre		
3	Providing and laying cement concrete 1:4:8 (one cement: four sand: eight graded crushed stone aggregate 40mm/ forty millimeter nominal size) mechanically mixed and curing complete excluding cost of form work in all work upto plinth level and breast wall including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1.88	Per cubic metre		
4	Providing form work with steel plates 3.15mm(three decimal fifteen millimeter) thick welded with angle iron in frame of 30x30x5 mm (thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering strutting and propping etcetera with wooden battens and ballies for all heights of propping and centering below supporting floor to ceiling not exceeding 4 meter and removal of same for in-situ reinforced concrete and plain concrete work in flat surfaces such as soffits of suspended floors roofs landings and the like floors in all thickness in all floor level including carriage of material entire within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	5.84	Per square metre		
5	Providing form work with steel plates 3.15mm(three decimal fifteen millimeter) thick welded with angle iron in frame of 30x30x5mm(thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering strutting and propping etcetera with wooden battens and ballies for all heights of propping and centering below supporting floor to ceiling not exceeding 4 meter and removal of the same for in-situ reinforced concrete and plain concrete work in beams cantilevers girders and lintels side and soffit of beams, beam haunchings, cantilevers, bressumers and lintels in any depth / heights /thickness upto all floor level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	5.96	Per square metre		

6	Providing form work with steel plates 3.15mm(three decimal fifteen millimetre) thick welded with angle iron in frame of 30x30x5mm(thirty into thirty into five millimetre) size so as to give fair finish including centering ,shuttering ,strutting and propping etcetera with wooden battens and ballies for all heights of propping and centering below supporting floor to ceiling not exceeding 4 meter and removal of the same for in-situ reinforced concrete and plain concrete work.- in edges of slabs and breaks in floors and walls etcetera upto any width /height complete upto all floor level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	13.82	Per Running metre			
7	Providing and laying reinforcement cement concrete work of grade M-25(M-Twenty five)design mix to obtain the minimum crushing strength of 25 N/mm2 (twenty five Newton per millimeter square) with minimum cement content of 400 kg (Four hundred kilogramme) per cubic meter mechanically mixed and vibrated including curing complete excluding cost of form work and reinforced concrete work in foundation,footing bases of columns and the like and mass concrete in all depth/heights including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.36	Per cubic metre			
8	Providing and laying mild steel medium tensile steel bars for steel (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make) reinforcement for reinforced cement concrete work including ,bending binding, straightening and placing in position complete in all floor level/ heights including cost of binding wire complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	219.60	Per Kilogramme			
9	Providing and laying damp proof course 38mm (thirty eight millimeter)thick with cement concrete 1:2:4 (One cement:two sand:four graded crushed stone aggregate 12.5mm (twelve point five millimeter)nominal size) and curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	3.97	Per square metre			
10	Applying a coat of hot bitumen (mexphalt 80/100(eighty/hundred) or equivalent using 1.70 kg. (one point seventy kilogramme)per square meter on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	3.62	Per square metre			
11	Brick work with common burnt clay F.P.S.(Non modular) bricks of class designation 7.5 in foundation and plinth in cement mortar 1:6(one cement: six sand) including curing complete in any depth/height including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.22	Per cubic metre			
12	Brick work with common burnt clay F.P.S.(Non modular) bricks of class designation 7.5 in superstructure above plinth level upto all floor level /height in all shapes and size cement mortar 1:6(one cement: six sand) including curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	5.32	Per cubic metre			
13	6mm (six millimetre) thick cement plaster in ceiling concrete or reinforced cement concrete work with cement mortar 1:3(one cement: three sand) and curing complete as per direction of Engineer-in-charge complete upto all floor level/any height .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	10.38	Per square metre			

14	15mm (fifteen millimetre) cement plaster in single coat on rough side of brick/concrete/stone walls for interior plastering in all floor level/any height including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm(eighty millimetre) in girth and finished even and smooth in cement mortar 1:6 (one cement : six sand) including curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	14.54	Per square metre		
15	12mm (twelve millimetre) cement plaster in single coat on fair side of brick/concrete/stone walls for interior plastering in all floor level/any height including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm(eighty millimetre) in girth and finished even and smooth in cement mortar 1:6 (one cement : six sand) including curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.68	Per square metre		
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW(B)/A(3)1/2020 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No PBW(B) A(3) 1/2020-1 dated 7.10.2021				Total	0



Executive Engineer
Haroli Division
HP, PWD, Haroli