

**Himachal Pradesh
Public Works Department**

No. PWP/Agr. Asstt./Tender/2024-25/ 19593-19612

Dated/ 28/2/2025

To

✓ The Executive Engineer (IT Cell),
Nirman Bhawan Nigam Vihar Shimla-2.
Himachal Pradesh Shimla -2.

Subject:- Publication of Tender Notice.

Enclosed please find herewith the Tender notice of works as given in the Notice inviting Tenders alongwith Schedule of quantities for uploading on departmental website as per Notification Secretary (PW) to the Govt. of HP letter No. PBW(B) A (3) 1/2024 dated Shimla -03.01.2024

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in public interest.

DA/ Stated as above

Executive Engineer
Palampur Division
HPPWD Palampur

Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

- 1 The Superintending Engineer 5th Circle, HP.PWD Palampur.
2. The drawing branch in this office.
- 3 All Assistant Engineer working under this Division
4. Notice Board.

Executive Engineer
Palampur Division
HPPWD Palampur

Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P. for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before 07.03.2025 up to 11.00 AM. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 06.03.2025 up to 4.00 P.M and the application for issue of tender form shall be received 05.03.2025 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	C/o Darati to Bharthadi Bridge (SH:- Providing and laying CC Pavement at RD 0/190 to 0/222 (MMGSY)	Rs. 99,408.00	Rs. 2,000.00	Three Months
2	C/o link road from Hanglow to Bhandoru Basti in GP Lahla Km 0/00 to 1/00 (SH:- Providing and laying G-II, CC Pavement at RD 0/000 to 0/022 (MNP)	Rs 98,472.00	Rs 2,000.00	Three Months
3	C/o link road from Spedu to Goarth Km 0/00 to 2/500 (SW:- Providing and laying CC pavement at RD 0/900 to 0/928 (MNP)	Rs. 98,244.00	Rs. 2,000.00	Three Months
4	C/o link road from Spedu to Goarth Km 0/00 to 2/500 (SW:- Providing and laying CC pavement at RD 1/110 to 1/137.50 (MNP)	Rs. 96,462.00	Rs. 2,000.00	Three Months
5	C/o Tanda Pantehar Band Vihar Molichak Dharaman Kandwari road Km 0/000 to 10/000(SW:- Providing and laying CC Pavement on side berm at RD 4/393 to 4/510 (OFC Deposit)	Rs. 99,540.00	Rs. 2,000.00	Three Months
6	C/o Tanda Pantehar Band Vihar Molichak Dharaman Kandwari road Km 0/000 to 10/000(SW:- Providing and laying CC Pavement on side berm at RD 4/251 to 4/383 (OFC Deposit)	Rs. 99,792.00	Rs. 2,000.00	Three Months
7	C/o Pucca Path from Sh. Kuldeep land towards Sh. Ravi Kumar House in Ward No. 2 G.P Chandropa (HP) (SW:- C/o Edge wall & P/L Interlocking Pavement in Foot Path (Deposit)	Rs. 98,508.00	Rs. 2,000.00	Three Months
8	Jeepable road from main road towards Sh. Kamaljeet & others house in Ward No. 5 GP Chandropa (HP) (SW:- Providing and laying Interlocking Concrete Block Pavement (Length= 27 mtrs) (Deposit)	Rs. 96,774.00	Rs. 2,000.00	Three Months
9	Dharamshala Yol Dadh Palampur road Km 27/00 to 33/00 (SW:- Painting steel work on various roads, Kilometer stones & Re-lettering of boards at various RDs) (MNP)	Rs. 98,648.00	Rs. 2,000.00	Three Months
10	Dharamshala Yol Dadh Palampur road Km 27/00 to 33/00 (SW:- Painting of Rain Shelter at Menjha Chowk (RD 27/500), Chimbahar (RD 29/450), SSB Chowk (RD 30/700) & Re-lettering of various boards (MNP)	Rs. 97,595.00	Rs. 2,000.00	Three Months
11	C/o link road Banuri to Bharmat Km 0/00 to 1/00 (SW:- Providing and laying Interlocking Concrete Block & 1:4:8 in Km 0/550 to 0/573.90 (OFC Deposit)	Rs. 99,542.00	Rs. 2,000.00	Two Months
12	C/o link road Banuri to Bharmat Km 0/00 to 1/00 (SW:- Providing and laying Interlocking Concrete Block & 1:4:8 in Km 0/574.90 to 0/598.75 (OFC Deposit)	Rs. 99,306.00	Rs. 2,000.00	Two Months
13	C/o link road from Ghar to Inner Dattal & Ghar to	Rs. 99,253.00	Rs. 2000.00	Two Months

14	C/o link road from Ghar to Upper Dattal & Ghar to Ropa Km 0/00 to 4/800 (SH:- Formation and cutting at RD 2/155 to 2/320) (MNP)	Rs. 99,000.00	Rs. 2,000.00	Two Months
15	Restoration of Rain damages on Parour Lahla Gopalpur Rakh Ghamrota Jyun Sukeri Bandla road Km 19/00 to 29/00 (SW:- Hiring of Breaker for breaking of stone) (RD)	Rs. 98,000.00	Rs. 2,000.00	Two Months
16	C/o link road from GMS Dharot to Harizan Basti via Hari Ram House in G.P. Lahla Km 0/00 to 1/500 (SW:- Hiring of JCB for tracking/ cutting road portion in KM 0/750 to 1/00) (MNP)	Rs. 98,900.00	Rs. 2,000.00	Two Months
17	C/o link road from GMS Dharot to Harizan Basti via Hari Ram House in G.P Lahla Km 0/00 to 1/500 (SH:- Providing and laying CC Pavement at RD 0/577 to 0/609) (MNP)	Rs. 98,982.00	Rs. 2,000.00	Two Months
18	C/o road Darti to Bharthadi Bridge (SH:- Providing and laying CC Pavement at RD 0/155 to 0/190) (MNP)	Rs. 99,225.00	Rs. 2,000.00	Two Months
19	C/o CHC at Gopalpur (SH:- Painting work of Doors & Windows of CHC Building) (Deposit)	Rs. 98,958.00	Rs. 1,300.00	Two Months
20	C/o link road to Angaria Basti KM 0/00 to 0/500 (SW:- C/o U-shape drain, gratiang work, and providing and laying CC Pavement at RD 0/00 to 0/013)	Rs. 99,126.00	Rs. 2,000.00	Three Months
21	C/o link road to Gujjar Basti Lamlehar KM 0/00 to 0/500 (SW:- C/o R/Wall and F.C from RD 0/00 to 0/400) (MMGSY)	Rs. 98,523.00	Rs. 2,000.00	Three Months
22	C/o road and Pulli from main road towards house of Verma & others (SH:- C/o B/Wall from RD 0/030 to 0/033.75b & C/o u-Shape drain from RD 0/000 to 0/050) (MMGSY)	Rs. 99,866.00	Rs. 2,000.00	Three Months
23	C/o road and Pulli from main road towards house of Verma & others (SH:- C/o R/Wall from RD 0/065 to 0/068.35) (MMGSY)	Rs. 99,603.00	Rs. 2,000.00	Three Months
24	C/o link road from Tanda Pantehar to Patial Basti Km 0/000 to 0/900 (SW:- P/L Cement Concrete Paver Block at RD 0/028 to 0/052)	Rs. 99,544.00	Rs. 2,000.00	Three Months
25	C/o link road from Tanda Pantehar to Patial Basti Km 0/000 to 0/900 (SW:- P/L Cement Concrete Paver Block at RD 0/00 to 0/024)	Rs. 98,727.00	Rs. 2,000.00	Three Months
26	Minor repair work of Type-I Quarter at HP.PWD Colonyb Holta (Quarter No. 65 & 66) (SW:- P/F cement board in ceiling, 15 MM cement plaster, wire gauge shutter, P/L tile flooring & painting work etc)	Rs. 98,076.00	Rs. 2,000.00	Three Months
27	Minor repair work of Judicial Court Complex at Palampur Distt. Kangra (HP) (SW:- Providing and fixing cupboard, Almirah, Renovation of toilet and tile flooring of JMFC & Additional Distt. Session Judge rooms)	Rs. 99,684.00	Rs. 2,000.00	Three Months
28	Restoration of rain damages on Bundla Ghuggar Thakurdwara road at RD 1/400 (SH:- Providing and fixing double Shank Pavement marker Cat eyes at Zebra crossing at various RDs)	Rs. 98,750.00	Rs. 2,000.00	One Month
29	Restoration of rain damages on Dharamshala Yol Dadh Holta Chadiyar Sandhole road at RD 34/300 (SH:- Providing and fixing double Shank Pavement marker Cat eyes at Zebra crossing at various RDs)	Rs. 98,750.00	Rs. 2,000.00	One Month

amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years

8. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand . Next tender will be issued only after completion of previous works in hand.

Executive Engineer
Palampur Division
HPWD Palampur

Work :- C/O Darati to Bharhadi Bridge
S. H. :- P/L CC Pavement at RD 0/190 to 0/222 (MMGSY)

Schedule of Quantity

Work No. ①
Estimated Cost : Rs. 99,408/-
Earnest Money : 2000/-
Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	3.00	Cubic metres			Per Cubic metre.	
2	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement: Two sand: four crushed stone aggregate) Nominal mix , P.C.C. grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802;803,1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	14.64	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Name of Work :- C/O link road from Hanglow to Bhandoru Basti in GP Lahla Km 0/000 to 1/000
(S. H. :- P/L G-II, CC Pavement at RD 0/000 to 0/022 (MNP)

Work No. 2

Estimated Cost : Rs. 98,472/-
Earnest Money : 2000/-
Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words				
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Km. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	6.60	Cubic metres			Per Cubic metre.	
2	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement: Two sand: four crushed stone aggregate) Nominal mix, P.C.C. grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802,803,1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	13.20	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

ame of Work :- C/O link road from Speru to Goarth Km. 0/000 to 2/500
(S. W. :- P/L CC Pavement at RD 0/900 to 0/928 (MNP)

Schedule of Quantity

Work No. ③

Estimated Cost : Rs. 98,244-
Earnest Money : 2000/-
Time limit : Three Months

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Km. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	6.62	Cubic metres		Per Cubic metre.	
2	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix .P.C.C. grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802.803, 1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	13.23	Cubic metre		Per Cubic metre	
					Total :-	

Executive Engineer
Palampur Division
HP, PWD Palampur

Name of Work :- C/O link road from Speru to Goarth Km. 0/000 to 2/500
(S. W. :- P/L CC Pavement at RD 1/110 to 1/137.50(MNP))

Schedule of Quantity

Work No. 4
Estimated Cost : Rs. 96,462-
Earnest Money : 2000/-

Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five milimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	6.50	Cubic metres			Per Cubic metre.	
2	Providing Concrete for plain/reinforced concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix, P.C.C. grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802, 803, 1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	12.99	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
HP, PWD Palampur

Name of Work : - C/O Tanda Panthar band vhar Molichak Dharman Kandwari road Km. 0/000 to 10/000
(S. W. :- P/L CC Pavement on side berms at RD 4/393 to 4/510 (OFC Deposit))

Schedule of Quantity

Estimated Cost : Rs. 99,540-
Earnest Money : 2000/-

Work No. (5)

Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement: Two sand: four crushed stone aggregate) Nominal mix, P.C.C. grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802, 803, 1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	15.80	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Work :- C/O Tanda Panthar band vihar Molichak Dharman Kandwari road Km. 0/000 to 10/000
W. :- P/L CC Pavement on side berms at RD 4/251 to 4/383 (OFC Deposit)

Schedule of Quantity

Work No. 6
Estimated Cost : Rs. 99,792-
Earnest Money : 2000/-

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing Concrete for plain/reinforced concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix .P.C.C.grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802.803.1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	15.84			Per Cubic metre	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

of Work :- C/O Pucca Path from Sh. Kuldeep Land towards Sh. Ravi Kumar house in Ward No.2, G.P. Chandropa (H.P.)

Estimated Cost : Rs. 98,508/-
Earnest Money : 2000/-
Time limit : Three Months

Work No. (7)

S. W. :- C/O Edge wall & P/L interlocking pavement in Foot Path (Deposit)

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Earth work in excavation in all kinds of soil by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. in Ordinary rock with in all leads, lifts and other incidental as per the Direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	2.25	Cubic metre			Per Cubic metre	
2	Providing and Laying concrete for plain/reinforced concrete in open foundations 1:5:10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete including the cost of form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; within all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	3.38	Cubic metre			Per Cubic metre	
3	Providing and Laying Concrete 1:4:8 (One Cement : Four Sand : Eight crushed stone aggregate) 40 mm. Nominal size for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate including octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the government.	4.50	Cubic metres			Per Cubic metre.	
4	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge includingcarriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	45.00	Square Metre			Per square metre	
5	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix.P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203, includingthe cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.95	Cubic metres			Per Cubic metre.	
	Total :-						

Executive Engineer
Palampur Division
HP, PWD Palampur

Schedule of Quantity

Name of Work :- Jeepable road from main road towards Sh. Kamaljeet & others house in Ward No.5, G.P. Chandropa (H.P.)
(S. W. :- P/L interlocking Conc. Block pavement (length= 27 metres) (Deposit)

Work No. **(8)**

Estimated Cost : Rs. 96,774/-
Earnest Money : 2000/-

Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Providing and Laying Concrete 1:4:8 (One Cement : Four Sand : Eight crushed stone aggregate) 40 mm. Nominal size for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the government.	5.40	Cubic metres			Per Cubic metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge includingcarriage of materials within all leads and lift and other incidentals.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	54.00	Square Metre			Per square metre	
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203. includingthe cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.62	Cubic metres			Per Cubic metre.	
						Total :-	

Executive Engineer
Palampur Division
HP,PWD Palampur

Schedule of Quantity

Name of Work :- D/Shala Yol Dadh Palampur road 27/000 to 33/000
(S. W. :- Painting Steel Work on various Boards, kilometre stones & Re-lettering of boards at various RD's (MNP)

Work No. 9
Estimated Cost : Rs. 98,648/-
Earnest Money : 2000/-

Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 lit/ 10 sqm over an under coat of primer applied @ 0.80 lit/ 10 sqm of approved brand and manufacture. (Make:- Asian Paint). The rate including of octroi, royalty, malkana, toll tax, Sale tax or other taxes imposed by the government.	55.01	Square metre			Per Square metre	
2	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	12.80	Square metres			Per Square metre	
3	Re-lettering with black Japan paint of approved brand and manufacture. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	50000.00	per letter per cm			per letter per cm	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work : - D/Shala Yol Dadh Palampur road 27/000 to 33/000

(S. W. :- Painting of rain shelter at Menjha Chowk (RD 27/500), Chimbahar (RD 29/450), SSB Chowk (RD 30/700) & Re-lettering of various boards (MNP)

Estimated Cost : Rs. 97,595/-

Earnest Money : 2000/-

Time limit : Three Months

Work No. 10

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	20.32			Per Square metres	
2	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives, New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	203.20			Per Square metre	
3	Re-lettering with black Japan paint of approved brand and manufacture. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	40000.00			per letter per cm	
					Total :-	

Executive Engineer
Palampur Division
HP, PWD Palampur

(N)

SCHEDULE OF QUANTITY

Name of work:- C/o Link road Banuri to Bharnat Km 0/00 to 1/00. (SH:- P/L Interlocking concrete block & 1:4:8 in Km 0/550 to 0/573.90). **OFC Deposit**

Name of work:- C/o Link road Banuri to Bharmat Km 0/00 to 1/00. (SH.- P/L Interlocking concrete block & 1:4:8 in Km 0/550 to 0/573.90). OFC Deposit							Estimated cost Rs.	99542.00		
Sr. No.							Quantity	Earnest Money Rs.		2000.00
								Time Limits		Two Months
Description of Item							Rate	Unit	Amount	
In Figures										In Word
1	Providing and laying cement concrete 1:4:8 (One Cement : Four Sand : Eight crushed stone aggregate) 40 mm (forty millimetre) nominal size for plain/ reinforced concrete in open foundations complete including the cost of form work and as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.						1.08	Per cubic metre.		
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.						71.70	Per square metre		
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.						0.48	Per cubic metre.		
Total										

Executive Engineer,
Palampur Division
HP PWD Palampur.

[Signature]

SCHEDULE OF QUANTITY

Name of work:- C/o Link road Banuri to Bharnat Km 0/00 to 1/00. (SH:- P/L Interlocking concrete block & 1:4:8 in Km 0/574.90 to 0/ 598.75) **OFC Deposit**

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying cement concrete 1:4:8 (One Cement : Four Sand : Eight crushed stone aggregate) 40 mm (forty millimetre) nominal size for plain/ reinforced concrete in open foundations complete including the cost of form work and as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1.07			Per cubic metre.	
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	71.55			Per square metre	
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.48			Per cubic metre.	
Total						

Executive Engineer
Palampur Division
HP PWD Palampur
24

13

SCHEDULE OF QUANTITY

Name of work:- C/o Link road from Ghar to Upper Dattal & Ghar to Ropa Km 0/00 to 4/800. (SH:- Formation and cutting at Rd 2/00 to 2/150). MNP

Name of work :- C/O Link road from Uhar to Upper Dattal & Ghar to Ropa Km 0/00 to 4/800. (SH:- Formation and cutting at Rd 2/00 to 2/150). MNP							99253.00
Estimated cost Rs.							
Earnest Money Rs.							2000.00
Time Limits							Two Month
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	620.33			Per cubic metre.		
	Total						

Executive Engineer,
Palampur Division
HP, PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Link road from Ghar to Upper Dattal & Ghar to Ropa Km 0/00 to 4/800. (SH:- Formation and cutting at Rd 2/155 to 2/320). **MNP**

Name of work:- C/o Link road from Ghar to Upper Dattal & Ghar to Ropa Km 0/00 to 4/800. (SH:- Formation and cutting at Rd 2/155 to 2/320). MNP						Estimated cost Rs.	99000.00
						Earnest Money Rs.	2000.00
						Time Limits	Two Month
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	618.75			Per cubic metre.		
	Total						

Executive Engineer,
Palampur Division
HP PWD Palampur

DRAFT SCHEDULE OF QUANTITY

DRAFT SCHEDULE OF QUANTITIES						
Name of work:- Restoration of Rain Damages on Parour Lahla Gopalpur Rakh Ghamrota Jyun Sukeri Bandla road Km 19/00 to 29/00. (SH:- Hiring of Breaker for breaking of stone).						
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
			1	Hiring of JCB (Breaker) including P.O.L charges shifting charges and other anciliary equipments as per required at site of work for breaking of rocks. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damages to the properties of the people or in case any damage took place, the contractor is liable for it. The work shall have to be carried out as per ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	49.00	
						98000.00
						2000.00
						Two Months

Executive Engineer,
Palampur Division
HP.PWD Palampur.

52

Estimated cost Rs.	98900.00
--------------------	----------

Earnest Money R.	2000.00
------------------	---------

Sr. No.	Description of item	Quantity	Time Limits		Two Months Amount
			In Figures	In Word	
1	Hiring of JCB (Excavator-Cum-Loader) including P.O.L. charges shifting charges and other ancillary equipments as per required at site of work for removal of slips. The disposal of this un-serviceable material has to be done in the required width of the road to avoid damages to the properties of the people or in case any damage mtook place, the contractor is liable for it. The work shall have to be carried out as per ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	86.00			
				Total	

Executive Engineer,
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Link road from GMS Dharot to Harizan Basti Via Hari Ram House in G.P. Lahla Km 0/00 to 1/500. (SH:- Providing and Laying C.C. Pavement at Rd 0/577 to 0/609). MNP

Estimated cost Rs.	98982.00
Earnest Money Rs.	2000.00
Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.00			Per cubic metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	14.64			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP PWD Palampur

18

SCHEDULE OF QUANTITY

Name of work:- C/o road Darai to Bharthadi Bridge (SH:- Providing and Laying C.C. Pavement at Rd 0/155 to 0/190). MMSY

Name of work:- C/o road Darau to Bhabhadi Bridge, (SH-2) Providing and Laying C.C. Pavement at Rd 0/155 to 0/190), MMISY						Estimated cost Rs.	99225.00
						Earnest Money Rs.	7000.00
Sr No	Description of Item	Quantity	Rate		Unit	Two Months Amount	
			In Figures	In Word			
1	Providing and laying concrete for plain reinforced Cement concrete 1:2:4 (One Cement Two Sand four crushed stone aggregate) Nominal Mix, P C C grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all bearings/lifts and other incidental. The rate is including octon, royalty, Malkana, toll tax, GST) or other taxes imposed by the Government time to time.	15.75			Per cubic metre		
	Total						


 Executive Engineer
 Palampur Division
 IIP PWD Palampur
 25

SCHEDULE OF QUANTITY

Name of work:- C/o CHC at Gopalpur. (SH:- Painting work of Doors & windows of CHC Building). **Deposit**

SCHEDULE OF QUANTITY						
Name of work:- C/o CHC at Gopalpur. (SH:- Painting work of Doors & windows of CHC Building). Deposit						
Sr. No.	Description of Item	Quantity	Estimated cost Rs.		Unit	Amount
			Earnest Money Rs.			
			In Figures	In Word		
3	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	790.00			Per kilogram	2000.00
2	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	161.32			Per square metre	
2	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	104.51			Per square metre	
Total						

Executive Engineer
Palampur Division
HP PWD Palampur

name of Work :- C/O link road to Angaria Basti Km. 0/000 to 0/500
Schedule of Quantity
(S. W. :- C/O U-shape drain, Grating work & P/L CC Pavement at Rd 0/00 to 0/013

Work No. 20
Estimated Cost :- Rs. 99,120/-
Earnest Money :- Rs. 2000/-

Time limit : Three Months

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. 3.13 grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	Cubic metre			Per Cubic metre	
2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of materials within all leads lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	Kilogram			Per Kilogram	
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203, including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	Cubic metres			Per Cubic metre.	
Total :-						

Executive Engineer
Palampur Division
HP, PWD Palampur

Schedule of Quantity

Name of Work :- C/O link road to Gujar Basti Lamlehar Km. 0/000 to 0/500
(S. W. :- C/O R/Wall & F.C. from RD 0/000 to 0/400 (MMGSY)

Estimated Cost : Rs. 98,523/-
Earnest Money : 2000/-
Time limit : Three Months

Work No. 21

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Excavation in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.2 including carriage of materials with in all leads, lifts and other incidental.	320.75			Per Cubic metre.	
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	4.08			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	10.10			Per Cubic metre	
4	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (V) : .20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the government.	3.00			Each	
5	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.	3.62			Per Cubic metre	
	Total :-					

Executive Engineer
Palampur Division
HP, PWD Palampur

Name of Work :- C/O road & Pulli from main road towards house of Verma & others
(S. W. :- C/O B/Wall from RD 0/030 to 0/033.75 & C/O U-Shape drain from RD 0/000 to 0/050 (MMGSY)

Work No. 22
Estimated Cost :- Rs. 99,866/-
Earnest Money :- Rs.2000/-

Schedule of Quantity

Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the Government..	21.71	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	38.31	Cubic metre		Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	18.40	Cubic metre		Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	12.00	Nos.		Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	7.44	Cubic metre		Per Cubic metre	
	Total :-					

Executive Engineer
 Palampur Division
 HP.PWD Palampur

Schedule of Quantity

Estimated Cost :- Rs. 99,544/-
Earnest Money :- Rs. 2000/-

Time limit : Three Months

Name of Work :- C/O link road from Tanda Panthar to Patial Basti Km. 0/000 to 0/900

(S. W. :- P/L Cement concrete Paver Block at RD 0/028 to 0/052

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the intersices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the government.	0.56	Cubic metres			Per Cubic metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge includingcarriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	74.40	Square Metre			Per square metre	
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix.P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203, includingthe cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.48	Cubic metres			Per Cubic metre.	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work :- C/O link road from Tanda Panthar to Patal Basti Km. 0/000 to 0/900
(S. W. :- P/L Cement concrete Paver Block at RD 0/000 to 0/024)

Estimated Cost :- Rs. 98,727/-
Earnest Money :- Rs. 2000/-

Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 K.n. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the government.	0.55	Cubic metres			Per Cubic metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm. as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	73.78	Square Metre			Per square metre	
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203, including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.48	Cubic metres			Per Cubic metre.	
	Total :-						

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of quantity

Work :- Minor repair work of Type-1 quarter at HPPWD colony Holta (quarter No. 65 & 66)
 10 Work :- P/F Cement board in ceiling, 15 mm. cement plaster, wire gauge shutter, P/L tile flooring & painting work etc.

Estimate Cost :- Rs. 98,076/-
 Earnest Money :- Rs. 2000/-

Time Limit :- Three Months

S. No	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In Words		Ruppes
1	Providing and fixing plain multipurpose cement board(Hight pressure steam cured) 6 mm thick Cement bonded wood particle board as per IS:14276 with suitable screws for cement particle board in ceiling etc. complete (frame work to be paid seperately) with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	14.30	Square metre			Per cubic metre	
2	Providing and fixing fly proof galvanized M.S. wire gauge to windows and clerestory windows & doors with M.S. Flat 15x3 mm and nuts & bolts complete using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm all complete with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the	2.40	Square metre			Per Square metre	
3	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement: 6 fine sand) with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.	50.10	Square metre			Per Square metre	
4	Removing dry oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	159.24	Square metres			Per Square metre	
5	Providing and applying white cement based putty of average thickness 1 mm (one millimetre), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	159.24	Square metre			Per Square metre	
6	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	159.24	Square metre			Per Square metre	
7	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	159.24	Square metres			Per Square metre	
8	Applying priming coats with ready mixed pink or grey primer on wood work (hard and soft wood) having VOC content less than 50 grams/ litre (fifty grammes per litre) of approved brand and manufacture, with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	16.78	Square metre			Per Square metre	
9	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm (zero point ninety litre per ten square metre)over an under coat of primer applied @0.75 ltr/10 sqm (zero point seventy five litre per ten square metre) of approved brand and manufacture with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	148.76	Square metre			Per Square metre	

finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications.					
Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two ornore coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture including carriage of materials with in all leads, lifts and other incidental. The rate include octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.					
11	Providing and laying in position cement concrete 1:2:4 (one Cement :two coarse sand : four graded stone aggregate 20 mm nominal size) excluding the cost of centering and shuttering - All work up to plinth level with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	1.06	Cubic metre		Per Square metre
12	Dismantling tile work for thickness of tiles 10 mm to 25 mm in floors and roofs laid in cement mortar including stacking material within 50 metres lead. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	14.76	Square metre		Per Square metre
13	Providing and laying vitrified floor tiles Size of Tile 600x600mm (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20 mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	3.36	Square metre		Per Square metre
14	Providing and fixing 15mm (Fifteen millimetre) nominal bore CP brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 690 gms.. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	2.00	Nos.		Each
15	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms (six hundred ninety grammes) 15 mm (fifteen Millimetres) nominal bore, as per the entire satisfaction and direction of Engineer-in-charge. The rate includes octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	5.00	Nos.		Each
16	Providing and fixing C.P. Brass extension nipple (size 15mmx50mm) of approved make and quality as per direction of Engineer-in-charge. The rate including of octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the Government	10.00	Nos.		Each
17	Providing and fixing PTMT grating of approved quality and colour. Circular type, 100 mm nominal dia. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.	4.00	Nos.		Each
18	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete. 15 mm nominal bore. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.	2.00	Nos.		Each
19	Providing and fixing high pressure PVC spigot and socket soil, waste and ventilating pipes ISI Marked i/c fixing with approved adhesive etc. Complete. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.				
	75 mm. (Seventy five millimetre) dia	5.00	Rmt		Per Running metre

Per Running metre	
Total	

Executive Engineer
Palampur Division
H.P.PWD Palampur

Schedule of quantity

Name of Work :- Minor repair work of Judicial Court Complex at Palampur Distt. Kangra (H.P.)

Sub Work :- Providing and fixing Cupboard/Almirah , Renovation of toilet & tile flooring of JMFC & Additional Distt. Session Judge Rooms

Estimate Cost :- Rs. 99,684/-
Earnest Money :- Rs. 2000/-
Time Limit :- Three Months

27

S. No	Description of Item	Quantity		In figure	Rate In Words	Unit	Amount Rupees
1	Providing and fixing cup board shutters with 25 mm thick veneered particle board IS : 3097 marked, exterior grade ((Grade I), of approved make, including IInd class teak wood lipping of 25 mm wide x 12 mm thick with necessary screws and bright finished stainless steel piano hinges, complete as per direction of Engineer-in-charge with non decorative veneering on both sides including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	12.16	Square metre			Per cubic metre	
2	Providing & Fixing decorative high pressure laminated sheet of plain / wood grain in gloss / matt/ suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S, including cost of adhesive of approved quality: 1.0 mm thick including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana,Tol tax, GST or any other taxes imposed by the Government.	6.42	Square metre			Per cubic metre	
3	Providing and fixing 125 mm. (one hundred twenty five millimetre) bright /matt finished Stainless Steel handles of approved quality & make with necessary screws etc all complete. The rate includes octroi, royalty, Malkana,Tol tax, GST or any other taxes imposed by the Government.	11.00	Nos.			Each	
4	Providing and fixing bright finished brass 100 mm mortice latch and lock, ISI marked, with six levers and a pair of anodised (anodic coating not less than grade AC 10 as per IS : 1868) aluminium lever handles of approved quality with necessary screws etc. complete. The rate includes octroi, royalty, Malkana,Tol tax, GST or any other taxes imposed by the Government.	2.00	Nos.			Each	
5	Providing and fixing magnetic catcher of approved quality in cupboard / ward robe shutters, including fixing with necessary screws etc. complete. Triple strip vertical type.The rate includes octroi, royalty, Malkana,Tol tax, GST or any other taxes imposed by the Government.	10.00	Nos.			Each	
6	Providing and fixing 600x450 mm.beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete. The rate includes octroi, royalty, Malkana,Tol tax, GST or any other taxes imposed by the Government.	2.00	Nos.			Each	
7	Providing and fixing White Vitreous China pedestal type water closet (European Type) with seat and lid,10 litre low level white vitrous china flushing cistern & C.P. flush bend with fittings & C.I. brackets,40 mm flush bend,overflow arrangement with specials of standard make and mosquito proof coupling of approved Municipal design complete,including painting of fittings and brackets,cutting and making good the walls and floors wherever required :W.C. pan with ISI marked white solid plastic seat and lid including carriage of materials all leads, lifts and other incidental. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	1.00	Nos.			Each	

8	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. 15 mm nominal outer dia Pipes including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	6.00	Running metre		Running metre	
9	Providing and fixing uplasticised PVC connection pipe with brass unions : 30cm length 15 mm nominal bore. The rate including of octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the Government	1.00	Nos.		Each	
10	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 : 15 mm nominal bore. The rate including of octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the Government	3.00	Nos.		Each	
11	Providing and fixing C.P. Brass extension nipple (size 15mmx50mm) of approved make and quality as per direction of Engineer-in-charge. The rate including of octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the Government	3.00	Nos.		Each	
12	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931, 15 mm nominal bore. The rate including of octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the Government	1.00	Nos.		Each	
13	Providing and fixing PTMT Towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour. 450 mm long towel rail with total length of 495 mm, 78 mm wide and effective height of 88 mm, weighing not less than 170 gms. The rate including of octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the Government	1.00	Nos.		Each	
14	Providing and fixing PTMT towel ring trapezoidal shape 215 mm long, 200 mm wide with minimum distances of 37 mm from wall face with concealed fittings arrangement of approved quality and colour, weighing not less than 88 gms. The rate including of octroi, royalty, Malkana, tolltax, GST or other taxes imposed by the Government.	3.00	Nos.		Each	
15	Providing and fixing high pressure PVC spigot and socket soil, waste and ventilating pipes ISI Marked i/c fixing with approved adhesive etc. Complete. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.					
(i)	75 mm. (Seventy five millimetre) Dia	4.00	Running metre		Per Running	
(ii)	100 mm. (One hundred millimetre) Dia	4.00	Running metre		Per Running metre	
16	Providing and fixing PTMT grating of approved quality and colour. Circular type, 100 mm nominal dia. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.	1.00	Nos.		Each	

17	Providing and laying vitrified floor tiles Size of Tile 600x600mm (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20 mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	27.43	Square metre		Per Square metre
18	Providing and laying Vitrified tiles Size of Tile 600x600 mm (thickness to be specified by manufacturer), with water absorption 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	15.41	Square metre		Each
					Total

Executive Engineer
Palampur Division
H.P.PWD Palampur

Draft Schedule of Quantity

Name of Work :- Restoration of rain damages on Bundla Guggar Thakurdwara road at RD. 1/400

Estimated Cost : Rs. 98,750/-
Earnest Money : Rs. 2000/-
Time limit : One Month.

Sub Work :- Providing and Fixing Double Shank pavement marker Cat Eyes at Zebra Crossing & various RDs Km.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing and Fixing pavement marker(cat Eyes)Made out of ABS 3M /Every or equivalent plastic of size 100x90x20mm (One hundred into Ninety into twenty millimetre) having high intensity 30 degree micro cube corner spark glow reflector White/Red/ yellow double shank Heavy duty without nails having 50 mm stem of ABS . The pavement marker shall be installed with suitable epoxy ABS including carriage of material and equipment in all leads and lifts with all mode of transportation and as per the direction of Engineer-in- charge.	250.00 Nos.			Each.	

Executive Engineer
Palampur Division
HP PWD Palampur

Draft Schedule of Quantity

Name of Work :- Restoration of rain damages on Dharamshala Vol Dadh Holta Chadiar Sandhole road at RD 34/300

Estimated Cost : Rs. 98,750/-
Earnest Money : Rs. 2000/-

Sub Work :- Providing and Fixing Double Shank pavement marker Cat Eyes at Zebra Crossing & various RDs Km.

Time limit : One Month.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing and Fixing pavement marker(cat Eyes)Made out of ABS 3M /Every or equivalent plastic of size 100x90x20mm (One hundred into Ninety into twenty millimetre) having high intensity 30 degree micro cube corner spark glow reflector White/Red/ yellow double shank Heavy duty without nails having 50 mm stem of ABS . The pavement marker shall be installed with suitable epoxy ABS including carriage.of material and equipment in all leads and lifts with all mode of transportation and as per the direction of Engineer-in-charge.	250.00 Nos.			Each.	

Executive Engineer
Palampur Division
HP PWD Palampur