Office of
Executive Engineer B&R Division HP.PWD. Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 03.05.2025 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 01.05.2025 up to 10.00 A.M. to 12:00 P.M. and tender form can be had from this office on 02.05.2025 from 2.00 P.M. to 5.00 Pm. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Repair and maintenance of Khudi to Basahi (SIDL:VKV/2015/959 deposit Rs. 1.75 lacs (SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc.).	Rs. 93,980/-	Rs. 2,00/-	Rs. 350/	Class "D"	One month
2	Restoration of rain damages on link road to house of Sahid Baldev Singh Km. 0/0 to 1/500 (SH:- Construction of retaining wall Km. 0/075 to 0/078 under deposit SID: NDF/2019/857).	Rs. 51,266/-	Rs. 1,000/-	Rs. 350/	Class "D"	One month
3	Construction of cement concrete road H/B Balhi 0/0 to 0/1000 Km. under MGNREGA (SH:- Supplying and stacking of crushed/broken stone aggregate 20mm and sand).	Rs. 90,518/-	Rs. 1,800/	Rs. 350/	Class "D"	Two months
4	C/O A/R M/O Dalana to Barto road Km. 0/0 to 1/499. under MGNREGA (SH:- Supplying and stacking of crushed/broken stone aggregate 20mm and sand).	Rs. 54,110/-	Rs. 1,100/	Rs. 350/	Class "D"	Two months
5	C/O A/R M/O Dalana to Loan road Km. 0/0 to 1/500. under MGNREGA (SH:- Supplying and stacking of crushed/broken stone aggregate 20mm and sand).	Rs. 53,900/-	Rs. 1,100/	Rs. 350/	Class "D"	Two months
6	Restoration of rain damages on Kundni Kas road Km. 0/0 to 3/765 (SH:- Construction of retaining wall at RD. 2/005 to 2/008.50).	Rs. 95,811/-	Rs. 1,900/-	Rs. 350/	Class "D"	Two months
7	Restoration of rain damages on Kundni Kas road Km. 0/0 to 3/765 (SH:- Construction of retaining wall at RD. 2/009 to 2/012.50).	Rs. 95,666/-	Rs. 1,900/-	Rs. 350/	Class "D"	Two months

Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-I/NIT/Press/2024-25- 989-1038 Dated:- 23/04/2025

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Notice Board.
9. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder

Job-1

Schedule of Quantity

Estimated Cost:- 93980.00
Earnest Money:- 2000.00
Time:- One month

Name of work:- Repair and Maintanance of Khuidi to Basahi (SIDL:VKV/2015/959 deposit Rs. 1.75 lacs
Sub Head:-Hiring of excavator cum loader for removal of slips,dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic Excavator having capacity of 1.00 (one point zero) cubic meter loader capacity for removal of slips,dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc. i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out bt the contractor/owner at his own risk,shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge.The rate is inclusive of all taxes including GST levy by the Govt. time to time.	74.00			Per working hours	
				Total:-		

Executive Engineer,
B&R Division HP.PWD,
Joginder Nagar

Job-2 E No. 365

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on link road to house of Sahid Baldev Singh Km. 0/0 to 1/500 (Sh:- Construction of retaining wall km.0/075 to 0/078 under Deposit SID: NDF/2019/857)				Estimate Cost:		51,266
				Earnest Money:		1,000
				Time Limit :		One Mon
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	Rs. P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Enginer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	3.00	Per cubic metre			
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty milimeters) nominal size) plums and curing complete including the cost of form work in **Retaining walls Breast walls,** in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	9.51	Per cubic metre			

3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentials.The rate is inclusive all taxes levy by the government time to time excluding GST.	2.16	Per cubic metre			
4	Providing **weep holes** in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of I (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	4.00	Each			
	Total					

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Schedule of Quantity Job-3

Estimated Cost:- Rs. 90518.00
Earnest Money:- Rs. 1800.00
Time:- TWO MONTH

Name of Work : C/o Cement Concrete Road H/B Balhi 0/0 to 0/1000 km MGNREGA
(Sub Head:- Suppling and stacking of Crushed/broken stone Agreegate, 20 mm and sand)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free form dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive aii texes levy by the goverment time to time including GST.	60.75			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive aii texes levy by the goverment time to time including GST.	31.73			Per cubic metre	
				Total:-		

Executive Engineer
B&R Division HP,PWD
Jogindar Nagar

Job - 4

Schedule of Quantity

Estimated Cost:- 54110.00
Earnest Money:- 1100.00
Time:- Two month

Name of work : C/O A/R M/O Dalana to Barto road KM 0/0 to 1/499 under **MGNREGA.**
Sub Head: Supplying and stacking of crushed/broken stone agg. 20mm and Sand)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twentey millimeter) nominal size free form dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The Rat is inclusive all texes levy by the government time to time including GST.	7.49			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect.he Rat is inclusive all texes levy by the government time to time including GST	15.68			Per cubic metre	
				Total:-		

Executive Engineer,
B&R Division HP. PWD.,
Joginder Nagar

Job-5

Schedule of Quantity

Estimated Cost:- 53900.00
Earnest Money:- 1100.00
Time:- Two month

Name of work : C/O A/R M/O Dalana to Loan road KM 0/0 to 1/500 under **MGNREGA.**
Sub Head: Supplying and stacking of crushed/broken stone agg. 20mm and Sand)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twentey millimeter) nominal size free form dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The Rat is inclusive all texes levy by the government time to time including GST.	7.46			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect.he Rat is inclusive all texes levy by the government time to time including GST	15.62			Per cubic metre	
				Total:-		

Executive Engineer,
B&R Division HP. PWD.,
Joginder Nagar

Job-6 EN0.477

(2)

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Kundni Kas road km.0/0 to 3/765 (Sub Head:-Construction of retaining wall at RD 2/005 to 2/008.50)				Estimate Cost: Earnest Money: Time Limit :		Two Mon
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	Rs. P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Enginer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	4.73	Per cubic metre			
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty milimeters) nominal size) plums and curing complete including the cost of form work in **Retaining walls Breast walls,** in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	18.10	Per cubic metre			
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentials.The rate is inclusive all taxes levy by the government time to time excluding GST.	5.99	Per cubic metre			

4	Providing **weep holes** in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of I (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	6.00	Each			
	Total					

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job-7 EN0.478

(3)

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Kundni Kas road km.0/0 to 3/765 (Sub Head:-Construction of retaining wall at RD 2/009 to 2/012.50)				Estimate Cost: Earnest Money: Time Limit :		Two Mon
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	Rs. P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Enginer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	4.72	Per cubic metre			
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty milimeters) nominal size) plums and curing complete including the cost of form work in **Retaining walls Breast walls,** in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	18.10	Per cubic metre			
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentials.The rate is inclusive all taxes levy by the government time to time excluding GST.	5.84	Per cubic metre			

4	Providing **weep holes** in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of I (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	6.00	Each			
	Total					

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar