

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Sealed item/ percentage rate tender of form NO. 6&8 are hereby invited by the Executive Engineer, Bilaspur Division No. I, HP.PWD., Bilaspur on behalf of Governor of Himachal Pradesh from the approved and eligible contractors enlisted in PWD Department so as to reach in this office on or before **28/05/2025** up to 10.30 A.M. and will be opened on the same day at 11.00 A.M. in the presence of the intending contractors or their authorized representatives who may like to be present. If it happens to be holiday on that day tenders will be opened on next working day. The application for obtaining the tender forms will be received up to **26/05/2025** up to 5.00 PM and the tender form can be had from this office on **27/05/2025** during the office hours.

The Earnest money in the shape of National Saving Certificate Time deposit Accounts/FDR of any Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, Division No. I, HP.PWD., Bilaspur must be accompanied with each application for obtaining the tenders. The tender application received without earnest money /cost of tender forms will similarly be rejected. The undersigned reserves the right to reject the tenders without assigning any reason.

Sr. No	Name of work	Estimated cost (In Rs.)	Earnest Money (In Rs.)	Cost of form (In Rs.)	Time limit
1	A/R & M/O residential quarters in Changer Sector Distt. Bilaspur. (SH:- P/f cup board, white washing E-2 T/S, P/F curtain rod E-5 & E-6 and PVC water tank at quarter No. F-29 S/S & G-60 D/S).	95,311	2000	350	Two months
2	A/R & M/O on rain shelter at Village Jamthal on Salaper to Jamthal road at 4/940 (Valley side). (SH:- Construction of balance work of rain shelter at Jamthal P/L tile/flooring and CC work 1:2:4 etc.).	86,288	2000	350	One month
3	Construction of Solag Jurassi road Km. 0/0 to 4/900. (SH:- C/o wire crate R/wall at RD. 1/822 to 1/932.50).	98,747	2000	350	One month
4	Construction of Solag Jurassi road Km. 0/0 to 4/900. (SH:- C/o wire crate R/wall at RD. 1/810 to 1/820.50).	98,458	2000	350	One month
5	Restoration of rain damages on Chandigarh Mandi Manali road Km. 127/00 to 156/750. (SH:- C/o B/wall at RD. 144/015 to 144/020).	80,848	2000	350	One month
6.	Improvement of Bhager Dehar road from Toll Plaza Baloh. (SH:- Providing and laying 900mm dia NP2 hume pipe, C/o toe and curtain wall etc. at RD. 11/765).	93,937	2000	350	One month
7.	Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/615. (SH:- C/o R/wall at RD. 15/930 to 15/935.50).	93,244	2000	350	One month
8.	Restoration of rain damages on Galu Jole Rohin road Km. 0/00 to 5/500. (SH:- C/o B/wall at RD. 4/270 to 4/276).	95,183	2000	350	One month

	Provision for Disabled Frindly toilet Distt. Court Complex Bilaspur Distt. Bilaspur. (SH:- Renovation of toilet at ground floor old complex and construction of toilet at ground floor new court complex at Bilaspur (Job No.1).	99,758	2000	350	One month
10.	Provision for Disabled Frindly toilet Distt. Court Complex Bilaspur Distt. Bilaspur. (SH:- Renovation of toilet at ground floor old complex and construction of toilet at ground floor new court complex at Bilaspur (Job No.II).	80,150	2000	350	One month
11.	Provision for Disabled Frindly toilet Distt. Court Complex Bilaspur Distt. Bilaspur. (SH:- Renovation of toilet at ground floor old complex and construction of toilet at ground floor new court complex at Bilaspur (Job NO.III).	89,548	2000	350	One month
12.	A/R & M/O Indoor Auditorium for Culture Programme at Bilaspur (H.P.). (SH:- P/L water proofing treatment on water storage tank).	51,556	2000	350	One month
13.	Restoration of rain damages on various roads under Sub-Divison Kuthera. (SH:- C/o unlined drain and dressing of berms).	99,996	2000	350	One month

1. Certified that the tenders for above said works are being called of emergent nature in exigency of public interest.

TERMS & CONDITIONS: -

1. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
2. The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactorily including adherence to quality future work will be awarded to him. All undertaking that he is not having more than two works in hand must be recorded in the application, failing which application of such contractor shall be rejected without any notice to him.
3. Earnest money should be accompanied with application. Application without earnest money will not be entertained.
4. The photo copy of Pan Number/renewal should be attached with the application otherwise tender form will not be issued.

NO.PW-BLP-I-CB-EA-I-Tender/ 2025- 2864-28

Executive Engineer,
Bilaspur, Division No.I
HP.PWD, Bilaspur.
Dated :- 16/5/25

Copy forwarded to the following for information please.

1. The Engineer-in-Chief, HP.PWD; Shimla-I.
2. The Chief Engineer (HZ) HP.PWD, Hamirpur.
3. The Superintending Engineer, 10th Circle, HP.PWD, Bilaspur.
4. The Executive Engineer (IT) O/o the Engineer-in-Chief, HP.PWD, Shimla through email:- cc-pwd-hp@nic.in alongwith copies of Schedule of quantities for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. All the contractors as per record of this office.
7. Accounts Branch/ Drawing Branch/Supdt. in this office.
8. Notice Board.

Executive Engineer,
Bilaspur, Division No.I,
HP.PWD, Bilaspur.

Tab No 1

Draft Schedule of quantity

Estimated cost Rs. 95,3113/-only						
Earnest Money Rs. 2,000/- only.						
Time Limit. = Two months						
Name of work:- A/R & M/O residential Qtrs in Changer Sector Distt. Bilaspur. (SH:- P/F cup board, white washing E-2 T/S, P/F curtain rod 5 & E-6 and PVC water tank at Qtrs No. F-29 S/S & G-60 D/S).						
No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	2	3	5	6	7	8
1	Removing dry oil bound distemper, water proofing cement paint and like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	272.31			Per Square Metre	
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	27.23			Per Square Metre	
3	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: One or more coats on old work including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	272.31			Per Square Metre	
4	Painting one coat(excluding priming coat)on previously painted wood and wood based surfaces with enamel paint brushing to given even shade including cleaning of all dirt,dust and other foreign matter sand papering and stopping including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	48.98			Per Square Metre	

5	Providing and fixing 16.75mm (Sixteen point seventy five millimetre) thick HDMR board plain , pre-laminated board (decorative lamination on one side and other balancing lamination board flat pressed, 3 layer or graded medium density grade-1 . including carriage of materials in all leads and lifts as directed by the Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.45			Per Square Metre
6	Providing and fixing 150mm (One hundred fifty millimetre) bright finished SS handles with screws etc. complete. as per HP.PWD Specification clause 12. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00			Each
7	Providing and fixing magnetic catcher of approved quality & make with necessary screw etc all complete, including carriage of materials in all leads and lifts as directed by the Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.00			Each
8	Providing and fixing chromium plated brass curtain rod having wall thickness of 1.25mm with two chromium plated brass brackets fixed with C.P. brass screws and PVC sleeves etc., wherever necessary complete : 25 mm dia including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	40.80			Per Running Metre
9	Providing and fixing rectangular high density polyethylene water storage loft tank with cover, conforming to ISI : 12701, colour of opaque white or as approved by Engineer-in-charge. The rate includes making necessary holes for inlet, outlet & over flow pipes. The base support i/c fittings & fixtures for tank shall be paid separately. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1500.00			Per Litre

0	Providing and fixing PTMT Ball cock of approved quality colour and make complete with epoxy coated aluminium rod with LP/HPHD plastic ball with in all leads and lifts as directed by the Engineer-in-Charge. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Per Square Metre	
11	Providing and fixing brass full way valve with wheel ISI marked including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax. Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Each	
TOTAL						


 Executive Engineer,
 Bilaspur Division No 1
 HP, PWD, Bilaspur.

Job No 2

Draft Schedule of quantity

Estimated cost Rs. 86,288/-only					
Earnest Money Rs. 2,000/- only.					
Time Limit. = One month					
Name of work: - A/R & M/O on rain shelter at village Jamthal on Sallaper to Jamthal road at 4/940 (Valley side). (SH:- Construction of ence work of rain shelter at Jamthal P/L tile / flooring and C.C work 1:2:4 etc.).					
Description of items.	Qty.	Rates		Unit	Amount
		In Figure	In Word		
2 Providing and fixing 10mm (Ten millimeter) thick anti skid water proof stain and impert resistant heavy duty vetrified tiles Nitco or equivalent 600x600mmx10mm (Six hundre into Six hundred into ten millimeter) manufactured of approved shade and colour in flooring, treads of 1.3 (One cement, Three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge as per HP PWD Specification clause 13 & 4.4.1. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	32.49	5	6	7 Per Square Meter	8
Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:2:4 (One cement : Two coarse sand) : Four graded stone aggregate 20 mm (Twenty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.47			Per Cubic Meter	
Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar work. including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	135.43			Per Kilogramme	
TOTAL					


 Executive Engineer,
 Bilaspur Division No 1
 HP, PWD Bilaspur.

Job No 3

DRAFT SCHEDULE OF QUANTITY.				Estimated cost Rs. = 98,747/-only		
				Earnest Money Rs. = 2000/- only.		
				Time Limit. = One Month		
Name of Work:- Construction of Solag Jurassoi road Km. 0/0 to 4/900. (SH:- C/O wire crate R/wall at RD. 1/822 to 1/832.50).						
Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	2	10.71	Per Cubic metre	5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centemere) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (TenPer Square Metre) on plan) including getting out and disposal of excavated earth lead upto 50 m (Fifty metre) and lift upto 1.5 m, (One point five metre) as directed by Engineer-in-charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other constnuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
2	Providing & making Gabion structure with Mechanically Woven Double Twisted Hexagonal Shaped Wire mesh Gabion Boxes as per IS 16014:2012,MORTH Clause 2500, of required size, Mesh Type 10x12 (Ten into twelve) (D=100 mm (One hundred milimetre) with tolerance of ± 2% (Two percent) Zinc coated. Mesh wire diameter 3.0 mm (Three milimetre) mechanically edged/selvedged with partitions at every 1m interval and shall have minimum 10 (Ten)umbers of openings per meter of mesh perpendicular to twist, tying with lacing wire of diameter 2.2mm. (Two point two milimetre) supplied @ 3% (Three percent) by weight of Gabion boxes, filled with boulders with least dimension of 200 mm, (Two hundred milimetre) as per drawing, all complete as per direction of Engineer-in-charge.. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax. Goods Service Tax, building and other constnuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.24	Per Cubic metre			
TOTAL						

Executive Engineer,
Bilaspur Division No 1
HP,PWD Bilaspur.

Job No 4

DRAFT SCHEDULE OF QUANTITY.				Estimated cost Rs. = 98,458/-only Earnest Money Rs. = 2000/- only. Time Limit. = One Month		
e of Work:- Construction of Solag Jurassoi road Km. 0/0 to 4/900. (SH:- C/O wire crate R/wall at RD. 1/810 to 1/820.50).						
No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centemere) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (TenPer Square Metre) on plan) including getting out and disposal of excavated earth lead upto 50 m (Fifty metre) and lift upto 1.5 m, (One point five metre) as directed by Engineer-in-charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other constreuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.45	Per Cubic metre	5	6	8
	Providing & making Gabion structure with Mechanically Woven Double Twisted Hexagonal Shaped Wire mesh Gabion Boxes as per IS 16014:2012,MORTH Clause 2500, of required size, Mesh Type 10x12 (Ten into twelve) (D=100 mm (One hundred milimetre) with tolerance of ± 2% (Two percent) Zinc coated, Mesh wire diameter 3.0 mm (Three milimetre) mechanically edged/selvedged with partitions at every 1m interval and shall have minimum 10 (Ten) umber of openings per meter of mesh perpendicular to twist, tying with lacing wire of diameter 2.2mm, (Two point two milimetre) supplied @ 3% (Three percent) by weight of Gabion boxes, filled with boulders with least dimension of 200 mm, (Two hundred milimetre) as per drawing, all complete as per direction of Engineer-in-charge.. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other constreuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.24	Per Cubic metre			
TOTAL						

Executive Engineer,
Bilaspur Division No 1
HP, PWD Bilaspur.

Job No 5

DRAFT SCHEDULE OF QUANTITY.

DRAFT SCHEDULE OF QUANTITY.						Estimated cost Rs. = 80,848/-only
						Earnest Money Rs. = 2000/- only.
						Time Limit. = One Month
Name of work:- Restoration of rian damages on Chandigarh Mandi Manali road Km. 127/00 to 156/750. (SH):- C/O B/Wall at Rd. 144/015 to 44/020).						
Sr No	Description of items.	Qty.	Rates		Amount	
			In Figure	In words		
		3	4	5	6	8
1	2	10.65	Per Cubic metre			
1	Earth work in excavation by mechanical means (Hydraulic excavator/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (TenPer Square Metre) on plan) including getting out and disposal of excavated earth lead upto 50 m (Fifty metre) and lift upto 1.5 m, (One point five metre) as directed by Engineer-in-charge including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same					
2	Centering and shuttering including strutting, propping etc and removal of form work for Foundations, footings, bases for columns including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.81	Per Square Metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	15.09	Per Cubic metre			
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v) 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	10.00	Nos.			
					TOTAL	



Executive Engineer,
Bilaspur Division No 1
HP, PWD Bilaspur.

Job No 6

DRAFT SCHEDULE OF QUANTITY.					Estimated cost Rs. = 93,937/-only	
					Earnest Money Rs. = 2000/- only.	
					Time Limit. = One Month	
Name of work:- Improvement of Bhager Dehar road from Toll Plaza Baloh. (SH:- Providing and laying 900mm diad NP 2 hume pipe, C/O toe & main wall etc. at RD. 11/765).						
No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
	2	88.88	Per Cubic metre	5	6	8
	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centemere) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (TenPer Square Metre) on plan) including getting out and disposal of excavated earth lead upto 50 m (Fifty metre) and lift upto 1.5 m. (One point five metre) as directed by Engineer-in-charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other consctruction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
2	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One Cement: two Sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 (1) 900mm dia (Nine hundred millimetres) dia including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other consctruction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.50	Running Meter			
3	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other consctruction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.46	Per Square Metre			

4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size). including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.68	Per Cubic metre			
		TOTAL				


 Executive Engineer,
 Bilaspur Division No 1
 HP, PWD Bilaspur.

Job No 7


DRAFT SCHEDULE OF QUANTITY.				Estimated cost Rs. = 93,244/-only Earnest Money Rs. = 2,000/- only. Time Limit. = One Month			
Name of Work:- Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/615. (SH:- C/O R/Wall at RD. 15/930 to 15/935.50).							
Sr No	Description of items.	Qty.		Rates		Amount	
		3	4	In Figure	In words		
1	2 Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.45	Per Cubic metre	5	6	8	
2	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.48	Per Square Metre				
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty milimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.32	Per Cubic metre				
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.00	Each				

5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.29	Per Cubic metre		
TOTAL					


 Executive Engineer,
 Bilaspur Division No 1
 HP, PWD Bilaspur.

Job No 8

DRAFT SCHEDULE OF QUANTITY.		Estimated cost Rs. = 95,183/-only Earnest Money Rs. = 2,000/- only. Time Limit. = One Month			
Name of Work:- Restoration of rain damages on Galu Jole Rohin road Km. 0/00 to 5/500. (SH:- C/O R/Wall at RD. 4/270 to 4/276).					
Sr No	Description of items.	Qty.	Rates		Amount
			In Figure	In words	
1	2	3	4	5	6
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan). including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.12	Per Cubic metre	5	8
2	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.90	Per Square Metre		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.90	Per Cubic metre		
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.00	Each		
		TOTAL			


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Job No 9

Draft Schedule of Quantity							Estimated cost Rs. = 99,758/- only
							Earnest Money Rs. = 2,000/- only
							Time = One Month.
Name of work:- Provision for Disabled Friendly toilet Distt. Court Complex Bilaspur Distt. Bilaspur. (SH:- Renovation of toilet at ground floor old complex and Construction of toilet at ground floor new court complex at Bilaspur) Job No. I.							
Sr No.	Description of items.	Qty.	Rate	Unit	Amount		
			In Figure	In words			
1	2	3	4	5	6	7	
1	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 (fifty) metres lead as per direction of Engineer-in-charge. In cement mortar. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.70			Per Cubic Metre		
2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50m (Fifty metres) lead as per direction of Engineer - in - charge Nominal concrete 1:3:6 (One:Three:Six) or richer mix (i/c equivalent design mix). including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.36			Per Cubic Metre		
3	Providing and fixing 10mm (Ten millimeter) thick anti skid water proof stain and impet resistant heavy duty vetrified tiles Nitco or equivalent 600x600mmx10mm (Six hundre into Six hundred into ten millimeter) manufactured of approved shade and colour in flooring, treads of 1:3 (One cement : Three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.44			Per Square Meter		

4	8mm thick tile work in skirting, risers of steps and dado up to 2 m height over 12 mm thick bed of cement mortar 1:3 (1 cement :3 coarse sand) and jointed with grey cement slurry @ 3.3 kg/sqm, including pointing in white cement mixed with pigment of matching shade complete. 8 mm (Eight millimetre) thick, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	23.33			Per Square Metre	
5	Providing and fixing G.I pipe 15 mm dia (fifteen milimetre) complete with G.I fittings and clamps, including cutting and making good the walls etc. internal work. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.00			Per Runing Metre	
6	Providing and fixing vitreous china wash down water closet of cera / hindware No. 3149 camelia with integral P or S trap etc. complete in all respect. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Each	
7	Providing and fixing vitreous China wash basin with single hole for pillar tap with C.I. or M.S. brackets painted white including cutting holes and making good the same but excluding fittings:- 630mmx450mm (Six hundred thirty into four hundred fifty millimeter) Cera of Jaquar perryware in white shade. Flat Back. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Each	

8	Providing and fixing vitreous China bowl pattern urinal including connection the urinal with waste pipe by means of white lead mixed with chopped hemp (waste pipe to be measured and paid for separately. Flat back type of size 430mm x 260x 350 mm (Four hundred thirty into two hundred sixty into three hundred fifty millimetre). including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Nos	
12	Providing and fixing uplasticised PVC connection pipe with brass unions : 30 cm length 15 mm nominal bore. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00			Each	
10	Providing and fixing C.P. brass waste for wash basin or sink : ALD- 705 Waste coupling 32mm Size Full Thread with 80mm height. Parryware / Cera / Hindware / Neycer / Sanitarware. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00			Each	
11	Providing and fixing 32mm (Thirty two millimetre) dia PVC D-plast FINOLEX waste pipe for wash basin or sink of superior quality approved by bureau of Indian Standard. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Each	
12	Providing and fixing PVC floor trap D-plast or equivalent make approved by the Bureau of Indian Standard of self cleaning design including fixing with approved adhesive etc. complete . including cost of cutting making good in the walls and floors complete . 110x90 mm (One hundred ten into ninety millimetre). including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00			Each	

13	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes FINOLEX including fixing with approved adhesive etc. Complete. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
13.1	110 mm (one hundred ten millimetre) diameter .	20.00			Per Running Metre	
13.2	75 mm (Seventy five millimetre) diameter .	20.00			Per Running Metre	
14	Providing and fixing PVC door bend with oval access door, insertion rubber washer 3mm thick bolts and nuts ISI marked complete including fixing with approved adhesive etc. complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
14.1	110 mm (one hundred ten millimetre) diameter .	3.00			Each	
14.2	75 mm (Seventy five millimetre) diameter .	3.00			Each	
		TOTAL				


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Job No/0


Draft Schedule of Quantity							Estimated cost Rs. = 80,150/- only
							Earnest Money Rs. = 2,000/- only
							Time = One Month.
Name of work:- Provision for Disabled Friendly toilet Distt. Court Complex Bilaspur Distt. Bilaspur. (SH:- Renovation of toilet at ground floor old complex and Construction of toilet at ground floor new court complex at Bilaspur) Job No. II.							
Sr No.	Description of items.	Qty.	In Figure	Rate In words	Unit	Amount	
1	2	3	4	5	6	7	
1	Providing and fixing PVC collars FINOLEX D-plast. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.						
1.1	For 110 mm (One hundred ten) millimetre)nominal size	4.00			Each		
1.2	75 mm (Seventy five millimetre) diameter .	4.00			Each		
2	Providing and fixing PVC plain bend of D-plast FINOLEX. including carriage of materials within all leads, lifts and other incidentals. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.						
2.1	110 mm (one hundred Ten millimetre) dia	3.00			Each		
2.2	75 mm (Seventy five millimetre) diameter .	3.00			Each		
3	Providing and fixing 100 mm (one hundred millimetre) dia chromium plated grating of superior quality for floor, gully/Nahini trap. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00			Each		

4	Providing and fixing C.P. brass bib cock Cera/Hindware/Jaquar or equivalent of approved quality conforming to IS:8931 : 15 mm nominal bore. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.00			Each	
5	Providing and fixing C.P. brass stop cock Cera/Hindware/Jaquar or equivalent of approved quality conforming to IS:8931 : 15 mm nominal bore. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.00			Each	
6	Providing and fixing stainless steel U-type Grab Bar of Jaquar or equivalent approved quality with wall supporting 300mm. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.00			Each	
7	Providing and fixing stainless steel Flip up Grab Bar of Jaquar or equivalent approved quality floor supporting. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00			Each	
8	Providing and fixing stainless steel L-shaped Grab Rail/Bar of Jaquar or equivalent approved quality foldable supporting. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00			Each	

9	Providing and fixing 600 X 450mm (Six hundred into Four hundred fifty millimetre) bevelled edge mirror of ATUL/MODI GUARD/GOLDEN FISH on 6mm (Six millimetre) thick A.C sheet Cera or equivalent or plywood sheet and fixed with wooden plug with C.P brass screws and washers. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Each	
10	Providing and fixing C.P. Brass Towel rail complete Cera/Hindware/Jaquar or equivalent of approved quality conforming to IS:8931 with C.P. Brass brackets fixed to wooden plugs with C.P. Brass screws :- 750mm x 20mm.(Seven hundred fifty into twenty millimetre). including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
11	Providing and fixing 600x120x5 mm (Six hundred x one hundred twenty x five millimetre) glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm long screws, rawl plugs etc. of KIGSTON / PARKO / TECHNO / JAL JAQUAR / GEM / ESS /SEIKO. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
12	Providing and fixing liquid soap container with C.P. Brass lid and brackets fixed to wooden plugs with C.P. Brass screws :- Plastic container. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Each	

13	Providing and fixing Chromium plated brass soap dish of Cera/Hindware/Jaquar conforming to IS:8931 with C.P. brass brackets fixed to wooden cleats with C.P. brass screws. including entire carriage of materials within all leads and lifts as per direction of Engineer-in-charge. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00			Each	
14	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash asteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : Polyester powder coated aluminium (minimum thickness of polyester powder coating 50 (Fifty) micron). including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	31.50			Kilogramme	
15	Providing and fixing C.P. brass toilet paper holder Cera/Hindware/Jaquar complete in all respect including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Each	

16	Providing and fixing Sanitary pad dispensator of approved quality complete in all respect including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other constuction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Each	
		TOTAL				



Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Job No //

Draft Schedule of Quantity						
			Estimated cost Rs. = 89,545/- only			
			Earnest Money Rs. = 2,000/- only			
			Time = One Month.			
Name of work:- Provision for Disabled Friendly toilet Distt. Bilaspur. (SH:- Renovation of toilet at ground floor old complex and Construction of toilet at ground floor new court complex at Bilaspur) Job No. III.						
Sr No.	Description of items.	Qty.	Rate		Unit	Amount
			In Figure	In words		
1	2	3	4	5	6	7
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash asteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
1.1	Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC15)	50.97			Kilogramme	
1.2	Polyester powder coated aluminium (minimum thickness of polyester powder coating 50 (Fifty) micron).	25.42			Kilogramme	
2	Providing and fixing 12 mm thick (Twelve milimetre) prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer- in-charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.08			Per Square Metre	

3	Removing dry oil bound distemper, water proofing cement paint and like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	41.10			Per Square Metre	
4	Providing and applying Birla white cement based putty of average thickness 1 mm. of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	41.10			Per Square Metre	
5	Distempering (two coat) with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give and even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth. Priming coat with distemper primer. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	41.10			Per Square Metre	
6	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten Per Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.26			Per Cubic Metre	
7	Stone soling under floor tightly hand packed including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.78			Per Cubic Metre	

8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (One Cement : Three coarse sand) : Six graded stone aggregate 20 mm(Twenty millimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.60			Per Cubic Metre
9	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (Seven point five) in superstructure above plinth level up to floor V level. Cement mortar 1:4 (One cement :four coarse sand) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.69			Per Square Metre
10	15 mm (Fifteen millimetre) cement plaster on the rough side of single or half brick wall of mix : 1:4 (One cement: Four fine sand). including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.38			Per Square Metre
11	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. Two coats. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.88			Per Square Meter
		TOTAL			


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Job No 12

Schedule of Quantity						
Name of work:- A/R & M/O Indoor Auditorium for Culture Programme at Bilaspur (H.P.). (SH:- P/L water proofing treatment on water storage tank).						
Estimated cost Rs. = 51,556/- only Earnest Money Rs. = 1,100/- only Time Limit. = One month						
Sr No	Description	Qty.	Rates		Unit	Amount
			In Figure	In words		
1	2	3	4	5	6	7
1	Providing and laying in Situ Seven course water proofing treatment with APP (Atactic polypropylene) modified Polymeric membrane over roof consisting of first coat of bitumen primer @ 0.40 (Zero point forty liter) litre per sqm, 2nd (Second), 4th (Four) & 6th (Six) courses of bonding material @ 1.20 Kg/sqm, (One point twenty kilogramme / Per Square Metre) which shall consist of blown type bitumen of grade 85/25 (Eighty five / Twenty five) conforming to IS : 702, 3rd and 5th layers of roofing membrane APP modified Polymeric membrane 1.5 mm (One point five millimetre) thick of 2.25 Kg/sqm (Two point twenty five Kilogramme/Per Square Metre) weight consisting of five layers prefabricated with centre core as 20 (Twenty) micron HMDPE film andwiched on both sides with polymeric mix and the polymeric mix is protected on both side with 20 (Twenty) micron HMDPE film. 7th, the top most layer shall be finished with brick tiles of class designation 10 (Ten) grouted with cement mortar 1:3 (One cement : Three fine sand) mixed with 2% (Two percent) integral water proofing compound by weight of cement over a 12 mm (Twelve millimetre) layer of cement mortar 1:3 (One cement : Three fine sand) and finished neat (item of laying brick tiles shall be paid for separately). including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavey or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	47.04			Per Square Metre	
TOTAL						


 Executive Engineer,
 Bilaspur Division No.1
 HPPWD Bilaspur

705/13

Estimated cost Rs. = 99,996/-only
 Earnest Money Rs. = 2,000/- only.
 Time Limit. = One Month

Schedule of Quantity

Name of Work:- Restoration of rain damages on various roads under Sub Division Kuthera. (SH :- C/O unlined drain and dressing of berms).

Sr No	Description of items.	Qty.	Rates		Amount
			In Figure	In words	
1	Construction of unlined surface drains of average cross-sectional area 0.20 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1330.21 Meter			
2	Surface dressing of the ground including dressing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	683.00 Square Meter			

Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur