

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No.PW-NHD-GA-TENDER/2025-26

2226-27

Dated: 20/06/2025

To

The Executive Engineer,
IT Cell Nirman Bhawan Nigam Vihar,
HP, PWD Shimla-02 (H.P)..

Subject:-

Regarding uploading of NIT on HP, PWD website .

Please find enclosed herewith the tender notice for the works as given in the Notice inviting tender for uploading on departmental website as per notification Pr. Sec. (PW) to the Govt. of (H.P.) letter No. PBW(B)A(3) 1/2024 dated 03 Jan.2024. The work mentioned in the tender notice are urgent in nature and public interest.

This is for your kind information and necessary action at your end please.

Encl:-NIT copy & 08 Nos. copy of schedule of quantity.


Executive Engineer,
National Highway Division
HP, PWD Hamirpur.

Copy to the Superintendent Engineer, National Highway Circle HP, PWD Shahpur for information please.

Executive Engineer,
National Highway Division,
HP, PWD Hamirpur.

CERTIFICATE

Certified that the tenders of works, called vide this office letter No. PW-NHD-GA-TENDER/2025-26²²⁰⁵⁻²⁵ Dated:- 20-06-25 are urgent nature.


Executive Engineer,
NH Division,
HP, PWD Hamirpur.

HIMACHAL PRADESH
Public Works Department
NOTICE INVITING TENDER

Sealed Tenders on item rate basis are hereby invited on behalf of Governor of H.P. by Executive Engineer, NH Division, HPPWD, Hamirpur (H.P) from the experienced contractor/ firms enlisted in appropriate class with HPPWD for the following works. The tender shall be received in this office on 01-07-2025 up to 11.00 A.M and the same shall be opened on the same day at 11:30 A.M. in the presence of Contractor/Firms or their authorized/representatives who wish to be present at the time of opening of tender. The application for issue of tender document shall be received on dated 28-06-2025 up to 12:30 P.M. on cash payment (Non-Refundable) and tender document will be issued on 30-06-2025 up to 4:00 P.M. If the office happens to be closed on the scheduled date the tender form document will be sold/ opened on the next working day at the same time and venue.

Sr. No	Name of work	Estimated cost	Earnest money	Time allowed	Cost of form
1	Restoration of road damages caused due to laying of OFC on NH-503 A. at Km 0/0 to 70/00 (SH:- Construction of Breast wall and V-shape drain at Km. 24/500 to 24/507.30(RHS). Deposit work	99990.00	2000.00	One Month	350/-
2	Restoration of road damages caused due to laying of OFC on NH-503 A. at Km 0/0 to 70/00 (SH:- Dressing of Berms in Km. 26/0 to 30/0 . (Deposit work)	98800.00	2000.00	One Month	350/-
3	Restoration of road damages caused due to laying of OFC on NH-503 A. at Km 0/0 to 70/00 (SH:- Dressing of Berms in Km. 30/0 to 35/750 . (Deposit work)	98800.00	2000.00	One Month	350/-
4	Restoration of road damages caused due to laying of OFC on NH-503 A. at Km 0/0 to 70/00 (SH:- Dressing of Berm and Bush cutting in Km. 38/350 to 39/700 . (Deposit work)	99400.00	2000.00	One Month	350/-
5	Restoration of road damages caused due to laying of OFC on NH-503 A. at Km 0/0 to 70/00 (SH:- Construction of Retaining wall at Km. 47/980 to 47/987.50 (LHS) (Deposit work)	99040.00	2000.00	One Month	350/-
6	Restoration of Road damages caused due to laying of OFC on NH - 503 Km 0/00 to 23/105 (SH:- Hiring of JCB and tipper in km. 0/00 to 23/105) Job-I.(Deposit work)	99800.00	2000.00	One Month	350/-
7	Restoration of Road damages caused due to laying of OFC on NH - 503 Km 0/00 to 23/105 (SH:- Hiring of JCB and tipper in km. 0/00 to 23/105) Job-II.(Deposit work)	99800.00	2000.00	One Month	350/-
8	Restoration of Road damages caused due to laying of OFC on NH - 303 Km 0/00 to 39/00 (SH:- Construction of slab culvert for providing access to residential area as well for agriculture demand on other side of Nallah at km 6/690.(Deposit work)	91630.00	2000.00	One Month	350/-

Draft notice inviting/ specification special conditions can be seen in this office on any working day between 11:00 AM to 4:00 PM ambiguous/ Telegraphic conditional tenders by fax shall not be entertained/ considered in any case. The contractors/ firms are requested to insert the rate of each item in words as well as in figure, failing which Executive Engineer, reserves the right to accept/ reject any or all tenders. The intending contractors/ firms are requested to see the site of work before submitting the tenders. All the application must accompany with the Earnest Money in the shape of call at deposit/ N.S.C. purchased from any post office in H.P/FDR from any nationalized bank duly pledged in favour of Executive Engineer. The application without earnest money will not be entertained and out rightly rejected.

CONDITIONS: - The following document are required to be attached with the application: -

- 1 A copy of valid enlistment and renewal certificate.
- 2 A copy of GST.
- 3 Any other information as desired by the Executive Engineer. Any application not accompanied by above documents shall not be entertained. The tender shall be issued to those contractors/ firms who are found eligible, suitable and competent. The decision of the Executive Engineer, regarding suitability, eligibility and competence of the contractor/ firm applying for issue of tenders shall be final. In case, of any information supplied by the

contractor/ firm, is found false at any stage the tender is liable to be rejected and action taken against contractor/firm.

Executive Engineer,
NH Division, HPPWD
Hamirpur.

NO.PW-NHD-HMR-GA-TENDER/2023-24

2205-25

DATED: - 20/06/2025

COPY FORWARDED TO THE FOLOWING for information please:

- 1 The Engineer-in-Chief, HPPWD, Shimla-I
- 2 The Chief Engineer (NH), HPPWD, Shimla-I.
- 3 All the Superintending Engineer, NH /B&R in HP.
- 4 The Director of information and public relation ,HP Shimla
- 5 All the Executive Engineer, NH/B&R in HP.
- 6 All the Assistant Engineer, NH/B&R in HP.
- 7 Drawing Branch/ Account Branch/ Notice Board of this office.

Executive Engineer,
NH Division, HPPWD
Hamirpur.

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of road damages caused due to laying of OFC on NH- 503 A. at Km 0/0 to 70/00 (SH:- Construction of Breast wall and V-shape drain at Km. 24/500 to 24/507.30(RHS). Deposit work

Estimated Cost:- Rs. 99990.00
Earnest Money:- Rs. 2000.00
Time Limit:- One Month

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and MORT&H specification clause 305.1 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all lead and lift, including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and structting and pumping and bailing out water (surface and sub soil water upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals charges. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government.	14.38	200.00	Rupees Two hundred and paise nil only	Per Cubic metre	2876.00
2	Providing and laying, mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation complete as per drawings and MORT&H specifications clause 802,803,1202 and 1203. PCC Grade M10 (Nominal mix 1:3:6) (One cement : three sand : six graded/ crushed stone aggregate) 20mm (Twenty millimetre) nominal size including entire carriage of materials within all leads and lifts and as per the direction of Engineer-in-charge. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government.	19.12	4700.00	Rupees Four thousand Seven hundred and paise nil only	Per Cubic metre	89864.00
3	Providing weep holes in brick masonry/ plain /reinforced concrete abutment wing wall/ return wall etcetra with 100mm dia (One Hundred Millimetre) PVC pipe extended through the full width of the structure with slope of 1(V) 20H towards drainage face complete as per drawing and MORT&H specification clause 614, 709, 1204.3.7 including carriage of material with in all leads and lifts as per the direction of Engineer-in-Charge. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government.	29.00	250.00	Rupees two hundred fifty and paise nil only	Each	7250.00
G.Total						99990.00

Draft schedule of quantity checked and approved for Rs. 99990 only

Executive Engineer,
National Highway Division,
HP.PWD., Haridwar (HP)

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of road damages caused due to laying of OFC on NH- 503 A. at Km 0/0 to 70/00 (SH:- Dressing of Berms in Km. 26/0 to 30/0 . (Deposit work)

				Estimated Cost:- Rs.	98800.00
				Earnest Money:- Rs.	2000.00
				Time Limit:-	One Month
Sr No.	Description of item.	Qty.	Rate		Amount
			In Figure	In Words	
1	Making up loose of material / irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification clause 1903 including entire carriage of material within all leads and lifts as per directions of Engineer-in-Charge and other incidental charges. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government.	3800.00	26.00	Rupees twenty six and paise nil only	98800.00
		G.Total			98800.00

Drafting Schedule of Quantity checked and approved to Rs. 98800/- only and estimated eight hundred only.

Executive Engineer,
National Highway Division,
MP.PWD., Hamirpur (HP)

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of road damages caused due to laying of OFC on NH-503 A. at Km 0/0 to 70/00 (SH:- Dressing of Berms in Km. 30/0 to 35/750 . (Deposit work)

Estimated Cost:- Rs.				Estimated Cost:- Rs.	
Earnest Money:- Rs.				2000.00	
Time Limit: -				One Month	
Sr No.	Description of item.	Qty.	Rate		Unit
			In Figure	In Words	
1	Making up loose of material / irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification clause 1903 including entire carriage of material within all leads and lifts as per directions of Engineer-in-Charge and other incidental charges. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government.	3800.00	26.00	Rupees twenty six and paise nil only	Per square metre
G.Total					98800.00

Drafts schedule of quantity checked and approved for Rs-98800/- (Rupees Ninety Eight thousand eight Hundred only)

Executive Engineer,
National Highway Division,
HP.PWD., Hamirpur (HP)

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of road damages caused due to laying of OFC on NH- 503 A. at Km 0/0 to 70/00 (SH:- Dressing of Berm and Bush cutting in Km. 38/350 to 39/700 . (Deposit work)					Estimated Cost:- Rs.		99400.00
					Earnest Money:- Rs.		2000.00
					Time Limit:-		One Month
Sr No.	Description of item.	Qty.	Rate		Unit	Amount	
			In Figure	In Words			
1	Making up loose of material / irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification clause 1903 including entire carriage of material within all leads and lifts as per directions of Engineer-in-Charge and other incidental charges. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government.	3200.00	26.00	Rupees twenty six and paise nil only	Per square metre	83200.00	
2	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm (Three hundred millimetre), removal of stumps of scuh trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, upto a lead of 1000m (One thousand metre) including removal and disposal of top organic soil not exceeding 150mm (one hundred fifty millimetre) in thickness as per Technical Specification clause 201. By manual means (In area of thorny jungle) including carriage of material in all leads and lifts and as per direction of the Engineer-in-charge. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government.	2700.00	6.00	Rupees and paise nil only	Per square metre	16200.00	
		G.Total				99400.00	

Draft Schedule of Quantity checked and approved for Rs. 99400/- only (Rs. Ninety nine thousand four hundred only).

Executive Engineer,
National Highway Division,
HP.PWD., Hamirpur (HP)

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of road damages caused due to laying of OFC on NH- 503 A. at Km 0/0 to 70/00 (SH:- Construction of Retaining wall at Km. 47/980 to 47/987.50 (LHS) (Deposit work)				Estimated Cost:- Rs. Earnest Money:- Rs. Time Limit:-		99040.00 2000.00 One Month
Sr No.	Description of item.	Qty.	In Figure	In Words	Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and MORT&H specification clause 305.1 and as per direction of, the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all lead and lift, including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and structting and pumping and bailing out water (surface and sub soil water upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals charges. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	10.65	200.00	Rupees Two hundred and paise nil only	Per Cubic metre	2130.00
2	Providing and laying, mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation complete as per drawings and MORT&H specifications clause 802.803,1202 & 1203. PCC Grade M10 (Nominal mix 1:3:6) (One cement : three sand : six graded/ crushed stone aggregate 20mm (Twenty millimetre) nominal size including entire carriage of materials within all leads and lifts and as per the direction of Engineer-in-charge. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	19.50	4700.00	Rupees Four thousand Seven hundred and paise nil only	Per Cubic metre	91650.00
3	Providing weep holes in brick masonry/ plain /reinforced concrete abutment wing wall/ return wall etcetra with 100mm dia (One Hundred Millimetre) PVC pipe extended through the full width of the structure with slope of 1(V) 20H towards drainage face complete as per drawing and MORT&H specification clause 614, 709, 1204.3.7 including carriage of material with in all leads and lifts as per the direction of Engineer-in-Charge. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	7.00	250.00	Rupees two hundred fifty and paise nil only	Each	1750.00
4	Back filling with granular material wing walls, return walls and retaining walls complete as per drawing and MORT&H specifications clause 1204.3.8 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals charges. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	5.40	650.00	Rupees Six hundred fifty and paise nil only	Per Cubic metre	3510.00
G.Total						99040.00

Draft Schedule of quantity checked and approved by
for Rs. 99040/- only (Rupees Ninety nine thousand forty) only

Executive Engineer,
National Highway Division,
HP, PWD., Hamirpur (HP)

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of Road damages caused due to laying of OFC on NH -503 Km 0/00 to 23/105 (SH:- Hiring of JCB and tipper in km. 0/00 to 23/105) Job-I.						Estimated Cost:- Rs.	99800.00
						Earnest Money:- Rs.	2000.00
						Time Limit:-	One Month
Sr No.	Description of item.	Qty.	Rate		Unit	Amount	
			In Figure	In Words			
1	Hiring of JCB/Excavator for removal of Slips and boulders in all kind of soil i/c rocky portion and saturated soil and disposing of all excavated earth or un-servisable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. The machine/JCB should work minimum 8.00 hours from 9.00 am to 5.00 pm daily and remove atleast 25 cum (Twenty five cubic metre) quantity of slips per hour. Any loss to the public/private property or any accident etcetera happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare, watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	43.00	1100.00	Rupees one thousand one hundred and paise nil only	Per Hours	47300.00	
2	Hiring of Tipper for carriage of debries/muck/unservicable material from the various reaches of the road including all leads and lifts and as per the direction of Engineer-in-charge.	15.00	3500.00	Rupees three thousand five hundred and paise nil only	Per Day	52500.00	
		G.Total					99800.00

Draft schedule of Quantity checked and approved for Rs 99800/- only.

Executive Engineer,
National Highway Division,
H.P.W.D., Hamirpur (HP)

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of Road damages caused due to laying of OFC on NH -503 Km 0/00 to 23/105 (SH:- Hiring of JCB and tipper in km. 0/00 to 23/105) Job-II.							Estimated Cost:- Rs.	99800.00
							Earnest Money:- Rs.	2000.00
							Time Limit:	One Month
Sr No.	Description of item.	Qty.	Rate		Unit	Amount		
			In Figure	In Words				
1	Hiring of JCB/Excavator for removal of Slips and boulders in all kind of soil i/c rocky portion and saturated soil and disposing of all excavated earth or un-serviseable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. The machine/JCB should work minimum 8.00 hours from 9.00 am to 5.00 pm daily and remove atleast 25 cum (Twenty five cubic metre) quantity of slips per hour. Any loss to the public/private property or any accident etcetera happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare, watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	43.00	1100.00	Rupees one thousand one hundred and paise nil only	Per Hours	47300.00		
2	Hiring of Tipper for carriage of debries/muck/unservicable material from the various reaches of the road including all leads and lifts and as per the direction of Engineer-in-charge.	15.00	3500.00	Rupees three thousand five hundred and paise nil only	Per Day	52500.00		
		G.Total				99800.00		

Draft Scheduled Quantity checked and Approved for Rs. 99800/- Only

*Executive Engineer,
National Highway Division,
NH-PWD, Hamirpur (HP)*

DRAFT SCHEDULE OF QUANTITY						
Name of work :- Restoration of Road damages caused due to laying of OFC on NH -303 Km 0/00 to 39/00 (SH:- Construction of slab culvert for providing access to residential area as well for agriculture demand on other side of Nallah at km 6/690.						
Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and laying, mechanically mixed & vibrated concrete for plain/ reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 & 1203. PCC Grade 1:2:4 (One cement : two sand : four graded/ crushed stone aggregates 20mm (Twenty millimeter) nominal size) including entire carriage of materials within all leads and lifts and as per the direction of Engineer-in-charge. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government	1.87	5500.00	Rupees five thousand five hundred and paise nil only	Per Cubic metre	10285.00
2	Supplying, fitting and placing TMT bar reinforcement (Fe 415) in substructure complete as per drawings and technical specifications Clauses 1002, 1005,1010 & 1202 including carriage of material and equipment in all leads and lifts with all mode of transportation and as per the direction of Engineer-in-Charge. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	525.00	85.00	Rupees eighty five and paise nil only	Per killogramme	44625.00
3	Providing plain/ reinforced concrete PCC 1:1.5:3 (One Cement: one point five sand: three aggregate) in open foundation complete as per drawings and technical specifications clause 802 ,803,1202 and 1203 including the cost of centering, shuttering and finishing as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government.	3.96	6000.00	Rupees six thousand and paise nil only	Per Cubic metre	23760.00
4	Providing and laying, mechanically mixed & vibrated concrete for plain/ reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 & 1203. PCC Grade 1:2:4 (One cement : two sand : four graded/ crushed stone aggregates 40mm (fourty millimeter) nominal size) including entire carriage of materials within all leads and lifts and as per the direction of Engineer-in-charge. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government	2.40	5400.00	Rupees five thousand four hundred and paise nil only	Per Cubic metre	12960.00
G.Total						91630.00

Draft Schedule of Quantity checked and approved for Rs 91630/- only.

*Executive Engineer,
National Highway Division,
HP.PWD., Hamirpur (HP)*