



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Tel. 01890-299219.

eePWD-chowari@hp.gov.in

No. PWD-CHW/Tender /2025-26-

To

3071.73

Dated:- 30/07/2025

The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject: - Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as give in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.

(Signature)
Executive Engineer,
Chowari Division,
HPPWD, Chowari.

Copy forwarded to the Superintending Engineer, 7th Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

(Signature)
Executive Engineer,
Chowari Division,
HPPWD, Chowari.

Certificate

Certified that the tenders called vide this office letter No. PWD-CHW/Tender
/2025-26.....dated..30/7/25 is emergent nature and in Public interest.

Executive Engineer,
Chowari Division,
HPPWD, Chowari.

1/1/2025 (11)

1/1/2025 (11)



Tel.01899-299219.

cepwd-chowari@hp.gov.in

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

“NOTICE INVITING TENDERS”

Sealed percentage/item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Chowari Division, HPPWD, Chowari on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

1. Date of issued/sale of tender form against
Cash payment (non refundable).
2. Date of open of tender

06.08.2025

07.08.2025

The tender shall be received upto **24.00 PM** on **06.08.2024** and will be opened on the day of **07.08.2025 at 12.00 PM** in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Non refundable) during the working hours on **06.08.2025**.

The Earnest Money in the shape of National Saving Certificate/Deposit at call/Time deposit/Account/in any Post Office/Nationalized Bank in HP duly pledged in favour of Executive Engineer, Chowari Division, HPPWD, Chowari must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1	Restoration of rain damage on Patka to Dalhousie road Km 14/00 to 32/00 (SH:- Hiring of Tipper for muck Divert Km 14/00 to 32/00).	97125/-	1943/-	Rs. 350/-	Three Month	Class-D & C
2	Restoration of rain damage on Motla Sukhiyad road Km 0/0 to 9/00 (SH:- Hiring of excavator cum loader for removal of slips Km 0/0 to 3/00).	99750/-	1995/-	Rs. 350/-	Three Month	Class-D & C
3	Restoration of rain damage on Link road to village Dangari Km 0/0 to 5/00 (SH:- Hiring of excavator cum loader for removal of slips in Km 0/0 to 3/00).	99600/-	1932/-	Rs. 350/-	Three Month	Class-D & C
4	Restoration of rain damage on link road to village Nahana Km 0/0 to 4/00 (SH:- Hiring of excavator cum loader for removal of slips Km 0/0 to 4/00).	99750/-	1995/-	Rs. 350/-	Three Month	Class-D & C
5	Restoration of rain damage on Motla Gola Kathla road Km 0/0 to 7/00 (SH:- Hiring of excavator cum loader for removal of slips Km 0/0 to 3/00).	98700/-	1974/-	Rs. 350/-	Three Month	Class-D & C
6	Restoration of rain damage on Motla Sukhiyad road Km 0/0 to 9/00 (SH:- Hiring of excavator cum loader for removal of slips Km 3/00 to 6/00).	99765/-	1995/-	Rs. 350/-	Three Month	Class-D & C
7	Restoration of rain damage on Nurpur Sanjhi Nallah Tunnuhatti road Km 15/390 to 25/00 (SH:- Hiring of Tipper and excavator cum loader for removal of slips Km 20/00 to 25/00).	99150/-	1982/-	Rs. 350/-	Three Month	Class-D & C

8	Restoration of rain damage on Nurpur Sanjhi Nallah Tunnuhatti road Km 15/390 to 25/00 (SH:- Hiring of Tipper and excavator cum loader for removal of slips Km 15/310 to 17/00).	99660/-	1993/-	Rs. 350/-	Three Month	Class-D & C
9	Restoration of rain damage on Nurpur Sanjhi Nallah Tunnuhatti road Km 15/390 to 25/00 (SH:- Hiring of Tipper and excavator cum loader for removal of slips Km 17/00 to 20/00).	99720/-	1994/-	Rs. 350/-	Three Month	Class-D & C
10	Restoration of rain damage on Patka to Dalhousie road Km 14/00 to 32/00 (SH:- Hiring of Tipper for muck Divert Km 23/00 to 32/00).	97680/-	1954/-	Rs. 350/-	Three Month	Class-D & C
11	Restoration of rain damage on Mandhiar Baloh Fagot road Km 0/0 to 8/00 (SH:-Hiring of Tipper and Excavator cum loader for removal of slips Km 4/00 to 8/00).	99720/-	1992/-	Rs. 350/-	Three Month	Class-D & C
12	Restoration of rain damage on Mandhiar Baloh Fagot road Km 0/0 to 8/00 (SH: - Hiring of Tipper & excavator cum loader for removal of slips Km 0/0 to 4/00).	99600/-	1992/-	Rs. 350/-	Three Month	Class-D & C
13	Restoration of rain damage on Shahpur Sihunta Chowari road Km 40/00 to 53/00 (SH:- Hiring of excavator cum loader for removal of slips Km 48/00 to 53/00).	99700/-	1974/-	Rs. 350/-	Three Month	Class-D & C
14	Restoration of rain damage on Patka to Dalhousie road Km 14/00 to 32/00 (SH: - Hiring of excavator cum loader for removal of slips Km 14/00 to 32/00).	99750/-	1995/-	Rs. 350/-	Three Month	Class-D & C
15	Restoration of rain damage on Ghatsani Pull to Bhalog Km 0/0 to 7/360 (SH:-Hiring of excavator cum loader for removal of slips Km 2/00 to 4/00).	99600/-	1992/-	Rs. 350/-	Three Month	Class-D & C
16	Restoration of rain damage on Ghatsani Pull to Bhalog Km 0/0 to 7/360 (SH:-Hiring of excavator cum loader for removal of slips Km 0/0 to 2/00).	99105/-	1982/-	Rs. 350/-	Three Month	Class-D & C
17	Restoration of rain damage on link road to village Fakhrodu Km 0/0 to 2/700 (SH:- Hiring of excavator cum loader for removal of slips Km 0/0 to 1/500).	96600/-	1932/-	Rs. 350/-	Three Month	Class-D & C
18	Restoration of rain damage on Ghatsani Pull to Bhalog Km 0/0 to 7/360 (SH:-Hiring of excavator cum loader for removal of slips Km 4/00 to 7/360).	99165/-	1983/-	Rs. 350/-	Three Month	Class-D & C
19	Restoration of rain damage on Link road to village Dangari Km 0/0 to 5/00 (SH:- Hiring of excavator cum loader for removal of slips in Km 3/00 to 5/00).	94500/-	1890/-	Rs. 350/-	Three Month	Class-D & C

20	Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti road Km 25/00 to 40/810 (SH:- Hiring of Tipper and excavator cum loader for removal of slips km 25/00 to 30/00).	99105/-	1982/-	Rs. 350/-	Three Month	Class-D & C
21.	Restoration of rain damage on Nanikhed to Samlue road Km 0/0 to 30/585(SH:- Hiring of Tipper and excavator cum loader for removal of slips Km 10/00 to 20/00).	99720/-	1994/-	Rs. 350/-	Three Month	Class-D & C
22	Restoration of rain damage on link road to village Fakhrodu Km 0/0 to 2/700 (SH:- Hiring of excavator cum loader for removal of slips Km 1/500 to 2/700).	98700/-	1974/-	Rs. 350/-	Three Month	Class-D & C
23	Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti road Km 25/00 to 40/810 (SH:- Hiring of Tipper and excavator cum loader for removal of slips Km 30/00 to 40/810).	99600/-	1992/-	Rs. 350/-	Three Month	Class-D & C
24.	Restoration of rain damage on Nanikhed to Samlue road Km 0/0 to 30/585(SH:- Hiring of Tipper and excavator cum loader for removal of slips Km 0/0 to 10/00).	98730/-	1975/-	Rs. 350/-	Three Month	Class-D & C
25	Restoration of rain damage on Patka to Dalhousie road Km 45/00 to 67/00 (SH: - Hiring of Tipper & excavator cum loader for removal of slips Km 56/0 to 67/00).	96630/-	1933/-	Rs. 350/-	Three Month	Class-D & C
26.	Restoration of rain damage on Nanikhed to Samlue road Km 0/0 to 30/585(SH: - Hiring of Tipper and excavator cum loader for removal of slips Km 20/00 to 30/00).	99225/-	1985/-	Rs. 350/-	Three Month	Class-D & C
27	Restoration of rain damage on Patka to Dalhousie road Km 45/00 to 67/00 (SH: - Hiring of Tipper & excavator cum loader for removal of slips Km 45/00 to 56/00).	99750/-	1994/-	Rs. 350/-	Three Month	Class-D & C
28.	Restoration of rain damage on Ghatsani Pul to Bhalog road Km 0/0 to 7/360 (SH:- Hiring of excavator cum loader for removal of slips).	98700/-	1974/-	Rs. 350/-	Three Month	Class-D & C
29	Restoration of rain damage on Parchhore to Naddal road Km 0/0 to 3/708 (SH:- Hiring of excavator cum loader for removal of slips).	95550/-	1911/-	Rs. 350/-	Three Month	Class-D & C
30	Restoration of rain damage on Bailly to Khaddi road Km 0/0 to 4/200 (SH:- Hiring of excavator cum loader for removal of slips).	98700/-	1974/-	Rs. 350/-	Three Month	Class-D & C
31.	Restoration of rain damage on Dukhar to Morthu road Km 0/0 to 8/00 (Sh:- C/o R/wall at RD 0/510 to 0/512.50).	97066/-	1941/-	Rs. 350/-	Three Month	Class-D & C
32.	Construction of link road Bagdhar to Chhunui Km 0/0 to 3/350 (SH:- C/o R/wall with Pustha at Rd 2/540 to 2/542.60).	96603/-	1932/-	Rs. 350/-	Three Month	Class-D & C

33	Construction of link road Bagdhar to Chhunui Km 0/0 to 3/350 (SH:- C/o R/wall with Pustha at Rd 2/545.10 to 2/547.70).	99247/-	1985/-	Rs. 350/-	Three Month	Class- D & C
----	---	---------	--------	-----------	-------------	-----------------

- 1 The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
- 2 The Contractor should have executed two similar types of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within list five year.
- 3 GST No/Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.

(Signature)
Executive Engineer,
Chowari Division,
HPIWD, Chowari.

1

SCHEDULE OF QTY

Estimate cost:-97125/-

Earnest Money:-1943/-

Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON PATKA TO DALHOUSE ROAD KM 14/00 TO 32/00 (SH:- HIRRING OF TIPPER FOR MUCK DIVERT 14/00 TO 23/00)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases .The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	175.00			Per Hours	
		Total				

(Signature)
Executive Engineer
Chowari Division
HPPW, Chowari

SCHEDULE OF QTY

Estimate cost:-99750/-
Earnest Money:-1995/-
Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON MOTLA SUKHIYARD ROAD KM 0/00 TO 9/00 (SH:- HIRING OF EXCAVATOR CUM LOADER FOR REMOVAL OF SLIP 0/00 TO 3/00)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner .The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royality ,malkana toll tax sale tax or any other taxes imposed by the Government.	95.00			Per Hours	
		Total				

Atul Kumar
Executive Engineer
Chowari Division
HPPW Chowari


23

SCHEDULE OF QTY

Estimate cost:-99600/-
Earnest Money:-1932/-
Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON LINK ROAD VILLAGE DANGARI KM 0/00 TO 5/00 (SH:- HIRRING OF EXCAVATOR CUM LOADER FOR REMOVAL OF SLIP 0/00 TO 3/00)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner. the fuel& operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	92.00			Per Hours	
Total						


 Executive Engineer
 Chowari Division
 HPPYD Chdwari

SCHEDULE OF QTY

Estimate cost:-99750/-
Earnest Money:-1995/-
Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON LINK ROAD VILLAGE NAHANA KM 0/00 TO 4/00 (SH:- HIRING OF EXCAVATOR CUM LOADER FOR REMOVAL OF SLIP 0/00 TO 4/00)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -In-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	95.00			Per Hours	
	Total					

Executive Engineer
Chowari Division
HP Pradip Chowari

5

SCHEDULE OF QTY

Estimate cost:-98700/-
Earnest Money:-1974/-
Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON MOTLA GOLA KATHLA ROAD KM 0/00 TO 7/00 (SH:- HIRING OF EXCVATOR CUM LOADER FOR REMOVAL OF SLIP 0/00 TO 3/00)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	94.00			Per Hours	
					Total	

Executive Engineer
Chowari Division
HPPW Chowari

SCHEDULE OF QTY

Estimate cost:-99765/-
Earnest Money:-1995/-
Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON MOTLA SUKHVIYARD ROAD KM 0/00 TO 9/00 (SH:- HIRRING OF TIPPER & EXCAVATOR CUM
LOADER FOR REMOVAL OF SLIP 3/00 TO 6/00)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-in-Charge .Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	67.00			Per Hours	
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private property or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases .The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	53.00			Per Hours	
		Total				

(Signature)
Executive Engineer
Chowari Division
HPWD Chowari

61

SCHEDULE OF QTY

Estimate cost:-99150/-
Earnest Money:-1982/-
Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON NURPUR SANJHI NALLAH TUNUHATTI ROAD KM 15/310 TO 25/00 (SH:- HIRLING OF TIPPER & EXCAVATOR CUM LOADER FOR REMOVAL OF SLIP 20/00 TO 25/00)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner. The fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site , which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	78.00			Per Hours	
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private property or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases. The fuel and operational staff for truck will be provided by the owner. The repair and spare ,watch &ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	31.00			Per Hours	
		Total				

Executive Engineer
Chowari Division
HP PWD Chowari

7

28

SCHEDULE OF QTY

Estimate cost:-99660/-
Earnest Money:-1993/-
Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON NURPUR SANJHI NALLAH TUNUHATTI ROAD KM 15/310 TO 25/00 (SH:- HIRRING OF TIPPER & EXCVATOR CUM LOADER FOR REMOVAL OF SLIP 15/310 TO 17/00)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malhana toll tax sale tax or any other taxes imposed by the Government.	78.00			Per Hours	
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases .The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	32.00			Per Hours	
		Total				

(Signature)
Executive Engineer
Chowaj Division
HPPWD Chawari

SCHEDULE OF QTY

Estimate cost:-99720/-
Earnest Money:-1994/-
Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON NURPUR SANHI NALLAH TUNUHATTI ROAD KM 15/310 TO 25/00 (SH:- HIRRING OF TIPPER & EXCVATOR CUM LOADER FOR REMOVAL OF SLIP 17/00 TO 20/00)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner .The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,mallkana toll tax sale tax or any other taxes imposed by the Government.	77.00			Per Hours	
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases .The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	34.00			Per Hours	
		Total				

Executive Engineer
Chowari Division
HPP
Chdvari


9

SCHEDUAL OF QTY

Estimate cost:-97680/-
Earnest Money:-1954/-
Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON PATKA TO DALHOUSE ROAD KM 14/00 TO 32/00 (SH:- HIRRING OF TIPPER FOR MUCK DIVERT 23/00 TO 32/00)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases .The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	176.00			Per Hours	
					Total	


Executive Engineer
Chowari Division
HPPW Chowari

SCHEDULE OF QTY

Estimate cost:-99720/-
Earnest Money:-1992/-
Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON MANDHIAR BALOH FAGOT ROAD KM 0/00 TO 8/00 (SH:- HIRRING OF TIPPER & EXCAVATOR CUM LOADER FOR REMOVAL OF SLIP 4/00 TO 8/00)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner . The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	77.00			Per Hours	
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases. The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	34.00			Per Hours	
		Total				

(Signature)
Executive Engineer
Chowari Division
HPPT, Chowari

SCHEDULE OF QTY

Estimate cost:-99600/-
Earnest Money:-1992/-
Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON MANDHIAR BALOH FAGOT ROAD KM 0/00 TO 8/00 (SH:- HIRING OF TIPPER & EXCAVATOR)
CUM LOADER FOR REMOVAL OF SLIP 0/00 TO 4/00)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty ,malakana toll tax sale tax or any other taxes imposed by the Government.	79.00			Per Hours	
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type material up to any leads and lifts as per direction and entire satisfaction of Engineer in charge. Any loss to public/private property or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases. The fuel and operational staff for truck will be provided by the owner. The repair and spare, watch & ward of machine also borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	30.00			Per Hours	
Total						

Executive Engineer
Chowari Division
HPWD Chowari

SCHEDULE OF QTY

Estimate cost:-99700/-

Earnest Money:-1974/-

Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON SHAHPUR SIHUNTA CHOWARI ROAD KM 40/00 TO 53/00 (SH:- HIRRING OF EXCAVATOR CUM
LOADER FOR REMOVAL OF SLIP 48/00 TO 53/00)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	94.00			Per Hours	
		Total				

(Signature)
Executive Engineer
Chowari Division
HPRD Chowari

SCHEDULE OF QTY

Estimate cost:-99750/-
Earnest Money:-1995/-
Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON PATKA TO DALHOUSE ROAD KM 14/00 TO 32/00 (SH:- HIRING OF EXCVATOR CUM LOADER FOR REMOVAL OF SLIP 14/00 TO 32/00)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	95.00			Per Hours	
Total						

(Signature)
Executive Engineer
Chowari Division
HPPWD Chowari

14

153

SCHEDULE OF QTY

Estimate cost:-99600/-
Earnest Money:-1992/-
Time limit:-Three Month

**NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON GHATASANI PULL BHOLAG KM 0/00 TO 7/360 (SH:- HIRRING OF TIPPER & EXCAVATOR CUM
LOADER FOR REMOVAL OF SLIP 2/00 TO 4/00)**

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner . The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	79.00			Per Hours	
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases . The fuel and operational staff for truck will be provided by the owner . The repair and spare ,watch &ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	30.00			Per Hours	
		Total				

(Signature)
Executive Engineer
Chowari Division
HIDWAD Chowari

SCHEDULE OF QTY

Estimate cost:-99105/-
Earnest Money:-1982/-
Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON GHATASANI PULL BHOLAG KM 0/00 TO 7/360 (SH:- HIRRING OF TIPPER & EXCAVATOR CUM
LOADER FOR REMOVAL OF SLIP 0/00 TO 2/00)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-in-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner. The fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	78.00			Per Hours	
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge. Any loss to public/private property or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases. The fuel and operational staff for truck will be provided by the owner. The repair and spare, watch & ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	31.00			Per Hours	
Total						

(Signature)
Executive Engineer
Chowari Division
HPWD Chokkari

16

SCHEDULE OF QTY

Estimate cost:-96600/-
Earnest Money:-1932/-
Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON LINK ROAD TO VILLAGE FAKRODU KM 0/00 TO 2/700 (SH:- HIRIRING OF EXCAVATOR CUM
LOADER FOR REMOVAL OF SLIP 0/00 TO 1/500)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner .The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	92.00			Per Hours	
		Total				

(Signature)
Executive Engineer
Chowari Division
HPD Chowari

SCHEDULE OF QTY

Estimate cost:-99165/-
Earnest Money:-1983/-
Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON GHATASANI PULL BHOLAG KM 0/00 TO 7/360 (SH:- HIRRING OF TIPPER & EXCAVATOR CUM
LOADER FOR REMOVAL OF SLIP 4/00 TO 7/360)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	77.00			Per Hours	
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases .The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	33.00			Per Hours	
Total						

Executive Engineer
Chowari Division
H.P. Choudhary

18

SCHEDULE OF QTY

Estimate cost:-94500/-
Earnest Money:-1890/-
Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON LINK ROAD VILLAGE DANGARI KM 0/00 TO 5/00 (SH:- HIRRING OF EXCVATOR CUM LOADER FOR REMOVAL OF SLIP 3/00 TO 5/00)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	90.00			Per Hours	
Total						

Executive Engineer
Chowari Division
HPWD Chowari

119

SCHEDULE OF QTY

Estimate cost:-99105/-
Earnest Money:-1982/-
Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON NURPUR SANJHI NALLAH TUNUHATTI ROAD KM 25/00 TO 40/810 (SH:- HIRRING OF TIPPER & EXCAVATOR CUM LOADER FOR REMOVAL OF SLIP 25/00 to 30/00)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty ,malakana toll tax sale tax or any other taxes imposed by the Government.	78.00			Per Hours	
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge. Any loss to public/private property or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases. The fuel and operational staff for truck will be provided by the owner. The repair and spare ,watch &ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	31.00			Per Hours	
		Total				

(Signature)
Executive Engineer
Chowari Division
HPP Chowari

60

SCHEDULE OF QTY

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON NANIKHAD TO SAMLEU ROAD KM 0/00 TO 30/585 (SH- HIRRING OF TIPPER & EXCAVATOR CUM
LOADER FOR REMOVAL OF SLIP 10/00 TO 20/00)

Estimate cost:-99720/-
Earnest Money:-1994/-
Time limit:-Three Month

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner .The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	77.00			Per Hours	
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private property or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases .The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also b borne by the contractor /Owner .The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	34.00			Per Hours	
		Total				

(Signature)
Executive Engineer
Chowari Division
HPPW, Kothowal

(91)

SCHEDULE OF QTY

Estimate cost:- 98700/-
Earnest Money:-1974/-
Time limit:- Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON LINK ROAD TO VILLAGE FAKRODU KM 0/00 TO 2/700 (SH:- HIRIRING OF EXCAVATOR CUM
LOADER FOR REMOVAL OF SLIP 1/500 TO 2/700)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner . The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	94.00			Per Hours	
Total						

(Signature)
Executive Engineer
Chowari Division
HPPW Chowari

92

SCHEDULE OF QTY

Estimate cost:-99600/-
Earnest Money:-1992/-
Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON NURPUR SANHI NALLAH TUNUHATTI ROAD KM 25/00 TO 40/810 (SH:- HIRIRING OF TIPPER & EXCAVATOR CUM LOADER FOR REMOVAL OF SLIP30/00 to 40/810)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner. the fuel& operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	79.00			Per Hours	
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private property or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases. The fuel and operational staff for truck will be provided by the owner. The repair and spare, watch &ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	30.00			Per Hours	
		Total				

(Signature)
Executive Engineer
Chowari Division
HPPW Chowari

23

SCHEDULE OF QTY

Estimate cost:-98730/-
Earnest Money:-1975/-

Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON NANIKHAD TO SAMLEU ROAD KM 0/00 TO 30/585 (SH:- HIRING OF TIPPER & EXCAVATOR CUM
LOADER FOR REMOVAL OF SLIP 0/00 TO 10/00)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	75.00			Per Hours	
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private property or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases .The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	36.00			Per Hours	
Total						

(Signature)
Executive Engineer
Chowari Division
HPPYD Chowari

24

ipeg

SCHEDULE OF QTY

Estimate cost:-96630/-
Earnest Money:-1933/-
Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON PATKA TO DALHOUSE ROAD KM 45/00 TO 67/00 (SH:- HIRRING OF TIPPER & EXCAVATOR CUM
LOADER FOR REMOVAL OF SLIP 56/00 TO 67/00)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	73.00			Per Hours	
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private property or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases .The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge.	36.00			Per Hours	
Total						

Executive Engineer
Chowari Division
HPPV B Chowari

SCHEDULE OF QTY

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON NANIKHAD TO SAMLEU ROAD KM 0/00 TO 30/585 (SH:- HIRRING OF TIPPER & EXCVATOR CUM
LOADER FOR REMOVAL OF SLIP 20/00 TO 30/00)

Estimate cost:-99225/-
Earnest Money:-1985/-
Time limit:-Three Month

96

40-jf

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	76.00			Per Hours	
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases .The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	35.00			Per Hours	
		Total				

Executive Engineer
Chowari Division
HPW Chowari

SCHEDULE OF QTY

Estimate cost:-99750/-
Earnest Money:-1994/-

Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON PATKA TO DALHOUSE ROAD KM 45/00 TO 67/00 (SH:- HIRING OF TIPPER & EXCAVATOR CUM
LOADER FOR REMOVAL OF SLIP 45/00 TO 56/00)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner . The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	77.00			Per Hours	
2	Hiring of tipper having capacity 5.50(Five decimal five Zero)cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge.Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases . The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also b borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	34.00			Per Hours	
		Total				

Executive Engineer
Chowari Division
HPW Chowari

SCHEDULE OF QUANTITY

Estimate cost:-98700/-
Earnest Money:-1974/-
Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON GHATASANI PULL TO BHOLAG ROAD KM 0/00 TO 7/360 (SH:- HIRRING OF EXCAVATOR CUM
LOADER OF SLIPS)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	94.00			Per Hours	
Total						

EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.P.W.D CHOWARI

29

SCHEDULE OF QUANTITY

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON PARCCHODE TO NADDAL ROAD KM 0/00 TO 3/708(SH:- HIRING OF EXCAVATOR CUM LOADER OF

SLIPS)

Estimate cost:-95550/-					
Earnest Money:-1911/-					
Time limit:-Three Month					
S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		AMOUNT
			In No	In Fig	
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner . The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malhana toll tax sale tax or any other taxes imposed by the Government.	91.00			Per Hours
Total					

EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.P.W.D CHOWARI

SCHEDULE OF QUANTITY

Estimate cost:-98700/-

Earnest Money:-1974/-

Time limit:-Three Month

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON BAILLY TO KHADDI ROAD KM 0/00 TO 4/200(SH:- HIRRING OF EXCAVATOR CUM LOADER OF SLIPS
IN KM 0/00 TO 4/200)

S.NO	EXCAVATION & SUB - HEAD	QTY	RATE		UNIT	AMOUNT
			In No	In Fig		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the LCB/Excavator owner .the fuel& operationa staff for machine will be provided by the owner . The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	94.00			Per Hours	
Total						

(Signature)
EXECUTIVE ENGINEER
CHOWARI DIVISION
H.P.P.W.D CHOWARI

Schedual of Qty


Estimated Cost:- Rs.97066.00
Earnest Money :- Rs. 1941.00
Time Limit :- Two Months.

NAME OF WORK :- RESTORATION OF RAIN DAMAGE ON DUKHAR TO MORTHU ROAD KM 0/00 TO 8/00(SH:- C/O
R/WALL AT RD 0/510 TO 0/512.50)

Sr.No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax or any other taxes imposed by the Government.	12.08			Per Cubic Metre	
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	18.53			Per Cubic Metre	

(21)

3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sales tax or any other taxes imposed by the Government.	1.13				Per Cubic Metre	
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.00				Each	
						Total: -	


 Executive Engineer
 Chowari Division
 HPPWD Chowari

Khigali


Schedual of Qty

Estimated Cost: - Rs.96603.00
Earnest Money :- Rs. 1932.00
Time Limit :- Two Months.

NAME OF WORK :- CONSTRUCTION OF LINK ROAD BAGDHAR TO CHHUNUI KM 0.00 TO 3/350(SH:- C/O R/WALL WITH PUSHTA AT RD 2/540 TO 2/542.60)

Sr.No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax or any other taxes imposed by the Government.	5.62			Per Cubic Metre	
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all hights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	19.92			Per Cubic Metre	

3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sales tax or any other taxes imposed by the Government.	3.33				Per Cubic Metre	
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.00				Each	
						Total: -	


 Executive Engineer
 Chowari Division
 HPPWD Chowari

33

Schedual of Qty

Estimated Cost: - Rs.99247.00
Earnest Money :- Rs. 1985.00
Time Limit :- Two Months.

NAME OF WORK :- CONSTRUCTION OF LINK ROAD BAGDHAR TO CHHUNUI KM 0.00 TO 3/350(SH:- C/O RWALL WITH PUSHTA AT RD 2/545.10 to 2/547.70)

Sr.No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax or any other taxes imposed by the Government.	3.64			Per Cubic Metre	
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all hights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.59			Per Cubic Metre	

3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sales tax or any other taxes imposed by the Government.	4.07			Per Cubic Metre	
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	5.00			Each	
					Total: -	


 Executive Engineer
 Chowari Division
 H.P. PWD
 CHOWARI