

OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG

PH: 01907-222229 Fax: 222229, e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2024-

3824

Dated:- 30⁷/2025

To

✓ The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.

Subject :-

Regarding publication of Tender on departmental site.

With reference to the notification issued by the Secretary(PW) to the Government of Himachal Pradesh No. P BW(B)A(3)1/2024 dated 03.01.2024 and PBW-B-F0(2)/3/2024-284016 dated 18.07.2025, enclosed please find herewith the copy of Notice Inviting Tender for the loading on departmental web-site as

Certified that the works mentioned in the Tender Notice are urgent in nature and in coordination with the Disaster Management Act, 2005 Section 24 (i).

Encl:- As above.

Executive Engineer,
B&R Division,
HP PWD Karsog

**OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG**
PH: 01907-222229 Fax: 222229 , E-mail : ee-kar-hp@nic.in

Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **08.08.2025 upto 11.00 AM** and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 07.08.2025** for which the application should reach in this office **upto 1.00 PM 07.08.2025**.

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/R damages on Sursi Kani Mandlah road Km. 0/00 to 4/500 (SH:- C/o R/wall at RD 0/875 to 0/895)	3,85,416/-	7,800/-	One month	350/-
2	R/R damages on Bakhrot Sanarli Kelodhar Luhri road (Portion Bakhrot to Behna) Km. 0/00 to 41/800) SH:- Repair of Bridge railing at RD 40/850 at Behna	1,54,104/-	3,100/-	One month	350/-
3	Consultancy Service for preparation FCA cases of various roads under Karsog under Karsog Sub-Division (SH:- Preparation & getting approval under FCA of Chera to Parlog Km. 0/00 to 4/00, Kelodhar Sainj road Km. 0/00 to 19/00 (SH:- FCA case Km. 15/340 to 19/00).	3,54,000/-	7,100/-	One year	350/-
4	R/R damages due to laying OFC cable on Chindi Pangna road Km. 0/00 to 12/480 (SH:- C/o R/wall at RD 4/005 to 4/019)	4,98,802/-	10,000/-	Two months	350/-

	R/R damages on Shimla Mandi via Tattapani road Km. 55/500 to 90/00 (SH:- Hiring of JCB/Excavator cum loader for removal of slips at Various RDs between Km. 55/00 to 65/00) Job-02	98,900/-	2,000/-	One month	350/-
6	R/R damages on Bag to Pokhi raod Km. 0/00 to 10/00 (SH:-Hiring of JCB/Excavator cum loader for removal of slips at various RDs in Km. 5/00 to 10/00)	98,900/-	2,000/-	One month	350/-
7	R/R damages on Bag to Pokhi raod Km. 0/00 to 10/00 (SH:-Hiring of JCB/Excavator cum loader for removal of slips at various RDs in Km. 0/00 to 5/00)	98,900/-	2,000/-	One month	350/-
8	R/R damages on Seri Shout road Km. 0/00 to 19/00 (SH:- Hiring of JCB for removal of slips, dressing of road surface and construction of road side katcha drain in various RDs) Job No. 2	98,900/-	2,000	One month	350/-
9	R/R damages on Kelodhar Chhatri road Km. 0/0 to 19/00 (SH:- Hiring of JCB for removal of slips, dressing of road surface and construction of road side katcha drain in various RDs)	97,750/-	2,000/-	One month	350/-
10	R/R damages on various roads under Alsindi section under HPPWD Sub-Division Churag (SH:- Hiring of Tipper for carriage and disposal of muck/debris at various RDs) Job 03	99,000/-	2,000/-	One month	350/-
11	R/R damages on various roads under Churag Sanction under HPPWD Churag Sub-Division (SH:- Hiring of Tipper for carriage and disposal of muck/debris at various RDs) Job 01	99,000/-	2,000/-	One month	350/-
12	R/R damages on Chamunallah to Bagshar road Km. 0/00 to 3/00 & Kamru to Khadihan road Km. 0/00 to 5/00 (SH:- Hiring of JCB/Excavator cum loader For removal of slips at various RDs)	98,900/-	2,000/-	One month	350/-
13	R/R damages on Kahnnoo to Prangan raod Km. 0/00 to 5/00 (SH:- Hiring of JCB/Excavator cum loader for removal of slips at various RDs)	98,900/-	2,000/-	One month	350/-
14	C/o Chholdhar to Panoutdehra road Km. 0/0 to 2/700 (SH:- C/o R/wall at RD 2/608 to 2/611) (Balance work) SCDP	87,800/-	1,800/-	Two months	350/-
15	R/R damages on Karsog Kanda road Km. 0/00 to 12/00 (SH:- C/o R/wall at RD 0/190 to 0/200)	4,98,486/-	10000	One month	350/
16	R/R Damages on Tattapani Khanderi Lumsher road Km 0/00 to 6/500 (SH:- Hiring of JCB/Excavator cum loader for removal of slips at various RDs between Km. 0/00 to 6/500) Job No.2	98,900/-	2,000/-	One month	350/-
17	R/R damages on Tattapani to Shakra road Km. 0/00 to 10/00 & R/R damages on Shakra to Parlog village Bindla Km. 0/00 to 6/250 (SH:- Hiring of JCB/Excavator cum loader for removal of slips at various RDs between Km. 0/00 to 6/00) Job No.2	98,900/-	2,000/-	One month	350/-
18	R/R damages on Shimla Mandi via Tattapani road Km. 55/500 to 90/00 (SH:- Hiring of JCB/Excavator cum loader for removal of slips at between Km. 72/00 to 80/00)	98,900/-	2,000/-	One month	350/-

19	R/R damages on Chauridhar Kotlu road Km. 0/00 to 8/00 (SH:- Hiring of JCB/Excavator cum loader for removal of slips at various RDs)	98,900/-	2,000/-	One month	350/-
20	R/R damages on Kelodhar Sainj road Km. 0/00 to 8/00 (SH:- Hiring of JCB/Excavator cum loader for removal of slips at various RDs)	98,900/-	2,000/-	One month	350/-
21	Preparation of Forest Case Conservation Act, 1980 for the Construction of road Behli mod to Neudi mohal Km. 0/00 to 1/200 (FRA Case)	30,000/-	600/-	Two months	350/-
22	R/R damages on Bakhrot Sanarli Kelodhar Luhri road (MDR-21) under HPPWD Pangna Sub-Division (SH:- Hiring of JCB/Excavator cum loader For removal of slips in Km. 20/00 to 30/00)	98,900/-	2,000/-	One month	350/-
23	R/O (Repair of) road from Sarahan to Haripur road Km. 0/00 to 10/00 (SH:- Removal of slips and maintenance of berm at various RDs) Deposit SDF/2024/156	1,99,416/-	4,000/-	One month	350/-
24	C/O (Construction of) road from Shakwa to Sarandi Km. 0/00 to 6/00 (SH:- C/o Earthen shoulder and maintenance of berm at various RDs) Deposit SDP/2024/249	1,99,859/-	4,000/-	One month	350/-
25	R/O (Repair of) road from Shakwa to Sarandi Km. 0/00 to 6/00 (SH:- Removal of slips & maintenance of berm at various RDs)	99,070/-	2,000/-	One month	350/-
26	R/R damages on Kotlu to Katanda road Km. 0/00 to 35/00 (SH:- C/o R/wall at RD 16/885 to 16/900)	4,99,628/-	10,000/-	One month	350/-

TERMS & CONDITIONS:-

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act.
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification PW/CTR/32-20Genl Inst-CPWD/2020-37996-38095 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.

Executive Engineer
B&R Division
HPPWD Karsog

No. PW-E-Tender-NIT/2025-26-

3818-23

Dated:-

30/3/2025

1. All the Assistant Engineers, working under this Division.
2. Copy to Drawing & Account Branch.
3. Notice board of this office.

Executive Engineer,
B&R Division,
HP PWD Karsog

Percentage BOQ

Name of Work: R/R Damages on Sursi Kant Mandah road Km. 0/00 to 4/500 (SH-1: C/O R/wall at RD 0/875 to 0/895)

Contract No:

Name of the Bidder/ Bidding Firm / Company

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT with all taxes including GST Rs. P	TOTAL AMOUNT with all taxes including GST Rs. P	TOTAL AMOUNT with all taxes including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shooting and bracing removal of stumps and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	39.60	Per Cubic Meter	390.20	15451.92	15451.92	INR Fifteen Thousand Four Hundred Fifty One & Paise Ninety Two Only
2	Providing and laying concrete for plain/reinforcement concrete 1:4:8 (one cement : eight sand : eight graded stone aggregate) in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	62.70	Per Cubic Meter	5500.00	344850.00	344850.00	INR Three Lakh Forty Four Thousand Eight Hundred Fifty & Paise Zero Only
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3, or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals	11.60	Per Cubic Meter	1200.00	13920.00	13920.00	INR Thirteen Thousand Nine Hundred Twenty & Paise Zero Only
4	Providing weepholes in bricks masonry/stone masonry plain/reinforced complete abutment wing wall, return wall with 100 mm (one hundred millimeter) dia PVC pipe extending through the full with the structure with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 70, 1204.3, 7 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	30.00	Each	373.15	11194.50	11194.50	INR Eleven Thousand One Hundred Ninety Four & Paise Fifty Only
Total In Figures					385416.42	385416.42	INR Three Lakh Eighty Five Thousand Four Hundred Sixteen & Paise Forty Two Only
Quoted Rate In Figures			Select		0.00	0.00	INR Zero Only
Quoted Rate In Words					INR Zero Only		

Bill of quantity checked and approved for Rs. 3,85,416.42
For the year 2025-26 Sr. No. - 49

Executive Engineer
Kansog Division
CHPPWD Kansog

Estimated Money 7,800/-
Time One month

Percentage Boq

Tender Inviting Authority: **Public Works Department, Government of Karnataka**

Name of Work: **Repair of Bridge falling at RD 40/850 at Belmal**

Contract No: **154104.57**

Name of the Bidder: **CHPPWD Karboog**

Item: **Repair of Bridge falling at RD 40/850 at Belmal**

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, also the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Value only)

Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. p	TOTAL AMOUNT with all taxes including GST in Rs. p	TOTAL AMOUNT with all taxes including GST in Rs. p	TOTAL AMOUNT with all taxes including GST in Words
1	Steel work welded in built up structural framed work, including cutting, blasting, fitting in position and applying a priming coat of approved steel primer using shop/dredge etc as required or as per direction of Engineer-in-Charge including carriage of material within all limits, fits and other incidental	204.16	Per Kilo Gram	180.50	36832.54	36832.54	INR Thirty Six Thousand Nine Hundred Thirty Two & Paise Only
2	Providing and laying of 1.5% concrete with G.I. fittings and clamps, the cutting and making good the walls etc. Internal work 50 mm (minimum) the removal layer or as per direction of Engineer-in-Charge including carriage of material within all limits, fits and other incidental	63.60	Per Cubic Meter	715.90	45547.24	45547.24	INR Forty Five Thousand Five Hundred Forty Seven & Paise Only
3	Providing and laying of 1.5% concrete with G.I. fittings and clamps, the cutting and making good the walls etc. Internal work 50 mm (minimum) the removal layer or as per direction of Engineer-in-Charge including carriage of material within all limits, fits and other incidental	10.99	Per Cubic Meter	6171.50	67824.79	67824.79	INR Sixty Seven Thousand Eight Hundred Twenty Four & Paise Only
Total in Figures					154104.57	154104.57	INR One Lakh Fifty Four Thousand One Hundred Four & Paise Only
Quoted Rate in Figures					0.00	0.00	INR Zero Only
Quoted Rate in Words							INR Zero Only

Bill of quantity checked and approved for Rs. 154104.57 for the year 2025-26 Sr. No 82

Executive Engineer
Karboog Division
CHPPWD Karboog

Price - one year
 E-memo - 3, 100/-
 Time - one month

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority:

Name of Work:- Consultancy Services for Preparation FCA cases of various roads under Karsog Sub Division (Sh:- Preparation & getting approval under FCA of Chera to Parlog Km 0/00 to 4/00, Kelodhar Sainj Road Km 0/00 to 19/00(Sh:- FCA case Km 15/340 to 19/00)

Contract No:

Name of the Bidder/ Bidding Firm / Company

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT with all taxes including GST Rs. P	TOTAL AMOUNT with all taxes including GST Rs. P	TOTAL AMOUNT with all taxes including GST In Words
1	Consultancy Services for Preparation of FCA cases of various roads under Karsog Sub Division H.P PWD Karsog including preparation of Revenue Papers (i.e field book, Jamabandi, Tatima etc.), Digital map, KML files, CA map and any other documents required until the final approval (Stage-I & Stage-II approval) for following roads as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other Incidentals.						
1.01	Chera to Parlog road Km 0/00 to 4/00	4.00	Per Job	177000.00	177000.00	177000.00	INR One Lakh Seventy Seven Thousand & Paise Zero Only
1.2	Kelodhar Sainj Road Km 0/00 to 19/00(Sh:- FCA case Km 15/340 to 19/00)	3.660	Per Job	177000.00	177000.00	177000.00	INR One Lakh Seventy Seven Thousand & Paise Zero Only
Total in Figures					354000.00	354000.00	INR Three Lakh Fifty Four Thousand & Paise Zero Only
Quoted Rate in Figures			Select		0.00	0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only		

Bill of Quantity checked and approved for Rs. 3,54,000/- only for the year 2025-26 Sr. No. 75

Executive Engineer
Karsog Division
Jammu & Kashmir

5-008-354,000/-
Five - one year

Percentage Schedule Of Quantity

Estimated Cost 498802
Earnest Money 10000
Time Two Months

Name of Work:- R/R Damages due to laying OFC cable on Chindi Pangna road km 0/00 to 12/480. (SH:- C/O R/Wall at RD 4/005 to 4/019)

Sub-Head and Items of works.

Sl.No.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	23.94	Per Cubic Metre	198.35	4748	Rupees Four Thousand Seven Hundred Forty Eight and Paise Forty Nine Only
2	4.62	Per Cubic Metre	390.20	1803	Rupees One Thousand Eight Hundred Two and Paise Seventy Two Only
3	82.74	Per Cubic Metre	5500.00	455070	Rupees Four Lakhs Fifty Five Thousand Seven and Paise Zero Only
4	15.00	Each	373.15	5597	Rupees Five Thousand Five Hundred Ninety Seven and Paise Twenty Five Only
5	26.32	Per Cubic Metre	1200.00	31584	Rupees Thirty One Thousand Five Hundred Eighty Four and Paise Zero Only
Total In Figures				498802	
Quoted Rate In Figures		Select			0.00
Quoted Rate In Words					

Executive Engineer,
Karsog Division,
CHPWARD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 98900
Earnest money 2000
Time One Month

Name of Work:- R/R Damages on Shimla Mandi via Tattapani road Km 55/500 to 90/00 (SH:- Hiring of JCB/Excavator cum loader for removal of slips at various RD's between KM 55/500 to 65/00) Job-02

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Hiring of JCB/excavator for removal of slips and boulder in all kinds of soil including rock portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts as per direction of Engineer-In-Charge. The machine/JCB should work 8 Hrs. daily and remove at least 25.0 cum. quantity of slips per hour. Any loss to the public/private property or any accident etc. should be absolute responsibility of the JCB/excavator owner which shall have to be fully compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, the repair and spare watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by Engineer-In-Charge.	86.00	Per Hour	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Total in Figures					98900.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
GHPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 98900
Earnest money 2000
Time One Month

Name of Work:- R/R Damages on Bag to Pokhi road Km. 0/00 to 10/00 (SH:- Hiring of JCB/Excavator cum loader for removal of slips at various RD's in Km. 5/00 to 10/00)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Hiring of JCB/excavator for removal of slips and boulder in all kinds of soil including rock portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts as per direction of Engineer-In-Charge. Any loss to the public/private property or any accident etc. should be absolute responsibility of the JCB/excavator owner which shall have to be fully compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, the repair and spare watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by Engineer-In-Charge.	86.00	Per Hour	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Total in Figures					98900.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 98900
Earnest money 2000
Time One Month

Name of Work:- R/R Damages on Bag to Pokhi road Km. 0/00 to 10/00 (SH:- Hiring of JCB/Excavator cum loader for removal of slips at various RD's in Km. 0/00 to 5/00)


Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Hiring of JCB/excavator for removal of slips and boulder in all kinds of soil including rock portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts as per direction of Engineer-In-Charge. Any loss to the public/private property or any accident etc. should be absolute responsibility of the JCB/excavator owner which shall have to be fully compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, the repair and spare watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by Engineer-In-Charge.	86.00	Per Hour	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Total in Figures					98900.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule of quantity

Work:-R/R Damages on Seri Shout road Km 0/00 to 19/0 (Sh:- Hiring of JCB for removal of slips,dressing of road surface and
 aruction of road side kutcha drain in various RD's) Job No.2


Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Hiring of JCB Machine for dressing of road surface consturion of road side kutcha drain and removal of slips from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-Charge. Any loss to the public/private property or any accident etc happened during the course of hiring period shall be absoluteresponsibility of the JCB owner which shall have to be fully compensated by him in all cases.The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/owner.The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	86.00	Hour	1150.00	Rupees One Thousand One Hundred & Fifty Only	98900.00
Total in Figures						98900.00
Quoted rate in figure						
Quoted rate in words						


 Executive Engineer,
 Karsog Division,
 QHPPWD, Karsog.

Percentage Schedule of quantity

Name of Work:- R/R Damages on Ketodhar Chhatri Road Km 0/0 to 19/0 (Sh:- Hiring of JCB for removal of slips, dressing of road surface and construction of road side kutchra drain in various RD's)

Sl. No.	Description of work	Qty.	Unit	Figures	Estimated cost:-	
					Earnest Money	97750.00
					Time	2000
					One month	
1	Hiring of JCB Machine for dressing of road surface consturion of road side kutchra drain and removal of slips from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-Charge. Any loss to the public/private property or any accident etc happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	85.00	Hour	1150.00	Rupees One Thousand One Hundred & Fifty Only	97750.00
Total in Figures						97750.00
Quoted rate in figure						
Quoted rate in words						



 Executive Engineer,
 Karsog Division,
 JHPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 99000
Earnest money 2000
Time One Month

Name of Work:- R/R Damages on various roads under Aisindi Senction under HPPWD Sub Division Churag(SH):- Hiring of Tipper for Carriage and disposal of muck/debris at various RD's) Job-03

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with	Total Amount with all taxes including GST in Words
1	Hiring of Tipper for Carriage and disposal of debris to dumping site of work with lift to suitable place with in all heads and lifts to the entire satisfaction of the Engineer-in-Charge. The Tipper should work minimum 08.00 (Eight) Hours daily and Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the Tipper owner which shall have to be fully compensated by him in all cases. The fuel and Tipper driver and lodging & boarding of operational staff will be provided by the Tipper owner the repair and spare including watch and ward of Tipper also borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by Engineer-In-Charge.	33.00	Per Day	3000.00	99000.00	Rupees Ninety Nine Thousand and Paise Zero Only
Total in Figures					99000.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage schedule Of Quantity

Estimated Cost 99000
Earnest money 2000
Time One Month

Name of Work:- R/R Damages on various roads under Churag Saction under HPPWD Churag Sub Division (SH:- Hiring of Tipper for Carriage and disposal of muck/debris at variousRD's) Job-01

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In	Toatal Amount with	Total Amount with all taxes
1	Hiring of Tipper for Carriage and disposal of debris to dumping site of work with lift to suitable place with in all leads and lifts to the entire satisfaction of the Engineer-in Charge. The Tipper should work minimum 8 Hrs. daily and Any loss to the public/private property or any accident etc. heppened during the course of hiring period shall be absolute responsibility of the Tipper owner which shall have to be fully compensated by him in all cases. The fuel and Tipper driver and lodging & boarding of operational staff will be provided by the Tipper owner the repair and spare including watch and ward of Tipper also borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by Engineer-In-Charge.	33.00	Per Day	3000.00	99000.00	Rupees Ninety Nine Thousand and Paise Zero Only
Total in Figures					99000.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98900
Earnest money 2000
Time One Month

Name of Work:- R/R Damages on Chamunallah to Bagshar road KM 0/00 to 3/00 & Kamru to Khadain road KM 0/00 to 5/00 (SH:- Hiring of JCB/Excavator cum loader for removal of slips at various RD's)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with	Total Amount with all taxes including GST in Words
1	Hiring of JCB/excavator for removal of slips and boulder in all kinds of soil including rock portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any heads and lifts as per direction of Engineer-in-Charge. The machine/JCB should work minimum 08.00 Hours (Eight) daily and remove at least 25.0 cum. Quantity of slips per hour. Any loss to the public/private property or any accident etc. should be absolute responsibility of the JCB/excavator owner which shall have to be fully compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, the repair and spare watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by Engineer-In-Charge.	86.00	Per Hour	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Total in Figures					98900.00	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost
Earnest money
Time

98900
2000
One Month

Name of Work:- R/R Damages on Kahnoo to Parangan road KM 0/00 to 5/00 (SH:- Hiring of JCB/Excavator cum loader for removal of slips at various RD's)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with	Total Amount with all taxes including GST in Words
1	Hiring of JCB/Excavator for removal of slips and boulder in all kinds of soil including rock portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts as per direction of Engineer-In-Charge. The machine/JCB should work minimum 08 00 Hours (Eight) daily and remove at least 25.0 cum. Quantity of slips per hour. Any loss to the public/private property or any accident etc. should be absolute responsibility of the JCB/Excavator owner which shall have to be fully compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, the repair and spare watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by Engineer-In-Charge.	86.00	Per Hour	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Total in Figures					98900.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest Money

87800
1800

Time

Two Months

Name of Work:- C/O Chholdhar to Panoutdehra Road Km 0/0 to 2/700 (SH:- C/O R/Wall at RD 2/608 to 2/611)(Balance work) SCDP

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	14.61	Per Cubic Metre	379.90	5550.00	Rupees Five Thousand Five Hundred & Fifty Only
2	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	9.52	Per Cubic Metre	5500.00	52360.00	Rupees Fifty Two Thousand Three Hundred & Sixty Only
3	Providing weapholes in brick masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm(One hundred milli meter) dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204,3.7 As per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	9.00	Each	373.15	3358.00	Rupees Three Thousand Three Hundred & Fifty Eight Only
4	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600 mm with smaller size towards the soil and bigger size to wards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification clause 1204,3.8, as per direction of Engineer - in - Charge including carriage of material within all leads and lifts and other incidentals.	22.11	Per Cubic Metre	1200.00	26532.00	Rupees Twenty Six Thousand Five Hundred & Thirty Two Only
Total in Figures					87800	
Quoted Rate In Figures						
Quoted Rate In Words						

Executive Engineer,
Karsog Division,
ChPRWD, Karsog.

Tender Inviting Authority:

Name of Work:- R/R Damages on Karsog Kanda road Km. 0000 to 1200SH:- C/O R/Wall at RD 0/190 to 0/200

Contract No:

Name of the Bidder Bidding Firm / Company

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

SL No.	Item Description	Quantity	Units	Estimated Rate in Rs. p	TOTAL AMOUNT with all taxes including GST Rs. p	TOTAL AMOUNT with all taxes including GST Rs. p	TOTAL AMOUNT including GST in Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stumps and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	29.70	Per Cubic Meter	390.20	11588.94	11588.94	INR Eleven Thousand Five Hundred Eighty Eight & Paise Ninety Four Only
2	Providing and laying concrete for plain/reinforcement concrete 1:4:8 (one cement : eight sand : eight graded stone aggregate) in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	81.60	Per Cubic Meter	5500.00	448800.00	448800.00	INR Four Lakh Forty Eight Thousand Eight Hundred & Paise Zero Only
3	Providing weepholes in bricks masonry/stone masonry plain/reinforced complete abutment wing wall, return wall with 100 mm (one hundred millimeter) dia PVC pipe extending through the full with the structure with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 70, 1204.3.7 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	50.00	Each	373.15	18657.50	18657.50	INR Eighteen Thousand Six Hundred Eighty Seven & Paise Fifty Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3. or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals	16.20	Per Cubic Meter	1200.00	19440.00	19440.00	INR Nineteen Thousand Four Hundred Forty & Paise Zero Only
Total In Figures					498486.44	498486.44	INR Four Lakh Ninety Eight Thousand Four Hundred Eighty Six & Paise Forty Four Only
Quoted Rate In Figures			Select		0.00	0.00	INR Zero Only
Quoted Rate In Words					INR Zero Only		

Bill of Quantity checked and approved for Rs. 4,98,486.44
For the year 2025-26 Sr.No 72

Executive Engineer
Karsog Division
CHPWARD Karsog

Percentage Schedule Of Quantity

Estimated Cost 98900
Earnest money 2000
Time One Month

Name of Work:- R/R Damages on Tattapani Khanderi Lumsher road Km 0/00 to 6/500 (SH:- Hiring of JCB/Excavator cum loader for removal of slips at various RD's between KM ~~0/00 to 6/500~~ Job-02

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Hiring of JCB/excavator for removal of slips and boulder in all kinds of soil including rock portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts as per direction of Engineer-In-Charge. The machine/JCB should work 8 Hrs. daily and remove at least 25.0 cum. quantity of slips per hour. Any loss to the public/private property or any accident etc. should be absolute responsibility of the JCB/excavator owner which shall have to be fully compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, the repair and spare watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by Engineer-In-Charge.	86.00	Per Hour	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Total in Figures					98900.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
APPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost
Earnest money
Time

98900
2000
One Month

Name of Work:- R/R Damages on Tattapani to Shakra road KM 0/00 to 10/00 & R/R Damages on shakra to Parlog Upto village Bindla Km 0/00 to 6/250(SH):- Hiring of JCB/Excavator
cum loader for removal of slips at various RD's Job-02

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with Amount with	Total Amount with all taxes including GST In Words Rupees Niney Nine Thousand and Paise Zero only
1	Hiring of JCB/Excavator for removal of slips and boulder in all kinds of soil including rock portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts as per direction of Engineer-In-Charge. The machine/JCB should work from 9:00 AM to 5:00 PM daily and remove at least 25.0 cum. Quantity of slips per hour. Any loss to the public/private property or any accident etc. should be absolute responsibility of the JCB/Excavator owner which shall have to be fully compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, the repair and spare watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by Engineer-In-Charge.	86.00	Per Hour	1150.00	98900.00	
Total in Figures					98900.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98900
Earnest money 2000
Time One Month

Name of Work:- R/R Damages on Shimla Mandi via Tattapani Road km 55/500 to 90/00 (SH:- Hiring of JCB/Excavator cum loader for removal of slips at Between KM 72/00 to 80/00)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/Excavator for removal of slips and boulder in all kinds of soil including rock portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts as per direction of Engineer-In-Charge. The machine/JCB should work minimum 08:00 Hours (Eight) daily and remove at least 25.0 cum. Quantity of slips per hour. Any loss to the public/private property or any accident etc. should be absolute responsibility of the JCB/Excavator owner which shall have to be fully compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, the repair and spare watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by Engineer-In-Charge.	86.00	Per Hour	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Total in Figures					98900.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
DPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98900
Earnest money 2000
Time One Month

Name of Work:- R/R Damages on Chauridhar Kotlu road Km. 0/00 to 8/00 (SH:- Hiring of JCB/Excavator cum loader for removal of slips at various

RD's) Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/excavator for removal of slips and boulder in all kinds of soil including rock portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts as per direction of Engineer-In-Charge. Any loss to the public/private property or any accident etc. should be absolute responsibility of the JCB/excavator owner which shall have to be fully compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, the repair and spare watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by Engineer-In-Charge.	86.00	Per Hour	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Total in Figures					98900.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
DPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost 98900
Earnest money 2000
Time One Month

Name of Work:- R/R Damages on Kelodhar Sainj road Km. 0/00 to 19/00 (SH:- Hiring of JCB/Excavator cum loader for removal of slips at various

RD's)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Hiring of JCB/excavator for removal of slips and boulder in all kinds of soil including rock portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts as per direction of Engineer-In-Charge. Any loss to the public/private property or any accident etc. should be absolute responsibility of the JCB/excavator owner which shall have to be fully compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, the repair and spare watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by Engineer-In-Charge.	86.00	Per Hour	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred and Paise Zero Only
Total in Figures					98900.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
CHPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost
Earnest money

30000
600

Time

Two Months

Name of Work:- Preparation of Forest Diversion case under Forest Conservation Act, 1980 for the Construction of road Behli mod to Neudi mohal km 0/00 to 1/200 (FRA Case)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Preparation of Forest Diversion case under Forest Conservation Act, 1980 including preparation of revenue papers of land falling on the road alignment and collection of the other field data. All relevant documents/ formats mandatory required would be attached with the case as per latest requirement of Ministry of Environment and Forest conservation Govt. of India after getting the joint inspection/site including computer typing in six copies, binding complete and getting it through from HPPWD, concern Sub - Division Karsog, HPPWD Division Karsog , Office of concern Range Officer, concern Office of Divisional Forest Officer Karsog. Including attending all the observation, if raised, at any time by any above mentioned office and to prepare the same by neatly and accurately filling in all the formats/ Documents complete in all respect as per direction and complete satisfaction of HPPWD and Forest Department. Preparation of Plan with GPS Coordinates 250 mtr. Interval with collecting data from site including preparation of KML files and PDF files of Maps. (FRA Case)	1.00	Per Job	30000.00	30000.00	Rupees Thirty Thousand and Paise Zero Only
Total in Figures					30000.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 98900
 Earnest money 2000
 Time One Month

Name of Work:- R/R Damages on Bakhtrot Sanarali Kelodhar Luhri road (MDR-21) under HPPWD Pangna Sub Division(SH:- Hiring of JCB/Excavator cum loader for removal of slips in km 2000 to 30/00)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs.	Total Amount with all taxes including GST in Words
1	Hiring of JCB/Excavator for removal of slips and boulder in all kinds of soil including rock portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts as per direction of Engineer-In-Charge. Any loss to the public/private property or any accident etc. should be absolute responsibility of the JCB/Excavator owner which shall have to be fully compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, the repair and spare watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by Engineer-In-Charge.	86.00	Per Hour	1150.00	98900.00	Rupees Ninety Eight thousand Nine Hundred and Paise Zero only
Total In Figures					98900.00	
Quoted Rate In Figures						
Quoted Rate in Words						

Executive Engineer,
 Karsog Division,
 HPPWD, Karsog.

7/4
 23
 E-way - 4000
 Five - one work

Percentage BoQ

Tender Invited - Amendment									
Name of Work: S.O. Repair of Road from Surawan to Hargur road Km. 0.00 to 10.00 (Sht. Removal of slips & maintenance of beam at various RDS) Deposit SDF-2024-155									
Contract No:									
Name of the Bidder/ Bidding Firm/ Company:									
PRICE SCHEDULE (This BOQ sample must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)									
S. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT with all taxes excluding GST Rs. P	TOTAL AMOUNT without all taxes and GST Rs. P	TOTAL AMOUNT in Words		
1	Removal of land slide slip clearance - Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of old material, with in all heads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all heads and lifts and other materials.	935.53	Per Cubic Meter	120.00	112263.60	112263.60	INR One Lakh Twelve Thousand Four Hundred Sixty Three 5 Paise Only		
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by using fresh approved selected soil and compacting it with appropriate equipment as per any as per technical specification clause 1303 with in all heads and lifts and other materials as per direction of Engineer-in-Charge with in all heads and lifts and other materials.	3951.50	Per Square Meter	22.00	87153.00	87153.00	INR Eighty Seven Thousand One Hundred Fifty Three 0 Paise Zero Only		
Total in Figures					199416.60	199416.60	INR One Lakh Ninety Nine Thousand Four Hundred Sixty Six Paise Six Only		
Quoted Rate in Figures			Select		0.00	0.00	INR Zero Only		
Quoted Rate in Words					INR Zero Only				

bill of quantity checked and approved for Rs 199416/- for the year 2025-26 Sr.No.5

Executive Engineer
 Karsog Division
 HP PWD Karsog

254

Percentage BOQ

Tender Inviting Authority:

Name of Work: C/O (Construction of) Road from Shakhwa to Sarandi Km. 0/00 to 6/00 (Sh. C/O earthen shoulder & maintenance of berm at various RD's) Deposit SDD/2024/249

Contract No:

Name of the
Bidder/ Bidding
Firm / Company

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. p	TOTAL AMOUNT with all taxes excluding GST Rs. p	TOTAL AMOUNT without all Taxes and GST Rs. p	TOTAL AMOUNT in Words
1	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of table 300.2 with any lead as per technical specification clause 303.1 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	375.64	Per Cubic Meter	268.50	100859.34	100859.34	INR One Lakh Eight Hundred Fifty Nine & Paise Thirty Four Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	4500.00	Per Square Meter	22.00	99000.00	99000.00	INR Ninety Nine Thousand & Paise Zero Only
Total in Figures					199859.34	199859.34	INR One Lakh Ninety Nine Thousand Eight Hundred Fifty Nine & Paise Thirty Four Only
Quoted Rate in Figures			Select		0.00	0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only		

Bill of quantity checked & approved
for Rs 199859.34 for the year
2025-26 at Sr No 3

Executive Engineer
Karsog Division
HP PWD Karsog

E-mat - 2 Year 1-
Time - One with

Percentage Schedule of Quantity

Estimated Cost	99070
Earnest Money	2000
Time	One Month

Name of Work:- R/O (Repair of) Road from Shakhwa to Sarandi Km. 0/00 to 6/00 (SH:- Removal of slips & mainteance of bearm at verious RD's)
Deposit SDF/2024/157

Sr. No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	322.33	Per Cubic Meter	120.00	38680.00	Rupees Thirty Eight Thousand Six Hundred Eighty and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	2745.00	Per Square Metre	22.00	60390.00	Rupees Sixty Thousand Three Hundred Ninety and Paise Zero Only
Total in Figures					99070.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words						

Executive Engineer,
Karsog Division
HPPWD, Karsog

Percentage BoQ

Tender Inviting Authority: _____

Name of Work: RR Damages on Kodu to Katanda Road KM 000 to 3500 (SH :- C/O R/Wall at RD 16/885 to 16/900)

Contract No: _____

Name of the Bidder/ Bidding Firm / Company _____

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT With Taxes in Rs. P	TOTAL AMOUNT In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stems and other deleterious materials and disposal upto lead any meter dressing of side and bottom and back filling in trenches with excavated suitable material ordinary soil upto any depth or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	59.10	Per Cubic Meter	390.20	23060.82	23060.82	INR Twenty Three Thousand Sixty & Paise Eighty Two Only
2	Providing and laying concrete for plain/reinforcement concrete 1:4:8 (one cement : eight sand : eight graded stone aggregate) in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	79.29	Per Cubic Meter	5500.00	436095.00	436095.00	INR Four Lakh Thirty Six Thousand Ninety Five & Paise Zero Only
3	Providing weepholes in bricks masonry/stone masonry plain/reinforced complete abutment wing wall, return wall with 100 mm (one hundred millimeter) dia PVC pipe extending through the full with the structure with slope of (1V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 70, 1204.3.7 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	39.00	Each	373.15	14552.85	14552.85	INR Fourteen Thousand Five Hundred Fifty Two & Paise Eighty Five Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3, or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals	21.60	Per Cubic Meter	1200.00	25920.00	25920.00	INR Twenty Five Thousand Nine Hundred Twenty & Paise Zero Only
Total In Figures					499628.67	499628.67	INR Four Lakh Ninety Nine Thousand Six Hundred Twenty Eight & Paise Sixty Seven Only
Quoted Rate In Figures			Select		0.00		
Quoted Rate In Words						0.00	INR Zero Only

Bill of Quantity checked and approved for Rs=4,99,628. Only for the Year 2025-26 Sr. No.76


 Engineer
 Karsang Division
 CHPPWD Karsang