

**Himachal Pradesh**  
**Public Works Department**  
**HP.PWD Division Shahpur, Distt. Kangra (H.P)-176206**  
**e-mail id: ee-shahpur-pwd@hp.gov.in**  
**"NOTICE INVITING TENDERS"**

Sealed percentage rate tenders on form 6 & 7/8 are hereby invited by the Executive Engineer, Shahpur Division HP.PWD Shahpur on behalf of Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under in H.P General Sales Tax Act 1968 so as to reach in his office on or before **11-07-2025 up to 11:00 AM**, and the same shall be opened on the same day at 11:30 AM. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on **10-07-2025 up to 5:00 P.M** and the application for issue of tender form shall be received on **09-07-2025** up to 12:00 Noon.

The earnest money in the shape of NSC/FDR/Saving account of the Post office/ Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/incomplete tenders & tenders without earnest money will be summarily rejected. The offer of tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit	Cost of tender form
1.	Construction of Jeepable road from Vakil Singh House to Kartar Singh House Village Gubber. (Deposit work). (S.H :-Construction of C.C. Pavement at RD 0/00 to 0/035 and Edge wall at RD 0/00 to 0/007).	99,735.00	2,000.00	Two Months	350/-
2.	C/o Mini Secretariat Building at Shahpur Tehsil Shahpur Distt Kangra (H.P). (S.H:-Providing and Laying GSB ,WBM G-III) .	94,130.00	1900.00	Two Months	350/-
3.	C/o Tatwani Tarmunda Mawa Road KM 0/000 to 5/700. (S.H:- Jungle clearance for conducting survey work and preparation of forest case KM 0/000 to 5/700.)(Under Nabard).	99,900.00	2000.00	One Month	350/-
4.	C/o Mini Secretariat Building at Shahpur Tehsil Shahpur Distt Kangra (H.P). (S.H- Providing and Laying cement concrete at RD.0/067 to 0/087).	97,266.00	1950.00	Two Months	350/-
5.	Restoration of rain damages Shahpur Kiari Gandhrrop road Km 0/00 to 2/400 in Tehsil Shahpur Distt Kangra (H.P). (S.H:-C/o Breast wall at Km 1/700 to 1/705.40).	98,447.00	2000.00	Two Months	350/-
6.	Replacement of old CGI Roofing at Home Guard camp at Dhanotu Tehsil Shahpur Distt Kangra ((H.P).SDF/2024/1043 (Deposit work).(S.H:- Dismantling of roofing and Providing and fixing prepainted sheet (Back side) .	99,514.00	2000.00	Two Months	350/-
7.	C/o Mini Secretariat Building at Shahpur Tehsil Shahpur Distt Kangra (H.P). (S.H- Providing and Laying cement concrete at RD.0/088 to 0/099).	97,396.00	1950.00	Two Months	350/-
8.	Restoration of rain damages Shahpur Kiari Gandhrrop road Km 0/00 to 2/400 in Tehsil Shahpur Distt Kangra (H.P). (S.H:-C/o Breast wall at Km 1/705.40 to 1/711.65).	98,969.00	2000.00	Two Months	350/-
9.	Construction of Link Road From Laleta To Banu Mahadev, Dhanotu I/C 40.00 Metre Span Bridge Over Chambhi Khad (Km 0/00 To 6/185) in District Kangra (HP) <b>under RIDF-XXX (NABARD)</b> . (S.H:- Providing board and Painting and writing lettering, figures etcetra.)	99,840.00	2000.00	One Month	350/-
10.	C/o Link road Harnera Mohar Chamdera Chattri Pehad Km 0/00 to 9/100 in Tehsil Shahpur, Distt. Kangra (HP) . (S.H:-C/o of R/Wall from Rd 7/054 to 7/066 ).	99,049.00	2000.00	Two Months	350/-
11.	Construction of Mini Secretariat Building at Shahpur Tehsil Shahpur Distt Kangra (H.P). (S.H:-Providing and Laying cement concrete at RD.0/100 to 0/114.60).	91,360.00	1850.00	Two Months	350/-
12.	C/o Link road Gharoh Dhima Paniyarri Bastti KM 0/000 to 3/127.(S.H:-C/o U-Shape Drain at RD 2/910 to 2/960).	86,151.00	1750.00	Two Months	350/-
13.	C/o Link road Harnera Mohar Chamdera Chattri Pehad Km 0/00 to 9/100 in Tehsil Shahpur, Distt. Kangra (HP).(S.H:-C/o of T/Wall and repair of catchpit at Rd 7/050.)	98,697.00	2000.00	Two Months	350/-
14.	AMP on Rehlu Durgella Palwala road KM 0/000 to 2/000 for year 2025-26.(S.H:-Maintenance of earthen shoulders between KM 0/00 to 2/00).	99,750.00	2000.00	One Month	350/-

15.	AMP on Pargod to Kalru road KM 1/000 to 2/000 for year 2025-26.(S.H:-Maintenance of earthen shoulders between KM 1/00 to 2/00).	98,750.00	2000.00	One Month	350/-
16.	AMP on Harnera Mohad Chattri road KM 1/000 to 5/000 for year 2025-26.(S.H:-Maintenance of earthen shoulders between KM 2/00 to 5/00).	99,000.00	2000.00	One Month	350/-
17.	C/o Thamba Ther Manoh Road KM 0/000 to 6/00. (S.H:-Jungle clearance for conducting survey work and preparation of forest case KM 0/000 to 6/00.)	99,900.00	2000.00	One Month	350/-
18.	Replacement of old CGI Roofing at Home Guard camp at Dhanotu Tehsil Shahpur Distt Kangra ((H.P).SDF/2024/1043 (Deposit work). (S.H:- Dismantling of roofing and Providing and fixing preprinted sheet in porch).	97,121.00	2000.00	Two Months	350/-
19.	C/o Link road Shahpur Kiari Chatrer Road Km 0/00 to 8/955 in Tehsil Shahpur, Distt. Kangra (HP) .(S.H:-C/o Approaches for extension of HP culvert at RD 7/330 to 7/739.	96,971.00	1950.00	Two Months	350/-
20.	R/D Shahpur Kiari Chatrer Road Km 0/00 to 9/000 in Tehsil Shahpur, Distt. Kangra (HP) .(S.H:-C/o Wire crates at RD 7/926 to 7/935).	94,938.00	1900.00	Two Months	350/-
21.	R/D Shahpur Kiari Chatrer Road Km 0/00 to 9/000 in Tehsil Shahpur, Distt. Kangra (HP) .(S.H:-C/o Wire crates at RD 7/916 to 7/925).	93,825.00	1900.00	Two Months	350/-
22.	R/D Shahpur Kiari Chatrer Road Km 0/00 to 9/000 in Tehsil Shahpur, Distt. Kangra (HP) .(S.H:-C/o Wire crates at RD 7/905 to 7/915).	95,224.00	1950.00	Two Months	350/-
23.	C/o Pulli and Re-construction of Path from Main road to Sh Milkhi Ram House ward No-04 in Gram Panchayat Rehlu in Tehsil Shahpur Distt Kangra (H.P.) (Deposit Work)(S.H:-Balance work Railing, Flooring etc. 5 Metre span culvert).	71,126.00	1450.00	One Month	350/-
24.	A/R and M/O Chambi to Dharamshala (MDR-45) road km 0/00 to 12/800. (Under MMSRRY 2025-26 ).(S.H:-Repair of Pot Hole / patch work between km 7/600 to 8/000).	98,192.00	2000.00	One Month	350/-
25.	A/R and M/O Chambi to Dharamshala (MDR-45) road km 0/00 to 12/800. (Under MMSRRY 2025-26 ).(S.H:-Repair of Pot Hole / patch work between km 5/100 to 6/450).	98,227.00	2000.00	One Month	350/-
26.	C/o of Mahila Mandal Bhawan Dodla in distt. Kangra Himachal Pradesh (SDP/2022/708) (Deposit work). (SH:- P/L tiles and Providing/fixing doors & windows and Painting & Distempering etc.)	96,747.00	1950.00	Two Months	350/-
27.	C/o link road Dramman to Dhukhru road KM 0/00 to 0/690 in Tehsil Shahpur Distt. Kangra (HP) (SH:- C/o 1.00 Mtr slab Culvert at Rd 0/030 substructure)	99,477.00	2000.00	Two Months	350/-
28.	C/o link road Dramman to Dhukhru road KM 0/00 to 0/690 in Tehsil Shahpur Distt. Kangra (HP) (SH:- C/o 1.00 Mtr slab Culvert at Rd 0/030 substructure)	93,485.00	2000.00	Two Months	350/-
29.	C/o link road Dramman to Dhukhru road KM 0/00 to 0/690 in Tehsil Shahpur Distt. Kangra (HP) (SH:- P/L Interlocking Paver block tiles from Rd 0/020 to 0/032)	99,395.00	2000.00	Two Months	350/-
30.	C/o link road Palwala to Lanjot Km 0/00 to 0/900. (C/o U-shape drain at Rd 0/622 to 0/642)	89,786.00	1800.00	Two Months	350/-
31.	C/o link road Palwala to Lanjot Km 0/00 to 0/900. (C/o U-shape drain at Rd 0/575 to 0/598)	90,987.00	1850.00	Two Months	350/-
32.	Amp on link road Ladwara to Bhowan Km 0/00 to 4/540 (SH:- C/o U-Shape drain at Rd 2/800 to 2/850)	88,935.00	1800.00	Two Months	350/-
33.	C/o Noun to Harizan Basti Hara road G.P. Shahpur Km 0/00 to 0/750 (Deposit work) (SH:- C/o Pushta for R/Wall from Rd 0/427 to 0/430)	98,918.00	2000.00	Two Months	350/-
34.	C/o Noun to Harizan Basti Hara road G.P. Shahpur Km 0/00 to 0/750 (Deposit work) (SH:- C/o Pushta for R/Wall from Rd 0/419 to 0/422)	99,321.00	2000.00	Two Months	350/-
35.	C/o Noun to Harizan Basti Hara road G.P. Shahpur Km 0/00 to 0/750 (Deposit work) (SH:- C/o Pushta for R/Wall from Rd 0/423 to 0/426)	99,395.00	2000.00	Two Months	350/-
36.	C/o link road from Ladwara Bhowan road km 0/000 to 4/540 in Tehsil Shahpur Distt Kangra (HP) (SH:- U-Shape Drain at RD 2/800 to 2/857)	98,938.00	2000.00	Two Months	350/-
37.	C/o link road to village Runehar Khad (Nared) Km 0/000 to 1/00 in Tehsil Shahpur Distt Kangra (HP) (under S.C.S.P) (SH:- Extension of Berm at Rd 0/151 to 0/175 (LHS and RHS) & Passing place at various Rds)	87,451.00	1750.00	Two Months	350/-

38.	C/o link road to village Runehar Khad (Nared) Km 0/000 to 1/00 in Tehsil Shahpur Distt Kangra (HP) (under S.C.S.P) (SH:- Extension of Berm at Rd 0/00 to 0/040 (LHS and RHS) & Passing place at various Rds)	91,258.00	1850.00	Two Months	350/-
39.	C/o link road to village Runehar Khad (Nared) Km 0/000 to 1/00 in Tehsil Shahpur Distt Kangra (HP) (under S.C.S.P) (SH:- Extension of Berm at Rd 0/176 to 0/200 (LHS and RHS) & Passing place at various Rds)	87,451.00	1750.00	Two Months	350/-
40.	C/o link road to village Baldi km 0/0 to 1/00 (SH:- C/o 3.00 mtr. Span RCC Slab culvert at RD 0/400)	79,533.00	1600.00	Two Months	350/-
41.	C/o link road to village Baldi km 0/0 to 1/00 (Balance work) (SH:- C/o 3.00 mtr. Span RCC Slab Culvert at RD 0/400)	83,086.00	1700.00	Two Months	350/-
42.	Protection/Treatment of Landslide Disaster on Bhaler to Dulli Road km 0/000 to 4/000 (Hiring of Excavator cum loader for removal of slips)	98,900.00	2000.00	One Month	350/-
43.	Restoration of Rain Damages on Various Roads under HPPWD Sub Division Gaggal. (SH:- Hiring of J.C.B/Excavator cum loader for removal of slips at various roads under Charri section)	99,000.00	2000.00	One Month	350/-
44.	Restoration of rain Damages on Various roads under HP.PWD sub division Shahpur (SH:- Hiring of JCB/excavator cum loader for removal of slips at various roads under Rait Section)	99,000.00	2000.00	Two Month	350/-
45.	Restoration of rain Damages on Various roads under HP.PWD sub division Shahpur (SH:- Hiring of JCB/excavator cum loader for removal of slips at various roads under Harchakian Section)	99,000.00	2000.00	Two Month	350/-
46.	Restoration of Rain Damages on Various Roads under HPPWD Sub Division Gaggal. (SH:- Hiring of J.C.B/Excavator cum loader for removal of slips at various roads under Gaggal section)	99,000.00	2000.00	Two Month	350/-
47.	Restoration of Rain Damages on Various Roads under HPPWD Sub Division Darini (SH:- Hiring of J.C.B/Excavator cum loader for removal of slips at various roads under Darini section)	99,000.00	2000.00	Two Month	350/-
48.	Restoration of rain Damages on Various roads under HP.PWD sub division Shahpur (SH:- Hiring of JCB/excavator cum loader for removal of slips on Shahpur Chakban Lapiana road)	99,000.00	2000.00	Two Month	350/-
49.	Restoration of Rain Damages on Various Roads under HPPWD Sub Division Darini (SH:- Hiring of J.C.B/Excavator cum loader for removal of slips at various roads under Boh section)	99,000.00	2000.00	Two Month	350/-

**Certified that tender of above works are being called of urgent nature in public interest.**

**Terms & Conditions: -**

1. The contractor/firm should be produce the attested copy of latest enlistment and renewal enlistment in HP.PWD. GST No. and EPF No. with the application falling which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The Contractor/Firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.

Executive Engineer,  
Shahpur Division,  
HP.PWD Shahpur.

(on behalf of Governor of Himachal Pradesh)

Dated: 01-07-2025

No.PWD/SD/Tender/NIT/2025-26/- 1582-90

Copy to following for information and necessary action:-

1. The Superintending Engineer, 5<sup>th</sup> Circle HPPWD Palampur.
2. The Executive Engineer (IT), Nigam Vihar Shimla. He is requested to upload the same on the department website.
3. All the Assistant Engineer under this Division.
4. The Drawing/Accounts Branch in this office.
5. N.I.T Register.
6. Notice Board

Executive Engineer,  
Shahpur Division,  
HP.PWD Shahpur.

**SCHEDULE OF QUANTITY**

ESTIMATED COST:- ₹ 99735.00  
 EARNEST MONEY:- ₹ 2000.00  
 TIME LIMIT : Two Months

**NAME OF WORK :-** Construction of Jeepable road from Vakil Singh House to Kartar Singh House Village Gubber. (Deposit work).

**SUB-HEAD :-** Construction of C.C. Pavement at RD 0/00 to 0/035 and Edge wall at RD 0/00 to 0/007).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8.22 Cubic metre	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2877.00
2	Stone filling with hard stone of approved quality dry hand packed tightly under floor. as per specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, GST and all type of other taxes imposed by the Government.	7.10 Cubic metre	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	6035.00
3	Construction of plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement and any other equivalent type as per Clause 1501 using M25 (Grade), (design mix) concrete having coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre), mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic meter) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished as approved, curing of concrete slabs for 14 (fourteen) days using curing compound (where specified) and water finishing lines and grade as per drawing and MORD Technical specification section 1500 and as directed by the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	10.83 Cubic metre	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	77435.00

4	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	2.45 Cubic metre	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	11638.00
5	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in- charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	5.00 Number	350.00	Rupees Three Hundred Fifty Only	Each	1750.00
TOTAL :-						99735.00
Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure )				
Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)				

P 351  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur




### SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 94130.00  
EARNEST MONEY :- ₹ 1900.00  
TIME LIMIT : Two Months

**NAME OF WORK :-** C/o Mini Secretariat Building at Shahpur Tehsil Shahpur Distt Kangra (H.P).  
**SUB-HEAD :-** Providing and Laying GSB ,WBM G-III .

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Construction of granular sub-base by providing well graded materials, spreading in uniform layers with tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller 80-100 (Eighty-hundred) kN static roller to achieve the desired density, complete as per MORD Technical Specification Clause 401 for grading-I material, as per the entire satisfaction and directions of Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	29.93	1450.00	Rupees One Thousand Four Hundred Fifty Only	Per cubic metre	43399.00
2	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm( seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	14.96	2350.00	Rupees Two Thousand Three Hundred Fifty Only	Per cubic metre	35156.00

3	Excavation in foundation and trenches in all heights and depths and in all kinds of soil including saturated soils comprising of pick work, jumper work, pick and jumper work, blasting work both in soft and hard rock, chiseling / wedging out of rock (Where blasting is prohibited) or any other mixed variety of soil including shoring, strutting, de-watering and pumping or bailing out water (surface and sub soil water) up to any heights / depths or any quantum of water including slush which may arise during de-watering, removal of slush and stacking the serviceable and un-serviceable materials clear from the edges of excavation and then returning the stacked soil in 15cm (fifteen centimeters) layers where required into plinth and side of foundation etcetera, consolidating each deposited layer by ramming & watering and then disposing of all surplus un-serviceable excavated earth as directed within all leads and lifts by head-load, mechanical transportation or by any other mode of transportation with all cost of labours, machineries and disposed materials to be neatly dressed and leveled as per specifications approved drawing, design, as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	44.50	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	15575.00
TOTAL :-						94130.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure )				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

4

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 99900.00  
EARNEST MONEY:- ₹ 2000.00  
TIME LIMIT : One month

NAME OF WORK:- C/o Tatwani Tarmuda Mawa Road km 0/000 to 5/700.

SUB-HEAD :- Jungle clearance for conducting survey work and preparation of forest case KM 0/000 to 5/700. (under Nabard)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Clearing jungle including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth up to 30 cm, removal of such tress and disposal of rubbish up to a distance of 50 metres outside the periphery of the cleared area as per item code 2.31 and as per direction of Engineer-in- Charge. The rate is inclusive octroi, royalty , Malkana, toll tax, GST or any other taxes imposed by the Government.	9000.00 Squire metre	11.10	Rupees Eleven And Paise Ten Only	Per square metre	99900.00
TOTAL :-						99900.00
Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure )				
Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,  
Shahpur Division,  
HPPWD Shahpur

**SCHEDULE OF QUANTITY**

ESTIMATED COST: - ₹ 97266.00  
 EARNEST MONEY: ₹ 1950.00  
 TIME LIMIT Two Months

**NAME OF WORK :-** C/o Mini Secretariat Building at Shahpur Tehsil Shahpur Distt Kangra (H.P).

**SUB-HEAD :-** Providing and Laying cement concrete at RD.0/067 to 0/087.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in open foundation of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	14.50	6350.00	Rupees Six Thousand Three Hundred Fifty Only	Per cubic metre	92075.00
2	Excavation in foundation and trenches in all heights and depths and in all kinds of soil including saturated soils comprising of pick work, jumper work, pick jumper work, blasting work both in soft and hard rock, chiseling / wedging out of rock (Where blasting is prohibited) or any other mixed variety of soil including shoring, strutting, de-watering and pumping or bailing out water (surface and sub soil water) up to any heights / depths or any quantum of water including slush which may arise during de-watering, removal of slush and stacking the serviceable and un-serviceable materials clear from the edges of excavation and then returning the stacked soil in 15cm (fifteen centimeters) layers where required into plinth and side of foundation etcetera, consolidating each deposited layer by ramming & watering and then disposing of all surplus un-serviceable excavated earth as directed within all leads and lifts by head-load, mechanical transportation or by any other mode of transportation with all cost of labours, machineries and disposed materials to be neatly dressed and leveled as per specifications approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	14.83	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	5191.00
<b>TOTAL :-</b>						<b>97266.00</b>
	<b>Quoted Rate in Figure (%)</b>	(Amount to be quoted by the contractor in Figure)				
	<b>Quoted Rate in Words (%)</b>	(Amount to be quoted by the contractor in words)				

351  
 Executive Engineer,  
 Shahpur Division,  
 HPWD Shahpur

# SCHEDULE OF QUANTITY



ESTIMATED COST: - ₹ 98447.00

EARNEST MONEY: - ₹ 2000.00


TIME LIMIT : Two Months

**NAME OF WORK** Restoration of rain damages Shahpur Kiari Gandhrup road Km 0/00 to 2/400 in Tehsil Shahpur Distt Kangra (H.P).

**SUB-HEAD :-** C/o Breast wall at Km 1/700 to 1/705.40

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-in-charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. All useful material such as stones shungle, aggregate and slates etcetra shall be sorted out and stacked in proper stack. Recovery of stone to the tune of 3166.36 cum (three thousand one hundred sixty six decimal three six cubic metres) quantity at the rate of 300/- (Rupees Three hundred) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	73.14	220.00	Rupees Two Hundred Twenty Only	Per cubic metre	16091.00
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drain and Parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 and as per direction of the Engineer- In – Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and lift including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layer not exceeding 150 mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth any quantam	4.25	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1488.00

3	Providing and laying mechanically mixed and vibrated plain cement concrete in all type of structure as per drawing and MORD technical specification section 800, 900, 1200 and 1600 for nominal mix 1: 4: 8 (one cement isto four sand isto eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depths including the cost of form work in retaining walls, breast walls etcetera as per the direction of Engineer-in-Charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	15.88	4850.00	Rupees Four Thousand Eight Hundred Fifty Only	Per cubic metre	77018.00
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope I(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	11.00	350.00	Rupees Three Hundred Fifty Only	Each	3850.00
<b>TOTAL :-</b>						<b>98447.00</b>
<b>Quated Rate in Figure (%)</b>		<b>(Amount to be quoted by the contractor in Figure )</b>				
<b>Quated Rate in Words (%)</b>		<b>(Amount to be quoted by the contractor in words)</b>				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY


ESTIMATED COST:- ₹ 99514.00  
EARNEST MONEY:- ₹ 2000.00  
TIME LIMIT : Two Months

NAME OF WORK :- Replacement of old CGI Roofing at Home Guard camp at Dhanotu Tehsil Shahpur Distt Kangra ((H.P).SDF/2024/1043 (Deposit work).

SUB-HEAD :- Dismantling of roofing and Providing and fixing prepainted sheet (Back side ).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Dismantling of roofing including ridges, hips, valleys gutter etc.and stacking the serviceable materials and disposal of un-serviceable materials with in 20 (twenty) metre, as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	47.10 Square metre	69.80	Rupees Sixty Nine And Paise Eighty Only	Per square metre	3288.00
2	Providing and fixing 0.60mm (Zero decimal Six Zero milimetres) thick prepainted steel sheet ISI marked - Z 120 of Tata Durashine/ Sail / Reliance / Jindal steel in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyster of 5 (five) microns over 5 (Five) microns primer fixing with prepainted iron J or L hooks,bolts and nuts with prepainted limpet and rubber washers complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax; GST or any other taxes imposed by the Government.	39.10 Square metre	1350.70	Rupees One Thousand Three Hundred Fifty And Paise Seventy Only	Per square metre	52812.00
3	Providing and fixing ridges or hips 60 cm (Sixty centimetres) over all with 0.60mm (Zero decimal Sixty milimetres) thick prepainted steel sheet ISI marked - Z 120 of approved make in ridges of Sail / Reliance / Jindal /Tata Durashine with hot dipped metallic Zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating of back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with prepainted iron J or L hooks, bolts and nuts 6mm (Six milimetres) diametres with prepainted G.I. limpet and bitumen washers complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	16.10 Running metre	575.75	Rupees Five Hundred Seventy Five And Paise Seventy Five Only	Per running metre	9270.00
4	Providing and fixing plain M.S. B.P. sheet of TATA/SAIL/JINDAL steel 2.00 mm (Two decimal zero millimeter) thick fixed in eaves board / fascia / soffits /ceiling including cutting, fixing and welding to steel rafter, member and applying a coat of red lead primer with gas/ electric welding in position complete (frame work is to be measured and paid for separately) within all leads, lifts of materials and other. incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	13.95 Square metre	1650.50	Rupees One Thousand Six Hundred Fifty And Paise Fifty Only	Per square metre	23024.00

5	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint in beams, joists, channels, angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like as per specification, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, malkana and all type of taxes imposed by the Government.	105.90 Kilograms	105.00	Rupees One Hundred Five Only	Per Kilogram	11120.00
TOTAL :-						99514.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

7

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 97396.00  
EARNEST MONEY:- ₹ 1950.00  
TIME LIMIT : Two Months

**NAME OF WORK :-** C/o Mini Secretariat Building at Shahpur Tehsil Shahpur Distt Kangra (H.P).  
**SUB-HEAD :-** Providing and Laying cement concrete at RD.0/088 to 0/099.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in open foundation of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	9.48	6350.00	Rupees Six Thousand Three Hundred Fifty Only	Per cubic metre	60198.00
2	Excavation in foundation and trenches in all heights and depths and in all kinds of soil including saturated soils comprising of pick work, jumper work, pick jumper work, blasting work both in soft and hard rock, chiseling / wedging out of rock (Where blasting is prohibited) or any other mixed variety of soil including shoring, strutting, de-watering and pumping or bailing out water (surface and sub soil water) up to any heights / depths or any quantum of water including slush which may arise during de-watering, removal of slush and stacking the serviceable and un-serviceable materials clear from the edges of excavation and then returning the stacked soil in 15cm (fifteen centimeters) layers where required into plinth and side of foundation etcetera, consolidating each deposited layer by ramming & watering and then disposing of all surplus un-serviceable excavated earth as directed within all leads and lifts by head-load, mechanical transportation or by any other mode of transportation with all cost of labours, machineries and disposed materials to be neatly dressed and leveled as per specifications approved drawing , design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	14.10	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	4935.00

3.	Providing and laying mechanically mixed and vibrated reinforced cement concrete in super structure as per drawing and M.O.R.D.. technical specification section 800, 900 and 1400 using R.C.C. grade M-25 ( twenty five) design mix with cement contents not less than 400 kg (four hundred kilogram) per cubic metre with 20mm (twenty millimetre ) nominal size graded crushed stone aggregate and curing complete including cost of form work but excluding the cost of reinforcement for reinforced concrete work in deck slab and to the entire satisfaction and as per the direction of Engineer-in-Charge including carriage of material within all leads , lifts and other incidentals .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.45	7250.00	Rupees Seven Thousand Two Hundred Fifty Only	Per cubic metre	32263.00
	Quoted Rate in Figure (%)	TOTAL :-				97396.00
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in Figure )				
		(Amount to be quoted by the contractor in words)				

Executive Engineer,  
Shahpur Division,  
HPEWD Shahpur

8

# SCHEDULE OF QUANTITY


ESTIMATED COST: ₹ 98969.00  
EARNEST MONEY: ₹ 2000.00  
TIME LIMIT : Two Months

NAME OF WORK :- Restoration of rain damages Shahpur Kiari Gandhrrop road Km 0/00 to 2/400 in Tehsil Shahpur Distt Kangra (H.P.)

SUB-HEAD :- C/o Breast wall at Km 1/705.40 to 1/711.65

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drain and Parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 and as per direction of the Engineer- In – Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and lift including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layer not executing 150 mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth any quantam of water including cleaning of slush which may arise out during dewatering complete as per direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	6.68	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2338.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in all type of structure as per drawing and MORD technical specification section 800, 900 ,1200 and 1600 for nominal mix 1: 4: 8 (one cement isto four sand isto eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depths including the cost of form work in retaining walls, breast walls etcetera as per the direction of Engineer-in-Charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	19.13	4850.00	Rupees Four Thousand Eight Hundred Fifty Only	Per cubic metre	92781.00

3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope I(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	11.00	350.00	Rupees Three Hundred Fifty Only	Each	3850.00
TOTAL :-						98969.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

# SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99840.00  
 EARNEST MONEY: - ₹ 2000.00  
 TIME LIMIT: One Month

**NAME OF WORK :-** Construction of Link Road From Laleta To Banu Mahadev, Dhanotu I/C 40.00 Metre Span Bridge Over Chambhi Khad (Km 0/00 To 6/185) in District Kangra (HP) under RIDF-XXX (NABARD)

**SUB-HEAD :-** Providing board and Painting and writing lettering, figures etcetra.)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Painting two coats (excluding priming coat) on previously steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning the surface to remove all dirt, dust and other foreign matter with enamel paint other than white including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	45.00	36.10	Rupees Thirty Six And Paise Ten Only	Per square metre	1625.00
2	Providing and erecting direction and place identification retro-reflective sign boards, as per IRC-67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting width, 2 mm (two millimeters) thick with area not exceeding 0.90 sqm (zero point nine zero) supported on mild steel iron post 75 mm x 75 mm x 6 mm, (seventy five into seventy five into six millimeters), 2 Nos. (two numbers) firmly fixed to the ground by mean of properly designed foundation with M-15 grade (M-fifteen grade) cement concrete 450x450x600mm (four hundred fifty into four hundred fifty into six hundred millimetre), 600mm (six hundred millimetre) below ground level as per approved drawings and technical specification section 1700, including painting angle iron post with primes and two coats of Epoxy paint as per specification and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	10500.00	Rupees Ten Thousand Five Hundred Only	Each	10500.00
3	Writing letters or figures on any surfaces with synthetic enamel paint (other than white) stops, commas, hyphens and the like not to be measured and paid separately, Block letters, Indian letters / figures etc. Including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	33100.00	2.65	Rupees Two And Paise Sixty Five Only	Per letter per centimetre high	87715.00
<b>TOTAL :-</b>						<b>99840.00</b>
<b>Quoted Rate in Figure (%)</b>		(Amount to be quoted by the contractor in Figure)				
<b>Quoted Rate in Words (%)</b>		(Amount to be quoted by the contractor in words)				

Executive Engineer,  
 Shahpur Division,  
 HP PWD Shahpur

10

**SCHEDULE OF QUANTITY**

ESTIMATED COST: - ₹ 99049.00  
EARNEST MONEY :- ₹ 2000.00  
TIME LIMIT : Two Months

**NAME OF WORK** :- C/o Link road Harnera Mohar Chamdera Chattri Pehad Km 0/00 to 9/100 in Tehsil Shahpur, Distt. Kangra (HP) .

**SUB-HEAD** :- C/o of R/Wall from Rd 7/054 to 7/066 .

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.56 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2296.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty milimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	20.96 Cubic metres	4300.00	Rupees Four Thousand Three Hundred Only	Per cubic metre	90128.00

3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope I(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in- charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	8.00 Number	350.00	Rupees Three Hundred Fifty Only	Each	2800.00
4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	4.50 Cubic metres	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	3825.00
<b>Quoted Rate in Figure (%)</b>						<b>TOTAL :- 99049.00</b>
<b>Quoted Rate in Words (%)</b>						<b>(Amount to be quoted by the contractor in words)</b>

Executive Engineer,  
Shahpur Division,  
HPPWD Shahpur

**SCHEDULE OF QUANTITY**

ESTIMATED COST:- ₹ 91360.00  
EARNEST MONEY:- ₹ 1850.00  
TIME LIMIT : Two Months

**NAME OF WORK :-** Construction of Mini Secretariat Building at Shahpur Tehsil Shahpur Distt Kangra (H.P).  
**SUB-HEAD :-** Providing and Laying cement concrete at RD.0/100 to 0/114.60.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in open foundation of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	13.50	6350.00	Rupees Six Thousand Three Hundred Fifty Only	Per cubic metre	85725.00
2	Excavation in foundation and trenches in all heights and depths and in all kinds of soil including saturated soils comprising of pick work, jumper work, pick jumper work, blasting work both in soft and hard rock, chiseling / wedging out of rock (Where blasting is prohibited) or any other mixed variety of soil including shoring, strutting, de-watering and pumping or bailing out water (surface and sub soil water) up to any heights / depths or any quantum of water including slush which may arise during de-watering, removal of slush and stacking the serviceable and un-serviceable materials clear from the edges of excavation and then returning the stacked soil in 15cm (fifteen centimeters) layers where required into plinth and side of foundation etcetera, consolidating each deposited layer by ramming & watering and then disposing of all surplus un-serviceable excavated earth as directed within all leads and lifts by head-load, mechanical transportation or by any other mode of transportation with all cost of labours, machineries and disposed materials to be neatly dressed and leveled as per specifications approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	16.10	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	5635.00
<b>TOTAL :-</b>						<b>91360.00</b>
	<b>Quoted Rate in Figure (%)</b>	to	(Amount to be quoted by the contractor in Figure )			
	<b>Quoted Rate in Words (%)</b>	to	(Amount to be quoted by the contractor in words)			

Executive Engineer,  
Shahpur Division,  
HPPWD Shahpur

**SCHEDULE OF QUANTITY**

ESTIMATED COST:- ₹ 86151.00  
EARNEST MONEY:- ₹ 1750.00  
TIME LIMIT : Two Months

NAME OF WORK :- C/o Link road Garoh Dhima Paniyarri Bastti KM 0/00 to 3/127.

SUB-HEAD :- C/O U-Shape Drain at RD 2/910 to 2/960.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	17.42 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	6097.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 ( M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	14.88 Cubic metres	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	80054.00
<b>Quoted Rate in Figure (%)</b>						<b>TOTAL :- 86151.00</b>
<b>Quoted Rate in Words (%)</b>						(Amount to be quoted by the contractor in words)

Executive Engineer,  
Shahpur Division,  
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98697.00  
 EARNEST MONEY: - ₹ 2000.00  
 TIME LIMIT : Two Months

NAME OF WORK :- C/o Link road Harnera Mohar Chamdera Chattri Peahd Km 0/00 to 9/100 in Tehsil Shahpur, Distt. Kangra (HP) .

SUB-HEAD :- C/o of T/Wall and repair of catchpit at Rd 7/050.


S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	14.23  Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	4981.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 ( M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	8.30  Cubic metres	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	44654.00



(14)


**SCHEDULE OF QUANTITY**

Name of Work:- AMP on Rehlu Durgella Palwala road km 0/00 to 2/00 for the year 2025-26				Estimated Cost		99750.00
(Sh:-Maintenance of earthen shoulders between km 0/00 to 2/00 )				Earnest Money		2000.00
				Time Limit		One Month
Sr. No.	Description of Item	Qty.	Rate in Figure	Rate in words	Unit	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil making up loss of material irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment complete as per direction and entire satisfaction of Engineer in Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana and toll tax, sale tax, GST or any other taxes imposed by the Government.	1500.00	50.00	Rupees Fifty only	Sqm	75000.00
2	Clearing and grabbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth up to 300 mm removal of terms of such trees and disposal of unsubsidiary material and staying of surplus material to be used up to a lead of 1000 m. The rate is inclusive of octroi, royalty, malkhana and toll tax, sale tax, GST or any other taxes imposed by the Government.	0.33	75000.00	Rupees Fifty eight thousand only	Per Hectare	24750.00
					Total	99,750.00
Quoted rate in Figure(%)		Rate Quoted by the contractor in Figure(%)				
Quoted rate in Words(%)		Rate Quoted by the contractor in Words(%)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

### SCHEDULE OF QUANTITY


Name of Work:- AMP on Pargod to Kalru road km 1/00 to 2/00 for the year 2025-26				Estimated Cost		98750.00
(Sh:-Maintenance of earthen shoulders between km 1/00 to 2/00 )				Earnest Money		2000.00
				Time Limit		One Month
Sr. No.	Description of Item	Qty.	Rate in Figure	Rate in words	Unit	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil making up loss of material irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment complete as per direction and entire satisfaction of Engineer in Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana and toll tax, sale tax, GST or any other taxes imposed by the Government.	1600.00	50.00	Rupees Fifty only	Sqm	80000.00
2	Clearing and grabbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth up to 300 mm removal of terms of such trees and disposal of unsubsidiary material and staying of surplus material to be used up to a lead of 1000 m. The rate is inclusive of octroi, royalty, malkhana and toll tax, sale tax, GST or any other taxes imposed by the Government.	0.25	75000.00	Rupees Fifty eight thousand only	Per Hectare	18750.00
					<b>Total</b>	<b>98,750.00</b>
<b>Quoted rate in Figure(%)</b>		<b>Rate Quoted by the contractor in Figure(%)</b>				
<b>Quoted rate in Words(%)</b>		<b>Rate Quoted by the contractor in Words(%)</b>				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

(18)

**SCHEDULE OF QUANTITY**


Name of Work:- AMP on Harnera Mohad Chattri road km 2/00 to 5/00 for the year 2025-26				Estimated Cost		99000.00
(Sh:-Maintenance of earthen shoulders between km 2/00 to 5/00 )				Earnest Money		2000.00
				Time Limit		One Month
Sr. No.	Description of Item	Qty.	Rate in Figure	Rate in words	Unit	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil making up loss of material irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment complete as per direction and entire satisfaction of Engineer in Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana and toll tax, sale tax, GST or any other taxes imposed by the Government.	1650.00	50.00	Rupees Fifty only	Sqm	82500.00
2	Clearing and grabbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth up to 300 mm removal of terms of such trees and disposal of unsubsidiary material and staying of surplus material to be used up to a lead of 1000 m. The rate is inclusive of octroi, royalty, malkhana and toll tax, sale tax, GST or any other taxes imposed by the Government.	0.22	75000.00	Rupees Fifty eight thousand only	Per Hectare	16500.00
					<b>Total</b>	<b>99,000.00</b>
	<b>Quoted rate in Figure(%)</b>	<b>Rate Quoted by the contractor in Figure(%)</b>				
	<b>Quoted rate in Words(%)</b>	<b>Rate Quoted by the contractor in Words(%)</b>				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

(17)

**SCHEDULE OF QUANTITY**

Name of Work:- C/O Thamba Ther Manoh road km 0/00 to 6/00				Estimated Cost		99900.00
(Sh:-Jungle clearance for conducting survey work and preparation of forest case km 0/00 to 6/00 )				Earnest Money		2000.00
				Time Limit		One Month
Sr. No.	Description of Item	Qty.	Rate in Figure	Rate in words	Unit	Amount
1	Clearing jungle including uprooting wild vegetation, grass, bushes, shrubs, saplings and tree of girth upto 30 cm, removal of such trees and disposal of rubbish up to a distance of 50 mtrs outside the periphery of the cleared area as per item code 2.31 and as per direction of Engineer-in-charge. The rate is inclusive of octroi, royalty, malkhana and toll tax, sale tax, GST or any other taxes imposed by the Government.	9000.00	11.10	Eleven Rupees and paise ten only	Sqm	99900.00
					Total	99,900.00
Quoted rate in Figure(%)		Rate Quoted by the contractor in Figure(%)				
Quoted rate in Words(%)		Rate Quoted by the contractor in Words(%)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY


ESTIMATED COST :- ₹ 97121.00  
EARNEST MONEY :- ₹ 2000.00  
TIME LIMIT :- Two Months

NAME OF WORK :- Replacement of old CGI Roofing at Home Guard camp at Dhanotu Tehsil Shahpur Distt Kangra ((H.P).SDF/2024/1043 (Deposit work).

SUB-HEAD :- Dismantling of roofing and Providing and fixing prepainted sheet in porch.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Dismantling of roofing including ridges, hips, valleys gutter etc.and stacking the serviceable materials and disposal of un-serviceable materials with in 20 (twenty) metre, as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	47.10 Square metre	69.80	Rupees Sixty Nine And Paise Eighty Only	Per square metre	3288.00
2	Providing and fixing 0.60mm (Zero decimal Six Zero millimetres) thick prepainted steel sheet ISI marked - Z 120 of Tata Durashine/ Sail / Reliance / Jindal steel in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyester of 5 (five) microns over 5 (Five) microns primer fixing with prepainted iron J or L hooks,bolts and nuts with prepainted limpet and rubber washers complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	40.20 Square metre	1350.70	Rupees One Thousand Three Hundred Fifty And Paise Seventy Only	Per square metre	54298.00
3	Providing and fixing ridges or hips 60 cm (Sixty centimetres) over all with 0.60mm (Zero decimal Sixty millimetres) thick prepainted steel sheet ISI marked - Z 120 of approved make in ridges of Sail / Reliance / Jindal /Tata Durashine with hot dipped metallic Zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating of back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with prepainted iron J or L hooks, bolts and nuts 6mm (Six millimetres) diametres with prepainted G.I. limpet and bitumen washers complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	19.50 Running metre	575.75	Rupees Five Hundred Seventy Five And Paise Seventy Five Only	Per running metre	11227.00
4	Providing and fixing plain M.S. B.P. sheet of TATA/SAIL/JINDAL steel 2.00 mm (Two decimal zero millimeter) thick fixed in eaves board / fascia / soffits /ceiling including cutting, fixing and welding to steel rafter, member and applying a coat of red lead primer with gas/electric welding in position complete (frame work is to be measured and paid for separately) within all leads, lifts of materials and other. incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	11.40 Square metre	1650.50	Rupees One Thousand Six Hundred Fifty And Paise Fifty Only	Per square metre	18816.00

5	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In beams, joists, channels, angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like as per specification, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, malkana and all type of taxes imposed by the Government.	90.40 Kilograms	105.00	Rupees One Hundred Five Only	Per Kilogram	9492.00
TOTAL :-						97121.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur


# SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 96971.00  
 EARNEST MONEY:- ₹ 1950.00  
 TIME LIMIT :- Two Months

NAME OF WORK :- C/o Link road Shahpur Kiari Chatrer Road Km 0/00 to 8/955 in Tehsil Shahpur, Distt. Kangra (HP) .  
SUB-HEAD :- C/o Approaches for extension of HP culvert at RD 7/330 to 7/739.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	14.33 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	5016.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty milimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	21.06 Cubic metres	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per cubic metre	89505.00

3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as,per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in- charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	7.00 Number	350.00	Rupees Three Hundred Fifty Only	Each	2450.00
TOTAL :-						96971.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure )				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

**SCHEDULE OF QUANTITY**

(20)

ESTIMATED COST: - ₹ 94938.00  
 EARNEST MONEY: - ₹ 1900.00  
 TIME LIMIT : Two Months

**NAME OF WORK :-** R/D Shahpur Kiari Chatrer Road Km 0/00 to 9/000 in Tehsil Shahpur, Distt. Kangra (HP) .

**SUB-HEAD :-** C/o Wire crates at RD 7/926 to 7/935.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying of boulder apron or gabin walls laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone bounders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	29.85	3180.50	Rupees Three Thousand One Hundred Eighty And Paise Fifty Only	Per cubic metre	94938.00
<b>Quoted Rate in Figure (%)</b>						<b>TOTAL :- 94938.00</b>
						(Amount to be quoted by the contractor in Figure )
<b>Quoted Rate in Words (%)</b>						(Amount to be quoted by the contractor in words)

138  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur


# **SCHEDULE OF QUANTITY**

ESTIMATED COST:- ₹ 93825.00  
 EARNEST MONEY:- ₹ 1900.00  
 TIME LIMIT : Two Months

**NAME OF WORK** :- R/D Shahpur Kiari Chatrer Road Km 0/00 to 9/000 in Tehsil Shahpur, Distt. Kangra (HP).

**SUB-HEAD** :- C/o Wire crates at RD 7/916 to 7/925.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying of boulder apron or gabin walls laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone bounders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	29.50	3180.50	Rupees Three Thousand One Hundred Eighty And Paise Fifty Only	Per cubic metre	93825.00
<b>TOTAL :-</b>						<b>93825.00</b>
<b>Quated Rate in Figure (%)</b>		<b>(Amount to be quoted by the contractor in Figure )</b>				
<b>Quated Rate in Words (%)</b>		<b>(Amount to be quoted by the contractor in words)</b>				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

22

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 95224.00  
EARNEST MONEY:- ₹ 1950.00  
TIME LIMIT : Two Months

NAME OF WORK :- R/D Shahpur Kiari Chatrer Road Km 0/00 to 9/000 in Tehsil Shahpur, Distt. Kangra (HP).

SUB-HEAD :- C/o Wire crates at RD 7/905 to 7/915.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying of boulder apron or gabin walls laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone bounders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	29.94	3180.50	Rupees Three Thousand One Hundred Eighty And Paise Fifty Only	Per cubic metre	95224.00
TOTAL :-						95224.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure )				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,  
Shahpur Division,  
HPPWD Shahpur

**SCHEDULE OF QUANTITY**


ESTIMATED COST: - ₹ 71126.00  
 EARNEST MONEY: - ₹ 1450.00  
 TIME LIMIT: - One Month

**NAME OF WORK** :- C/o Pulli and Re-construction of Path from Main road to Sh Milkhi Ram House ward No-04 in Gram Panchayat Rehlu in Tehsil Shahpur Distt Kangra (H.P.) (Deposit Work)

**SUB-HEAD** :- Balance work Railing, Flooring etc. 5 Metre span culvert.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.36	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1876.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government. te is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	6.38	4850.00	Rupees Four Thousand Eight Hundred Fifty Only	Per cubic metre	30943.00

3	Providing and laying mechanically-mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	2.08	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per cubic metre	12792.00
4	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint in beams, joists, channels, angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like, complete as per specification, approved drawing, design, as per the entire satisfaction and direction of the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	243.00	105.00	Rupees One Hundred Five Only	Per Kilogram	25515.00
<b>TOTAL :-</b>						<b>71126.00</b>
<b>Quoted Rate in Figure (%)</b>		<b>(Amount to be quoted by the contractor in Figure)</b>				
<b>Quoted Rate in Words (%)</b>		<b>(Amount to be quoted by the contractor in words)</b>				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

24

**SCHEDULE OF QUANTITY**

ESTIMATED COST:- ₹ 98192.00  
EARNEST MONEY:- ₹ 2000.00  
TIME LIMIT : One Month

**NAME OF WORK :-** A/R and M/O Chambi to Dharamshala (MDR-45) road km 0/00 to 12/800. (Under MMSRRY 2025-26 ).  
**SUB-HEAD :-** Repair of Pot Hole / patch work between km 7/600 to 8/00)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm( seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	1.99	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	4478.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	294.33	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6622.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0~9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	294.33	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	87092.00
<b>TOTAL :-</b>						<b>98192.00</b>
(Amount to be quoted by the contractor in Figure )						
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in words)
Quoted Rate in Words (%)						

Executive Engineer,  
Shahpur Division,  
HPRWD Shahpur


# SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 98227.00  
 EARNEST MONEY:- ₹ 2000.00  
 TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Dadhamb Durgella Bhatech via Tandu road km 0/00 to 6/450. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 5/100 to 6/450)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm( seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	2.15	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	4838.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	293.31	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6599.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0~9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	293.31	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	86790.00
<b>TOTAL :-</b>						<b>98227.00</b>
	<b>Quoted Rate in Figure (%)</b>	(Amount to be quoted by the contractor in Figure )				
	<b>Quoted Rate in Words (%)</b>	(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPD Shahpur

26

# SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 96747.00  
 EARNEST MONEY: - ₹ 1950.00  
 TIME LIMIT : Two Months

**NAME OF WORK :-** Construction of Mahila Mandal Bhawan Dodla in Distt. Kangra Himachal Pradesh.(SDP/2022/708) (Deposit Work).

**SUB-HEAD :-** Providing and laying tiles and providing / fixing doors & windows and Painting & Distempering etc.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying 600x600 mm ( six hundred into six hundred millimetre) Double Charged / Ultra charged vitrified antiskid floor tiles of Restile/ Johnson/ Nitco/ Rak / Kajaria / AGL / Simpolo / Somany /Orient Bell as per approved shade and design of the office (thickness to be specified by the manufacturer) with water absorption less than 0.08% ( zero decimal zero eight percentage) and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm ( twenty millimetre) thick cement mortar 1:4 (one cement isto four coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm ( three decimal three kilogram per squaremetre) including grouting the joints with white cement and matching pigments etcetera complete, as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	22.68	1450.00	Rupees One Thousand Four Hundred Fifty Only	Per square metre	32886.00
2	Providing and fixing aluminium work for shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15 (fifteen) within all leads, lifts of materials and other incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	72.88	508.30	Rupees Five Hundred Eight And Paise Thirty Only	Per Kilogram	37045.00
3	Providing and fixing 12mm thick Phenol bonded (both side) prelaminated BWP Grade partical board in matt finish flat pressed three layer or graded wood partical board conforming to IS :12823 of Action Tesa/Greelam/Merinolam/Kitlam/ Vista of approved shade Grade - I, Type II, in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass/stainless steel screws etcetera complete as per architectural drawing and direction of Engineer- in- charge. Pre-laminated partical board with decorative lamination on one side and balancing lamination on other side as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.01	933.90	Rupees Nine Hundred Thirty Three And Paise Ninety Only	Per square metre	1877.00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
4	Providing and fixing Glazings with frosted glass panes 4mm (Four milimetre) thickness glass panes (weight not less than 10.00kg/square metre) of modi guard/saint gobain/AIS/Atul/Gold Plus in door, windows, ventilators shutter and partitions with EPDM rubber/Neoprene gastet etcetera as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.49	1310.00	Rupees One Thousand Three Hundred Ten Only	Per square metre	1952.00
5	Providing and fixing stainless steel (grade 304) wire gauze of 0.50 mm (zero decimal five milimetre ) dia wire and 1.4 mm (one decimal four milimetre) aperture on both sides fly proof wire gauze to window, clerestory windows & door with M.S Flat 15x3 mm and nuts and bolts complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.49	945.90	Rupees Nine Hundred Forty Five And Paise Ninety Only	Per square metre	1409.00
6	Providing and fixing 300x16mm (Three hundred into Sixteen milimetres) size Pilot/sheel anodized aluminium sliding door bolts anodized transparent or dyed to required colour and shade with necessary screws etc. within all leads, lifts of materials and other incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	4.00	250.00	Rupees Two Hundred Fifty Only	Each	1000.00
7	Providing and fixing aluminium Pilot/sheel anodized transparent or dyed to required colour and shade with necessary screws etc. Tower bolts (Barrel type) as approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.					
a	250x10mm (Two hundred fifty into Ten milimetres) size	4.00	93.30	Rupees Ninety Three And Paise Thirty Only	Each	373.00
b	150x10mm (One hundred fifty into Ten milimetres) size	10.00	78.20	Rupees Seventy Eight And Paise Twenty Only	Each	782.00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
4	Providing and fixing Glazings with frosted glass panes 4mm (Four millimetre) thickness glass panes (weight not less than 10.00kg/square metre) of modi guard/saint gobain/AIS/Atul/Gold Plus in door, windows, ventilators shutter and partitions with EPDM rubber/Neoprene gasket etcetera as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.49	1310.00	Rupees One Thousand Three Hundred Ten Only	Per square metre	1952.00
5	Providing and fixing stainless steel (grade 304) wire gauze of 0.50 mm (zero decimal five millimetre ) dia wire and 1.4 mm (one decimal four millimetre) aperture on both sides fly proof wire gauze to window, clerestory windows & door with M.S Flat 15x3 mm and nuts and bolts complete with all accessories as required within all leads, lifts of materials and other incidentals. as per approved architectural drawing, design and specification and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.49	945.90	Rupees Nine Hundred Forty Five And Paise Ninety Only	Per square metre	1409.00
6	Providing and fixing 300x16mm (Three hundred into Sixteen millimetres) size Pilot/sheel anodized aluminium sliding door bolts anodized transparent or dyed to required colour and shade with necessary screws etc. within all leads, lifts of materials and other incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	4.00	250.00	Rupees Two Hundred Fifty Only	Each	1000.00
7	Providing and fixing aluminium Pilot/sheel anodized transparent or dyed to required colour and shade with necessary screws etc. Tower bolts (Barrel type) as approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.					
a	250x10mm (Two hundred fifty into Ten millimetres) size	4.00	93.30	Rupees Ninety Three And Paise Thirty Only	Each	373.00
b	150x10mm (One hundred fifty into Ten millimetres) size	10.00	78.20	Rupees Seventy Eight And Paise Twenty Only	Each	782.00

S.No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
	Providing and fixing aluminium Pilot/heel or equivalent anodized transparent or dyed to required colour and shade and of approved make with necessary screws etc. handles with the necessary screws etc. complete. within all leads, lifts of materials and other. incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.					
a	125mm (one hundred twenty five millimetres) size	4.00	73.10	Rupees Seventy Three And Paise Ten Only	Each	292.00
b	100mm (one hundred millimetres) size	10.00	66.00	Rupees Sixty Six Only	Each	660.00
9	Providing and fixing M.S (mild steel) hooks and eyes 100 mm (One hundred millimetre) (Barrel type) anodized transparent or dyed to required colour and shade with necessary screws etcetera complete including carriage of material within all leads, lifts and other. incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	10.00	87.10	Rupees Eighty Seven And Paise Ten Only	Each	871.00
10	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg ( thirty five kilogram) and door width upto 700 mm ( seven hundred millimetres), with necessary accessories and screws etc. complete as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government. other taxes imposed by the Government.	2.00	1040.80	Rupees One Thousand Forty And Paise Eighty Only	Each	2082.00
11	Providing and fixing aluminium hanging floor door stopper, Twin rubber stopper ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.00	65.40	Rupees Sixty Five And Paise Forty Only	Each	131.00
12	Applying a priming coat over wall based surfaces with Nerolac/ Asian paint after and including preparing the surfaces by thoroughly cleaning oil, grease, dirt and other foreign matters sand papering and knotting with ready mixed paint brushing wood primer pink including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	104.76	37.40	Rupees Thirty Seven And Paise Forty Only	Per square metre	3918.00

No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
13	Painting with synthetic enamel paint: Asian / Dulux / Berger / Nerolac Suraksha paints of approved brand and manufacture of required colour to give an even shade One or more coats on old wood & steel work, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.33	82.40	Rupees Eighty Two And Paise Forty Only	Per square metre	192.00
14	Distempering (two or more coats) with oil bound distemper of Asian paints of approved brand and manufacture and of required shade on undecorated wall surfaces to give an even shade and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	40.56	118.60	Rupees One Hundred Eighteen And Paise Sixty Only	Per square metre	4810.00
15	Finishing wall with water proofing cement paint of approved brand and manufacture and of required shade on undecorated wall surfaces (two coats) to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	27.33	95.50	Rupees Ninety Five And Paise Fifty Only	Per square metre	2610.00
16	Providing and applying white cement based putty of Birla / JK average thickness 1 mm ( one millimetre) over the plastered wall surface to prepare the surface even and smooth complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	40.56	95.10	Rupees Ninety Five And Paise Ten Only	Per square metre	3857.00
TOTAL :-						96747.00
Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure )				
Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,  
Shahpur Division,  
HPPWD Shahpur

SCHEDULE OF QUANTITY


ESTIMATED COST: - ₹ 99477.00  
 EARNEST MONEY: - ₹ 2000.00  
 TIME LIMIT : Two Months

NAME OF WORK :- C/o Link road Dramman to Dhukhru road KM 0/00 to 0/690 in Tehsil Shahpur, Distt. Kangra (HP) .

SUB-HEAD :- C/o 1.00 Mtr slab Culvert at Rd 0/030 substructure

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	19.60 Cubic metres	350	Rupees Three Hundred Fifty Only	Per cubic metre	6860.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.59 Cubic metres	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	15617.00

3	Providing and laying mechanically mixed and vibrated concrete for plain/ cement concrete in sub structure for all type of structure complete using plain cement concrete grade M-15 ( M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilograme) per cubic metre in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800, 900 and 1200, and as per the direction of Engineer-in-Charge including carriage of material within all leads lifts and other incidentals The rate is including octroi, royalty, GST, toll tax, or other taxes imposed	14.00 Cubic metres	5500.00	Rupees Five Thousand Five Hundred Only	Per cubic metre	77000.00
TOTAL :-						99477.00
		(Amount to be quoted by the contractor in Figure )				
Quated Rate in Figure (%)		(Amount to be quoted by the contractor in words)				
Quated Rate in Words (%)						

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹

93485.00

EARNEST MONEY: - ₹

2000.00

TIME LIMIT :


Two Months

NAME OF WORK :- C/o Link road Dramman to Dhukhru road KM 0/00 to 0/690 in Tehsil Shahpur, Distt. Kangra (HP) .

SUB-HEAD :- C/o 1.00 Mtr slab Culvert at Rd 0/030 superstructure

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying mechanically mixed and vibrated concrete for plain/ cement concrete in sub structure for all type of structure complete using plain cement concrete grade M-15 ( M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilograme) per cubic metre in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800, 900 and 1200, and as per the direction of Engineer-in-Charge including carriage of material within all leads , lifts and other incidentals .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	0.93 Cubic metres	5500	Rupees Five Thousand Five Hundred Only	Per cubic metre	5115.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in sub structure grade M-20 (M-Twenty) design mix with cement contents not less than 330 kg (Three hundred thirty killogram) per cubic metre with 40mm (Forty millimetres) nominal size graded crushed stone aggregate in abutments etcetra as per drawings and MORD technical specifications section 800, 900 and 1200 including the cost of form work and curing complete including carriage of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-In-Charge. The rate is including octroi, royalty, Malkhana, toll tax, GST or other taxes imposed by the Government.	5.49 Cubic metres	6600.00	Rupees Six Thousand Six Hundred Only	Per cubic metre	36234.00

3	Supplying fitting and placing HYSD bar reinforcement (Fe-415) in superstructure complete as per drawing and M.O.R.D. technical specifications section 1000 and 1200 including cutting, bending, binding and placing in position complete in all respect including cost of binding wire as per the directions of the Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government.	548.80 Killogram	95.00	Rupees Ninety Five Only	Per Killograme	52136.00
<b>TOTAL :-</b>						<b>93485.00</b>
<b>Quoted Rate in Figure (%)</b>		(Amount to be quoted by the contractor in Figure )				
<b>Quoted Rate in Words (%)</b>		(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

29

**SCHEDULE OF QUANTITY**

ESTIMATED COST: - ₹ 99395.00  
EARNEST MONEY :- ₹ 2000.00  
TIME LIMIT : Two Months

**NAME OF WORK** :- C/o Link road Dramman to Dhukhru road KM 0/00 to 0/690 in Tehsil Shahpur, Distt. Kangra (HP) .

**SUB-HEAD** :- Providing and laying Interlocking Paver block tiles from Rd 0/020 to 0/032.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty milimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	5.12 Cubic metres	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	24320.00
2	Providing and laying 60 mm (Sixty millimetre) thick Interlocking M-50 (M-Fifty) grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 80mm (eighty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shell be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	68.25 Squire metres	1100.00	Rupees One Thousand One Hundred Only	Per squire metre	75075.00
<b>TOTAL :-</b>						<b>99395.00</b>
<b>Quated Rate in Figure (%)</b>		<b>(Amount to be quoted by the contractor in Figure )</b>				
<b>Quated Rate in Words (%)</b>		<b>(Amount to be quoted by the contractor in words)</b>				


P-359  
Executive Engineer,  
Shahpur Division,  
HPPWD Shahpur

# **SCHEDULE OF QUANTITY**

ESTIMATED COST :- ₹ 89786.00  
 EARNEST MONEY :- ₹ 1800.00  
 TIME LIMIT : Two Months

**NAME OF WORK :-** Construction of link road Palwala to Lajot KM 0/00 TO 0/900.  
**SUB-HEAD :-** Construction of U-Shape drain at Rd 0/622 to 0/642.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.80 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2380.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 ( M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	15.95 Cubic metres	5480.00	Rupees Five Thousand Four Hundred Eighty Only	Per cubic metre	87406.00
<b>TOTAL :-</b>						<b>89786.00</b>
<b>Quoted Rate in Figure (%)</b>		(Amount to be quoted by the contractor in Figure )				
<b>Quoted Rate in Words (%)</b>		(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

# SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 90987.00  
EARNEST MONEY: - ₹ 1850.00  
TIME LIMIT : Two Months

**NAME OF WORK :-** Construction of link road Palwala to Lajot KM 0/00 TO 0/900.

**SUB-HEAD :-** Construction of U-Shape drain at Rd 0/575 to 0/598.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.10 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2485.00
2	providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 ( M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall ecttera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	16.15 Cubic metres	5480.00	Rupees Five Thousand Four Hundred Eighty Only	Per cubic metre	88502.00
TOTAL :-						90987.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure )				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,  
Shahpur Division,  
HPPWD Shahpur

(32)

**SCHEDULE OF QUANTITY**

ESTIMATED COST :- ₹ 88935.00  
 EARNEST MONEY :- ₹ 1800.00  
 TIME LIMIT : Two Months

**NAME OF WORK :-** AMP of link road from Ladwara to Bhowan KM 0/00 TO 4/540.

**SUB-HEAD :-** Construction of U-Shape drain at Rd 2/800 to 2/850.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	12.00 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	4200.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	15.75 Cubic metres	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	84735.00
<b>TOTAL :-</b>						<b>88935.00</b>
<b>Quoted Rate in Figure (%)</b>		<b>(Amount to be quoted by the contractor in Figure)</b>				
<b>Quoted Rate in Words (%)</b>		<b>(Amount to be quoted by the contractor in words)</b>				

Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY

33

ESTIMATED COST: ₹ 98918.00  
EARNEST MONEY ₹ 2000.00  
TIME LIMIT Two Months

NAME OF WORK :- Construction of Noun to Harizan Basti Hara road G.P. Shahpur Km 0/00 to 0/750. (Deposit work)

SUB-HEAD :- Construction of Pushta for R/wall from RD 0/427 to 0/430.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth-work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.95 Cubic metre	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2083.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 ( M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.Q.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	18.10 Cubic metre	5350.00	Rupees Five Thousand Three Hundred Fifty Only	Per cubic metre	96835.00
<b>TOTAL :-</b>						<b>98918.00</b>
	<b>Quoted Rate in Figure (%)</b>	(Amount to be quoted by the contractor in Figure )				
	<b>Quoted Rate in Words (%)</b>	(Amount to be quoted by the contractor in words)				

Executive Engineer,  
Shahpur Division,  
HPPWD Shahpur

**SCHEDULE OF QUANTITY**

34

ESTIMATED COST: ₹ 99321.00  
EARNEST MONEY ₹ 2000.00  
TIME LIMIT Two Months

**NAME OF WORK :-** Construction of Noun to Harizan Basti Hara road G.P. Shahpur Km 0/00 to 0/750. (Deposit work)

**SUB-HEAD :-** Construction of Pushta for R/wall from RD 0/419 to 0/422.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.88 Cubic metre	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2058.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	18.18 Cubic metre	5350.00	Rupees Five Thousand Three Hundred Fifty Only	Per cubic metre	97263.00
<b>TOTAL :-</b>						<b>99321.00</b>
	<b>Quoted Rate in Figure (%)</b>	(Amount to be quoted by the contractor in Figure)				
	<b>Quoted Rate in Words (%)</b>	(Amount to be quoted by the contractor in words)				

B-7  
Executive Engineer,  
Shahpur Division,  
HPPWD Shahpur


SCHEDULE OF QUANTITY

ESTIMATED COST: ₹ 99395.00  
EARNEST MONEY ₹ 2000.00  
TIME LIMIT Two Months

NAME OF WORK :- Construction of Noun to Harizan Basti Hara road G.P. Shahpur Km 0/00 to 0/750. (Deposit work)

SUB-HEAD :- Construction of Pushta for R/wall from RD 0/423 to 0/426.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.09 Cubic metre	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2132.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	18.18 Cubic metre	5350.00	Rupees Five Thousand Three Hundred Fifty Only	Per cubic metre	97263.00
TOTAL :-						99395.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

  
Executive Engineer,  
Shahpur Division,  
HREWD Shahpur

36

**SCHEDULE OF QUANTITY**

ESTIMATED COST: - ₹ 98938.00  
 EARNEST MONEY: - ₹ 2000.00  
 TIME LIMIT : Two Months

**NAME OF WORK :-** C/o Link road from Ladwara Bhowan road KM 0/00 to 4/540 in Tehsil Shahpur, Distt. Kangra (HP) .

**SUB-HEAD :-** U-shape Drain at RD 2/800 to 2/857.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	13.68 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	4788.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 ( M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	17.50 Cubic metres	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	94150.00
<b>TOTAL :-</b>						<b>98938.00</b>
<b>Quoted Rate in Figure (%)</b>		<b>(Amount to be quoted by the contractor in Figure )</b>				
<b>Quoted Rate in Words (%)</b>		<b>(Amount to be quoted by the contractor in words)</b>				

Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 87451.00  
 EARNEST MONEY:- ₹ 1750.00  
 TIME LIMIT : Two Months

NAME OF WORK :- C/o Link road to village Runehar khad (Nared)KM 0/00 TO 1/00 in Tehsil Shahpur, Distt. Kangra (HP) Under S.C.S.P)

SUB-HEAD :- Extension of Berm at Rd. 0/151 to 0/175 (LHS and RHS) & passing place at various Rds.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm( seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	1.50 Cubic metres	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	3375.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.25 Cubic metres	4800.00	Rupees Four Thousand Eight Hundred Only	Per cubic metre	15600.00

3	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	4.95  Cubic metres	6250.00	Rupees Six Thousand Two Hundred Fifty Only	Per cubic metre	30938.00
4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 ( M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etctera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	6.85  Cubic metres	5480.00	Rupees Five Thousand Four Hundred Eighty Only	Per cubic metre	37538.00
						<b>TOTAL :-</b>
Quoted Rate in Figure (%)						87451.00
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

Executive Engineer,  
Shahpur Division,  
HPPWD Shahpur


# SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 91258.00  
EARNEST MONEY: - ₹ 1850.00  
TIME LIMIT : Two Months

**NAME OF WORK :-** C/o Link road to village Runehar khad (Nared)KM 0/00 TO 1/00 in Tehsil Shahpur, Distt. Kangra (HP) Under S.C.S.P)  
**SUB-HEAD :-** Extension of Berm at Rd. 0/00 to 0/040 (LHS and RHS) & passing placed at various Rds.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm( seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	1.68 Cubic metres	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	3780.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty milimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.34 Cubic metres	4800.00	Rupees Four Thousand Eight Hundred Only	Per cubic metre	16032.00

3	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	5.32  Cubic metres	6250.00	Rupees Six Thousand Two Hundred Fifty Only	Per cubic metre	33250.00
4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 ( M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall ectera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	6.97  Cubic metres	5480.00	Rupees Five Thousand Four Hundred Eighty Only	Per cubic metre	38196.00
TOTAL :-						
Quoted Rate in Figure (%)			(Amount to be quoted by the contractor in Figure )			
Quoted Rate in Words (%)			(Amount to be quoted by the contractor in words)			
			91258.00			

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

(24) (39)

ESTIMATED COST: - ₹ 87451.00  
EARNEST MONEY :- ₹ 1750.00  
TIME LIMIT : Two Months


**SCHEDULE OF QUANTITY**

**NAME OF WORK** :- C/o Link road to village Runehar khad (Nared)KM 0/00 TO 1/00 in Tehsil Shahpur, Distt. Kangra (HP) Under S.C.S.P)

**SUB-HEAD** :- Extension of Berm at Rd. 0/176 to 0/200 (LHS and RHS) & passing place at various Rds.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm( seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	1.50 Cubic metres	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	3375.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.25 Cubic metres	4800.00	Rupees Four Thousand Eight Hundred Only	Per cubic metre	15600.00

3	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	4.95  Cubic metres	6250.00	Rupees Six Thousand Two Hundred Fifty Only	Per cubic metre	30938.00
4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 ( M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall ectera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	6.85  Cubic metres	5480.00	Rupees Five Thousand Four Hundred Eighty Only	Per cubic metre	37538.00
<b>TOTAL :-</b>						<b>87451.00</b>
<b>Quoted Rate in Figure (%)</b>			(Amount to be quoted by the contractor in Figure )			
<b>Quoted Rate in Words (%)</b>			(Amount to be quoted by the contractor in words)			

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

40

SCHEDULE OF QUANTITY

Name of work :-Construction of link road to Village Baldi km 0/0 to 1/00. (SH:- Construction of 3.00 mtr. Span RCC Slab Culvert at RD 0/400)				Estimated cost Rs.		79,533.00
				Earnest Money Rs.		1,600.00
				Time Limits		Two Months
S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
12	Providing and laying mechanically mixed and vibrated reinforced cement concrete grade M-25 (M-Twenty-five) designed mix with cement contents not less than 400 Kgs(Four hundred kilograms) per cubic metre with 20mm(Twenty millimetres) nominal size graded crushed stone aggregate (extra cement as per design mix above the minimum cement contents specified shall not be paid extra) in approach slab including cost of form work and reinforcement complete as per drawings and MORD technical specifications section 800, 900, 1000 and 1400 as directed by the Engineer-In-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	9.10	7250.00	Rupees Seven Thousand Two Hundred Fifty Only	Per Metric Tonne	65975.00
7	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	15.95	850.00	Rupees Eight Hundred Fifty Only	Per Metric Tonne	13558.00
Total						79533.00
Quoted Rate in Figure (%)			(Amount to be quoted by the contractor in Figure )			
Quoted Rate in Words (%)			(Amount to be quoted by the contractor in words)			


13-7  
Executive Engineer,  
Shahpur Division,  
HP.PWD Shahpur

SCHEDULE OF QUANTITY

(41)

Name of work :-Construction of link road to Village Baldi km 0/0 to 1/00.( Balance work). (SH:- Construction of 3.00 mtr. Span RCC Slab Culvert at RD 0/400)				Estimated cost Rs.	83,086.00
				Earnest Money Rs.	1,700.00
				Time Limits	Two Months
S. No.	Description of Item	Quantity	Rate	Unit	Amount
1	Providing and laying mechanically mixed and vibrated concrete for plain concrete in flooring of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	1.35	6150.00	Rupees Six Thousand One Hundred Fifty Only	8303.00
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete of grade M-20 (M-Twenty) design mix with cement contents not less than 330Kgs (Three hundred thirty kilograms) per cubic metre with 20mm (Twenty millimetres) nominal size graded crushed stone aggregate in sub-structure as per drawings and MORD technical specifications for Roads section 800, 900 and 1200 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block, dirt walls, up to any floor level and curing complete including carriage of materials in all kinds of leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including Octroi, Royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	1.40	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	9590.00
3	Providing and laying mechanically mixed and vibrated reinforced cement concrete in super structure as per drawing and M.O.R.D.. technical specification section 800, 900 and 1400 using R.C.C. grade M-25 ( twenty five) design mix with cement contents not less than 400 kg (four hundred kilogram) per cubic metre with 20mm (twenty millimetre ) nominal size graded crushed stone aggregate and curing complete including cost of form work but excluding the cost of reinforcement for reinforced concrete work in deck slab and to the entire satisfaction and as per the direction of Engineer-in-Charge including carriage of material within all leads , lifts and other incidentals .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.90	7150.00	Rupees Seven Thousand One Hundred Fifty Only	20735.00
4	Providing and laying mechanically mixed and vibrated reinforced cement concrete wearing coat of grade M -30 (M-thirty) design mix with cement contents not less than 407 kgs/cum ( four hundred seven kilogram per cubic metre) with 20mm (twenty millimetre) nominal size graded crushed stone aggregate including reinforcement complete as per drawing and MORTH technical specification section 1500,1600 ,1700 and 2700 including cost of form work and curing complete and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	0.95	7850.00	Rupees Seven Thousand Eight Hundred Fifty Only	7458.00

5	Supplying fitting and placing HYSD bar reinforcement in super-structures complete as per drawings and MORTH technical specifications clause 1600 and 2200, including cutting bending, binding, Straightening and placing in position complete in all respect including the cost of binding, wire upto all heights and depths and as per direction and entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The rate is including Royalty, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government.	0.400	92500.00	Rupees Ninety Two Thousand Five Hundred Only	Per Metric Tonne	37000.00	
						Total	83086.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)					
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)					

  
 Executive Engineer,  
 Shahpur Division,  
 HP.PWD Shahpur


# **SCHEDULE OF QUANTITY**

ESTIMATED	₹	98900.00
EARNEST	₹	2000.00
TIME LIMIT		One Month

**NAME OF WORK** :- Protection/Treatment of landslide Disaster on Bhaler to Dulli Road KM 0/000 to 4/000

**SUB-HEAD** :- Hiring of Excavator cum loader for removal slips

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Hiring of Excavator cum loader for improvement of profile correction of road in various reaches up to any height and lead including trimming to required line, width and grade in all kind and classification of soil including rocky portion and saturated soil as per and saturated soil as per direction and entire specification of Engineer-in-charge. The direction JCB/Excavator cum loader should work minimum 8 hours from 9.00 to 5.00 daily and excavate at least 30 cum Qty per hour. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge.	86.00 Hours	1150.00	Rupees one thousand one hundred fifty only	Per hours	98900.00
<b>TOTAL :-</b>						<b>98900.00</b>
	<b>Quoted Rate in Figure (%)</b>	<b>(Amount to be quoted by the contractor in Figure )</b>				
	<b>Quoted Rate in Words (%)</b>	<b>(Amount to be quoted by the contractor in words)</b>				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

### SCHEDULE OF QUANTITY

Estimated cost:- Rs. 99000.00


Earnest Money:- Rs.2000.00

Time Allowed:- One Month

Name of Work: Restoration of Rain Damages On various Roads under HP.PWD SUB Division Gaggal


Sub Head:- Hiring of J.C.B/ Excavator cum loader for removal of slips at various Roads under Charri section.

Sr. No.	Sub-Head/ Items of Work.	Quantity	Rates		Unit	Amount
			In Figures	In Words		
1.	Hiring of J.C.B/Excavator cum loader for Removal of slips including trimming of Edge cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil due to non Availability of departmental machinery as per the direction and entire satisfaction of Engineer-in charge. The direction JCB/Excavator cum loader should work minimum 8 hours from 9.00 to 5.00 daily and excavate at least 30 cum Qty per hour. Any loss to the public/Private property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare, watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is including octroi, Royalty, Malkana , toll tax ,GST or other taxes imposed by the government . No Deviation shall be allowed in any case.	90.00	1100.00	(Rupees one Thousand One Hundred Fifty only)	Per Hour	99000.00
					<b>Total:-</b>	<b>99000.00</b>
	<b>Quoted Rate in Figure (%)</b>	<b>Amount to be Quoted by contractor in Figure</b>				
	<b>Quoted Rate in Words (%)</b>	<b>Amount to be Quoted by contractor in Words</b>				

  
Executive Engineer  
Shahpur Division,  
HPPWD, Shahpur


**D.N.I.T./ SCHEDULE OF QUANTITY**

Name of work :-Restoration of rain Damages on Various roads under HP.PWD Sub Division Shahpur (Sub Head: - Hiring of JCB/excavator cum loader for removal of slips at various roads under Rait Section).				Estimated cost Rs.		99,000.00
				Earnest Money Rs.		2,000.00
				Time Limits		Two Month
S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of J.C.B./Excavator cum loader for removal of slip including trimming and edge cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil due to non availability of departmental machinery as per direction and entire satisfaction of engineering-in- Charge. The J.C.B./Excavator cum loader should work minimum 8.00 (eight) hours daily and excavated at least 30.00(thirty) cubic metre quantity per hour . Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. No deviation shall be allowed in any case.	90.00 Hour	1100.00	Rupees one thousand one hundred only	Per Hour	99000.00
	Total					99000.00
	Quoted Rate( in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

  
 Executive Engineer,  
 Shahpur Division,  
 HP.PWD Shahpur


**D.N.I.T./ SCHEDULE OF QUANTITY**

Name of work :-Restoration of rain Damages on Various roads under HP.PWD Sub Division Shahpur (Sub Head: - Hiring of JCB/excavator cum loader for removal of slips at various roads under Harchakian Section).				Estimated cost Rs.		99,000.00
				Earnest Money Rs.		2,000.00
				Time Limits		Two Month
S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of J.C.B./Excavator cum loader for removal of slip including trimming and edge cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil due to non availability of departmental machinery as per direction and entire satisfaction of engineering-in- Charge. The J.C.B./Excavator cum loader should work minimum 8.00 (eight) hours daily and excavated at least 30.00(thirty) cubic metre quantity per hour . Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. No deviation shall be allowed in any case.	90.00 Hour	1100.00	Rupees one thousand one hundred only	Per Hour	99000.00
<b>Total</b>						<b>99000.00</b>
<b>Quoted Rate( in Figures) Percentage</b>		<b>Excess (+)</b>			%	
		<b>Less (-)</b>			%	
<b>G.Total in Figures</b>						
<b>G.Total in Words</b>						

  
 Executive Engineer,  
 Shahpur Division,  
 HP.PWD Shahpur

**D.N.I.T./ SCHEDULE OF QUANTITY**


Name of work :-Restoration of rain Damages on Various roads under HP.PWD Sub Division Gaggal (Sub Head: - Hiring of JCB/excavator cum loader for removal of slips at various roads under Gaggal Section).				Estimated cost Rs.		99,000.00
				Earnest Money Rs.		2,000.00
				Time Limits		Two Month
S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of J.C.B./Excavator cum loader for removal of slip including trimming and edge cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil due to non availability of departmental machinery as per direction and entire satisfaction of engineering-in- Charge. The J.C.B./Excavator cum loader should work minimum 8.00 (eight) hours daily and excavated at least 30.00(thirty) cubic metre quantity per hour . Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. No deviation shall be allowed in any case.	90.00 Hour	1100.00	Rupees one thousand one hundred only	Per Hour	99000.00
	Total					99000.00
	Quoted Rate( in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

  
 Executive Engineer,  
 Shahpur Division,  
 HP.PWD Shahpur

47

### D.N.I.T./ SCHEDULE OF QUANTITY


Name of work :-Restoration of rain Damages on Various roads under Darini section under HP.PWD Sub Division Darini (Sub Head: - Hiring of JCB/excavator cum loader for removal of slips at various roads under Darini Section).				Estimated cost Rs.		99,000.00
				Earnest Money Rs.		2,000.00
				Time Limits		Two Month
S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of J.C.B./Excavator cum loader for removal of slip including trimming and edge cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil due to non availability of departmental machinery as per direction and entire satisfaction of engineering-in- Charge. The J.C.B./Excavator cum loader should work minimum 8.00 (eight) hours daily and excavated at least 30.00(thirty) cubic metre quantity per hour . Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Exacavator owner which shall have to be fully compensated by the contrator in all cases. The fule and operational staff for Excavator will be provided by the owner. The repair and spare, watch and waid of Excavator also be born by the cō.tractor/owner. The daily log book wii be maintained at site which should be duly verified by the Engineer-in-Charge.The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. No deviation shall be allowed in any case.	90.00 Hour	1100.00	Rupees one thousand one hundred only	Per Hour	99000.00
<b>Total</b>						<b>99000.00</b>
<b>Quoted Rate( in Figures) Percentage</b>		<b>Excess (+)</b>			%	
		<b>Less (-)</b>			%	
<b>G.Total in Figures</b>						
<b>G.Total in Words</b>						

  
 Executive Engineer,  
 Shahpur Division,  
 HP.PWD/Shahpur

98


### D.N.I.T./SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Various roads under HP.PWD Sub Division Shahpur (Sub Head: - Hiring of JCB/excavator cum loader for removal of slips on Shahpur Chakban Lapiana road ).				Estimated cost Rs.		99,000.00
				Earnest Money Rs.		2,000.00
				Time Limits		Two Month
S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of J.C.B./Excavator cum loader for removal of slip including trimming and edge cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil due to non availability of departmental machinery as per direction and entire satisfaction of engineering-in- Charge. The J.C.B./Excavator cum loader should work minimum 8.00 (eight) hours daily and excavated at least 30.00(thirty) cubic metre quantity per hour . Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. No deviation shall be allowed in any case.	90.00 Hour	1100.00	Rupees one thousand one hundred only	Per Hour	99000.00
<b>Total</b>						<b>99000.00</b>
<b>Quoted Rate( in Figures) Percentage</b>		<b>Excess (+)</b>			%	
		<b>Less (-)</b>			%	
<b>G.Total in Figures</b>						
<b>G.Total in Words</b>						

  
 Executive Engineer,  
 Shahpur Division,  
 HP.PWD Shahpur

**D.N.I.T./ SCHEDULE OF QUANTITY**

Name of work :-Restoration of rain Damages on Various roads under HP.PWD Sub Division Darini (Sub Head: - Hiring of JCB/excavator cum loader for removal of slips at various roads under Boh Section).				Estimated cost Rs.		99,000.00
				Earnest Money Rs.		2,000.00
				Time Limits		Two Month
S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of J.C.B./Excavator cum loader for removal of slip including trimming and edge cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil due to non availability of departmental machinery as per direction and entire satisfaction of engineering-in- Charge. The J.C.B./Excavator cum loader should work minimum 8.00 (eight) hours daily and excavated at least 30.00(thirty) cubic metre quantity per hour . Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. No deviation shall be allowed in any case.	90.00 Hour	1100.00	Rupees one thousand one hundred only	Per Hour	99000.00
<b>Total</b>						<b>99000.00</b>
<b>Quoted Rate( in Figures) Percentage</b>		<b>Excess (+)</b>			<b>%</b>	
		<b>Less (-)</b>			<b>%</b>	
<b>G.Total in Figures</b>						
<b>G.Total in Words</b>						

  
 Executive Engineer,  
 Shahpur Division,  
 HP.PWD Shahpur