



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in

NO: PWD/BN/TA/NIT/2025-26/-
To

5882-87

Dated:-02.08.2025

✓
The Executive Engineer, (IT Cell),
Nirman Bhawan Nigam Vihar,
Shimla-2.

Subject:- Publication of Tender Notice on the Departmental website.


Dear Sir,

Enclosed herewith is the Tender Notice for the work specified in the Notice Inviting tender (NIT). You are kindly requested to upload the same on the official website of the department in accordance with Notification No.PBW(B)A(3)1/2024 dated 03.01.2024, issued by the Secretary (PW) to the Government of Himachal Pradesh.

The works mentioned in the Notice Inviting Tender are urgent/emergent nature of works in public interest. Kindly ensure the prompt publication of the same on the website.

Encl: Notice Inviting Tender
& Schedule of Quantity.

Yours faithfully,


Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.

Copy forwarded for information to:-

1. The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
2. All the Assistant Engineers working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.

Executive Engineer,
Baijnath Division.,
H.P.PWD..Baijnath.



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Sealed percentage rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **19.08.2025** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **18.08.2025 between 2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **14.08.2025 up to 12.00 Noon**.


The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	Repair of road from main road to Katoch Basti ward no.2 (SDF/2025/206) (SH: P/L interlocking paver blocks at RD 0/00 to 0/024)	97,984/-	2000/-	Rs.350/-	Two Months
2	C/o Road from Upper Thehad to Kudang Km 0/00 to 1/00 (SH: C/O R/Wall at RD 0/060 to 0/064.20)	97,363/-	2000/-	Rs.350/-	One Month
3	Reconstruction/Restoration on Barot to Nalhota Road Km 0/00 to 15/500 (SCA Deposit) (SH: Construction of R/wall in wire crate at km 9/095 to 9/102)	99,677/-	2000/-	Rs.350/-	Two Months
4	Repair of Road to katoch Basti Main Road to GP Kothi Mohal (SDF/2025/207) (SH: P/L GSB, C.C. pavement at RD 0/00 to 0/022.50)	96,472/-	2000/-	Rs.350/-	Two Month
5	Restoration and Reconstruction on Baijnath Deol Phatar road km 0/00 to 10/180 (SH: C/O Protection wall at RD 7/435 and U-Shape drain at RD 7/420 to 7/430) SCA Deposit	82,184/-	1,700/-	Rs.350/-	Two Months
6	Re-construction/Restoration of Baijnath Deol Phatar road Km 0/00 to 8/00 (SH: C/O Kuhal Crossing at RD 7/060 to 7/067 along with grating & U/S, D/S Toe wall of culvert at RD 3/250)	99,463/-	2000/-	Rs.350/-	Two Months
7	R/D on various road under Bir Sub-Division (Multhan Section) (SH: Hiring of Tipper for Shifting of Carriage/disposal of Muck, derbies)	99,000/-	2000/-	Rs.350/-	One Month
8	Reconstruction/Restoration on Barot to Nalhota Road Km 0/00 to 15/500 (SCA Deposit) (SH: Construction of R/wall in wire crate at km 5/915 to 5/921)	91,820/-	1900/-	Rs.350/-	Two Months
9	C/O Bhadar Ghar at kathog/Baijnath (SH: C/O Civil works) (Deposit work VKV/2023/1653)	99,646/-	2000/-	Rs.350/-	One Month

1. The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.

E.E.

3. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
4. Only two tenders form will be issued to the contractor/firm which may be noted.
5. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
6. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
7. The contractor shall have all required machinery such as Truck/Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
8. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
9. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
10. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.


Executive Engineer
Balrath Division
H.P.P.W.D. Balrath
For & On behalf of the governor of H.P.

DNT/DRAFT SCHEDULE OF QUANTITY

Name of work :- Repair of road from main road to Katoch Basti Ward no. 2 (SDF/2025/206).
(SH-P/L interlocking paver blocks at RD 0/00 to 0/024)

Estimate Cost: 97,984.00/-
Earnest Money: 2,000.00/-
Time Limit : Two months

SCHEDULE OF WORKS					
Sr. No.	Description of work	No. or Qty.	Unit	Rate	AMOUNT Rs. P
				Figures Words	
1	Providing and laying hard stone Soiling properly hand packed intersects with kharanja stone and consolidating with power / hand roller to requested gradient and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	2.24	Per Cubic metre	1,850.00 Rupees One Thousand Eight Hundred & Fifty Only	4,144.00
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 40 mm as per drawing and Technical Specification Clause 1504 entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate shall include all lead, lift and proper stacking complete in all respect as per the direction of the Engineer-in-charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	62.40	Per Square metre	1,450.00 Rupees One Thousand Four Hundred & Fifty Only	90,480.00
3	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	0.48	Per Cubic metre	7,000.00 Rupees Seven Thousand Only	3,360.00
Total					97,984.00
Quoted rates Percentage in figures					
Quoted rates Percentage in words					

Condition :-

1. Rate should be quoted for all heights including all leads and lifts
2. Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per Indian standard in market should confirm to bureau of Indian standards

D.N.I.T. Checked and approved for Rs. 97,984.00 only
Rupees Ninety Seven Thousand Nine Hundred Eighty Four Only

Engineer
Bairnath Division
HPPWD Bairnath

DNT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Road from Upper thechad to Kudang km 0/00 to 1/00
(SH-C/O R/wall at RD 0/060 to 0/064,20)

Estimate Cost: 97,363.00/-
Earnest Money: 2,000.00/-
Time Limit : One Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	3.32	Per Cum	290.00	Rupees Two Hundred & Ninety Only	963.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	18.71	Per Cum	4950.00	Rupees Four Thousand Nine Hundred & Fifty Only	92,912.00
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	1.18	Per Cum	990.00	Rupees Nine Hundred & Ninety Only	1,168.00
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	8.00	Each	290.00	Rupees Two Hundred & Ninety Only	2,320.00
Quoted rates Percentage in figures						
Quoted rates Percentage in words						
Total						97,363.00

D.N.I.T. Checked and approved for Rs. 97,363.00 only
Rupees Ninety Seven Thousand Three Hundred Sixty Three Only

Executive Engineer
Bajinath Division
HPPWD Bajinath

DNIT/DRAFT SCHEDULE OF QUANTITY

3

Name of work: **Reconstruction / Restoration on Barot to Nalhotra Road km 0/00 to 15/500 (S.C.A Deposit)**
(SH : Construction of R/wall in wire crate at km 9/095 to 9/102)

Estimate Cost: 99,677.00/-
Earnest Money: 2,000.00/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Figures	Rate	AMOUNT Rs. P
				Words	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost.	9.19	Per Cubic metre	290.00	Rupees Two Hundred Ninety Only	2,665.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS 280 and IS 4826 in 150 mm x 150 mm mesh (woven diagonally) including 10 per extra for laps and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specifications clause 1301 Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	32.81	Per Cubic metre	2700.00	Rupees Two Thousand Seven Hundred Only	88,587.00
3	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1604.7 and section 300, as per direction of Engineer-In-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	8.51	Per Cubic metre	990.00	Rupees Nine Hundred Ninety Only	8,425.00
	Quoted rates Percentage in figures					99,677.00
	Quoted rates Percentage in words					

Estimate Checked and approved for Rs. 99,677.00 only
Rupees Ninety Nine Thousand Six Hundred Seventy Seven Only

Executive Engineer
Bajinath Division
HPPW/D Bajinath

(4)

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- Repair of Road to Katoch Basti Main Road to GP Kotli Mohal (SDF/2025/207)
(SH.-P/L GSB, C C Pavement at RD 0/00 to 0/022.50)

Estimate Cost: 96,472.00/-
Earnest Money: 2,000.00/-
Time Limit : Two Months

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Words		
1	Providing and laying Granular sub-base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification (Clause 408 as per direction of Engineer with in all leads and lifts and other incidental the entire satisfaction and through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	8.86	Per Cubic metre	Rupees Two Thousand Five Hundred & Fifty Only		22,593.00
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications (Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	10.63	Per Cubic metre	Rupees Six Thousand Nine Hundred & Fifty Only		73,879.00
Total						96,472.00
Quoted rates Percentage in figures						
Quoted rates Percentage in words						

Condition :-

1. Rate should be quoted for all heights including all leads and lifts
2. Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per indian standard in market should confirm to bureau of indian standards

D.N.I.T. Checked and approved for Rs.

96,472.00 only

Rupees Ninety Six Thousand Four Hundred Seventy Two Only

Executive Engineer
Bainnath Division
HPPWD Bainnath

DNIT/DRAFT SCHEDULE OF QUANTITY

5 (a)

Name of work :- Restoration and Reconstruction on Baijnath Deol Phatar road km 0/00 to 10/180
(SH:-C/O Protection wall at RD 7/435 and U-shape drain at RD 7/420 to 7/430) **SCA Defect**


Estimate Cost: 82,184.00/-
Earnest Money: 1,700.00/
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling, wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-in-Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	14.78	Per Cum	290.00 Rupees Two Hundred & Ninety Only		4,286.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	7.66	Per Cum	5000.00 Rupees Five Thousand Only		38,300.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm (forty millimeter) nominal size) in or under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work, and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer-in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	5.15	Per cubic metre	5500.00 Rupees Five Thousand Hundred Only		28,325.00
4	Providing weep holes in brick masonry/stone masonry, plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	2.00	Each	290.00 Rupees Two Hundred & Ninety Only		580.00
5	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals, including entire carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.71	Per Cum	990.00 Rupees Nine Hundred & Ninety Only		1,693.00

(5) (6)

6	20mm cement plaster in single coat on the rough side of brick/concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (Eighty millimeter) in rough side with cement mortar 1:6 (One :six) as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	40.00	Sqm	225.00	Rupees Two Hundred & Twenty Five Only	9,000.00
	Quoted rates Percentage in figures					82,184.00
	Quoted rates Percentage in words					
	Total					82,184.00

D.N.I.T. Checked and approved for Rs. 82,184.00 only
Rupees Eighty Two Thousand One Hundred Eighty Four Only


Executive Engineer
Bainnath Division
HPPWD Bainnath

6

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- ReConstruction / Restoration of Baijnath Deol Phatar road km 0/00 to 8/00
(SH:-C/O Kuthal crossing at RD 7/060 to 7/067 along with grating & U/S, D/S Toe wall of culvert at RD 3/250)

Estimate Cost: 99,463.00/-
Earnest Money: 2,000.00/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling (wedging out rocks). Where blasting is prohibited for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer - in - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	4.70	Per Cum	290.00	Rupees Two Hundred & Ninety Only	1,363.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in - Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	15.00	Per cubic metre	5560.00	Rupees Five Thousand Five Hundred & Sixty Only	83,400.00
3	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position in beams, joists channels, angles, tee, flats with connecting plates or angle cleats as in main and cross beams, ship and jack rafters, girders connected to common rafters and the like work including cutting, hoisting, fixing in position & applying a priming coat of red lead paint complete including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	150.00	Kg	98.00	Rupees Ninety Eight Only	14,700.00
Quoted rates Percentage in figures						
Quoted rates Percentage in words						
Total						99,463.00

D.N.I.T. Checked and approved for Rs.

99,463.00 only

Rupees Ninety Nine Thousand Four Hundred Sixty Three Only

Condition :-

Executive Engineer
Baijnath Division
HPPWD Baijnath

1. Rate should be quoted for all heights including all leads and lifts
2. Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per indian standard in market should confirm to bureau of indian standards

DNIT/SCHEDULE OF QUANTITY

(7)

Estimated Cost:- 99,000.00 ✓
Earnest Money:- 2000.00 ✓
Time Limit:- One Month ✓

Name of work:- : R/D on various road under Bir Sub Division (Multan section)
(SH:- Hiring of Tipper for Shifting of Carriage/disposal of Muck, derbies.)

Sr. No.	Description of items	Quantity	Rates (in Rupees)		Unit	Amount (in Rupees)
			In Figure	In words		
1	2	3	4	5	6	7
1.	Hire charges of tipper for carriage/shifting of soling stone earth, moorum, premix material, seal coat etc. having capacity of 5.50 (five point five zero) cubic metre per trip and covering 70 (seventy) kilometers per day (9AM to 5PM), the contractor/ owner of tipper shall bear the expensive of POL charges, repair of machineries including driver and helper wages. Any accident and other damages to private and Govt property occur during the working hours in the work shall be the responsibility of the contractor and disposal of excavated material/ slips debris with in all leads and lifts as per the direction of Engineer-in-Charge. The rates are inclusive of all taxes including GST levy by the Govt. time to time.	22.00 ✓	4500.00 ✓	Rupees four thousand five hundred only ✓	Per Working Day ✓	99,000.00 ✓
Total						99,000.00 ✓
Rate						
Percentage						

TERMS AND CONDITIONS:-

- The work should be carried out as per directions of Engineer-in-Charge. ✓
- The tipper should be inclusive of all rates as lubricants repair charges etc.
- The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge.

DNIT checked and approved for Rs 99,000.00 only

Executive Engineer
Bajinath Division
H.P.P.W.D. Bajinath

DNT/DRAFT SCHEDULE OF QUANTITY

Name of work: Reconstruction / Restoration on Barot to Nalhotla Road km 0/00 to 15/500 (Sec. A Deposit)
(SH : Construction of R/wall in wire crate at km 5/915 to 5/921)

Estimate Cost: 91,820.00/-
Earnest Money: 1,900.00/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Figures	Rate	AMOUNT Rs. P
					Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D. technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost.	7.20	Per Cubic metre	290.00	Rupees Two Hundred Ninety Only	2,088.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS 280 and IS 4826 in 100mm x 100 mm mesh (woven diagonally) including 10 per extra for laps and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specifications clause 1301 Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	29.38	Per Cubic metre	2850.00	Rupees Two Thousand Eight Hundred Fifty Only	83,733.00
3	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1604.7 and section 300, as per direction of Engineer-In-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.06	Per Cubic metre	990.00	Rupees Nine Hundred Ninety Only	5,999.00
	Quoted rates Percentage in figures					91,820.00
	Quoted rates Percentage in words					

Estimate Checked and approved for Rs. 91,820.00 only
Rupees Ninety One Thousand Eight Hundred Twenty Only

Executive Engineer
Bajinath Division
HPP/WD Bajinath

DNIT/DRAFT SCHEDULE OF QUANTITY

(9)

Name of work :- C/O Bhadar Char at Kathog / Baijnath
(SH:- C/O Civil works) (Deposit work VK V/2023/1653)

Sr.n	Description of work	No.or Qty.	Unit	Estimate Cost: 99,646.00 ✓ Earnest Money: 2000.00 ✓ Time Limit : One month ✓	
				Figures	Rate Words
1	Steel work welded in built up sections, runsses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In gratings framed guard bars, ladders, railing, brackets and similar works. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1027.28 ✓	KG ✓	97.00 ✓	Rupees Ninety Seven Only ✓
	Quoted rates Percentage in figures				
	Quoted rates Percentage in words				
					AMOUNT Rs. P 99,646.00 ✓

D.N.I.T. Checked and approved for Rs.

99,646.00 only ✓

Rupees Ninety Nine Thousand Six Hundred Forty Six Only ✓

Executive Engineer
Baijnath Division
HPPW D/Baijnath

(Signature)