Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal **Pradesh Public works Department Baijnath-176125**
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in

NO: PWD/BN/TA/NIT/2025-26/- 7048-53 Dated:-**19.08.2025**
To

The Executive Engineer, (IT Cell),
Nirman Bhawan Nigam Vihar,
Shimla-2.

Subject:- Publication of Tender Notice on the Departmental website.

Dear Sir,

Enclosed herewith is the Tender Notice for the work specified in the Notice Inviting tender (NIT). You are kindly requested to upload the same on the official website of the department in accordance with Notification No.PBW(B)A(3)1/2024 dated 03.01.2024, issued by the Secretary (PW) to the Government of Himachal Pradesh.

The works mentioned in the Notice Inviting Tender are urgent/emergent nature of works in public interest. Kindly ensure the prompt publication of the same on the website.

Encl: Notice Inviting Tender
& Schedule of Quantity.

Yours faithfully,

Executive Engineer,
Baijnath Division
H.P.PWD. Baijnath

Copy forwarded for information to:-

1. The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
2. All the Assistant Engineers working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.

Executive Engineer,
Baijnath Division.,
H.P.PWD..Baijnath.

Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Sealed percentage rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **05.09.2025** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **04.09.2025 between 2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **03.09.2025 up to 12.00 Noon.**

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	C/O Dhandole to Jamthala Road Km 0/00 to 1/00 (SH: C/O R/Wall at RD 0/915 to 0/920.50)	98,148/-	2,000/-	Rs.350/-	One Month
2	C/O Baijnath Deol Phatar road Km 0/00 to 10/180 (SH: C/O E/Wall at RD 5/090 to 5/114) OFC	98,348/-	2,000/-	Rs.350/-	Two Months
3	Reconstruction/Restoration on Sanghrehar to Dharman Road Km 0/00 to 2/200 (SH: Removal of slips between Km 0/00 to 0/380)	99,357/-	2,000/-	Rs.350/-	One Month
4	Reconstruction/Restoration on Barot to Nalhota Road Km 0/00 to 15/500 (SH: Construction of R/Wall in wire crate at Km 5/936 to 5/941)	85,543/-	1,800/-	Rs.350/-	Two Months
5	Reconstruction/Restoration on Barot to Nalhota Road Km 0/00 to 15/500 (SH: Construction of R/Wall in wire crate at Km 10/962 to 10/970)	91,472/-	1,900/-	Rs.350/-	Two Months
6	Reconstruction/Restoration on Barot to Nalhota Road Km 0/00 to 15/500 (SH: Construction of R/Wall in wire crate at Km 5/922 to 5/928)	92,353/-	1,900/-	Rs.350/-	Two Months
7	Restoration of Rain Damages on Baijnath Deol Phatar Road Km 0/00 to 8/000 (SH: Construction of R/Wall in wire crate at Km 3/465 to 3/470)	85,543/-	1,800/-	Rs.350/-	Two Months

1. The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
3. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
4. Only two tenders form will be issued to the contractor/firm which may be noted.
5. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
6. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
7. The contractor shall have all required machinery such as Truck/Tipper,Mixture,water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
8. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
9. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
10. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer
Baijnath Division
H.P.P.W.D. Baijnath.

Executive Engineer,
Baijnath Division,
H.P.P.W.D. Baijnath.
For & On behalf of the governor of H.P.

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work: C/O Dhandole to Jamthala Road km 0/00 to 1/00
(Sh:- C/O R/wall at RD 0/915 to 0/920.50).

Estimate Cost: 98,148.00/-
Earnest Money: 2,000.00/-
Time Limit :One Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	Rs. P
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.the rate including of octroi, royality, Malkana, tolltax, or other taxes imposed by the government.	10.12	Per Cum	290.00	Rupees Two Hundred & Ninety Only	2,935.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 &1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royality, Malkana, tolltax, or other taxes imposed by the government.	18.15	Per cubic metre	4950.00	Rupees Four Thousand Nine Hundred & Fifty Only	89,843.00
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals.The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.96	Per Cum	990.00	Rupees Nine Hundred & Ninety Only	3,920.00
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals.the rate including of octroi, royality, Malkana, tolltax, or other taxes imposed by the government.	5.00	Each	290.00	Rupees Two Hundred & Ninety Only	1,450.00
	Total					**98,148.00**
	Quated rates Percentage in figures					
	Quated rates Percentage in words					

D.N.I.T. Checked and approved for Rs. 98,148.00 only
Rupees Ninety Eight Thousand One Hundred Forty Eight Only

Executive Engineer
Baijnath Division
HPPWD Baijnath

Condition :-

1. Rate should be quoted for all heights including all leads and lifts
2. Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per indian standard in market should confirm to bureau of indian standards

(2)

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Baijnath Deol Phatar road km 0/00 to 10/180
(SH:-C/O E/wall at RD 5/090 to 5/114) OFC

Estimate Cost:98,348.00/-
Earnest Money: 2,000.00/-
Time Limit :Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.the rate including of octroi, royality, Malkana, tolltax, or other taxes imposed by the government.	19.20	Per Cum	290.00	Rupees Two Hundred & Ninety Only	5,568.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 &1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royality, Malkana, tolltax, or other taxes imposed by the government.	17.28	Per Cum	5000.00	Rupees Five Thousand Only	86,400.00
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals.the rate including of octroi, royality, Malkana, tolltax, or other taxes imposed by the government.	22.00	Each	290.00	Rupees Two Hundred & Ninety Only	6,380.00
	Total					**98,348.00**
	Quated rates Percentage in figures					
	Quated rates Percentage in words					

D.N.I.T. Checked and approved for Rs. 98,348.00 only
Rupees Ninety Eight Thousand Three Hundred Forty Eight Only

Executive Engineer
Baijnath Division
HPPWD Baijnath

Condition :-

1. Rate should be quoted for all heights including all leads and lifts
2. Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per indian standard in market should confirm to bureau of indian standards

(3)

D.N.I.T/ SCHEDULE OF QUANTITY

Name of Work:-Reconstruction / Restoration on Sanghrehar to Dharman Road km 0/00 to 2/200

(SH:- Removal of slips between km 0/00 to 0/380 .)

Estimated Cost:- 99,357.00

Earnest Money:- 2,000.00

Time:- One Month

SR. No.	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				In Figure	Figures	
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cuut material with in lift upto 1.50 mtr. And less than 100 mtr. As per technical specification 302.3.5 and 1611. Including carriage of materials within leads and lifts and other incidental.The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	821.13	Per cum	121.00	One Hundred Thirty Eight rupees only .	99357.00
	Total:-					**99357.00**
	Quated rates Percentage in figures					
	Quated rates Percentage in words					

D.N.I.T. Checked and approved for Rs. 99,357.00 only

Rupees Ninety Nine Thousand Three Hundred Fifty

Executive Engineer
Baijnath Division
HPPWD Baijnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work: Reconstruction / Restoration on Barot to Nalhota Road km 0/00 to15/500
(SH : Construction of R/wall in wire crate at km 5/936 to 5/941)

Estimate Cost:85,543.00/-
Earnest Money: 1,800.00/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	Rs. P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Enginer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .	6.00	Per Cubic metre	290.00	Rupees Two Hundred & Ninety Only	1,740.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire confirming to IS 280 and IS 4826 in 100mm x 100 mm mesh (woven diagonally) including 10 per exra for laps and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specifications clause 1301 Including carriage of materials within all leads and lifts and other incidental.The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	27.65	Per Cubic metre	2850.00	Rupees Two Thousand Eight Hundred & Fifty Only	78,803.00
3	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1604.7 and section 300, as per direction of Engineer-In-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	5.05	Per Cubic metre	990.00	Rupees Nine Hundred & Ninety Only	5,000.00
	Quated rates Percentage in figures					**85,543.00**
	Quated rates Percentage in words					

Estimate Checked and approved for Rs. 85,543.00 only
Rupees Eighty Five Thousand Five Hundred Forty Three Only

Executive Engineer
Baijnath Division
HPPWD Baijnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work: Reconstruction / Restoration on Barot to Nalhota Road km 0/00 to15/500
(SH : Construction of R/wall in wire crate at km 10/962 to 10/970)

Estimate Cost:91,472.00/-
Earnest Money: 1,900.00/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	Rs. P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Enginer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .	4.32	Per Cubic metre	290.00	Rupees Two Hundred & Ninety Only	1,253.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire confirming to IS 280 and IS 4826 in 100mm x 100 mm mesh (woven diagonally) including 10 per exra for laps and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specifications clause 1301 Including carriage of materials within all leads and lifts and other incidental.The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	30.53	Per Cubic metre	2850.00	Rupees Two Thousand Eight Hundred & Fifty Only	87,011.00
3	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1604.7 and section 300, as per direction of Engineer-In-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.24	Per Cubic metre	990.00	Rupees Nine Hundred & Ninety Only	3,208.00
	Quated rates Percentage in figures					**91,472.00**
	Quated rates Percentage in words					

Estimate Checked and approved for Rs. 91,472.00 only
Rupees Ninety One Thousand Four Hundred Seventy Two Only

Executive Engineer
Baijnath Division
HPPWD Baijnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work: Reconstruction / Restoration on Barot to Nalhota Road km 0/00 to15/500
(SH : Construction of R/wall in wire crate at km 5/922 to 5/928)

Estimate Cost:92,353.00/-
Earnest Money: 1,900.00/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	Rs. P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Enginer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .	6.84	Per Cubic metre	290.00	Rupees Two Hundred & Ninety Only	1,984.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire confirming to IS 280 and IS 4826 in 100mm x 100 mm mesh (woven diagonally) including 10 per exra for laps and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specifications clause 1301 Including carriage of materials within all leads and lifts and other incidental.The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	29.52	Per Cubic metre	2850.00	Rupees Two Thousand Eight Hundred & Fifty Only	84,132.00
3	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1604.7 and section 300, as per direction of Engineer-In-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.30	Per Cubic metre	990.00	Rupees Nine Hundred & Ninety Only	6,237.00
						92,353.00
	Quated rates Percentage in figures					
	Quated rates Percentage in words					

Estimate Checked and approved for Rs. 92,353.00 only
Rupees Ninety Two Thousand Three Hundred Fifty Three Only

Executive Engineer
Baijnath Division
HPPWD Baijnath

W D 274

(4)

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work: Restoration of Rain Damages on Baijnath Deol Phatar Road km 0/00 to 8/000 (SH : Construction of R/wall in wire crate at km 3/465 to 3/470)				Estimate Cost:85,543.00/- Earnest Money: 1,800.00/- Time Limit : Two Months		
Sr. No.	**Description of work**	**No. or Qty.**	**Unit**	**Rate**		**AMOUNT**
				Figures	**Words**	**Rs. P**
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Enginer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .	6.00	Per Cubic metre	290.00	Rupees Two Hundred & Ninety Only	1,740.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire confirming to IS 280 and IS 4826 in 100mm x 100 mm mesh (woven diagonally) including 10 per exra for laps and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specifications clause 1301 Including carriage of materials within all leads and lifts and other incidental.The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	27.65	Per Cubic metre	2850.00	Rupees Two Thousand Eight Hundred & Fifty Only	78,803.00
3	Back filling with granular material behind abutments, wing walls, return walls complete as per drawing and M.O.R.D. technical specification clause 1604.7 and section 300, as per direction of Engineer-In-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	5.05	Per Cubic metre	990.00	Rupees Nine Hundred & Ninety Only	5,000.00
						85,543.00
	Quated rates Percentage in figures					
	Quated rates Percentage in words					

Estimate Checked and approved for Rs. 85,543.00 only
Rupees Eighty Five Thousand Five Hundred Forty Three Only

Executive Engineer
Baijnath Division
HPPWD Baijnath