

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PWD/DEH/CB/TENDER/2024-25-
To

3660-85

DATED: 04/8/25

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject :- Tender Notice.

Enclosed kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on Department website as per notification of Principal Secretary (PW) to the Govt. of HP vide No. PBW(B)A(3)1/2024 dated 03.01.2024 as the works mentioned in the notice inviting tender are urgent/emergent nature of works in public interest.

Encl:-As above

Executive Engineer,
HPPWD Division,
Dehra.

Copy forwarded to the following:-

1. The FC-Cum Secy.(PW) to the Govt. of HP.Shimla-2.
2. The Engineer-in-Chief, HPPWD., Shimla.
3. The Chief Engineer(KZ) HP.PWD. Dharamshala.
4. The Superintending Engineer, Circle HP.PWD. Dehra.
5. All the Executive Engineer under North Zone.
6. All the Assistant Engineer under Dehra Division.
7. The Deputy Commissioner Kangra at Dharamshala.
8. The SDM/Tehsil/President MC Dehra.
9. The BDO Dehra /Pragpur/ Nagrota Surian.
10. Notice Board.
11. All the Head of Branches.
12. All the Contractors working under Dehra Division.

Executive Engineer,
Dehra Division HP.PWD.,
Dehra.

H. P. P.W.D. TENDER

Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Dehra Division HPPWD., Dehra on behalf of the Governor of HP for the following works from the approved and eligible contractors (C&D Class) enlisted in HPPWD.

TENDER SCHEDULE:

- | | |
|---|----------------------------|
| 1. Date and time of receipt of application for tender form: | 13.08.2025 upto 12.00 Noon |
| 2. Date and time of issue of tender form: | 14.08.2025 upto 5.00 PM |
| 3. Date and time of receipt of tenders: | 18.08.2025 upto 10.30AM |
| 4. Date and time of opening of tenders: | 18.08.2025 at 11.00 AM |

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dehra Division HPPWD Dehra must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
01	Restoration of Rain Damages on link road from Marhera to Houd KM 0/0 to 1/00 (SH: P/L 900mm dia HPC at RD 0/870).	Rs. 84,580.00	Rs.2,000/-	One Month	Rs.350/-
02	Restoration of Rain Damages on Darkata to Thathar Road KM 0/0 to 3/00 (SH: C/o B/Wall from KM 0/220 to 0/234 on RHS).	Rs. 99,803.00	Rs.2,000/-	Two Months	Rs.350/-
03	A/R & M/O Judge Residence Building at Dehra in District Kangra (H.P.) (SH: C/o U-Shape Drain and C/o Grating).	Rs. 93,647.00	Rs.2,000/-	Two Months	Rs.350/-
04	Repair and Maintenance of Civil Hospital at Dehra in District Kangra (H.P.) (SH: P/F Door Window Frames and Shutters, Painting and Distemping etc.).	Rs. 75,916.00	Rs.2,000/-	Two Months	Rs.350/-
05	Repair and Maintenance of Civil Hospital at Dehra in District Kangra (H.P.) (SH: Dismantling Tile Work, P/L Tile Work and Aluminium Work).	Rs. 93,230.00	Rs.2,000/-	Two Months	Rs.350/-
06	Restoration of Rain Damages on Guler to Dhangar Road KM 0/0 to 5/360 (SH: C/o R/Wall between KM 2/875 to 2/879 on RHS).	Rs. 98,756.00	Rs.2,000/-	One Month	Rs.350/-
07	Restoration of Rain Damages on Guler to Dhangar Road KM 0/0 to 5/360 (SH: C/o R/Wall between KM 2/879 to 2/883 on RHS).	Rs. 98,874.00	Rs.2,000/-	Two Months	Rs.350/-
08	Construction of Dehra to Kuru Road (SH: Deployment of Excavator-Cum-Loader for Removal of Slips/Clearance of Drains in various RD's) Section: Dehra	Rs. 99,000.00	Rs.2,000/-	One Month	Rs.350/-
09	Construction of Dehra to Kuru Road (SH: Deployment of Excavator-Cum-Loader for Removal of Slips/Clearance of Drains in various RD's) Section: Dehra	Rs. 99,000.00	Rs.2,000/-	One Month	Rs.350/-
10	Construction of GSSS Serabari Khas Dhiman Basti Harizan Basti to Dehra Jawali Raja-Ka-Talab Road KM 0/0 to 1/500 (SH: Deployment of Excavator-Cum-Loader for Removal of Slips/Clearance of Drains in various RD's) Section: Dehra	Rs. 99,000.00	Rs.2,000/-	One Month	Rs.350/-
11	Construction of GSSS Serabari Khas Dhiman Basti Harizan Basti to Dehra Jawali Raja-Ka-Talab Road KM 0/0 to 1/500 (SH: Deployment of Excavator-Cum-Loader for Removal of Slips/Clearance of Drains in various RD's) Section: Dehra	Rs. 99,000.00	Rs.2,000/-	One Month	Rs.350/-

12	A/R & M/O HPPWD Rest House Dehra in District Kangra (H.P.) (SH: Steel Work, Tile Work, Wood Work etc.).	Rs. 99,966.00	Rs.2,000/-	Two Months	Rs.350/-
1	The contractors/firms should possess the following documents (Photocopy to be attached): (i) Latest renewal of enlistment. (ii) PAN (Permanent Account No.) (iii) Registration under HP GST/ (TIN No.). (iv) EPF (Employee Provident Fund Account No.)				
2	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.				
3	If any of the date mentioned above happened/to be Gazetted Holidays the same shall be processed on next working day.				
4	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).				
5	The Contractor will have to submit affidavit alongwith application for issue of tender that he has not more than two works in hand.				
6	The next tender will be issued only after completion of previous works in hand.				
7	The offer of the tender shall remain valid upto 30 days after the opening.				


 Executive Engineer
 HPPWD Division Dehra
 Distt Kangra H.P.


on behalf of Governor of Himachal Pradesh

Exigency Certificate

It is certified that the tenders invited vide this office NIT
No.....3660-85.....dated.....04/08/2025 are of emergent nature of work and in
public interest.

Place:

Dated:


Executive Engineer,
HPPWD Division,
Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 84580.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.
 Name of work:- Restoration of Rain Damages on link road from Marehra to hor Km. 0/0 to 1/00 (SH:- P/L 900mm dia HPC at RD 0/870).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying (to level or slope) 900mm (Nine Hundred millimeter) diameter ISI marked reinforced cement concrete Light duty non pressure pipes I.S class NP-2 as per design for culverts on type 'A' (concrete cradle) bedding of M-15 (M-fifteen) grade cement concrete in single row including providing and fixing collar with cement mortar 1:2 (one cement isto two sand) but excluding the cost of excavation, protection works, back filling, concrete and masonry work in head walls and parapets etcetera as per drawing and MORD technical specification as clause 1106 complete and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, Toll tax, sale tax or any other taxes imposed by the Government.	20.00 Running meter	3800.00	Rupees Three Thousand Eight Hundred Only	Per Running meter	76,000.00
2	Filling in foundation, trenches as per drawing and MORD technical specification as per clause 305.3.9 earth filling (Marshy soil) and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	28.60 Cubic Metre	300.00	Rupees Three Hundred Only	Per Cubic Meter	8,580.00
Total						84,580.00
		% Above/Below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

*Bill of quantity checked and approved
for Rs. 84,580.00/- only.*

Executive Engineer,
J/Mukhi Division,
HPPWD J/Mukhi

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,803.00
 Earnest Money :-Rs. 2,000.00
 Time Limit :- Two Months.

Name of work:- Restoration of rain damages on Darkata to Thathar road Km 0/00 to 3/000 (SH:- Construction of Breast wall from RD 0/220 to 0/234 RHS).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of road structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown in the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification section 300 & 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	3.78 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	1,096.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in open foundation for all type of structure and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900 and 1200 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	23.94 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	96,957.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	7.00 Number s	250.00	Rupees Two Hundred Fifty Only	Each	1,750.00
	Total					99,803.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

*Bill of quantity checked and approved
for Rs. 99,803.00/- only.*

[Signature]
Executive Engineer,
Dehra Division,
HPPWD Dehra

126

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 93,647.00
 Earnest Money :- Rs. 2,000.00
 Time Limit :- Two Months.

name of work:- A/R & M/O of Judge Residence Building at Dehra Distt. Kangra (H.P) (SH:- Construction of U-Shape Drain and C/o Grating).

Sl. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	14.31 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	4,150.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-10 (M-Ten) nominal mix 1:3:6 (One cement isto three sand isto six graded crushed stone aggregate 40mm(Forty millimeter) nominal size), on ground or under water in open foundation for all type of structure and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900 and 1200 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	9.94 Cubic metre	4600.00	Rupees Four Thousand Six Hundred Only	Per Cubic metre	45,724.00

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Structural Steel work riveted, bolted or welded in built up sections, truss and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	416.89 Kilogramme	105.00	Rupees One Hundred Five Only	Per Kilogramme	43,773.00
TOTAL					93,647.00
% Above/below					
Quoted Amount in Figures					
Quoted Amount in Words					

*percentage being quantity checker
approved by 93647*

Executive Engineer,
Dehra Division,
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 75,916.00
 Earnest Money :- Rs. 2,000.00
 Time Limit :- Two Months.

name of work:- Repair and Maintenance of Civil Hospital at Dehra District Kangra (H.P.) (SH):- Providing and fixing Doors windows frames and shutters, Painting and Distemping etc.

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead of area 3 Sqm and below including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.00 Number s	60.80	Rupees Sixty And Paise Eighty Only	Each	243.00
Providing and fixing andosied aluminium work for door window, ventilator and partitions with extruded built up standard tubulrand other sections of approved make confirming of IS 733 and IS 1285 andosied transparent fixed with rawl plugs and screw or with fixing clips with expansion hold fastners i/c necessary filling up of gaps at junctions all complete as per architectural drawings and the directions of Engineer-in-Charge The rates including including Royalty, Malkhana, Octroi, Toll tax, sale tax, GST or any taxes imposed by the Government	36.80 Kilogra mme	550.00	Rupees Five Hundred Fifty Only	Per Kilogra mme	20,240.00
Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etcetera with EPDM rubber / neoprene gasket etcetera complete as per the architectural drawings and the directions of Engineer-in-Charge (Cost of aluminium snap beading shall be paid in basic item) With float glass panes of 4.0mm (Four point zero millimetre) thickness (weight not less than 10 kg/ sqm) as per direction of Engineer-in-Charge The rates including including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any taxes imposed by the Government	2.56 Square metre	560.00	Rupees Five Hundred Sixty Only	Per Square metre	1,434.00
Providing and fixing aluminium wire gauge shutters using of average width of aperture 4 mm in both directions with wire of dia 0.63mm, for doors, windows and clerestory windows with hinges and necessary screws Second class teak wood complete including carriage of materials within all leads, lifts and other incidental, and as per directions of Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	2.56 Square metre	530.00	Rupees Five Hundred Thirty Only	Per Square metre	1,357.00

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to steel windows by welding including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	43.93 Kilogramme	129.20	Rupees One Hundred Twenty Nine And Paise Twenty Only	Per Kilogramme	5,676.00
Applying priming coat with ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood) complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications, drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	11.16 Square metre	38.95	Rupees Thirty Eight And Paise Ninety Five Only	Per Square metre	435.00
Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications, drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	53.80 Square metre	94.30	Rupees Ninety Four And Paise Thirty Only	Per Square metre	5,073.00
Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications, drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	10.88 Square metre	89.90	Rupees Eighty Nine And Paise Ninety Only	Per Square metre	978.00
Repair to plaster of thickness 12mm to 20 mm in patches of area 2.5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications, drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	62.90 Square metre	399.75	Rupees Three Hundred Ninety Nine And Paise Seventy Five Only	Per Square metre	25,144.00

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Distemper with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications, drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	158.35 Square metre	96.85	Rupees Ninety Six And Paise Eighty Five Only	Per Square metre	15,336.00
TOTAL					75,916.00
% Above/below					
Quoted Amount in Figures					
Quoted Amount in Words					

*Bill of quantity checked and approved
for Rs. 75,916.00/- only.*

Executive Engineer,
Dehra Division,
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 93,230.00

Earnest Money :- Rs. 2,000.00

Time Limit :- Two Months.

Name of work:- Repair and Maintenance of Civil Hospital at Dehra District Kangra (H.P.) (SH:- Dismantling tile work, P/L Tile works & Aluminium work).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead For thickness of tiles 10mm to 25mm complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	47.45 Square metre	31.20	Rupees Thirty One And Paise Twenty Only	Per Square metre	1,480.00
2	Providing and laying full double charged Vitrified tiles in different sizes of Johnson/ Nitco/ Orient & Bell as per approved shade and design of the office Size of Tile 600x600mm (Six hundred into six hundred millimetre) (thickness to be specified by manufacturer), with water absorption less than 0.08% (Zero point zero eight percent) and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12mm (Twelve millimetre) thick bed of cement mortar 1:4 (One cement isto four coarse sand) jointing with grey cement slurry @ 3.3 kg/ sqm (Three point three kilogram per square metre) including grouting the joint with white cement and matching pigments etcetera complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications, drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	33.77 Square metre	1280.00	Rupees One Thousand Two Hundred Eighty Only	Per Square metre	43,226.00
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in Cement mortar 1:6 (One cement isto six coarse sand) complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.28 Cubic metre	6500.00	Rupees Six Thousand Five Hundred Only	Per Cubic metre	21,320.00

S. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
4	Demolishing brick work In cement mortar manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	7.34 Cubic metre	847.95	Rupees Eight Hundred Forty Seven And Paise Ninety Five Only	Per Cubic metre	6,224.00
5	Providing and fixing 300x16mm (Three hundred into sixteen millimetre) ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00 Number s	173.10	Rupees One Hundred Seventy Three And Paise Ten Only	Each	173.00
6	Providing and fixing 200x10mm (Two hundred into ten millimetre) ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etcetera complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.00 Number s	56.50	Rupees Fifty Six And Paise Fifty Only	Each	226.00
7	Providing and fixing 125mm (One hundred twenty five millimetre) ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etcetera complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.00 Number s	132.40	Rupees One Hundred Thirty Two And Paise Forty Only	Each	530.00
8	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg and door width upto 700 mm), with necessary accessories and screws etc. complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00 Number s	2000.00	Rupees Two Thousand Only	Each	4,000.00
9	Providing and fixing bright finished brass hanging type floor door stopper with necessary screws, etcetera complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00 Number s	105.65	Rupees One Hundred Five And Paise Sixty Five Only	Each	211.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
0	Providing and fixing 300mm (Three Hundred millimetre) bright finished brass hard drawn hooks and eyes complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	12.00 Number s	84.35	Rupees Eighty Four And Paise Thirty Five Only	Each	1,012.00
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead Nominal concrete 1:4:8 or leaner mix (including equivalent design mix) complete including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.66 Cubic metre	619.05	Rupees Six Hundred Nineteen And Paise Five Only	Per Cubic metre	1,647.00
2	Providing and laying in position cement concrete 1:4:8 (One cement isto four coarse sand isto eight graded stone aggregate 40mm (Forty millimetre) nominal size including curing complete mechanically mixed and vibrated of specified grade excluding the cost of centering and shuttering, All work up to all floor level including carriage of material within all leads, lifts and other incidentals as per direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	2.66 Cubic metre	4955.20	Rupees Four Thousand Nine Hundred Fifty Five And Paise Twenty Only	Per Cubic metre	13,181.00
	TOTAL					93,230.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

*Bid of quantity checked and approved
for Rs. 93,230.00/- only.*

Executive Engineer,
Dehra Division,
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 98,756.00
 Earnest Money :-Rs. 2,000.00
 Time Limit :- Two Months.

Name of work:- Restoration of rain damages on Guler to Dhangar road Km 0/00 to 5/360 (SH:- Construction of Retaining wall between RD 2/875 to 2/879 RHS).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of road structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown in the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification section 300 & 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	12.79 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	3,709.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in open foundation for all type of structure and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900 and 1200 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	21.63 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	87,602.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	6.00 Number s	250.00	Rupees Two Hundred Fifty Only	Each	1,500.00
4	Back filling with granular material behind abutment Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200 & 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	3.24 Cubic metre	750.00	Rupees Seven Hundred Fifty Only	Per Cubic metre	2,430.00
5	Providing and laying mechanically mixed and vibrated concrete for plain-cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) on ground or under water in drain including pumping or bailing out water/dewatering removal of the slush as required at site which may arise at the time of laying concrete, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification section 800, 900 and 1200 or as directed by Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	0.71 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	3,515.00
	Total					98,756.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

*Bill of quantity checked and approved.
for Rs. 98,756.00/-only.*

[Signature]
Executive Engineer,
Dehra Division,
HPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 98,874.00
 Earnest Money :-Rs. 2,000.00
 Time Limit :- Two Months.

Name of work:- Restoration of rain damages on Guler to Dhangar road Km 0/00 to 5/360 (SH:- Construction of Retaining wall between RD 2/879 to 2/883 RHS).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of road structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown in the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification section 300 & 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	13.48 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	3,909.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in open foundation for all type of structure and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900 and 1200 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	21.63 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	87,602.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	6.00 Number s	250.00	Rupees Two Hundred Fifty Only	Each	1,500.00
4	Back filling with granular material behind abutment Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200 & 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	3.13 Cubic metre	750.00	Rupees Seven Hundred Fifty Only	Per Cubic metre	2,348.00
5	Providing and laying mechanically mixed and vibrated concrete for plain-cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) on ground or under water in drain including pumping or bailing out water/dewatering removal of the slush as required at site which may arise at the time of laying concrete, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification section 800, 900 and 1200 or as directed by Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, toll tax or any other taxes imposed by the Government.	0.71 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	3,515.00
	Total					98,874.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

*Bill of quantity created and approved
for Rs 98,874.00/- only.*

*Executive Engineer,
Dehra Division,
HPPWD Dehra.*

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99000.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:-C/o Dehra to Kuru Road (SH):- Deployment of Excavator Cum Loader for Removal of slips/ Clearance of drain in various RD:s).(Under Dehra Section)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Deployment of excavator cum loader on through rate basis for removal of slips and removal of formation deficiency in all kinds of soil from road formation, removal of slips, berms dressing, clearing of drains etc. complete in all respect as per direction of the Engineer-in-Charge including all leads lifts. The cost of lubricant diesel etc be borne by the contractor.	90.00 Hours	1100.00	Rupees One Thousand One Hundred Only	Per Hours	99,000.00
	Total					99,000.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Team & Conditions:-

- 1 Hire charges shall be quoted per hour rate.
- 2 Hire charges shall be include all expenses including fuel lubricat establishment major and repair over hauling replacement of equipment if required.
Hire charges also including insurance of mechninery and department shall not be responsible for 3 and fatal and non fatal accident.
- 4 Hire charges shall be include local and other taxes including tax if any imposed by the Govt.
- 5 for drain and 1.20cum side cutting $(0.75 \times 0.80\%) + (6.00 \times 20\%)$.

*Bill of quantity checked
 & approved for Rs. 99,000/-*

CS
 Executive Engineer,
 Dehra Division,
 HPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99000.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month.

Name of work:-C/o Dehra to Kuru Road (SH:- Deployment of Excavator Cum Loader for Removal of slips/ Clearance of drain in various RD;s).(Under Dehra Section)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Deployment of excavator cum loader on through rate basis for removal of slips and removal of formation deficiency in all kinds of soil from road formation, removal of slips, berms dressing, clearing of drains etc. complete in all respect as per direction of the Engineer-in-Charge including all leads lifts. The cost of lubricant diesel etc be borne by the contractor.	90.00 Hours	1100.00	Rupees One Thousand One Hundred Only	Per Hours	99,000.00
	Total					99,000.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Team & Conditions:-

- 1 Hire charges shall be quoted per hour rate.
- 2 Hire charges shall be include all expenses including fuel lubricat establishment major and repair over hauling replacement of equipment if required.
- 3 Hire charges also including insurance of machinery and department shall not be responsible for and fatal and non fatal accident.
- 4 Hire charges shall be include local and other taxes including tax if any imposed by the Govt.
- 5 for drain and 1.20cum side cutting (0.75x0.80%)+(6.00x20%).

*Bill of quantity checked
& approved for Rs. 99,000/-*

[Signature]
Executive Engineer,
Dehra Division,
HPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99000.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:-Construction of Govt. Senior Secondary School Serabari Bari Khas Dhiman Basti Harizan Basti to Dehra Jawali Raja Ka Talab road in Km 0/0 to 1/500 (SH:- Deployment of Excavator Cum Loader for Removal of slips/ Clearance of drain in various RD;s).(Under Dehra Section)

Sr. No.	Description of Item	Quantity		Rate in		Unit	Amount
		Figures	Words	Figures	#NAME?		
1	Deployment of excavator cum loader on through rate basis for removal of slips and removal of formation deficiency in all kinds of soil from road formation, removal of slips, berms dressing, clearing of drains etc. complete in all respect as per direction of the Engineer-in-Charge including all leads lifts. The cost of lubricant diesel etc be borne by the contractor.	90.00	Hours	1100.00		Per Hours	99,000.00
	Total						99,000.00
	% Above/below						
	Quoted Amount in Figures						
	Quoted Amount in Words						

Team & Conditions:-

- Hire charges shall be quoted per hour rate.
- Hire charges shall be include all expenses including fuel lubricat establishment major and repair over hauling replacement of equipment if required.
Hire charges also including insurance of machinery and department shall not be responsible for 3 and fatal and non fatal accident.
- Hire charges shall be include local and other taxes including tax if any imposed by the Govt.
- for drain and 1.20cum side cutting (0.75x0.80%)+(6.00x20%).

Bill of quantity checked
 & approved for Rs. 99,000/-

Executive Engineer,
 Dehra Division,
 HPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99000.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:-Construction of Govt. Senior Secondary School Serabari Bari Khas Dhiman Basti Harizan Basti to Dehra Jawali Raja Ka Talab road in Km 0/0 to 1/500 (SH):- Deployment of Excavator Cum Loader for Removal of slips/ Clearance of drain in various RD;s).(Under Dehra Section)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Deployment of excavator cum loader on through rate basis for removal of slips and removal of formation deficiency in all kinds of soil from road formation, removal of slips, berms dressing, clearing of drains etc. complete in all respect as per direction of the Engineer-in-Charge including all leads lifts. The cost of lubricant diesel etc be borne by the contractor.	90.00 Hours	1100.00	#NAME?	Per Hours	99,000.00
	Total					99,000.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

*Bill of quantity sheet
 & 4722222 for Rs 99,000/-*

Team & Conditions:-

- 1 Hire charges shall be quoted per hour rate.
- 2 Hire charges shall be include all expenses including fuel lubricat establishment major and repair over hauling replacement of equipment if required.
Hire charges also including insurance of machinery and department shall not be responsible for 3 and fatal and non fatal accident.
- 4 Hire charges shall be include local and other taxes including tax if any imposed by the Govt.
- 5 for drain and 1.20cum side cutting $(0.75 \times 0.80\%) + (6.00 \times 20\%)$.

Executive Engineer,
 Dehra Division,
 HPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,966.00
 Earnest Money :- Rs. 2,000.00
 Time Limit :- Two Months.

me of work:- A/R & M/O to HPPWD Rest House at Dehra Tehsil Dehra Distt. Kangra H.P (SH:- Steel Work, Tiles, wood work etc.).

Sl. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Structural Steel work riveted, bolted or welded in built up sections, truss and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	584.68 Kilogra mme	94.00	Rupees Ninety Four Only	Per Kilogra mme	54,960.00
2	Repair of wire gauge / Panned shutters with hinges and necessary screws: 35mm (Thirty five millimetre) thick shutters as per the direction of Engineer in Charge including carriage of material with all leads and lifts and other incidental. The rates including including Royalty, Malkhana, Octroi, toll tax, sale tax or any taxes imposed by the Government	6.00 Number s	400.00	Rupees Four Hundred Only	Each	2,400.00
3	Providing and fixing Matrix EWC (European water closet) of vitreous China fixed with Jet pressure of Hindware/Cera/Jaguar in Divyang toilet complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Octroi, GST, Toll Tax Sale tax or any other taxes imposed by the Government.	1.00 Number s	12000.00	Rupees Twelve Thousand Only	Each	12,000.00
4	Providing and laying full double charged Vitrified tiles in different sizes of Johnson/ Nitco/ Orient & Bell as per approved shade and design of the office Size of Tile 600x600mm (Six hundred into six hundred millimetre) (thickness to be specified by manufacturer), with water absorption less than 0.08% (Zero point zero eight percent) and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12mm (Twelve millimetre) thick bed of cement mortar 1:4 (One cement isto four coarse sand) jointing with grey cement slurry @ 3.3 kg/ sqm (Three point three kilogram per square metre) including grouting the joint with white cement and matching pigments etcetera complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications, drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	16.65 Square metre	1130.00	Rupees One Thousand One Hundred Thirty Only	Per Square metre	18,815.00

Description of Item	Quantity	Rate in		Unit	Amount
		Figures	Words		
Providing and Fixing Water Storage tank Cover standard design and of approved make conforming to IS:8931 complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications, drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	2.00 Number s	500.00	Rupees Five Hundred Only	Each	1,000.00
Providing and fixing PVC water storage tank of ISI marked G.I. inlet and outlet connection 15mm nominal bore ball valve and mosquito proof PVC cover with locking arrangement including hoisting upto all heights above ground level 1000 litres net capacity tankas per direction of Engineer in Charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government...	1.00 Number s	10791.00	Rupees Ten Thousand Seven Hundred Ninety One Only	Each	10,791.00
TOTAL					99,966.00
% Above/below					
Quoted Amount in Figures					
Quoted Amount in Words					

*Bill of quantity checked and approved
for Rs. 99,966.00/- only.*

[Signature]
Executive Engineer,
Dehra Division,
HPPWD Dehra