

Himachal Pradesh
Public Works Department

No. PWH/HD/CB/T-I/2025-26
To

3160-63

Dated: - 11/08/2025

The Executive Engineer (IT Cell)
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject: - Publication of Notice inviting tender.

Sir,

Enclosed please find herewith copy of notice inviting tender for publishing on departmental website for favour of further necessary action please.

Encl: As above

Executive Engineer,
HPPWD Division Haroli,
Distt. Una HP).

Copy along with copy of notice inviting tender is forwarded for information and necessary action to:-

1. The Superintending Engineer, 15th Circle, HP: PWD, Una.
2. Copy to Notice board.

Executive Engineer,
HPPWD Division Haroli,
Distt. Una HP).

Certificate

Certified that the tenders for the works called vide this office letter No. PWH/HD/CB/T-1/2024-25

3/08-63

dated

11/8/2025

are required to be carried out immediately being emergent nature of work in public interest.

Executive Engineer,
Haroli Division, HPPWD
Haroli Distt.Una HP).

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

“ NOTICE INVITING TENDERS ”

Short term Percentage rate tender on PWD Form No. 6 & 8 are hereby invited by the Executive Engineer, Haroli Division H.P. on behalf of Governor of H.P for the following works from the approved and eligible contractors/firms enlisted in PWD Department as per latest instructions, so as to reach and open in his office as per time schedule given below. The offer of the tender will be open for 45 days from the date of opening of tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of application for the tender form a/w requisite documents: - 14/8/2025 up to 10.30 (AM).
2. Date of issue/sale of tender forms against cash payment(non-refundable): - 14/8/2025 up to 3.00 PM
3. Date of receipt of tenders: - 19/08/2025 up to 10.30 AM
4. Date of opening of tenders: - 19/08/2025 at 11.00 AM

Sr. No.	Name of work	Estimate d cost	EMD	Time Limit	Cost of tender	Eligible class of contract or
1	2	3	4	5	6	7
1	Repair & Restoration of rain damage on Pandoga Bridge on Panjavar Bathri road at RD 5/904 (SH: P/L Cement concrete M-10 below raft Peir 11 to Peir-12	99418	2000/-	One Month	350/-	Class- C & D
2	Repair & Restoration of rain damage on Pandoga Bridge on Panjavar Bathri road at RD 5/904 (SH: P/L Cement concrete M-10 below raft Peir 12 to Peir-13	99519	2000/-	One Month	350/-	Class- C & D
3	Repair & Restoration of rain damage on Pandoga Bridge on Panjavar Bathri road at RD 5/904 (SH: P/L Cement concrete M-10 below raft Peir 13 to Peir-14	99522	2000/-	One month	350/-	Class- C & D
4	Repair & Restoration of rain damage on Pandoga Bridge on Panjavar Bathri road at RD 5/904 (SH: P/L Cement concrete M-10 below raft Peir 14 to Peir-15	99623	2000/-	One month	350/-	Class- C & D
5	Repair & Restoration of rain damage on Pandoga Bridge on Panjavar Bathri road at RD 5/904 (SH: P/L Cement concrete M-10 below raft Peir 15 to Peir-16	99623	2000/-	One Month	350/-	Class- C & D
6	Repair & Restoration of rain damage on Pandoga Bridge on Panjavar Bathri road at RD 5/904 (SH: P/L Cement concrete M-10 below raft Peir 16 to Peir-17	99623	2000/-	One Month	350/-	Class- C & D
7	Repair & Restoration of rain damage on Pandoga Bridge on Panjavar Bathri road at RD 5/904 (SH: P/L Cement concrete M-10 below raft Peir 17 to Peir-18	99623	2000/-	One month	350/-	Class- C & D
8	Repair & Restoration of rain damage on Pandoga Bridge on Panjavar Bathri road at RD 5/904 (SH: C/o Toe wall at RD 5/960 to 5/966.70)	99864	2000/-	One Month	350/-	Class- C & D
9	Repair & Restoration of rain damage on Pandoga Bridge on Panjavar Bathri road at RD 5/904 (SH: C/o Toe wall at RD 5/966.70 to 5/973.40)	99763	2000/-	One Month	350/-	Class- C & D

The earnest money in the shape of National Saving certificate/ time deposit/ saving account of any post office or FDR, Nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected. The tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained. The copy of valid enlistment, GST registration No., Income Tax, Pan No. and epf no. must be attached with application.

SPECIAL CONDITION: -

1. The contractor should produce a copy of valid enlistment/renewal letter at the time of application.

3. The contractor/firm shall have his resignation and GST No. and copy of same be attached with the application.
4. The earnest money for the above work should be submitted duly pledged in favour of Executive Engineer, Haroli Division HPPWD with the application for the purchase of tender forms. The application received without earnest money shall summarily rejected.
5. The contractor/firms are required to insert the rate in words as well as figures, failing which Executive Engineer reserves the right to accept/rejects any or all tenders. If any of the date mentioned above happens to be local/gazetted holidays, the same shall be process on next date.
6. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their application a/w proof of ownership of machinery/legal tie up arrangement).
7. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.
8. The conditional/ambiguous/telegraphic tenders by fax shall not entertained/considered in any case.

HIM SUCHANA AVAM JAN SAMPARK.


Executive Engineer
HPPWD Division Haroli
Distt.Una(HP).Pin Code-177220
Email: ee.haroli-hp@hp.gov.in
On behalf of Governor of Himachal Pradesh

Name of work : Restoration of rain damage on Pandoga bridge on Panjagar Bathri road at RD 5/904 (SH: Providing and laying cement concrete M-10 below raft Peir 11 to Peir-12) ✓		Estimated Cost	99418
		Earnest Money	2000/-
		Time limit	One month
Sl. No.	Description of work	Unit	RATE In
			Figures Words
			160.00 Rupees one hundred sixty only
			AMOUNT
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	3.96 Per cubic metre	634
2	Providing and laying M-10 (M-Ten) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete standard design mix of with cement contents not to be less than 250 kg.(two hundred fifty kilogram) per cubic metre) in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD Technical specification Clause 2100 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	19.60 Per cubic metre	98784
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018			Total: 99418
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No.PBW(B) A(3)/1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021			
Percentage quoted rate in Figures			
Percentage quoted rate in words			
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.			

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

2

SCHEDULE OF QUANTITY									
						Estimated Cost		99519	
						Earnest Money		2000/-	
						Time limit		One month	
Sl. No.	Description of work	Unit	Figures	RATE In		AMOUNT			
				Words	Words				
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	Per cubic metre	3.96	160.00	Rupees one hundred sixty only	634			
2	Providing and laying M-10 (M-Ten) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete standard concrete design mix of with cement contents not to be less than 250 kg (two hundred fifty kilogram) per cubic metre) in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD Technical specification Clause 2100 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	Per cubic metre	19.62	5040.00	Rupees five thousand forty only	98885			
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				Total:		99519			
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021									
Percentage quoted rate in Figures									
Percentage quoted rate in words									
Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.									

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)


3

SCHEDULE OF QUANTITY									
Name of work: Restoration of rain damage on Pandoga bridge on Panjagar Bathri road at RD 5/904 (SH: Providing and laying cement concrete M-10 below raft Peir 13 to Peir-14)		Estimated Cost		99522		Earnest Money		2000/-	
						Time limit		One month	
Sl. No.	Description of work	Unit	Figures	Words	RATE In	Figures	Words	Amount	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	3.98	Per cubic metre	160.00	Rupees one hundred sixty only			637	
2	Providing and laying M-10 (M-Ten) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete standard design mix of with cement contents not to be less than 250 kg.(two hundred fifty kilogram) per cubic metre) in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD Technical specification Clause 2100 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	19.62	Per cubic metre	5040.00	Rupees five thousand forty only			98885	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/2/20212 dated 7.8.2018						Total:		99522	
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No. PBW(B) A(3)1/2020 & Govt. of HP vide letter No. PBW(B) A(3) 1/2020-1 dated 7.10.2021									
Percentage quoted rate in Figures									
Percentage quoted rate in words									
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.									

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Name of work Restoration of rain damage on Pandoga bridge on Panjawar Bathri road at RD 5/904 (SH: Providing and laying cement concrete M-10 below raft Peir 14 to Peir-15)				Estimated Cost		99623
				Earnest Money		2000/-
				Time limit		One month
Sl. No.	Description of work	Unit	Figures	RATE In		AMOUNT
				Words	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	Per cubic metre	3.98	Rupees one hundred sixty only	637	
2	Providing and laying M-10 (M-Ten) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete standard concrete design mix of with cement contents not to be less than 250 kg (two hundred fifty kilogram) per cubic metre) in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD Technical specification Clause 2100 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	Per cubic metre	19.64	Rupees five thousand forty only	98986	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)©(17/20212 dated 7.8.2018				Total:	99623	
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.						


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

6

SCHEDULE OF QUANTITY						
Name of work		Estimated Cost		99623		
(SH: Providing and laying cement concrete M-10 below raft Peir 15 to Peir-16)		Earnest Money		2000/-		
		Time limit		One month		
Sl. No.	Description of work	Unit	Figures	Words	AMOUNT	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	Per cubic metre	160.00	Rupees one hundred sixty only	637	
2	Providing and laying M-10 (M-Ten) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete standard concrete design mix of with cement contents not to be less than 250 kg.(two hundred fifty kilogram) per cubic metre) in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD Technical specification Clause 2100 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	Per cubic metre	5040.00	Rupees five thousand forty only	98986	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17/2/20212 dated 7.8.2018				Total:	99623	
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.						

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

DRAFT SCHEDULE OF QUANTITY

Name of work <i>Restoration of rain damage on Pandoga bridge on Panjwar Bathri road at RD 5/904</i> (SH: Providing and laying cement concrete M-10 below raft Peir 16 to Peir-17)		Estimated Cost		99623	
		Earnest Money		2000/-	
		Time limit		One month	
Sl. No.	Description of work	Unit	Figures	Words	AMOUNT
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	Per cubic metre	160.00	Rupees one hundred sixty only	637
2	Providing and laying M-10 (M-Ten) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete standard design mix of with cement contents not to be less than 250 kg.(two hundred fifty kilogram) per cubic metre) in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD Technical specification Clause 2100 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	Per cubic metre	5040.00	Rupees five thousand forty only	98986
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B)A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B)A(3) 1/2020-1 dated 7.10.2021			Total:	99623
	Percentage quoted rate in Figures				
	Percentage quoted rate in words				
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.				

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Repaired

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.

SCHEDULE OF QUANTITY

		Name of work		Estimated Cost		99864
		(SH: C/O Toe wall at RD 5/960 to 5/966.70)		Earnest Money		2000/-
				Time limit		One month
Sl. No.	Description of work			Unit	RATE In	AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	18.09	Per cubic metre	160.00	Rupees one hundred sixty only	2894
2	Providing and laying M-10 (M-Ten) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete standard concrete design mix of with cement contents not to be less than 250 kg.(two hundred fifty kilogram) per cubic metre) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD Technical specification Clause 2100 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	19.24	Per cubic metre	5040.00	Rupees five thousand forty only	96970
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)©(17)/20212 dated 7.8.2018				Total:	99864
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.					


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

224

9

SCHEDULE OF QUANTITY

Repair & Restoration of rain damage on Pandoga bridge on Panjwar Bathri road at RD 5/904
(SH: C/O Toe wall at RD 5/966.70 to 5/973.40)

Name of work Restoration of rain damage on Pandoga bridge on Panjagar Bathri road at RD 5/904 (SH: C/O Toe wall at RD 5/966.70 to 5/973.40)							Estimated Cost	99763
							Earnest Money	2000/-
							Time limit	One month
Sl. No.	Description of work	Unit	RATE In		AMOUNT			
			Figures	Words				
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	Per cubic metre	18.09	160.00	Rupees one hundred sixty only	2894		
2	Providing and laying M-10 (M-Ten) Grade Design Mix mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete standard concrete design mix of with cement contents not to be less than 250 kg.(two hundred fifty kilogram) per cubic metre) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and MORD Technical specification Clause 2100 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	Per cubic metre	19.22	5040.00	Rupees five thousand forty only	96869		
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@ (17)2/0212 dated 7.8.2018				Total:	99763		
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021							
	Percentage quoted rate in Figures							
	Percentage quoted rate in words							
Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.								

Executive Engineer
Haroli Division
HPPWD Haroli

225