

OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh Works Department Jaisinghpur
176095 Phone No. 01894-228030 Email ee-jaipwd-hp@gov.in

"NOTICE INVITING TENDERS"

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **23.08.2025 up to 11:00 A.M.** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **22.08.2025 up to 4:00 PM** and the application for issue of tender form shall be received on **22.08.2025 up to 11.30 AM**. The applications for issue of tender forms should accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD., Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for **75 days**:-


Sr. No.	Name of Work	Estimated Cost (Rs.)	EMD	Time limit	Cost of tender form
1	A/R & M/O link road from Gander to Kudana road Km 0/00 to 8/688 Tehsil Jaisinghpur Distt. Kangra (HP) under Balakrupi Sub Division) (SH:- Preparation of forest Diversion case under FCA,1980)	95000.00	2000.00	Two Month	350/-
2	Restoration of rain damages to various roads under Jaisinghpur Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and clearing of berms various road under Lambagoan Section)	98400.00	2000.00	Two Month	350/-
3	Restoration of rain damages on various roads under Panchrukhi Sub-Division (SH:- Removal of slips under Jalag Section)	99743.00	2000.00	One Month	350/-
4	Restoration of rain damages on various roads under Panchrukhi Sub-Division (SH:- Removal of slips under Panchrukhi Section)	99788.00	2000.00	One Month	350/-
5	Restoration of rain damages on various roads under Jaisinghpur Sub-Division (SH:- Clearing of Blocked/Choked Culverts) under Sari Section)	99345.00	2000.00	One Month	350/-
6	Restoration of rain damages on link road Papalah Bandahu Odri road Km 0/00 to 7/465 (SH:- C/O C/O B/wall at RD 4/780 to 4/787) DC Deposit	98367.00	2000.00	One Month	350/-
7	A/R & M/O of Non Residential building in Sub Division Jaisinghpur (SH:- P/L 60 mm thick paver block old Tehsil building)	86400.00	2000.00	Two Month	350/-
8	Restoration of rain damages on Draman to Jalag road Km 0/000 to 2/500 (SH:- C/O B/wall at RD 1/180 to 1/189)	97385.00	2000.00	One Month	350/-
9	Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Balakrupi Section)	99935.00	2000.00	One Month	350/-
10	Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Gander Section)	99660.00	2000.00	One Month	350/-
11	Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Alampur Section)	99550.00	2000.00	Two Month	350/-
12	Restoration of rain damages on Gander to Barram road Km 0/00 to 5/00 (SH:- C/O R/wall at RD 3/017 to 3/021.20)	99925.00	2000.00	Two Month	350/-
13	Restoration of rain damages on Jaisinghpur to Vijapur via sita Ram khad road Km 0/00 to 1/500 (SH:- C/O B/wall at RD 0/400 to 0/406)	99000.00	2000.00	Two Month	350/-
14	A/R & M/O of Non Residential building in sub Division Jaisinghpur (SH:- P/L 60 mm thick paver block old Tehsil building)	61205.00	2000.00	Two Month	350/-
15	Improvement of Black Spot various roads Under Balakrupi sub Division (Gander Section) (SH:- Providing and fixing of Glow cat eyes studs under)	99330.00	2000.00	Two Month	350/-
16	Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Gander Section)	99440.00	2000.00	Two Month	350/-
17	A/R & M/O link road from Gander to Kudana road Km 0/00 to 8/688 (Portion 0/00 to 5/00) Tehsil jaisinghpur Distt. Kangra (HP) under Balakrupi Sub Division) (SH:- Preparation of forest Diversion case under FCA,1980)	70800.00	2000.00	Two Month	350/-
18	Restoration of rain damages on link road Papalah Bandahu Odri road Km 0/00 to 7/465 (SH:- C/O B/wall at RD 4/787 to 4/794) DC Deposit	98617.00	2000.00	One Month	350/-
19	Restoration of rain damages on Gander to Barram road Km 0/00 to 5/00 (SH:- C/O R/wall at RD 3/022 to 3/026)	95293.00	2000.00	Two Month	350/-

20	Restoration of rain damages to various roads under Jaisinghpur Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and clearing of berms various road under Lambagoan Section)	99500.00	2000.00	Two Month	350/-
21	Restoration of rain damages on Tinbar Jaisinghpur road Km 0/00 to 18/300 (SH:- C/O R/wall at RD 9/100 to 9/110)	99350.00	2000.00	Two Month	350/-
22	Restoration of rain damages on Dharamshala Dadh Holta Chadhar Sandhole road Km 40/500 to 56/00 (SH:- C/O Breast wall from RD 54/405 to 54/428)	97244.00	2000.00	Two Month	350/-
23	Restoration of rain damages on Bandahu to Bhairghatta road Km 0/00 to 2/615 (SH:- C/O R/wall at Rd 0/370 to 0/374 20) DC Deposit	99925.00	2000.00	Two Month	350/-
24	Completion of floor Tile work of Guru Ravi Dass Sarai Bhawan Andretta (SH:-P/L Tile work in Rooms and Kota Stone in Yard) Deposit SDP/2024/938 & 763(3.00 Lakh)	283066.00	5700.00	Two month	350/-
25	C/O Approach road from Jaisinghpur Bus Stand towards Panchyat Ghar and Chogan Ground Jaisinghpur (SH:- C/O 80 mm thick Paver Block from 0/00 to 0/057)(Deposit VKV/2025/59) 5.00 Lac)	499707.00	10000.00	Two Month	350/-
26	A/R & M/O various roads under Balakrupi Sub Division (Section Balakrupi) (SH:-Painting, lettering of Kms stones and sign boards ect.)	99799.00	2000.00	Two Month	350/-
27	C/O road main road to village Gharloon Km 0/00 to 0/500 (SH:-C/O R/wall from RD 0/090 to 0/105and B/wall from RD 0/100 to 0/110) (SDP/2023/1244)	498089.00	10000.00	Two Month	350/-
28	Restoration of rain damages on Bhuana Ashapuri road KM-0/00 to 12/300 (SH:- C/O R/Wall from RD 1/310 to 1/314.50)	99159.00	2000.00	Two month	350/-
29	Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulders of various roads under Gander Section)	99770.00	2000.00	Two month	350/-
30	Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulders of various roads under Alampur Section)	99880.00	2000.00	Two month	350/-

Certified that the above works are of urgent nature and tenders are being called in exigency of works in public interest.

Terms & conditions:-

1. The contractors will have to produce a copy of enlistment / renewal of valid class at time of application.
2. The contractors will have to produce a copy of GST,EPF and PAN.
3. The contractors are directed to insert the rate / percentage both in figures and words.
4. The tenders forms will not be issued to those contractors who have not completed their previous works / commitments or whose performance is not found satisfactory.
5. The Executive Engineer reserves the right to reject / cancel any or all the tenders without assigning any reason.



Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.


On behalf of Governor of Himachal Pradesh)

No.PWD/JSPR/CB/Tenders/2025-26- 3795-3804

Dated: 18/08/2025

Copy to the following for information and necessary action:-

1. The Chief Engineer (K.Z.) HP.PWD., Dharamshala.
2. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
3. The Executive Engineer (IT) O/O E-in-C, HP.PWD., Shimla.
- 4-6. All the Assistant Engineer under this Division.
- 7-8. The Drawings / Accounts Branch in this office.
9. N.I.T. Register.
10. Notice Board.





Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.




OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh Works
Department Jaisinghpur 176095 Phone No. 01894-228030
Email ee-jaipwd-hp@gov.in

"CERTIFICATE"

Certified that the tenders are being called in exigency of works of public interest vide
this office letter No. PWD/JSD/TA/NIT/ 2025-26- 3795-3804 dated 18/08/2025


Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur.


SCHEDULE OF QUANTITY						
Name of work :-A/R & M/O for Preparation of forest diversion case under FCA,1980 for the C/O link road from Gander to Kudana road Km 0/00 to 8/688 Tehsil Jaisinghpur Distt. Kangra (HP) under Balakrupi Sub Division) (SH:- Preparation of forest Diversion case under FCA,1980)				Estimated cost Rs.		95000.00
				Earnest Money Rs.		2000.00
				Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
3	Preparation of KML File and Geo Reference Digital map of proposed land and CA Area. Preparation of CA Scheme. Reclamation Plan, Cost Benefit Analysis. Muck Management. uploading Main Application Part I on Parivesh portal complete in all respect. Assistance to User Agency to attend the queries and clarification sought by MoEF. Submission of Stage I compliance report for obtaining Stage II Approval. Assistance to User Agency to make presentation for REC Meeting as required by MoEF. The Rates are inclusive of all equipments within all leads and lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	1.000	95000.00	Rupees Ninety Five Thousand Only	Each	95000.00
Total						95000.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

2

SCHEDULE OF QUANTITY


Name of work :- Restoration of rain damages to various roads under Jaisinghpur Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and clearing of berms various road under Lambagoan Section)

Estimated cost Rs.	98400.00
Earnest Money Rs.	2000.00
Time Limits	One month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. Note:- The hire charges of plant machinery on per hour basis	64.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	70400.00
2	Hiring of carriage Tipper for carriage of material such as Crusher and Sand labour and T & P stricals and other essential material from PWD store Jaisinghpur/quarry site to various roads Under Jaisinghpur Sub Division in HP.PWD. Jaisinghpur as directed by the Engineer-In-Charge. Any loss to the public private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for carriage vehicle also be borne by the contractor owner. The daily 70 Km per day running charges will be assuming and log book will also be maintained at site which should be verified by the Engineer-in-Charge. Note:- The hire charges of plant machinery on per day basis	8.00	3500.00	Rupees Three Thousand Five Hundred Only	Per Day	28000.00
	Total					98400.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur


SCHEDULE OF QUANTITY						
Name of work :-Restoration of rain damages on various roads under Panchrukhi Sub-Division (SH:- Removal of slips under Jalag Section)				Estimated cost Rs.		99743.00
				Earnest Money Rs.		2000.00
				Time Limits		One month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000 metre as per technical specification 302.3.5 and 1611 (One hours hiring will be justified after removal of 25 cubic metre quantity of disposed material) as per drawing as per the direction of Engineer-in-Charge within all lifts and other lifts and other incidentals. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	890.56	112.00	Rupees One Hundred Twelve Only	Per cubic metre.	99743.00
	Total					99743.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer.
 Jaisinghpur Division.
 HP.PWD Jaisinghpur

4

SCHEDULE C. QUANTITY


Name of work :-Restoration of rain damages on various roads under Panchrukhi Sub-Division (SH:- Removal of slips under Panchrukhi Section)				Estimated cost Rs.		99788.00
				Earnest Money Rs.		2000.00
				Time Limits		One month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000 metre as per technical specification 302.3.5 and 1611 (One hours hiring will be justified after removal of 25 cubic metre quantity of disposed material) as per drawing as per the direction of Engineer-in-Charge within all lifts and other lifts and other incidentals. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	890.96	112.00	Rupees One Hundred Twelve Only	Per cubic metre.	99788.00
	Total					99788.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

5

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on various roads under Jaisinghpur Sub-Division (SH:- Clearing of Blocked/Choked Culverts) under Sari Section)				Estimated cost Rs.		99345.00
				Earnest Money Rs.		2000.00
				Time Limits		One month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Maintenance of Hume pipe culvert by way of clearing, Cleaning as per drawing and technical specification clause 1908 with in all leads and lifts and other incidental. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	31.00	2973.60	Rupees Two Thousand Nine Hundred Seventy Three And Paise Sixty Only	Each	92182.00
2	Maintenance of slab type culverts by way of clearing, Cleaning as per drawing and technical specification clause 1908 with in all leads and lifts and other incidental. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	2.00	3581.50	Rupees Three Thousand Five Hundred Eighty One And Paise Fifty Only	Each	7163.00
		Total				99345.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					




Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on link road Papalah Bandahu Odri road Km 0/00 to 7/465 (SH:- C/O C/O B/wall at RD 4/780 to 4/787)				Estimated cost Rs.	98367.00	
				Earnest Money Rs.	2000.00	
				Time Limits	One month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all-type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	19.13	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	4304.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	24.15	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	90563.00


3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	14.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	3500.00
	Total					98367.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

7

SCHEDULE OF QUANTITY

Name of work :-A/R & M/o of non residential building in sub Division Jaisinghpur (SH:- P/L 60 mm thick paver block old Tehsil building)				Estimated cost Rs.		86400.00
				Earnest Money Rs.		2000.00
				Time Limits		One month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying 60 mm thick Interlocking M-40 grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	72.00	1200.00	Rupees One Thousand Two Hundred Only	Per square metre	86400.00
	Total					86400.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					




Executive Engineer.
Jaisinghpur Division.
H.R.PWD Jaisinghpur

SCHEDULE OF QUANTITY


Name of work :-Restoration of rain damages on Draman to Jalag road Km 0//000 to 2/500 (SH:- C/O B/wall at RD 1/180 to 1/189)				Estimated cost Rs.		97385.00
				Earnest Money Rs.		2000.00
				Time Limits		One month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	20.88	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	4698.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	23.49	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per Cubic Metre	90437.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government	9.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	2250.00
	Total					97385.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer.
 Jaisinghpur Division,
 HP PWD Jaisinghpur


SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Balakrupi Section)				Estimated cost Rs.		99935.00
				Earnest Money Rs.		2000.00
				Time Limits		One month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. Note:- The hire charges of plant machinery on per hour basis	90.85	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99935.00
	Total					99935.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur


SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Gander Section)				Estimated cost Rs.		99660.00
				Earnest Money Rs.		2000.00
				Time Limits		One month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.Note:- The hire charges of plant machinery on per hour basis	90.60	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99660.00
Total						99660.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY


Name of work :-Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Alampur Section)					Estimated cost Rs.		99550.00
					Earnest Money Rs.		2000.00
					Time Limits		One month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.Note:- The hire charges of plant machinery on per hour basis	90.50	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99550.00	
Total						99550.00	
Quoted Rate (in Figures) Percentage		Excess (+)			%		
		Less (-)			%		
G.Total in Figures							
G.Total in Words							


Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Gander to Barram road Km 0/00 to 5/00 (SH:- C/O R/wall at RD 3/017 to 3/021.20)						Estimated cost Rs.	99925.00
						Earnest Money Rs.	2000.00
						Time Limits	One month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The	10.54	220.00	Rupees Two Hundred Twenty Only	Per Cubic Metre	2319.00	
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	24.11	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	90413.00	
3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government	12.00	240.00	Rupees Two Hundred Forty Only	Per Running Metre	2880.00	


4	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200, 1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	4.54	950.00	Rupees Nine Hundred Fifty Only	Per cubic Metre	4313.00
	Total					99925.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

13

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Jaisinghpur to Vijapur via sita Ram khad road Km 0/00 to 1/500 (SH:- C/O B/wall at RD 0/400 to 0/406)				Estimated cost Rs.		99000.00
				Earnest Money Rs.		2000.00
				Time Limits		One month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	22.50	4200.00	Rupees Four Thousand Two Hundred Only	Per Cubic Metre	94500.00
2	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	18.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	4500.00
Total						99000.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						


 Executive Engineer,
 Jaisinghpur Division,
 HP PWD Jaisinghpur


14

SCHEDULE OF QUANTITY

Name of work :-A/R & M/o of non residential building in sub Division Jaisinghpur (SH:- P/L 60 mm thick paver block old Tehsil building)				Estimated cost Rs.		61205.00
				Earnest Money Rs.		2000.00
				Time Limits		One month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	5.40	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per Cubic Metre	22950.00
2	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:2:4 (One cement : Two coarse sand : four graded stone aggregate 20mm (Twenty milimetre) nominal size) in foundation and footing including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana,Tol tax, GST or any other taxes imposed by the Government.	2.79	6200.00	Rupees Six Thousand Two Hundred Only	Per Cubic Metre	17298.00

3	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.48	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	1458.00
4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi	3.78	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per cubic metre	18711.00


5	Providing form work with steel plates 3.15 mm (three point fifteen millimetre) thick welded with angle iron in frame 30 X 30 X 5 mm (thirty into thirty into five millimetre) so as to give a fair finish including centring, shuttering, strutting and propping etcetera with wooden battens and ballies, in all heights of propping and centering below supporting floor to ceiling and removal of the same for insitu-reinforced concrete and plain concrete work in Flat surfaces such as soffits of suspended floors, roofs, landings and the like floor etcetera upto any thickness as per specifications approved drawing , design or as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	3.15	250.00	Rupees Two Hundred Fifty Only	Per Square metre	788.00
	Total					61205.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 H.P.W.D Jaisinghpur

15

SCHEDULE OF QUANTITY

Name of work :-Improvement of black spot various roads Under Balakrupi sub Division (Gander Section) (SH:- Providing and fixing of Glow cat eyes studs under)				Estimated cost Rs.		99330.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and fixing 3M Glow studs of size 100x20 mm(one hundred into twenty millimetre) made of heavy duty body shall be moulded ASA (Acrylic styrene cryloretrite) or HIP (High impact polystyrene) or ABS having electronically welded micro-prismatic lens with abrasion resistant coating as approved by Engineer in charge. The glow stud shall support a load of 13635 kg tested in accordance with ASTM D4280. The slope of retro-reflective surface shall be 35 (+/-5) degress to base.The reflective panels on both side with at least 12 cm of reflective area up each side. The luminance intensity should be as per the specification and shall be tested as described in ASTM I: 809 as recommended in BS: 873 part 4 : 1973. The studs shall be fixed to the Road surface using the adhesive conforming to IS, as per procedure recommended by the manufacturer complete and directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	231.00	430.00	Rupees Four Hundred Thirty Only	Each	99330.00
	Total					99330.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP/PWD Jaisinghpur

12

SCHEDULE OF QUANTITY


Name of work :-Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Gander Section)						Estimated cost Rs.	99440.00
						Earnest Money Rs.	2000.00
						Time Limits	One month
S. N.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.Note:- The hire charges of plant machinery on per hour basis	90.40	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99440.00	
	Total					99440.00	
	Quoted Rate (in Figures) Percentage	Excess (+)			%		
		Less (-)			%		
	G.Total in Figures						
	G.Total in Words						

SCHEDULE OF QUANTITY

Name of work :-A/R & M/O for Preparation of forest diversion case under FCA,1980 for the C/O link road from Gander to Kudana road Km 0/00 to 8/688 (Portion 0/00 to 5/00) Tehsil Jaisinghpur Distt. Kangra (HP) under Balakrupi Sub Division) (SH:- Preparation of forest Diversion case under FCA,1980)

Estimated cost Rs.	70800.00
Earnest Money Rs.	2000.00
Time Limits	Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
3	Preparation of revenue paper for land acquire in the project, Layout Plan of the Project. Khasra wise detail of forest and non-forest both, enumeration list, village wise beneficiary information and Joint Inspection Report. Assistance to User Agency to procure DC Certificate for unavoidable and in-escapable and Certificate NFL for CA from Director Land Records, Shimla as per latest requirement of ministry of environment and forest conservation Govt. of India. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.000	14160.00	Rupees Fourteen Thousand One Hundred Sixty Only	Per kilometre	70800.00
	Total					70800.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur


SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on link road Papalah Bandahu Odri road Km 0/00 to 7/465
(SH:- C/O B/wall at RD 4/787 to 4/794)

Estimated cost Rs.	98617.00
Earnest Money Rs.	2000.00
Time Limits	One month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	19.13	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	4304.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	24.15	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	90563.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	15.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	3750.00
	Total					98617.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur


SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Gander to Barram road Km 0/00 to 5/00 (SH:- C/O R/wall at RD 3/022 to 3/026)

Estimated cost Rs.	95293.00
Earnest Money Rs.	2000.00
Time Limits	One month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The	10.04	220.00	Rupees Two Hundred Twenty Only	Per Cubic Metre	2209.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	22.96	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	86100.00
3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700.1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete. including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government	12.00	240.00	Rupees Two Hundred Forty Only	Per Running Metre	2880.00

4	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200, 1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	4.32	950.00	Rupees Nine Hundred Fifty Only	Per cubic Metre	4104.00
	Total					95293.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP PWD Jaisinghpur


50

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages to various roads under Jaisinghpur Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and clearing of berms various road under Lambagoan Section)

Estimated cost Rs.	99500.00
Earnest Money Rs.	2000.00
Time Limits	One month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. Note:- The hire charges of plant machinery on per hour basis	65.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	71500.00
2	Hiring of carriage Tipper for carriage of material such as Crusher and Sand labour and T & P stricals and other essential material from PWD store Jaisinghpur/quarry site to various roads Under Jaisinghpur Sub Division in HP.PWD, Jaisinghpur as directed by the Engineer-In-Charge. Any loss to the public private property or any accidnetetc. happened during the course of hiring period shall be the absolute reponsibilty of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and opertaioinal staff for carriage vehicle also be born by the contractor owner. The daily 70 Km per day running charges will be assuming and log book will also be maintained at site which should be verified by the Engineer-in-Charge. Note:- The hire charges of plant machinery on per day basis	8.00	3500.00	Rupees Three Thousand Five Hundred Only	Per Day	28000.00
	Total					99500.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer
 Jaisinghpur Division
 HPWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Tinbar Jaisinghpur road Km 0/00 to 18/300 (SH:- C/O R/wall at RD 9/100 to 9/110)				Estimated cost Rs.		99350.00
				Earnest Money Rs.		2000.00
				Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	18.00	200.00	Rupees Two Hundred Only	Per Cubic Metre	3600.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	25.00	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	93750.00

5	Providing 100mm (one Hundred millimeter,) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	8.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	2000.00
	Total					99350.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					




Executive Engineer,
Jaisinghpur Division,
H.P.W.D Jaisinghpur

22

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Dharamshala Dadh Holta Chadhiar sandhole road Km 40/500 to 56/00 (SH:- C/O Breast wall from RD 54/405 to 54/428)				Estimated cost Rs.		97244.00
				Earnest Money Rs.		2000.00
				Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	15.64	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	3519.00
2	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	20.70	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per Cubic Metre	87975.00


3	Providing 100mm (one hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	23.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	5750.00
	Total					97244.00
	Quoted Rate (in Figures) Percentage	Excess (-)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP, PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Bandahu to Bhairghatta road Km 0/00 to 2/615 (SH:- C/O R/wall at Rd 0/370 to 0/374.20) DC Deposit				Estimated cost Rs.		99925.00
				Earnest Money Rs.		2000.00
				Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.54	220.00	Rupees Two Hundred Twenty Only	Per Cubic Metre	2319.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	24.11	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	90413.00
3	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200, 1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	4.54	950.00	Rupees Nine Hundred Fifty Only	Per cubic Metre	4313.00

4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700.1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	12.00	240.00	Rupees Two Hundred Forty Only	Per Running Metre	2880.00
	Total					99925.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur


SCHEDULE OF QUANTITY

Name of work :- Completion of floor Tile work of Guru Ravi Dass sarai Bhawan Andretta (SH:-P/L Tile work in Rooms and Kota Stone in Yard) Deposit SDP/2024/938 & 763

Estimated cost Rs.	283066.00
Earnest Money Rs.	5700.00
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying double charge vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622. of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm ncluding grouting the joints with white cement and matching pigments etc.. complete Size of Tile 500x500 mm.	104.12	1400.00	Rupees One Thousand Four Hundred Only	Per square Metre	145768.00
2	Providing and laying double charge Vitrified tiles in different sizes Sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622. of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete Size of Tile 500 x 500 mm.	5.74	1400.00	Rupees One Thousand Four Hundred Only	Per square Metre	8036.00
3	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	6.660	1200.00	Rupees One Thousand Two Hundred Only	Per cubic metre	7992.00
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering-All work upto plinth level cement concrete 1:6:12 (One cement: six sand: twelve graded crushed/broken stone aggregate 40mm (Forty milimetre) nominal size) including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana,Tol tax, GST or any other taxes imposed by the Government.	6.66	3700.00	Rupees Three Thousand Seven Hundred Only	Per cubic Metre	24642.00

5	Kota stone slab flooring 20 mm(average) thick base of cement mortar 1:4 (1 cement :4 sand) laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab. including rubbing and polishing complete. as per specifications approved drawing, design. as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	66.64	1450.00	Rupees One Thousand Four Hundred Fifty Only	Per Square Metre	96628.00
	Total					283066.00
		Excess (+)			%	
	Quoted Rate (in Figures) Percentage	Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP PWD Jaisinghpur


25

SCHEDULE OF QUANTITY

Name of work :- C/O Approach road from Jaisinghpur Bus Stand towards panchyat Ghar and Chogan Ground
Jaisinghpur (SH.- C/O 80 mm thick Paver Block from 0/00 to 0/057)(Deposit VKV/2025/59)


Estimated cost Rs.	499707.00
Earnest Money Rs.	10000.00
Time Limits	Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	22.80	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per Cubic Metre	96900.00
2	Providing and laying 80 mm thick Interlocking M-40 grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 80mm (eighty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	285.00	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per square metre	356250.00
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:2:4 (One cement : Two coarse sand : four graded stone aggregate 20mm (Twenty milimetre) nominal size) in foundation and footing including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana,Tol tax, GST or any other taxes imposed by the Government.	7.39	6300.00	Rupees Six Thousand Three Hundred Only	Per Cubic Metre	46557.00
	Total					499707.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP/PWD Jaisinghpur

SCHEDULE OF QUANTITY


Name of work :-A/R & M/O various roads under Balakrupi Sub Division (Section Balakrupi) (SH:-Painting, lettering of Kms stones and sign boards ect.)				Estimated cost Rs.		99791.00
				Earnest Money Rs.		2000.00
				Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
13	Painting two coats (excluding priming coat) on new steel and other metal surfaces with enamel paint of Asian/ Nerolac brushing to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters with enamel paint of approval shade as per specifications, approved drawing , design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, GST and all type of other taxes imposed by the Government.	58.00	70.00	Rupees Seventy Only	Per square metre	4060.00
2	Applying Painting two coats(excluding priming coat on new concrete masonry/plaster surfaces with readymixed paint brushing for use on floors to give an even shade including cleaning the surface of all dirt,dust and other foreign matter and sand papering as required. The rate includes octroi,royalty,Malkana,Tol tax, sale tax, GST or any other taxes imposed by the Government.	53.00	18.15	Rupees Eighteen And Paise Fifteen Only	Per Square metre	962.00
3	Writing letters of figures on any surface with synthetic enamel paint (other than white) (stop, comas, border, hyphens and like not to be measured and paid separately) in Indian letter/figure complete and as per directions of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation with in all leads, lifts and other incidental The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	48850.00	1.94	Rupees One And Paise Ninety Four Only	Per letter per centimetre	94769.00
		Total				99791.00
		Quoted Rate (in Figures) Percentage	Excess (+)		%	
			Less (-)		%	
		G.Total in Figures				
		G.Total in Words				


 Executive Engineer,
 Jaisinghpur Division,
 HP/PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-C/O road main road to village Gharloon Km 0/00 to 0/500 (SH-C/O R/wall from RD 0/090 to 0/105and B/wall from RD 0/100 tro 0/110) (SDP/2023/1244)				Estimated cost Rs.	498089.00	
				Earnest Money, Rs.	10000.00	
				Time Limits	Two month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	43.51	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	9790.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	112.66	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per Cubic Metre	433741.00

3	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	159.30	275.00	Rupees Two Hundred Seventy Five Only	Per cubic Metre	43808.00
4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	43.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	10750.00
	Total					498089.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					



 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

28

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Bhuana Ashapuri road Km 0/00 to 12/300 (SH:- C/O R/wall from RD 1/310 to 1/314.50)				Estimated cost Rs.		99159.00
				Earnest Money Rs.		2000.00
				Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.81	250.00	Rupees Two Hundred Fifty Only	Per Cubic Metre	2453.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	21.02	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per Cubic Metre	80927.00


3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	2.43	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per cubic metre	12029.00
4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	15.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	3750.00
	Total					99159.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					



Executive Engineer,
Jaisinghpur Division,
H.P.W.D Jaisinghpur


SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Gander Section)				Estimated cost Rs.		99770.00
				Earnest Money Rs.		2000.00
				Time Limits		One month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. Note:- The hire charges of plant machinery on per hour basis	90.70	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99770.00
	Total					99770.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 H.P. PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Alampur Section)			Estimated cost Rs.		99880.00	
			Earnest Money Rs.		2000.00	
			Time Limits		One month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.Note:- The hire charges of plant machinery on per hour basis	90.80	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99880.00
	Total					99880.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 H.P.PWD Jaisinghpur