

NOTICE INVITING TENDER

Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Division, HP: PWD, Kangra on behalf of the Governor of Himachal Pradesh for the following work from the approved and eligible contractors/firms enlisted in HPPWD in the appropriate class for the work mentioned below on **14.08.2025 up to 11-00 A.M.** and will be opened on the same day at **11-30 A.M.** in the presence of intending contractors or their authorized representatives who may wish to be present. The tender forms can be obtained from this office on cash payment (non refundable) on **13.08.2025 up to 4.00 P.M.** The tender applications for issue of tender forms will be received in this office on **12.08.2025 up to 05.00 P.M.** The earnest money in shape FDR National Saving certificate/Saving Account/Time Deposit Account in any of the Post Office/National Bank in H.P. duly pledged in favour of Executive Engineer, HPPWD., Division, Kangra. The conditional tenders and the tenders received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost of tender form	Time Limit
1.	Improvement of Black Spot on Kalka Mata to Chilibai road (SH- Providing & Erecting Crash Barrier at RD 1/285 to 1/297)	45696/-	1200/-	350/-	One Month
2.	Improvement of Black Spot on Salot to Bhartha (SH- Providing & Erecting Crash Barrier at RD 1/200 to 1/208)	30464/-	700/-	350/-	One Month
3.	Improvement of Black Spot on Daulatpur Jalari Khart Road km. 0/00 to 5/740 (SH- Providing and Erecting Crash Barrier at RD 2/185 to 2/209)	91392/-	2000/-	350/-	One Month
4.	Improvement of Black Spot on Daulatpur Jalari Khart Road km. 0/00 to 5/740 (SH- Providing and Erecting Crash Barrier at RD 2/209 to 2/233)	91392/-	2000/-	350/-	One Month
5.	Repair and Maintenance of HPPWD Section Store at Abdulapur (Zamanabad Section) (SH- Providing and fixing fencing wire around the HPPWD Store Zamanabad section)	40063/-	800/-	350/-	Two Month
6.	C/O Pucca Path interlocking tile from Amar Singh Thola House towards Banwari House ward No. 02 G.P. Abdulapur (SH- C/O Cement concrete Paver Block (Deposit work) (SDP)	49993/-	1000/-	350/-	Two Month
7.	C/O Pucca Path interlocking tile from Sanjay Kumar House towards Ashwani Kumar House ward No. 06 G.P. Abdulapur (SH- C/O Cement concrete Paver Block (Deposit work) (SDP)	50000/-	1000/-	350/-	Two Month
8.	Improvement of Black Spot on Daulatpur Jalari Khart Road km. 0/00 to 5/740 (SH- Providing and Erecting Crash Barrier at RD 2/233 to 2/257)	91392/-	2000/-	350/-	One Month
9.	Balance work of Mahila Mandal Kholi Tandyali Basti Mohal Kholi (SH- Providing and Laying Vitrified Tiles Skirting, Painting, Woven plains G.I. Wire Fencing etc.)	99025/-	1950/-	350/-	Two Month
10.	Balance work of Mahila Mandal Kholi Tandyali Basti Mohal Kholi (SH- Providing and Laying Vitrified Tiles Flooring & Protection Work etc.)	99935/-	2000/-	350/-	Two Month
11.	Up gradation in the infrastructure in selected School in Govt. Primary School at Matour (SH- Providing and fixing Door, Window Shutter, Wooden Paint and Painting work)	61207/-	1500/-	350/-	One Month

Certified that tender of above works are being called of urgent nature in public interest.
TERMS & CONDITIONS:-

- The contractors/firms should produce the attested copy of latest enlistment and renewal enlisted in HPPWD, GST No. and EPF No. with the application failing which their application will not be entertained.
- If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
- The Earnest Money for the above works should be required at the time of sale of tender forms.
- The contractor/firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
- The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason

Executive Engineer,
HPPWD, Division, Kangra.
Distt. Kangra (H.P.)

(On behalf of Governor of Himachal Pradesh)

Endst:- No.PW/KD/CB/Tenders/2025-26-
Copy is forwarded to:-

- The Computer Cell Office of the Engineer-in-Chief, HPPWD., Shimla for uploading the NIT on the Department website.
- The Chief Engineer (KZ) HPPWD., Dharamshala for information please.
- The Superintending Engineer, 5th Circle, HPPWD., Palampur for information please.
- All the Assistant Engineer's working under Kangra Division.
- NIT Register.
- All Head of Branches.
- Notice Board.

Executive Engineer,
HPPWD, Division, Kangra.
Distt. Kangra (H.P.)

2413-30

Dated:- 7/08/25

SCHEDULE OF QUANTITY					
Name of work :- Improvement of black spot on Saloto Bhartha. (Sh:-Providing & erecting Crash Barrier at RD 1/200 to 1/208				Estimate cost-	30464.00
Sub-Head and items of work				Earnest money- Time limit-	700.00 One month.
Sr.N o.	Quantity	Unit	Rates in	Figures	Words
1	8.00	Per/Runnin g metre	3808.00	Rupees Three Thousand Eight Hundred & Eight Only	30464.00
Providing and erecting a "W-metal beam crash barrier comprising of 3 mm thick corrugated sheet metal beam rail, 70 cm above road/ ground level, fixed on ISMC series Channel vertical post, 150 X75X 5 mm spaced 2 m centre to centre, 1.8 m high, 1.1 m below ground/ road level, all steel parts and fittings to be galvanised by hot dip process, all fittings to confirm to IS: 1367 and IS: 1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x5 mm, 330 mm long complete as per clause 810.					30464.00

EXCESS =

%

LESS =

%

[Signature]


Executive Engineer
HP PWD. Division
Kangra Division

SCHEDULE OF QUANTITY

NAME OF WORK :-IMPROVEMENT OF BLACK SPOT ON DOULATPUR JALARI KHART ROAD KM. 0/00 TO 5/740(SH:- PROVIDING AND ERECTING CRASH BARRIER AT RD.2/185 TO2/209					Estimated Cost:-	91392.00
					Earnest Money:-	2000/-
					Time Limit:-	ONE Month
Sr. No.	Description of work	Qty	Unit	Rates		AMOUNT
				In Figures	In Words	
1	Providing and erecting a "W-metal beam crash barrier comprising of 3mm thick corrugated sheet metal beam rail,70 cm above road/ground level, fixed on ISMC series channel vertical post 150x75x5 mm spaced 2.00 mtr. Centre to centre, 1.8m high, 1.1 m below ground/road level, all steel parts and fittings to be galvanised by hot dip process, all fittings to conform to IS: 1367 and IS:1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5mm, 330mm long complete as per clause 810 as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	24.00	Per Running metre	3808.00	Rupees Three Thousand Eight Hundred & Eight Only	91392.00
Total:						91392.00

EXCESS =%

LESS =%



 Executive Engineer,
 HPPWD Kangra
 Division Kangra.

SCHEDULE OF QUANTITY

NAME OF WORK :-IMPROVEMENT OF BLACK SPOT ON DOULATPUR JALARI KHART ROAD KM. 0/00 TO 5/740(SH:- PROVIDING AND ERECTING CRASH BARRIER AT RD.2/209 TO2/233					Estimated Cost:-	91392.00
					Earnest Money:-	2000/-
					Time Limit:-	ONE Month
Sr. No.	Description of work	Qty	Unit	Rates		AMOUNT
				In Figures	In Words	
1	Providing and erecting a "W-metal beam crash barrier comprising of 3mm thick corrugated sheet metal beam rail,70 cm above road/ground level fixed on ISMC series channel vertical post 150x75x5 mm spaced 2.00 mtr. Centre to centre, 1.8m high, 1.1 m below ground/road level, all steel parts and fittings to be galvanised by hot dip process, all fittings to confirm to IS: 1367 and IS:1364,metal beam rail to be fixed on the vertical post with a spacer of channelsection 150x75x5mm, 330mm long complete as per clause 810as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	24.00	Per Running metre	3808.00	Rupees Three Thousand Eight Hundred & Eight Only	91392.00
Total:						91392.00

EXCESS =%

LESS =%


 Executive Engineer,
 HPPWD Kangra
 Division Kangra


SCHEDULE OF QUANTITY

NAME OF WORK :-REPAIR AND MAINTENANCE OF HP,PWD SECTIONAL STORE AT ABDULLAPUR(ZAMANABAD SECTION) SUB HEAD:- PROVIDING AND FIXING FENCING WIRE AROUND THE HP,PWD STORE ATZAMANBAD SECTION							Estimated Cost:- Earnest Money:- 40063.00 800/-
Sr. No.	Description of work	Qty	Unit	Rates		Time Limit:- Two Month	
				In Figures	In Words		
						AMOUNT	
1	Excavation in foundation, trenches etcetra in earth work in all kind of classification of soil such as pick work, jumper work, pick jumper work, blasting work, soft and hard blasting and doing work in saturated soil, including chiselling or wedging out rocks where blasting work is prohibited or any other mixed variety of soil including shoring, strutting, de-watering and pumping or bailing out water (surface and sub soil water) upto any depths any quantum of water including slush which may arise during de-watering or removal of slush, lift upto any height stacking the excavated soil not more than 3 metres (Three metres) clear from the edge of excavation and then returning the stacked soil in 15cm (Fifteen centimetre) layers, when required into plinths, sides of foundation etcetra consolidating each deposited layer by ramming, watering and then disposing of all surplus excavated earth as per specification, approved drawing design as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	2.07	Per Cubic metres	489.20	Rupees Four Hundred & Eighty Nine - Paise Twenty Only	1013.00	
2	Providing and laying mechanically mixed and vibrated, concrete for plain cement concrete in open foundation of all type of structure complete, grade- M-20 (M twenty) nominal mix 1:2:4 (One cement isto Two sand isto Four graded crushed stone aggregate 20mm (Twenty millimetre) nominal size with cement contents not les than of 330 (Three hundred thirty) Kilogramme Per Cubic metre with 20mm (Twenty millimetre) nominal size graded crushed stone aggregate and curing complete, for all heights/ depths including the cost of form work as per drawings and MORD technical section 800, 900 and 1200 and as per the direction of Engineer-in-Charge. The rate is inclusive for carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.07	Per Cubic metres	6321.20	Rupees Six Thousand Three Hundred & Twenty One - Paise Twenty Only	13085.00	
3	R.C.C.Standards post/ struts/rails/pales of mix 1:1.5:3(1cement:1.5 coarse sand:3 graded stone aggregate 12.5 mm nominal size) with wooden plugs or 6mm bar nls wherever required as per direction of engineer-in- Charge(cost of earth work in excavation, concrete works in foundation to be paid separately)The rate is inclusive for carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	0.36	Per Cubic metres	21821.95	Rupees Twenty One Thousand Eight Hundred & Twenty One - Paise Ninety Five Only	7856.00	

4	Fencing with R.C.C. Post placed at required distance, embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and end post one side only, provided with horizontal lines and two diagonals of barbed wire weighting 9.38 kg per 100 metres (minimum), between the two posts fitted and fixed with G.I. staples on wooden plugs or G.I. binding wire tied to 6mm bar nbs fixed while casting the post (cost of R.C.C. posts, struts, earth work and concrete to be paid for separately) payment to be made per metre cost of total length of barbed wire used The rate is inclusive for carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	357.20	Per Running metre	10.15	Rupees Ten - Paise Fifteen Only	3626.00
5	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying coat of approved steel primer using structural steel etc. as required in grating, frames, guard bar, ladder, railing, brackets, gate and similar works and as per the direction of Engineer-in-Charge including carriage of material with in all leads and lifts and other incidental. The rate including of octroi, royalty, Malkhana, toll tax, GST or other taxes imposed by the government.	116.80	Per kilogram	124.00	Rupees One Hundred & Twenty Four Only	14483.00
		Total:				40063.00

EXCESS = %

LESS = %


Executive Engineer,
HPPWD Kangra
Division Kangra

SCHEDULE OF QUANTITY

NAME OF WORK : CONSTRUCTION OF PUCCA PATH INTERLOCKING TILE FROM AMAR SINGH THOLA HOUSE TOWARDS BANWARI HOUSE WARD NO. 02 G.P. ABDULAPUR (SUB HEAD:- C/O CEMENT CONCRETE PAVER BLOCK (DEPOSIT WORK) (SDP)					Estimated Cost:- Earnest Money:- Time Limit:-	49993.00 1000/- Two Month
Sr. No	Description of work	Qty	Unit	In Figures	Rates	
						AMOUNT
1	Providing and laying 60mm (Sixty millimetre) thick NTC interlocking blocks heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50 (M-fifty) grade i.e. border or kurb black grey or coloured over sub base of concrete with 25mm (Twenty five millimetre) thick average thickness of cement mortar 1:4 (One cement isto Four sand) laid over joint ted with neat cement slurry mixed with pigment to match the shade of blocks including curing, rubbing of polishing complete (sub base concrete floor to be paid for separately) as directed by the Engineer-in-charge, within all leads, lifts of materials and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	44.59	Per Square Metere	1054.55	Rupees One Thousand & Fifty Four - Paise Fifty Five Only	47022.00
2	Providing and laying mechanically mixed and vibrated, concrete for plain cement concrete in open foundation of all type of structure complete, grade- M-20 (M twenty) nominal mix 1:2:4 (One cement isto Two sand isto Four graded crushed stone aggregate 20mm (Twenty millimetre) nominal size with cement contents not les than of 330 (Three hundred thirty) Kilogramme Per Cubic metre with 20mm (Twenty milimetre) nominal size graded crushed stone aggregate and curing complete, for all heights/ depths including the cost of form work as per drawings and MORD technical section 800, 900 and 1200 and as per the direction of Engineer-in-Charge. The rate is inclusive for carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	0.47	Per Cubic Metere	6321.20	Rupees Six Thousand Three Hundred & Twenty One - Paise Twenty Only	2971.00
TOTAL						49993.00

EXCESS = %

LESS = %



 EXECUTIVE ENGINEER,
 KANGRA DIVISION
 HP.PWD.KANGRA

SCHEDULE OF QUANTITY

NAME OF WORK :CONSTRUCTION OF PUCCA PATH INTERLOCKING TILE FROM SANJAY KUMAR HOUSE TOWARDS ASHWANI KUMAR HOUSE WARD NO-06 G.P. ABDULLAPUR SUB HEAD:- C/O CEMENT CONCRETE PAVEMENT BLOCK(DEPOSIT WORK)(SDP)					Estimated Cost:- Earnest Money:- Time Limit:-	50000.00 1000/- Two Month
Sr. No	Description of work	Qty	Unit	In Figures	Rates	
						AMOUNT
1	Providing and laying 60mm (Sixty millimetre) thick NTC interlocking blocks heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50 (M-fifty) grade i.e. border or curb black grey or coloured over sub base of concrete with 25mm (Twenty five millimetre) thick average thickness of cement mortar 1:4 (One cement isto Four sand) laid over joint ted with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing of polishing complete (sub base concrete floor to be paid for separately) as directed by the Engineer-in-charge, within all leads, lifts of materials and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	43.52	Per Square Metere	1054.55	Rupees One Thousand & Fifty Four - Paise Fifty Five Only	45894.00
2	Providing and laying mechanically mixed and vibrated, concrete for plain cement concrete in open foundation of all type of structure complete, grade- M-20 (M twenty) nominal mix 1:2:4 (One cement isto Two sand isto Four graded crushed stone aggregate 20mm (Twenty millimetre) nominal size with cement contents not les than of 330 (Three hundred thirty) Kilogramme Per Cubic metre with 20mm (Twenty millimetre) nominal size (graded crushed stone aggregate and curing complete, for all heights/ depths including the cost of form work as per drawings and MORD technical section 800, 900 and 1200 and as per the direction of Engineer-in-Charge. The rate is inclusive for carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	0.65	Per Cubic Metere	6321.20	Rupees Six Thousand Three Hundred & Twenty One - Paise Twenty Only	4109.00
TOTAL						50000.00

EXCESS = %

LESS = %



EXECUTIVE ENGINEER,
KANGRA DIVISION,
H.P.P.W.D.KANGRA

SCHEDULE OF QUANTITY

NAME OF WORK :-IMPROVEMENT OF BLACK SPOT ON DOULATPUR JALARI KHART ROAD KM. 0/00 TO 5/740(SH):- PROVIDING AND ERECTING CRASH BARRIER AT RD.2/233 TO2/257					Estimated Cost:-	91392.00
					Earnest Money:-	2000/-
					Time Limit:-	ONE Month
Sr. No.	Description of work	Qty	Unit	Rates		AMOUNT
				In Figures	In Words	
1	Providing and erecting a "W-metal beam crash barrier comprising of 3mm thick corrugated sheet metal beam rail,70 cm above road/ground level,fixxed on ISMC series channel vertical post 150x75x5 mm spaced 2.00 mtr. Centre to centre, 1.8m high, 1.1 m below ground/road level, all steel parts and fittings to be galvanised by hot dip process, all fittings to conform to IS: 1367 and IS:1364,metal beam rail to be fixed on the vertical post with a spacer of channelsection 150x75x5mm, 330mm long complete as per clause 810as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	24.00	Per Running metre	3808.00	Rupees Three Thousand Eight Hundred & Eight Only	91392.00
Total:						91392.00

EXCESS =%

LESS =%


 Executive Engineer,
 HPPWD Kangra
 Division Kangra


SCHEDULE OF QUANTITY

NAME OF WORK :BALANCE WORK OF MAHILA MANDAL KHOLI TANDYALI BASTI MOHAL KHOLI(SUB HEAD:- PROVIDING AND LAYING VITRIFIED TILES SKIRTING,PAINTING, WOVENPLAINS G.I WIRE FENCING ETC.							Estimated Cost:- Earnest Money:- Time Limit:-	99025.00 1950.00 Two Month
Sr. No	Description of work	Qty	Unit	Rates		AMOUNT		
				In Figures	In Words			
1	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying coat of approved steel primer using structural steel etc.as required in grating, frames, guard bar, ladder, railing, brackets, gate and similar works and as per the direction of Engineer-in-Charge including carriage of material with in all leads and lifts and other incidental. The rate including of octroi, royalty, Malkhana, toll tax, GST or other taxes imposed by the government.	221.66	Per kilo gram	124.00	Rupees One Hundred & Twenty Four Only	27486.00		
2	Supplying and fixing wovenplains G.I wire fencing of mesh 50mm(Five Zero millimetre) to 150 mm (one Five Zero Milimeter) to any type of standard rails, straining bolts, Etc.including provision of binding wire, staples etc. as per the direction of Engineer-in-Charge including carriage of material with in all leads and lifts and other incidental. The rate including of octroi, royalty, Malkhana, toll tax, GST or other taxes imposed by the government.	23.77	Per Square metres	578.45	Rupees Five Hundred & Seventy Eight - Paise Forty Five Only	13750.00		
3	Applying Birla J.K. white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dirt, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete upto all floor level, as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana and toll tax, GST or any other taxes imposed by the Government.	224.81	Per Square metres	90.05	Rupees Ninety - Paise Five Only	20244.00		
4	Finishing wall with weather proof interiors and exterior grade emulsion of approved design (Apexhlitma or its equarlred on undecorated wall surfaces[Two coats] to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana and toll tax, GST or any other taxes imposed by the Government.	224.81	Per Square metres	124.70	Rupees One Hundred & Twenty Four - Paise Seventy Only	28034.00		
5	Applying priming coat over new wood and wood based surfaceswith Nerolac/Asian or its equivalent after and including prepering the surface by thoroughly cleaning oil,grease,dirt and other foreign matter) sand papering and knoting with Ready mixed paint brushing wood primer pink . as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana and toll tax, GST or any other taxes imposed by the Government.	16.90	Per Square metres	38.95	Rupees Thirty Eight - Paise Ninety Five Only	658.00		

6	Painting two coats(excluding coat) on new wood and wood based surfaces with ready mixed enamel paint of approved brand and manufacture of approved shade brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter,sand papering & stopping with ready mixed paint other then white as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana and toll tax, GST or any other taxes imposed by the Government.	16.90	Per Square metres	94.30	Rupees Ninety Four - Paise Thirty Only	1594.00
7	Painting two coats (excluding priming coat on new steel and other metal surfaces with enamel paint of approved brand and manufacture(Narolac/Asian or equivalent paints)and of approved shade brushing to give an even shade including cleaning the surface of all dirt,dust and other foreign matterscomplete as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana and toll tax, GST or any other taxes imposed by the Government.	1.56	Per Square metres	90.20	Rupees Ninety - Paise Twenty Only	141.00
8	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete Size of Tile 600x600 mm as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The	4.81	Per Square metres	1479.80	Rupees One Thousand Four Hundred & Seventy Nine - Paise Eighty Only	7118.00
Total:						99025.00

EXCESS = %

LESS = %


Executive Engineer,
HPPWD Kangra
Division Kangra




SCHEDULE OF QUANTITY

NAME OF WORK : BALANCE WORK OF MAHILA MANDAL KHOLI TANDYALI BASTI MOHAL KHOLI (SUB HEAD:- PROVIDING AND LAYING VITRIFIED TILES FLOORING, & PROTECTION WORK ETC.						
Estimated Cost:- 99935.00						
Earnest Money:- 2000.00						
Time Limit:- Two Month						
Sr. No	Description of work	Qty	Unit	Rates		AMOUNT
				In Figures	In Words	
1	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., in flooring complete size 600x600 mm as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana and toll tax, GST or any other taxes imposed by the Government.	44.01	Per Square metres	1500.00	Rupees One Thousand Five Hundred Only	66015.00
2	Earthwork in excavation for all type of road structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3 m depth The rate is inclusive for carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, toll tax, sale tax or other taxes imposed by the Government.	4.73	Per Cubic metres	489.20	Rupees Four Hundred & Eighty Nine - Paise Twenty Only	2314.00
3	Providing and laying cement concrete 1:5:10 (One Cement isto Five Sand isto Ten graded crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and curing complete excluding the cost of form work, in foundation and Plinth, as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	5.90	Per Cubic metres	4998.81	Rupees Four Thousand Nine Hundred & Ninety Eight - Paise Eighty One Only	29493.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia(Hundred millimetre) PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drainage face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction and entire satisfaction of Engineer-in-charge including carriage of material.	5.00	Each	422.50	Rupees Four Hundred & Twenty Two - Paise Fifty Only	2113.00
		Total:				99935.00

EXCESS = %

LESS = %


 Executive Engineer,
 HPPWD Kangra
 Division Kangra

Name of work :- Upgradation in the infrastructure in selected school in Govt. Primary School at Matour. (Sh:- Providing & Fixing Door, Window Shutter, Wooden Paint and Painting work).


SCHEDULE OF QUANTITY						
Name of work :- Upgradation in the infrastructure in selected school in Govt. Primary School at Matour. (Sh:- Providing & Fixing Door, Window Shutter, Wooden Paint and Painting work).						
Sr No.	Sub-Head and items of work	Quantity	Unit	Rates in		Amount
				Figures	Words	
1	Providing and fixing Second class teak wood wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws 35 mm thick shutters with ISI marked M.S. pressed butt hinges bright finished of required as per direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including ectroi,royalty,Malkana,toll tax sale tax or other taxes imposed by the Government	3.78	Per/Sqm	4066.95	Rupees Four Thousand & Sixty Six - Paise Ninety Five Only	15373.00
2	Providing and fixing glazed shutters for doors, windows and clerestory windows using 4 mm thick float glass panes, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws as per direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including ectroi,royalty,Malkana,toll tax sale tax or other taxes imposed by the Government	3.78	Per/Sqm	4200.00	Rupees Four Thousand Two Hundred Only	15876.00
3	Providing and fixing plain M.S. (Mild steel) Grills of required pattern in structural steel frames of windows etcetera with Mild Steel flats square or round bars with headed bolts and nuts or screws including welding with frames complete in all respect, as per specification, approved drawing, design, as per direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including ectroi,royalty,Malkana,toll tax sale tax or other taxes imposed by the Government	60.48	Kg.	94.00	Rupees Ninety Four Only	5685.00
				Estimate cost-		61207.00
				Earnest money-		1500.00
				Time limit-	One month.	

4	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters 35 mm thick including ISI marked stainless steel butt hinges with necessary screws as per specification, approved drawing, design, as per direction of Engineer-in-charge including carriage of materials within all leads andlifts and other incidental. The rate including ectroi,royalty,Malkana,toll tax sale tax or other taxes imposed by the Government	2.21	Per/Sqm	2832.75	Rupees Two Thousand Eight Hundred & Thirty Two - Paise Seventy Five Only	6260.00
5	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour orshade, with nuts and screws etc. complete as per direction of Engineer-in-charge including carriage of materials within all leads andlifts and other incidental. The rate including ectroi,royalty,Malkana,toll tax sale tax or other taxes imposed by the Government	1.00	Each	239.60	Rupees Two Hundred & Thirty Nine - Paise Sixty Only	240.00
6(i)	Providing and fixing 250 x 10 mm size of aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete as per direction of Engineer-in-charge including carriage of materials within all leads andlifts and other incidental. The rate including ectroi,royalty,Malkana,toll tax sale tax or other taxes imposed by the Government	1.00	Each	99.20	Rupees Ninety Nine - Paise Twenty Only	99.00
6(ii)	Providing and fixing 100 x 10 mm size of aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete as per direction of Engineer-in-charge including carriage of materials within all leads andlifts and other incidental. The rate including ectroi,royalty,Malkana,toll tax sale tax or other taxes imposed by the Government	26	Each	55.35	Rupees Fifty Five - Paise Thirty Five Only	1439.00
7	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per direction of Engineer-in-charge including carriage of materials within all leads andlifts and other incidental. The rate including ectroi,royalty,Malkana,toll tax sale tax or other taxes imposed by the	85.48	Per Sqm.	90.05	Rupees Ninety - Paise Five Only	7697.00

8	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour per direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including ectroi,royalty,Malkana,toll tax sale tax or other taxes imposed by the Government	85.48	Per Sqm.	90.57	Rupees Ninety - Paise Fifty Seven Only	7742.00
9	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over a under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture as per direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including ectroi,royalty,Malkana,toll tax sale tax or other taxes imposed by the Government	3.78	Per Sqm.	120.55	Rupees One Hundred & Twenty - Paise Fifty Five Only	456.00
10	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture as per direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including ectroi,royalty,Malkana,toll tax sale tax or other taxes imposed by the Government	3.78	Per Sqm.	89.90	Rupees Eighty Nine - Paise Ninety Only	340.00
total						61207.00

EXCESS = %

LESS = %


Executive Engineer
HP.PWD. Division
Kangra Division

HP.PWD. Division
Kangra Division