

OFFICE OF
EXECUTIVE ENGINEER, SALOONI DIVISION HPPWD SALOONI
HIMACHAL PRADESH, PUBLIC WORKS DEPARTMENT SALOONI
Phone No. 01899-233287 Email: ee-slo-hp@nic.in
NOTING INVITING TENDER

Sealed item rate tender on form 6&8 are hereby invited by the Executive Engineer, Salooni Division HPPWD Salooni on behalf of the Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD. So as to reach in his office on or before **14.08.2025 to 11:00 AM** and the same shall be opened on the same day at **11:30 AM**, in the presence of the Intending Contractor or their authorized representatives if any. The tender form can be obtained from his office on cash payment (Non refundable) on **13.08.2025 upto 01.30 PM** and the application for issue of tender form shall be received on **13.08.2025 upto 04.00 P.M.** The earnest money in the form of FDR from nationalized bank in HP duly pledged in favour of the Executive Engineer, Salooni Division HPPWD Salooni must be accompanied with each tender. The tender form will be issued to contractor who giving proof of enlistment, GST, Conditional tenders and the tenders received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer, reserves the right to reject the tender without assigning any reason. Special care should be taken to write the rates both in figure and in words.

Sr. No.	Name of work	Estimated Cost	Earnest money	Cost of form	Time limit	Eligible Class
1.	Restoration of rain damages on Kuthed to Kandhwara road K.M. 0/0 to 12/100 (SH: Removal of slips at various RD.s)	99,910/-	2000/-	350/-	90 Days	D & C
2.	Restoration of rain damages on Bihali Bachuni Chhambur Katara road K.M. 0/0 to 11/100 (SH: Removal of slips at R.D. 2/070 to 2/090, 2/210 to 2/250, 4/300 to 4/330)	99,743/-	2000/-	350/-	90 Days	D & C
3.	Restoration of rain damages on Sundla Girjindoo road K.M. 0/0 to 36/500 (SH: Removal of slips at various RD.s)	98,380/-	2000/-	350/-	90 Days	D & C
4.	Restoration of rain damages on Bathri Sundla Langer J & K boundary road K.M. 57/0 to 93/400 (SH: Construction of PCC Retaining walls at R.D. 92/577 to 92/579)	99,507/-	2000/-	350/-	90 Days	D & C
5.	Restoration of rain damages on near Telka to Thaloga road K.M. 0/0 to 4/600 (SH: Removal of slips at various RD.s)	99,829/-	2000/-	350/-	90 Days	D & C
6.	Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Removal of slips at various RD's)	99,565/-	2000/-	350/-	90 Days	D & C
7.	Restoration of rain damages on Bhalei Matta Temple to village Saphan road K.M. 0/0 to 4/825 (SH: Removal of slips at various RD's)	99,354/-	2000/-	350/-	90 Days	D & C
8.	Restoration of rain damages on Bathri Sundla Langer J & K boundary road K.M. 13/130 to 28/0 (SH: Removal of slips between R.D. 24/040 to 24/060, 24/920 to 24/940 24/200 to 25/285 and 26/210 to 26/230)	99,785/-	2000/-	350/-	90 Days	D & C


9.	Restoration of rain damages on Chakoli road to Dhalla K.M. 0/0 to 5/100 (SH: Removal of slips at various RD's)	95,790/-	2000/-	350/-	90 Days	D & C
10.	Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Removal of slips at R.D. 0/620 to 0/660, 1/840 to 1/880 and 2/150 to 2/180)	99,925/-	2000/-	350/-	90 Days	D & C
11.	Restoration of rain damages on Salooni Ghall road K.M. 0/0 to 7/500 (SH: Removal of slips at various RD's)	97,850/-	2000/-	350/-	90 Days	D & C
12.	Restoration of rain damages on link road Rolka to Halela K.M. 0/0 to 3/400 (SH: Construction of Retaining walls in wire crate at R.D. 0/270 to 0/277.50)	95,722/-	2000/-	350/-	90 Days	D & C
13.	Restoration of rain damages on Chudhra to Thuien road K.M. 0/0 to 2/225 (SH: Construction of PCC Retaining walls at R.D. 1/765.50 to 1/768)	96,939/-	2000/-	350/-	90 Days	D & C
14.	Restoration of rain damages on Bhalei Matta Temple to village Saphan road K.M. 0/0 to 4/825 (SH: Removal of slips at various RD's)	95,747/-	2000/-	350/-	90 Days	D & C
15.	Restoration of rain damages on Kund to Siula road K.M. 0/0 to 6/255 (SH: Removal of slips at various RD.s)	98,880/-	2000/-	350/-	90 Days	D & C
16.	Restoration of rain damages on Bhalei to Dhar road K.M. 0/0 to 3/500 (SH: Hiring of JCB for removal of slips at various RD's)	99,493/-	2000/-	350/-	90 Days	D & C
17.	Restoration of rain damages on Chouga to Khal road K.M. 0/0 to 13/705 (SH: Removal of slips between R.D. 2/060 to 2/080, 3/120 to 3/340, 5/560 to 5/680 and 6/180 to 6/195)	99,214/-	2000/-	350/-	90 Days	D & C
18.	Restoration of rain damages on Lachori to Seri road K.M. 0/0 to 8/500 (SH: Removal of slips between R.D. 0/900 to 0/920, 3/030 to 3/050, 4/740 to 4/760, 5/700 to 5/720 and 7/840 to 7/855)	99,741/-	2000/-	350/-	90 Days	D & C
19.	Restoration of rain damages on Bathri Sundla Langer J & K boundary road K.M. 13/130 to 28/0 (SH: Removal of slips between R.D. 17/750 to 17/765, 18/640 to 18/660, 21/100 to 21/120, 22/340 to 22/360 and 23/260 to 23/280)	99,873/-	2000/-	350/-	90 Days	D & C
20.	Restoration of rain damages on link road to village Kuthed K.M. 0/0 to 6/0 (SH: Construction of PCC and Crate work Retaining wall at R.D. 1/270 to 1/272.50)	99,619/-	2000/-	350/-	90 Days	D & C
21.	Restoration of rain damages on Bathri Sundla Langer J & K boundary road K.M. 13/130 to 28/0 (SH: Removal of slips between R.D. 13/495 to 13/510, 14/230 to 14/250 and 15/525 to 15/535)	99,864/-	2000/-	350/-	90 Days	D & C

22.	Restoration of rain damages on Sundla Girjindoo road K.M. 0/0 to 36/500 (SH: Removal of slips at R.D. 11/030 to 11/100, 14/045 to 14/065 and 16/850 to 16/870)	99,873/-	2000/-	350/-	90 Days	D & C
23.	Restoration of rain damages on Bathri Sundla Langer J & K boundary road K.M. 57/0 to 93/400 (SH: Construction of PCC Retaining walls at R.D. 92/581 to 92/583)	99,767/-	2000/-	350/-	90 Days	D & C
24.	Restoration of rain damages on Hutta Ligga Ladwah road K.M. 0/0 to 36/500 (SH: Removal of slips at R.D. 0/285 to 0/330, 1/075 to 1/105 and 4/970 to 4/990)	99,829/-	2000/-	350/-	90 Days	D & C
25.	Restoration of rain damages on Kandhwara Bhadela road K.M. 0/0 to 4/100 (SH: Removal of slips at various RD's)	96,820/-	2000/-	350/-	90 Days	D & C
26.	Restoration of rain damages on Sundla Danoon Kund Patruma road K.M. 0/0 to 2/040 (SH: Removal of slips at R.D. 0/300 to 0/360, 0/840 to 0/860 and 1/510 to 1/540)	99,741/-	2000/-	350/-	90 Days	D & C
27.	Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Removal of slips at R.D. 0/980 to 1/0, 1/970 to 1/990, 2/240 to 2/260 and 5/300 to 5/330)	99,829/-	2000/-	350/-	90 Days	D & C
28.	Restoration of rain damages on link road to village Kuthed K.M. 0/0 to 6/0 (SH: Construction of PCC and Crate work Retaining wall at R.D. 1/275 to 1/277.50)	99,593/-	2000/-	350/-	90 Days	D & C
29.	Restoration of rain damages on Chouga to Khal road K.M. 0/0 to 13/705 (SH: Removal of slips between R.D. 7/820 to 7/855, 7/950 to 7/970, 9/040 to 9/070 and 11/710 to 11/740)	99,873/-	2000/-	350/-	90 Days	D & C
30.	Restoration of rain damages on Bhalei Matta Temple to village Saphan road K.M. 0/0 to 4/825 (SH: Removal of slips at R.D. 0/020 to 0/040, 1/645 to 1/665, 2/145 to 2/180 and 2/375 to 2/405)	99,829/-	2000/-	350/-	90 Days	D & C
31.	Restoration of rain damages on Bhalei to Dhar road K.M. 0/0 to 3/500 (SH: Removal of slips at R.D. 0/600 to 0/630, 0/800 to 0/830, 2/530 to 2/550 and 2/630 to 0/650)	99,653/-	2000/-	350/-	90 Days	D & C
32.	Restoration of rain damages on Chudhra to Thuien road K.M. 0/0 to 2/225 (SH: Construction of PCC Retaining walls at R.D. 1/763 to 1/765.50)	97,285/-	2000/-	350/-	90 Days	D & C
33.	Restoration of rain damages on Sundla Girjindoo road K.M. 0/0 to 36/500 (SH: Removal of slips at R.D. 26/830 to 26/870, 31/020 to 31/060 and 33/210 to 33/240)	99,860/-	2000/-	350/-	90 Days	D & C

34.	Restoration of rain damages on Chakoli Lader road K.M. 0/0 to 20/0 (SH: Removal of slips at various RD's)	99,910/-	2000/-	350/-	90 Days	D & C
35.	Restoration of rain damages on Hutta Ligga Ladwah road K.M. 0/0 to 36/500 (SH: Removal of slips at R.D. 0/620 to 0/650, 1/200 to 1/240 and 2/045 to 2/075)	99,785/-	2000/-	350/-	90 Days	D & C
36	Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Removal of slips at R.D. 8/330 to 8/360, 8/920 to 8/940 and 9/790 to 9/830)	99,565/-	2000/-	350/-	90 Days	D & C

TERMS AND CONDITIONS:-

1. The contractor should produce a copy of enlistment /renewal at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor /firm have his registration and GST No., the copy of same be attached with the application.
4. The earnest Money shall be deposited duly pledged in favour of Executive Engineer, Salooni Division HPPWD Salooni and cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. The contractor /firms are requested to insert the rate of each item in works as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reasons at any stage.


Executive Engineer,
Salooni Division
HPPWD Salooni.

No. PW/SD/GA/Contract/Tender/2025-2026- **3749-98**

Dated: - **6** /08/2025

Copy forwarded to:-

1. The F.C-Cum-Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information, please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (Kangra Zone) HPPWD Dharamshala.
4. The Superintending Engineer, 7th Circle HPPWD Dalhousie.
5. The Executive Engineer (IT Cell) office of Engineer-in-Chief HPPWD Shimla for uploading the NIT on the Departmental website.
6. All the Assistant Engineers under Salooni Division.
7. All the Contractor working under this division.
8. H.D.M./Supdt./Acctt. of this office.
9. Notice Board.


Executive Engineer,
Salooni Division
HPPWD Salooni.

OFFICE OF
EXECUTIVE ENGINEER, SALOONI DIVISION HPPWD SALOONI
HIMACHAL PRADESH, PUBLIC WORKS DEPARTMENT SALOONI
Phone No. 01899-233287 Email: ee-slo-hp@nic.in

CERTIFICATE

Certified that tender of works, as called vide this office
letter No./PW/SD/GA/Contract/tender/2025-2026-3749-98 Dated: 06/08/25 are emergent
natures in exigency of public interest.


Executive Engineer,
Salooni Division
HPPWD Salooni.

Schedule of Quantity

Name of work:- Restoration of rain damages on Kuthed to Kandhwara road K.M. 0/0 to 12/100 (SH: Removal of slips at various P.D.s)


Name of work:- Restoration of rain damages on Kuthed to Kandhwara road K.M. 0/0 to 12/100 (SH: Removal of slips at various P.D.s)					Estimated cost	99910.00
					Earnest money	2000.00
S. N.	Description of Item	Quantity	Rate	Unit	Time limit	90 days
1	Hiring of Excavator cum loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statification of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00		Per Hours		Amount
Total						


 Executive Engineer
 Saloomi Division
 HPPWD Saloomi

Schedule of Quantity

Name of work:- Restoration of rain damages on Bihali Bachuni Chamber Katara road K.M. 0/0 to 11/100 (SH: Removal of slips at R.D. 2/070 to 2/090, 2/210 to 2/250, 4/300 to 4/330)


Name of work:- Restoration of rain damages on Bihali Bachuni Chhambher Katara road K.M. 0/0 to 11/100 (SH: Removal of slips at R.D. 2/070 to 2/090, 2/210 to 2/250, 4/300 to 4/330)							Schedule or Quantity		Estimated cost		
S. N.		Description of item			Quantity	Rate	Unit	In Words	Amount	Time limit	
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.			1108.81		Per Cubic Metre				90 days	
Total										99793.00	2000.00


Executive Engineer
 Salooni Division
 HPPWD Salooni

Schedule of Quantity

Name of work:- Restoration of rain damages on Sundla Girjindoo road K.M. 0/0 to 36/500 (SH: Removal of slips at various RD.s)

S. N.	Description of Item	Quantity	Rate	Estimated cost	
				Earnest money	98380.00
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1093.11		Time limit	2000.00
				Unit	90 days
				Per Cubic Metre	
				In Words	
				Amount	
Total					


 Executive Engineer
 Salooni Division
 HPPWD Salooni

Schedule of Quantity


Name of work:- Restoration of rain damages on Bathni Sundia Langer 1 & K boundary road K.M. 57/0 to 93/400 (SH: Construction of PCC Retaining walls at R.D. 92/577 to 92/579)

Estimated cost
Earnest money
99907.00
2000.00

S. N.	Description of Item	Quantity	Rate	Unit	In Words	Time limit	
						90 days	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	8.66		Per Cubic Metre			
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	14.52		Per Cubic Metre			
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe (Finolex/ Vertex) with slope of 1 (v): 20(H) towards drainage face complete as per drawing and MORD technical specification section 700 and 1200 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-in-Charge. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	3.00		Each			
4	Backfilling behind retaining wall/breast wall complete as per drawing and technical specification clause 1204.3.8 in granular material within all leads and lift of material as per direction of Engineer-in-Charge and other incidentals. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	2.58		Per Cubic Metre			
Total							

Executive Engineer
Saloomi Division
HPWD Saloomi

Schedule of Quantity					
Name of work:- Restoration of rain damages on near Telka to Thaloga road K.M. 0/0 to 4/600 (SH: Removal of slips at various RD.s)					
S. N.	Description of Item	Quantity	Rate	Estimated cost	
				Earnest money Time limit	99829.00 2000.00 90 days
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1109.21		Per Cubic Metre	
Total					


 Executive Engineer
 Salooni Division
 HPPWD Salooni

Schedule of Quantity

Name of work:- Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Removal of slips at various RD's)


Estimated cost 99505.00
Earnest money 2000.00

S. N.	Description of Item	Quantity	Rate	Time limit		In Words	Amount
				Unit			
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1106.28		Per Cubic Metre			
Total							


Executive Engineer
Salooni Division
HPPWD Salooni

Schedule of Quantity


Name of work:- Restoration of rain damages on Bhalei Matta Temple to village Saphan road K.M. 0/0 to 4/825 (SH: Removal of slips at various RD's)					Estimated cost	99354.00
					Earnest money	2000.00
					Time limit	90 days
S. N.	Description of item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	1103.93		Per Cubic Metre		
Total						


 Executive Engineer
 Salooni Division
 HPPWD Salooni

Schedule of Quantity

Name of work:- Restoration of rain damages on Bathri Sundla Langera J & K boundary road K.M. 13/130 to 28/0 (SH: Removal of slips between R.D. 24/040 to 24/060, 24/920 to 24/940 24/200 to 25/285 and 26/210 to 26/230)


S. N.	Description of Item	Quantity	Rate	Estimated cost	
				Earnest money	99785.00
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1108.72		Per Cubic Metre	2000.00
Total					90 days


Executive Engineer
 Salooni Division
 HPPWD Salooni


Schedule of Quantity

Name of work:- Restoration of rain damages on Chakoli road to Dhalla K.M. 0/0 to 5/100 (5H: Removal of slips at various RD's)


S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount	Estimated cost
							Earnest money
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statification of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	93.00		Per Hours			95790.00
Total							2000.00
							90 days


 Executive Engineer
 Salooni Division
 HPPWD Salooni

Schedule of Quantity						
Name of work:- Restoration of rain damages on Kandi to Ached road K.M. 0/0 to 12/0 (SH: Removal of slips at R.D. 0/620 to 0/660, 1/840 to 1/880 and 2/150 to 2/180)						
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1110.28		Per Cubic Metre		
Total						


 Executive Engineer
 Salooni Division
 HPPWD Salooni

Schedule of Quantity						
Name of work:- Restoration of rain damages on Salooni Ghall road K.M. 0/0 to 7/500 (SH: Removal of slips at various RD's)						
S. N.	Description of Item	Quantity	Rate	Estimated cost		
				Earnest money	Time limit	Amount
1			Per Hours	In Words	90 days	
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statification of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	95.00				
Total						


 Executive Engineer
 Salooni Division
 HPPWD Salooni

Schedule of Quantity

Name of work:- Restoration of rain damages on link road Rolka to Halela K.M. 0/0 to 3/400 (SH: Construction of Retaining walls in wire crate at R.D. 0/270 to 0/277.50)

S. N.	Description of Item	Quantity	Rate	Estimated cost	
				Earnest money	95722.00
				Time limit	90 days
				Unit	Amount
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 and 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness blind age and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost in all cases. The rate is including royalty, Malkana, Tol tax, sale tax, GST or other taxes imposed by the Government.	16.65		Per Cubic Metre	
2	Providing and laying boulder apron laid in wire crate with 4mm dia G.I. wire confirming to IS 280 and IS 4826 in 100 mm x100mm (hundred millimeters into hundred millimeters) mesh(woven diagonally) including 10%for laps & joints laid with stone boulders weighing not less than 40kg (forty kilogram) each in toe walls as per drawing and MORD technical specifications clause 2503 and as per direction of the Engineer - in -Charge including carriage of materials within all leads and lifts and other incidental. The rate also includes octroi,royalty, maikana, toll tax sale tax or other taxes imposed by the Government.	31.20		Per Cubic Metre	
Total					



Executive Engineer
Salooni Division
HPPWD Salooni

Schedule of Quantity

Name of work:- Restoration of rain damages on Chudhra to Thuien road K.M. 0/0 to 2/225 (SH: Construction of PCC Retaining walls at R.D. 1/765.50 to 1/768)

S. N.

Description of item

Quantity

Rate

Estimated cost
Earnest money
96939.00
2000.00
90 days
Amount

Time limit

In Words

Amount

1 Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.

2 Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.


3 Backfilling behind retaining wall/breast wall complete as per drawing and technical specification clause 1204.3.8 in granular material within all leads and lift of material as per direction of Engineer-in-Charge and other incidentals. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.

4 Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe (Finolex/ Vertex) with slope of 1 (V): 20(H) towards drainage face complete as per drawing and MORD technical specification section 700 and 1200 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-in-Charge. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.

Total

Executive Engineer
Salooni Division
HPWD Salooni

Schedule of Quantity						
Name of work:- Restoration of rain damages on Bhalei Matta Temple to village Saphan road K.M. 0/0 to 4/825 (SH: Removal of slips at various RD's)						
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1063.85		Per Cubic Metre		
Total						


 Executive Engineer
 Salooni Division
 HPPWD Salooni

Estimated cost 95747.00

Earnest money 2000.00

Time limit 90 days


Schedule of Quantity						
Name of work:- Restoration of rain damages Kund to Siula road K.M. 0/0 to 6/255 (SH: Removal of slips at various RD.s)				Estimated cost	98880.00	
S. N.				Earnest money	2000.00	
Description of item				Time limit	90 days	
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statification of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	Quantity	Rate	Unit	In Words	Amount
		96.00		Per Hours		
Total						


 Executive Engineer
 Salooni Division
 HPPWD Salooni


Schedule of Quantity						
Name of work:- Restoration of rain damages on Bhalei to Dhar road K.M. 0/0 to 3/500 (SH: Hiring of JCB for removal of slips at various RD's)					Estimated cost	99493.00
S. N.					Earnest money	2000.00
Description of Item					Time limit	90 days
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	Quantity 1105.48	Rate	Unit Per Cubic Metre	In Words	Amount
Total						


 Executive Engineer
 Salooni Division
 HPPWD Salooni

Schedule of Quantity						
Name of work:- Restoration of rain damages on Chouga to Khal road K.M. 0/0 to 13/705 (SH: Removal of slips between R.D. 2/060 to 2/080, 3/120 to 3/340, 5/560 to 5/680 and 6/180 to 6/195)				Estimated cost	99214.00	
				Earnest money	2000.00	
				Time limit	90 days	
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1102.38		Per Cubic Metre		
Total						


 Executive Engineer
 Salooni Division
 HPPWD Salooni

Schedule of Quantity					
Name of work:- Restoration of rain damages on Lachori to Serl road K.M. 0/0 to 8/500 (SH: Removal of slips between R.D. 0/900 to 0/920, 3/030 to 3/050, 4/740 to 4/760, 5/700 to 5/720 and 7/840 to 7/855)					
S. N.	Description of Item	Quantity	Rate	Unit	Estimated cost Earnest money Time limit In Words Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1108.23		Per Cubic Metre	99741.00 2000.00 90 days
Total					


 Executive Engineer
 Salooni Division
 HPPWD Salooni

Schedule of Quantity

Name of work:- Restoration of rain damages on Bathri Sundia Langeri J & K boundary road K.M. 13/130 to 28/0 (SH: Removal of slips between R.D. 17/750 to 17/765, 18/640 to 18/660, 21/100 to 21/120, 22/340 to 22/360 and 23/260 to 23/280)


Estimated cost	99873.00
Earnest money	2000.00

S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1109.70		Per Cubic Metre		
Total						



Executive Engineer
Salooni Division
HPPWD Salooni

Schedule of Quantity
Name of work:- Restoration of rain damages on link road to village Kuthed K.M. 0/0 to 6/0 (SH: Construction of PCC and Crate work Retaining wall at R.D. 1/270 to 1/272.50)


S.N.		Description of Item		Time limit		Estimated cost	
		Quantity	Rate	Unit	In Words	Amount	99619.00
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer in-Charge including carriage of materials within all leads, lifts and other incidentals.	5.90		Per Cubic Metre			2000.00
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	9.18		Per Cubic Metre			
3	Providing and laying boulder apron laid in wire crate with 4mm dia G.I. wire conforming to IS 280 and IS 4825 in 100 mm x100mm (hundred millimeters into hundred millimeters) mesh(woven diagonally) including 10% for laps & joints laid with stone boulders weighing not less than 40kg (forty kilogram) each in toe walls as per drawing and MORD technical specifications clause 2503 and as per direction of the Engineer - in -Charge including carriage of materials within all leads and lifts and other incidentals. The rate also includes octroi, royalty, malkana, toll tax sale tax or other taxes imposed by the Government.	15.63		Per Cubic Metre			
4	Backfilling behind retaining wall/breast wall complete as per drawing and technical specification clause 1204.3.8 in granular material within all leads and lift of material as per direction of Engineer-in-Charge and other incidentals. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	4.20		Per Cubic Metre			
5	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe (Finolex/Vertex) with slope of 1 (V): 20(H) towards drainage face complete as per drawing and MORD technical specification section 700 and 1200 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidentals complete in all respect and as per the direction of Engineer-in-Charge. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	2.00		Each			
Total							


 Executive Engineer
 Salooni Division
 HPPWD Salooni

Schedule of Quantity						Estimated cost
Name of work:- Restoration of rain damages on Bathri Sundla Langera J & K boundary road K.M. 13/130 to 28/0 (SH: Removal of slips between R.D. 13/495 to 13/510, 14/230 to 14/250 and 15/525 to 15/535)						99864.00
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1109.60		Per Cubic Metre		
Total						


 Executive Engineer
 Salooni Division
 HPPWD Salooni

Schedule of Quantity					
Name of work:- Restoration of rain damages on Sundla Girjindoo road K.M. 0/0 to 36/500 (SH: Removal of slips at R.D. 11/030 to 11/100, 14/045 to 14/065 and 16/850 to 16/870)					
S. N.	Description of Item	Quantity	Rate	Unit	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1109.70		Per Cubic Metre	
Total					


 Executive Engineer
 Salooni Division
 HPPWD Salooni

Estimated cost 99873.00
 Earnest money 2000.00
 Time limit 90 days

Schedule of Quantity

Name of work:- Restoration of rain damages on Bathri Sundia Langera J & K boundary road K.M. 57/0 to 93/400 (SH: Construction of PCC Retaining walls at R.D. 92/581 to 92/583)

S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	8.54		Per Cubic Metre		
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like quantum of water including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	14.52		Per Cubic Metre		
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe (Finolex/ Vertex) with slope of 1 (v): 20(H) towards drainage face complete as per drawing and MORD technical specification section 700 and 1200 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-in-Charge. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government	4.00		Each		
4	Backfilling behind retaining wall/breast wall complete as per drawing and technical specification clause 1204.3.8 in granular material within all leads and lift of material as per direction of Engineer-in-Charge and other incidentals. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	2.58		Per Cubic Metre		
Total						

Estimated cost 99767.00


Earnest money 2000.00

Time limit 90 days


(Signature)

Executive Engineer
Salooni Division
HPPWD Salooni

Schedule of Quantity					
Name of work:- Restoration of rain damages on Hutta Ligga Ladwah road K.M. 0/0 to 36/500 (SH: Removal of slips at R.D. 0/285 to 0/330, 1/075 to 1/105 and 4/970 to 4/990)					
S. N.	Description of Item	Quantity	Rate	Unit	Estimated cost
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1109.21		Per Cubic Metre	99829.00
Total					2000.00


 Executive Engineer
 Salooni Division
 HPPWD Salooni

Schedule of Quantity					
Name of work:- Restoration of rain damages on Kandhwara Bhadela road K.M. 0/0 to 4/100 (SH: Removal of slips at various RD's)					
S. N.	Description of Item	Quantity	Rate	Estimated cost	
				Earnest money	95820.00
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statification of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute reosonsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	94.00		Time limit	2000.00
				Unit	90 days
				Per Hours	Amount
Total					


 Executive Engineer
 Salooni Division
 HPPWD Salooni

Schedule of Quantity					
Name of work:- Restoration of rain damages on Sundla Danoon Kund Patruma road K.M. 0/0 to 2/040 (SH: Removal of slips at R.D. 0/300 to 0/360, 0/840 to 0/860 and 1/510 to 1/540)					
S. N.	Description of Item	Quantity	Rate	Unit	Estimated cost Earnest money Time limit In Words Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1108.23		Per Cubic Metre	99741.00 2000.00 90 days
Total					


 Executive Engineer
 Salooni Division
 HPPWD Salooni

Schedule of Quantity						Estimated cost
Name of work:- Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Removal of slips at R.D. 0/980 to 1/0, 1/970 to 1/990, 2/240 to 2/260 and 5/300 to 5/330)						99829.00
S.N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1109.21		Per Cubic Metre		
Total						


 Executive Engineer
 Salooni Division
 HPPWD Salooni


Schedule of Quantity

Name of work:- Restoration of rain damages on link road to village Kuthed K.M. 0/0 to 6/0 (SH: Construction of PCC and Crate work Retaining wall at R.D. 1/275 to 1/277.50)

S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount	Estimated cost
							Earnest money
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other Incidentals.	5.85		Per Cubic Metre			99593.00
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days. In open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other Incidentals. The rate includes octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	9.18		Per Cubic Metre			
3	Providing and laying boulder apron laid in wire crate with 4mm dia G.I. wire confirming to IS 280 and IS 4826 in 100 mm x100mm (hundred millimeters into hundred millimeters) mesh(woven diagonally) including 10%for laps & joints laid with stone boulders weighing not less than 40kg (forty kilogram) each in toe walls as per drawing and MORD technical specifications clause 2503 and as per direction of the Engineer - in - Charge including carriage of materials within all leads and lifts and other incidental. The rate also includes octroi,royalty, malkana, toll tax sale tax or other taxes imposed by the Government.	15.63		Per Cubic Metre			
4	Backfilling behind retaining wall/breast wall complete as per drawing and technical specification clause 1204.3.8 in granular material within all leads and lift of material as per direction of Engineer-in-Charge and other Incidentals. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	4.20		Per Cubic Metre			
5	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe (Finolex/ Vertex) with slope of 1 (v): 20(H) towards drainage face complete as per drawing and MORD technical specification section 700 and 1200 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-in-Charge. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	2.00		Each			
Total							

Executive Engineer
Salooni Division
HPPWD Salooni


Schedule of Quantity					
Name of work:- Restoration of rain damages on Chouga to Khal road K.M. 0/0 to 13/705 (SH: Removal of slips between R.D. 7/820 to 7/855, 7/950 to 7/970, 9/040 to 9/070 and 11/710 to 11/740)					
S. N.	Description of Item	Quantity	Rate	Unit	Estimated cost Earnest money
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1109.70		Per Cubic Metre	99873.00 2000.00
Total					90 days Amount


 Executive Engineer
 Salooni Division
 HPPWD Salooni


Schedule of Quantity

Name of work:- Restoration of rain damages on Bhalei Matta Temple to village Saphan road K.M. 0/0 to 4/825 (SH: Removal of slips at R.D. 0/020 to 0/040, 1/645 to 1/665, 2/145 to 2/180 and 2/375 to 2/405)

S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount	Estimated cost
							Earnest money
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1109.21		Per Cubic Metre			99829.00
							2000.00
							90 days
	Total						



 Executive Engineer
 Salooni Division
 HPPWD Salooni

Schedule of Quantity						
Name of work:- Restoration of rain damages on Bhailei to Dhar road K.M. 0/0 to 3/500 (SH: Removal of slips at R.D. 0/600 to 0/630, 0/800 to 0/830, 2/530 to 2/550 and 2/630 to 0/650)						
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1107.25		Per Cubic Metre		
Total						



 Executive Engineer
 Salooni Division
 HPPWD Salooni

Schedule of Quantity
Name of work:- Restoration of rain damages on Chudhra to Thulen road K.M. 0/0 to 2/225 (SH: Construction of PCC Retaining walls at R.D. 1/763 to 1/765.50)


S. N.	Description of item	Quantity	Rate	Unit	In Words	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	8.65		Per Cubic Metre		97285.00
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	14.70		Per Cubic Metre		
3	Backfilling behind retaining wall/breast wall complete as per drawing and technical specification clause 1204.3.8 in granular material within all leads and lift of material as per direction of Engineer-in-Charge and other incidentals. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	2.88		Per Cubic Metre		
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe (Finolex/ Vertex) with slope of 1 (v): 20(H) towards drainage face complete as per drawing and MORD technical specification section 700 and 1200 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-in-Charge. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	6.00		Each		
Total						


 Executive Engineer
 Salooni Division
 HPPWD Salooni


Schedule of Quantity						Estimated cost	99860.00
Name of work:- Restoration of rain damages on Sundia Girjindoo road K.M. 0/0 to 36/500 (SH: Removal of slips at R.D. 26/830 to 26/870, 31/020 to 31/060 and 33/210 to 33/240)						Earnest money	2000.00
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Time limit	90 days
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1109.55		Per Cubic Metre			
Total							


 Executive Engineer
 Salooni Division
 HPPWD Salooni

Schedule of Quantity					
Name of work:- Restoration of rain damages on Chakoli Lader road K.M. 0/0 to 20/0 (SH: Removal of slips at various RD's)				Estimated cost	99910.00
S. N.	Description of Item	Quantity	Rate	Earnest money	2000.00
				Time limit	90 days
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all rxcavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statification of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00		Per Hours	Amount
Total					


 Executive Engineer
 Salooni Division
 HPPWD Salooni

Schedule of Quantity						Estimated cost	99785.00
Name of work:- Restoration of rain damages on Hutta Ligga Ladwah road K.M. 0/0 to 36/500 (SH: Removal of slips at R.D. 0/620 to 0/650, 1/200 to 1/240 and 2/045 to 2/075)						Earnest money	2000.00
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Time limit	90 days
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of stops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1108.72		Per Cubic Metre			
Total							


 Executive Engineer
 Salooni Division
 HPPWD Salooni

Schedule of Quantity					
Name of work:- Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Removal of slips at R.D. 8/330 to 8/360, 8/920 to 8/940 and 9/790 to 9/830)					
S. N.	Description of Item	Quantity	Rate	Unit	Estimated cost Earnest money
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1106.28		Per Cubic Metre	99565.00 2000.00
Total					90 days


 Executive Engineer
 Salooni Division
 HPPWD Salooni