

Himachal Pradesh
Public Works Department
HP.PWD Division Shahpur, Distt. Kangra (H.P)-176206
e-mail id: ee-shahpur-pwd@hp.gov.in
"NOTICE INVITING TENDERS"

Sealed percentage rate tenders on form 6 & 7/8 are hereby invited by the Executive Engineer, Shahpur Division HP.PWD Shahpur on behalf of Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under in H.P General Sales Tax Act 1968 so as to reach in his office on or before **14-08-2025 up to 11:00 AM.** and the same shall be opened on the same day at 11:30 AM. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on **12-08-2025 up to 5:00 P.M** and the application for issue of tender form shall be received on **11-08-2025 up to 2:00 PM**

The earnest money in the shape of NSC/FDR/Saving account of the Post office/ Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/incomplete tenders & tenders without earnest money will be summarily rejected. The offer of tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit	Cost of tender form
1.	Restoration of rain Damages on link road to village Lahari to Ward No.07km 0/00 to 0150 (S.H:- providing and laying Kharanja Soling	79,819/-	2,000/-	Two Months	350/-
2.	Restoration of rain damages on Various roads under Boh Section under HP.PWD Sub Division Darini . (S.H:-Hiring of Excavator cum loader for removal of slips).	99,000/-	2,000/-	one month	350/-
3.	Restoration of rain damages on Various roads under Rait Section under HP.PWD Sub Division Shahpur . (S.H:-Hiring of JCB/excavator cum loader for removal of slips).	99,000/-	2,000/-	one month	350/-
4.	Restoration of rain damages on Various roads under Darini Section under HP.PWD Sub Division Darini . (S.H:-Hiring of JCB/excavator cum loader for removal of slips.)	98,900/-	2,000/-	one month	350/-
5.	C/o Link road Grappa Mod Bagru Basnoor Sheetla Mata Purana Road Km 0/00 to 3/550 in Tehsil Shahpur, Distt. Kangra (HP).(S.H:-C/o U-Shape Drain at RD 3/163 to 3/185 & R/Wall at RD 3/163 to 3/171 .)	99,619/-	2,000/-	Two Months	350/-
6.	C/o Health Sub Center at Bhaled in sub Tehsil Darini Distt Kangra (H.P). (S.H- Providing and Fixing W.S& S.I and c/o Edge wall etc (Balance work)	94,556/-	1,900/-	Two Months	350/-
7.	Repair and restoration of Rain damages of various roads under Shahpur Sub-Division (S.H:-hiring of Rock Breaker under Harchakin section.	99,200/-	2,000/-	Two Months	350/-
8.	C/o Link road Grappa Mod Bagru Basnoor Sheetla Mata Purana Road Km 0/00 to 3/550 in Tehsil Shahpur, Distt. Kangra (HP).(S.H:-C/o U-Shape Drain at RD 3/140 to 3/160 & R/Wall at RD 3/140 to 3/148.20	98,542/-	2,000/-	Two Months	350/-
9.	Restoration of rain damages on Various roads under Boh Section under HP.PWD Sub Division Darini . (S.H:-Hiring of Excavator cum loader for removal of slips).	99,000/-	2000/-	one month	350/-
10.	Restoration of rain damages on Various roads under Rait Section under HP.PWD Sub Division Shahpur . (S.H:-Hiring of JCB/excavator cum loader for removal of slips).	99,000/-	2000/-	one month	350/-
11.	C/o Health Sub Center at Bhaled in sub Tehsil Darini Distt Kangra (H.P). (S.H- Providing and Fixing Cup Board,providing and laying Painting, W.S& S.I etc (Balance work)	92,461/-	2,000/-	Two Months	350/-
12.	C/o Shed at Dadbaru Ward No.3 in G.P Prai Tehsil Shahpuri Distt Kangra (H.P). (S.H- Providing and Laying painting and grill etc.)	65,120/-	1,310/-	Two Months	350/-
13.	Repair and restoration of Rain damages of various roads under Shahpur Sub-Division (S.H:-hiring of Rock Breaker on breaker on Shahpur chakban Lapiyana Road Km 0/000 to 20/00)	99,200/-	2,000/-	Two Months	350/-
14.	C/o Shed at Dadbaru Ward No.3 in G.P Prai Tehsil Shahpuri Distt Kangra (H.P)(Deposit work). (S.H- Providing and Laying Tile Flooring and Plaster work etc).	84,561/-	1,700/-	Two Months	350/-

15.	C/o Mini Secretariat Building at Shahpur Tehsil Shahpur Distt Kangra (H.P). (S.H- C/o U-Shape drain at RD.0/067 to 0/088).	98,803/-	2,000/-	Two Months	350/-
16.	Special Repair of Veterinary Hospital Gohju in Tehsil Shahpur at Distt. Kangra (H.P)(S.H:- C/o Piller for boundry wall)	93,061/-	1,900/-	Two Months	350/-
17.	Restoration of rain damages Shahpur Kiari Gandhrrop road Km 0/00 to 2/400 in Tehsil Shahpur Distt Kangra (H.P). (S.H:-C/o Breast wall at Km 1/712 to 1/718).	98,795/-	2000/-	Two Months	350/-
18.	Construction of community Bhawan at Ghad Mata Gram Panchayat Nerti (Deposit Work)(S.H:- construction of Ground Floor.(Balance Work)	98,513/-	2,000/-	Two Months	350/-
19.	C/o Mini Secretariat Building at Shahpur Tehsil Shahpur Distt Kangra (H.P). (S.H- C/o water tank and stand).	99,642/-	2,000/-	Two Months	350/-
20.	Construction of Link road link road Palwala to Lanjot in G.P Durgella Km 0/000 to 0/900 in Tehsil Shahpur Distt Kangra (H.P).(under S.C.S.P)(S.H:-Providing and Laying G-II &G-III at RD 0/480 to 0/543 .	99,100/-	2000/-	Two Months	350/-
21.	Construction of community Bhawan at Ghad Mata Gram Panchayat Nerti (Deposit Work)(S.H:- construction of Ground Floor.	99,483/-	2,000/-	Two Months	350/-
22.	C/o Mini Secretariat Building at Shahpur Tehsil Shahpur Distt Kangra (H.P). (S.H- C/o U-Shape drain at RD 0/089 to 0/114.60.	95,708/-	1,950/-	Two Months	350/-
23.	Construction of Link road link road Palwala to Lanjot in G.P Durgella Km 0/000 to 0/900 in Tehsil Shahpur Distt Kangra (H.P).(Under SCSP)(S.H:- Construction of V-Shape Drain at RD0/448 to 0/462 RHS.)	74,355/-	1,500/-	Two Months	350/-
24.	Construction of Link road link road Palwala to Lanjot in G.P Durgella Km 0/000 to 0/900 in Tehsil Shahpur Distt Kangra (H.P).(S.H:-Providing and Laying G-II & G-III at RD 0/545 to 0/608 (Under SCSP)	97,597/-	2,000/-	Two Months	350/-
25.	Construction of community Bhawan at Ghad Mata Gram Panchayat Nerti (Deposit Work)(S.H:- construction of Slab in first Floor.)	94,897/-	1,900/-	Two Months	350/-
26.	C/o Mini Secretariat Building at Shahpur Tehsil Shahpur Distt Kangra (H.P). (S.H- C/o Rain water surface of water tank).	99,678/-	2,000/-	Two Months	350/-
27.	Construction of Link road link road Palwala to Lanjot in G.P Durgella Km 0/000 to 0/900 in Tehsil Shahpur Distt Kangra (H.P).(Under SCSP)(S.H:- Construction of V-Shape Drain at RD 0/432 to 0/446 RHS.	75,240/-	1,550/-	Two Months	350/-
28.	Construction of Link road link NH 154 To Dhanotu via Bad Basti km 0/00 to 3/670 Distt Kangra (H.P). Under RIDF-XXX (NABARD)(S.H:-Providing Board and Painting and writing Lettering, Figures etcetra.	99,708/-	2,000/-	Two Months	350/-
29.	Restoration of Rain Damages on link road from Rajol To Dolla Bhatti km 0/000 to 3/000 (S.H:- Construction of Egde wall & Embankment between km 1/705 to 1/720 (Rajol side)	97,449/-	1,950/-	Two Months	350/-
30.	Digital Survey of Govt. College Rirkmar (S.H:- prepartion of Detailed Project report & Digital Survey)	75,000/-	1,500/-	One Months	350/-
31.	Consruction of Pargod to Kalru road KM 0/000 to 4/000 (Construction of Retaining Wall in wire crates at KM 2/090 to 2/096.35	98,625/-	2,000/-	Two Months	350/-
32.	Consruction of stairs of Akhada at Chhinj Mela Ground Manai (SDP/2022/371)(Deposit work)(S.H:- Construction of Stairs Steps (Balance Work)	98,995/-	2,000/-	Two Months	350/-
33.	Consruction of Pargod to Kalru road KM 0/000 to 4/000 (Construction of Retaining Wall in wire crates at KM 1/367 to 1/373.30	97,832/-	2,000/-	Two Months	350/-
34.	Consruction of stairs of Akhada at Chhinj Mela Ground Manai (SDP/2022/371)(Deposit work)(S.H:- Construction of Stairs Steps (Balance Work)	97,918/-	2,000/-	Two Months	350/-
35.	Special Repair of Veterinary Hospital Gohju in Tehsil Shahpur at Distt. Kangra (H.P)(S.H:- C/o Cow Shed	98,018/-	2,000/-	Two Months	350/-

36.	C/o Health Sub Center at Bhaled in sub Tehsil Darini Dist Kangra (H.P). (S.H:- Providing and Laying Painting and Distemping etc.) (Balance work)	99,214/-	1,900/-	Two Months	350/-
37.	C/O Chattri Pehad Road km 0/00 to 3/780 (S.H:- C/O B/Wall at Rd 3/610 to 3/615 and V-Shape Drain from RD 3/608 to 3/620 (portion Kholi Khad road km 3/000 to 3/780	90,692/-	2,000/-	Two Months	350/-
38.	C/O Link Road from NH-154 to Hiet College at Shahpur in Kharsa No.1 (Deposit work)(S.H:- P/L PCC 1:4:8 side locking in CC 1:2:4 and 80mm thick cement concrete interlocking paver blocks from 1/208 to 1/220.	89,305/-	1,800/-	Two Months	350/-
39.	A/R & M/O Various roads under Shahpur Sub Division HP.PWD Shahpur . (S.H:-Hiring of JCB/excavator cum loader for removal of slips under Rait Section).	99,000/-	2,000/-	Two Months	350/-
40.	A/R & M/O various roads under Draman Section under HPPWD Sub division Shahpur (S.h:- Hiring of JCB/ Excavator cum Loader for removal of slips)	99,000/-	2,000/-	Two Months	350/-
41.	Restoration of Rain Damages on Salli to kanol Road km 0/00 to 2/250 (S.H:- Providing and laying wearing at RD 0/300 to 0/478)	97,763/-	2,000/-	Two Months	350/-
42.	Restoration of rain damages on Various roads under Darini Section under HP.PWD Sub Division Darini . (S.H:-Hiring of JCB/excavator cum loader for removal of slips).	99,000/-	2,000/-	One month	350/-
43.	Landslide Disaster Realed Mitigation work on salli to Khari Behi Road km 0/00 to 9/570 (S.H:-C/O Edge Wall with pusta at Rd 4/208 to 4/215.20 and 3/190 to 3/193)	91,375/-	1,850/-	Two Months	350/-
44.	construction of Stairs at Chhinj Mela Batwala G.P.Manie (VKV/2022/2152) (Deposit work) (S.H:- Constrution of stairs steps)	98,950/-	2,000/-	Two Months	350/-
45.	Restoration of Rain Damages on Salli to kanol Road km 0/00 to 2/250 (S.H:- Providing and laying G-II at Various RDs	99,338/-	2,000/-	Two Months	350/-
46.	A/R & M/O link road Salli to lahari Road km 0/00 to 1/750 (S.H:- Providing and laying G-II at RD 1/545 to 1/680 (under MMSRRY)	99,225/-	2,000/-	Two Months	350/-
47.	Contingencies against Various Deposit head under shahpur Division (Providing and installation of HP desktop,Printer and UPS in HPPWD Sub Division office Shahpur.)	99,757/-	2,000/-	one month	350/-
48.	Stock Storage under HPPWD Sub Division Gaggal (providing and Laying Brick Work above Plinth)	98,841/-	2,000/-	Two Months	350/-
49.	Stock Storage under HPPWD Sub Division Gaggal (S.H:- Construction of foundation for Gate)	99,817/-	2,000/-	Two Months	350/-
50.	C/O Link Road from NH-154 to Hiet College at Shahpur in Kharsa No.1 (Deposit work)(S.H:- P/L PCC 1:4:8 side locking in CC 1:2:4 and 80mm thick cement concrete interlocking paver blocks from 1/194 to 1/206	88,539/-	1,800/-	Two Months	350/-
51.	A/R & M/O link road Salli to lahari Road km 0/00 to 1/750 (S.H:- Providing and laying G-II at RD 1/400 to 1/540 (under MMSRRY)	99,225/-	2,000/-	Two Months	350/-
52.	C/O Link Road from NH-154 to Hiet College at Shahpur in Kharsa No.1 (Deposit work)(S.H:- P/L PCC 1:4:8 side locking in CC 1:2:4 and 80mm thick cement concrete interlocking paver blocks from 1/150 to 1/162.50)	89,634/-	1,800/-	Two Months	350/-
53.	C/O Link Road from NH-154 to Hiet College at Shahpur in Kharsa No.1 (Deposit work)(S.H:- P/L PCC 1:4:8 side locking in CC 1:2:4 and 80mm thick cement concrete interlocking paver blocks from 1/165 to 1/177.50)	90,254/-	1,950/-	Two Months	350/-
54.	Restoration of Rain Damages on Various Roads under Boh section (S.H:- Hiring of Poclain for removal of slips)	99,200/-	2,000/-	One month	350/-
55.	Restoration of Rain Damages on Various Roads under Boh section (S.H:- Hiring of Poclain for removal of slips)	99,200/-	2,000/-	One month	350/-
56.	C/o Jeepable road form main road Ranjeet Singh House to Chuni Lal House ward No-03 Uperla Dibbar (VKV2024/957) Deposit Work) (SH:- C.C. Pavement at KM 0/126 to 0/150)	73,236/-	1,500/-	Two months	350/-

57.	C/o Jeepable road from main road Ranjeet Singh House to Chuni Lal House ward No-03 Uperla Dibbar (VKV2024/957) Deposit Work) (SH:- C.C. Pavement at KM 0/100 to 0/125)	73,207/-	1,500/-	Two months	350/-
58.	C/o Pucca Path alongwith Protection wall near the House of Sh. Bhisham Singh S/o Bhuri Singh, Ward No-2 G.P Mundla (under Head- VKVNY(MLALAD) (Deposit Work) (SH:- Protection wall)	98,407/-	2,000/-	Two months	350/-
59.	C/o Pucca Path alongwith Protection wall near the House of Sh. Bhisham Singh S/o Bhuri Singh, Ward No-2 G.P Mundla (under Head- VKVNY(MLALAD) (Deposit Work) (SH:- Protection wall and Providing and fixing M.S. Grating)	93,168/-	1,900/-	Two months	350/-
60.	A/R & M/O Rulehar to Lam road km 0/000 to 4/000 in Tehsil Shahpur Distt. Kangra (HP) (SH:- Hiring of JCB/excavator cum loader at Rd on 00/00 to 4/00)	99,000/-	2,000/-	Two months	350/-
61.	C/o link road from NH-154 to Hiet College at Shahpur in Khasra No.1 (Deposit work) (SH:- P/L PCC 1:4:8 side locking in CC 1:2:4 and 80 MM thick cement concrete interlocking paver blocks from Km 1/180 to 1/192.40)	89,501/-	1,800/-	Two months	350/-
62.	C/o 35.00 Metre span Bridge Over Banoi Khad at Km 0/300 on link road Ruhru to Narghota km 0/00 to 1/500 (SH:- Investigation of Soil Bearing Capacity of Bridge) Abutment-I	97,500/-	2,000/-	One Month	350/-
63.	C/o 35.00 Metre span Bridge Over Banoi Khad at Km 0/300 on link road Ruhru to Narghota km 0/00 to 1/500 (SH:- Investigation of Soil Bearing Capacity of Bridge) Abutment-II	97,500/-	2,000/-	One Month	350/-
64.	Annual repair and Maintenance of various roads under HP.PWD Sub Division Shahpur. (SH:- Painting and Writing lettering, figures and kilometre stone ectra under Harchakin section)	99,273/-	2000/-	Two Months	350/-

Certified that tender of above works are being called of urgent nature in public interest.

Terms & Conditions: -

1. The contractor/firm should be produce the attested copy of latest enlistment and renewal enlistment in HP.PWD. GST No. and EPF No. with the application falling which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The Contractor/Firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.


Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

(on behalf of Governor of Himachal Pradesh)

Dated: 05-08-2025

No.PWD/SD/Tender/NIT/2025-26/- **2325- 33**

Copy to following for information and necessary action:-

1. The Superintending Engineer, 5th Circle HPPWD Palampur.
2. The Executive Engineer (IT), Nigam Vihar Shimla. He is requested to upload the same on the department website.
3. All the Assistant Engineer under this Division.
4. The Drawing/Accounts Branch in this office.
5. N.I.T Register.
6. Notice Board


Executive Engineer,
Shahpur Division,
HPPWD Shahpur.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 79819.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Restoration of rain damages on link road to Village lahari to ward No-07 Km 0/0 to 0/150.

SUB-HEAD :- Providing and laying Kharanja stone soling.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm (twenty two decimal five centimetre) depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earthwith lead upto 50 metres. as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other Incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	412.50 square metres	12.40	Rupees Twelve And Paise Forty Only	Per square metre	5115.00
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) as per drawing and technical specification. as per direction of Engineer-in-Charge including carriage of materials within all leads , lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax or any type of taxes imposed by the Government.	64.96 Cubic metres	1150.00	Rupees One Thousand One Hundred Fifty Only	Per cubic metre	74704.00
TOTAL :-						79819.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

(2) 228

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99000.00
EARNEST MONEY: - ₹ 1000.00
TIME LIMIT: - One Month

NAME OF Restoration of Rain damages on various roads under Boh Section under HP.PWD Darini Sub- Division.

SUB-HEAD :- Hiring of Excavator cum loader for removal of silps.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Hiring of Excavator cum loader required for removal of silps, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks etc, completely as per instructions of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99000.00
TOTAL :-						99000.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HP.PWD Shahpur

237 → (3)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99000.00
EARNEST MONEY: - ₹ 2000.00
TIME LIMIT : One Month

NAME OF Restoration of Rain damages on various roads under Rait Section under HP.PWD Shahpur Sub- Division.

SUB-HEAD :- Hiring of Excavator cum loader for removal of slips.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Hiring of Excavator cum loader required for removal of slips, clearing road such opening of drains and catchpits etc. In all kind of earths, boulder, rocks work done etc. completely as per inspection of engineer-in-charge and minimum 25 (Twenty-five) cubic per hours output for slips / removal activates. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees One Thousand one hundred only	Per Hour	99000.00
TOTAL :-						99000.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur


SCHEDULE OF QUANTITY

Estimated cost:- Rs. 98900.00
Earnest Money:- Rs.2000.00
Time Allowed:- One Month

Name of Work:- Restoration of Rain Damages On various Roads under Darini Section under Darini Sub-Division.
Sub Head:- Hiring of Excavator cum loader for removal of slips.

Sr. No.	Sub-Head/ Items of Work.	Quantity	Rates		Unit	Amount
			In Figures	In Words		
1.	Hiring of Excavator cum loader for improvement of profile correction of road in various reaches up to any height and lead including trimming to required line,width and grade in all kind and classification of soil including rocky portion and saturated soil as per and saturated soil as per direction and entire specification of Engineer-in-charge.The direction JCB/Excavator cum loader should work minimum 8 hours from 9.00 to 5.00 daily and excavate at least 30 cum Qty per hour.A ny loss to the public property or accident etc.happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases.The fuel and operational staff for excavator will be provided by the owner.The repair and spare watch and ward of excavator also born by rhe contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge.	86.00	1150.00	(Rupees one Thousand One Hundred Fifty only)	Per Hour	98900.00
					Total:-	98900.00
	Quated Rate in Figure (%)		Amount to be Quoted by contractor in Figure			
	Quated Rate in Words (%)		Amount to be Quoted by contractor in Words			


Assistant Engineer
H.P.P.W.D.
Sub-Division Darini


Executive Engineer
Shahpur Division,
H.P.P.W.D. Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99619.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- C/o Link road Grappa Mod Bagru Basnoor Sheetla Mata Purana Road KM 0/00 to 3/550 in Tehsil Shahpur Distt Kangra (H.P).

SUB-HEAD :- C/o U-Shape Drain at RD 3/163 to 3/185 & R/wall at RD 3/163 to 3/171.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drain and Parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 and as per direction of the Engineer- In - Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and lift including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layer not executing 150 mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth any quantam of water including cleaning of slush which may arise out during dewatering complete as per direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	13.17	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	4610.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall ectera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.94	5250.00	Rupees Five Thousand Two Hundred Fifty Only	Per cubic metre	31185.00

3	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty milimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other Incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	13.92	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per cubic metre	59160.00
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other Incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	4.00	350.00	Rupees Three Hundred Fifty Only	Each	1400.00
5	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other Incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	3.84	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	3264.00
TOTAL :-						99619.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

13-1
Executive Engineer,
Sahapur Division,
H.P.W.D. Sahapur

SCHEDULE OF QUANTITY


ESTIMATED COST :- ₹ 94556.00
EARNEST MONEY :- ₹ 1900.00
TIME LIMIT : Two Months

NAME OF WORK :- Construction of Health sub center at Bhaled in Sub Tehsil Darini at in Distt. Kangra Himachal Pradesh.
SUB-HEAD :- Providing and fixing W.S&S.I and C/o Edge wall etc.(Balance work).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and fixing 10.00 (Ten) litres capacity P.V.C low level dual flushing cistern (Sleek plus) of Cera/Hindware/Jaguar/ Hindustan with a pair of G.I or mild steel brackets complete with fittings such as including PVC syphonic apparatus, mosquito proof lid of PVC union and coupling for connection with inlet, outlet and over flow pipe including cutting holes and making good the same and connection the flush baard with cistern and closet (over-flow pipe to be measured and paid for separately) including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In- Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	3.00	1050.00	Rupees One Thousand Fifty Only	Each	3150.00
2	Providing and fixing vitreous china wash basin Garnet No 10072 and size 58x43 cm (fifty eight into forty three centimeters) of Hindware/Cera/Jaguar of of white/ snow white with double hole for pillar trap with C.I. or M.S. brackets painted white including cutting holes in walls and making good the same including all fitting complete in all respect including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2.00	2350.00	Rupees Two Thousand Three Hundred Fifty Only	Each	4700.00
3	Providing and fixing stainless steel A ISI 304 (18/8) kitchen sink size 510 x1040 mm (Five hundred ten into One Thousand forty millimetre) with bowl depth 250 mm (two hundred fifty millimetre) of AMC unik / diamond approved standard ISI make with drain board and C.P, waste with C.I. or M.S. Brackets painted including cutting holes and making good the same but excluding fitting within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00	4850.00	Rupees Four Thousand Eight Hundred Fifty Only	Each	4850.00
4	Providing and fixing 32 mm (thirty two millimetre) C.P. Brass Waste pipe for wash basin or sink including brass check net with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	6.00	350.00	Rupees Three Hundred Fifty Only	Each	2100.00
5	Providing and fixing 32 mm (thirty two millimetre) PVC Waste pipe for wash basin or sink including brass check net with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	6.00	100.00	Rupees One Hundred Only	Each	600.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
6	Providing and fixing 600mmx450mm (six hundred millimetre into four hundred fifty millimetre) beveled edge mirror of superior glass 6mm (six millimetre) thick of Modiguard/ Alul/ Golden Fish mounted on 6mm (six millimetre) thick A.C. Sheet or plywood sheet and fixed to wooden plugs with C.P. screws and washers including entire carriage of material within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	3.00	750.00	Rupees Seven Hundred Fifty Only	Each	2250.00
7	Providing and fixing C.P. brass towel rail size 750x20mm (Seven hundred fifty into twenty millimetre) of continental series of Jaguar/Classic of Hindware/ floral series of Cera/Hindon series of Jal with C.P. brass brackets fixed to wooden plugs with C.P. brass screws including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing as per as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	3.00	300.00	Rupees Three Hundred Only	Each	900.00
8	Providing and fixing chromium plated brass soap dish of continental series of Jaguar/ Classic series of Hindware/ Floral series of Cera/ Hindon series of Jal/ ESS with C.P. brass brackets fixed with cleats C.P. brass screws including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	6.00	105.00	Rupees One Hundred Five Only	Each	630.00
9	Providing and fixing concealed C.P. brass stop cock of continental series of Jaguar/ Classic series of Hindware/ Floral series of Cera/ Hindon series of Jal (heavy duty makes ISI marked) 15mm (Fifteen millimetre) as per specifications including entire carriage of material within all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	10.00	850.00	Rupees Eight Hundred Fifty Only	Each	8500.00
10	Providing and fixing C.P. brass pillar tap of Continental/Classic/ Floral series of Jagware/Hindware/Cera 15mm (fifteen millimetre) dia (Heavy duty makes ISI marked No. 8931 & 8934) as per specifications including entire carriage of material within all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	3.00	950.00	Rupees Nine Hundred Fifty Only	Each	2850.00
11	Providing and fixing 15mm (fifteen millimetre) C.P. Brass Angle valve of Continental Series of Jaguar contess plus series /Hindware / Ocean series of Nintage series of Kerovite/ hindon series of Jal/ Cera/ Jal as per specifications with nuts & bolts including carriage of material within all leads, lifts, and other incidentals. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	6.00	950.00	Rupees Nine Hundred Fifty Only	Each	5700.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
12	Providing and fixing PVC connection pipe brass union 450 mm length 15mm dia ISI marked of Including fitting within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	6.00	160.00	Rupees One Hundred Sixty Only	Each	960.00
13	Providing and placing water tank of PVC (Poly vinyl chloride) Sintex/Supreme/Finolex (Triple layer) ISI marked having capacity 1000 (One thousand) litres each with necessary fitting including over flow pipes, scour pipe, ball valve and with cover locking arrangement of good quality including providing pads of sizes as required good quality all complete as per specifications including entire carriage of material within all leads, lifts and other incidentals. as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	1.00	9500.00	Rupees Nine Thousand Five Hundred Only	Each	9500.00
14	Excavation in drains and channels etcetra in earth work in all classification of soil, such as pick work, jumper work, pick jumper work, blasting work, hard and soft blasting, saturated soil including chiseling or any other mixed variety of soil, lift upto any heights, stacking the excavated soil for all heights from the edge of excavation and then returning the stacked soil in 15cm (Fifteen centimeter) layer when required into plinths sides of foundations etcetra Consolidating each deposited layer by ramming, watering and then disposing of all surplus excavated earth as directed by the Engineer- Incharge, within all leads, lifts of material and other incidentals. Rate is inclusive of royalty, malkana, toll tax, GST and any other taxes imposed by the government.	5.93	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2076.00
15	Providing and laying cement concrete 1:4:8 (One Cement isto Four Sand isto eight) graded stone aggregate 40mm (Forty millimetre) nominal size for haunching of pipes of the 150 mm (One hundred fifty millimetre) internal diameters, necessary form work and curing complete within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government..	9.64	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	45790.00
TOTAL :-						94556.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99200.00
 EARNEST MONEY: - ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Repair and Restoration of various roads under Shahpur Sub-Division.

SUB-HEAD :- Hiring of rock breaker under Harchakin Section.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Hiring of Rock Breaker having 2 to 4 tonne hammer capacity for removal of boulder slips, rock cutting for drains, removal of boulders from catchpits, opening of blocked drains due to boulder etc. and other similar road works requiring breaking of rock and boulders on road in various reached up to any height, depth and disposal of material up to 20.00 meters lead in all kind and classification of soil including rocky portion as per direction and entire satisfactions of Engineer-in-charge. The rock Breaker should work minimum 8.00 hours daily. Any loss to the property or any accident etc. happened during the course of hiring period /execution of work, shall be the absolute responsibility of the Rock Breaker owner which shall have to be provided by the owner. The repair, spare and watch and ward of Rock Breaker will also be born by the Contractor/Owner. The daily log book will be maintained at site which should be duly certified by the Engineer -in -charge . The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	32.00	3100.00	#NAME?	Per Hour	99200.00
TOTAL :-						99200.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98542.00
 EARNEST MONEY: - ₹ 2000.00
 TIME LIMIT: - Two Months

NAME OF WORK :- C/o Link road Grappa Mod Bagru Basnoor Sheetla Mata Purana Road KM 0/00 to 3/550 in Tehsil Shahpur Distt Kangra (H.P).

SUB-HEAD :- C/o U-Shape Drain at RD 3/140 to 3/160 & R/wall at RD 3/140 to 3/148.20.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drain and Parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 and as per direction of the Engineer- In – Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and lift including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layer not exceeding 150 mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth any quantam of water including cleaning of slush which may arise out during dewatering complete as per direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	12.70	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	4445.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall ectetra as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.40	5250.00	Rupees Five Thousand Two Hundred Fifty Only	Per cubic metre	28350.00

3	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	14.27	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per cubic metre	60648.00
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	5.00	350.00	Rupees Three Hundred Fifty Only	Each	1750.00
5	Back filling with granular material behind abutments, wing walls, return walls and retaning walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	3.94	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	3349.00
TOTAL :-						98542.00
Quoted Rate in Figure (%)			(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)			(Amount to be quoted by the contractor in words)			


 Executive Engineer,
 Shahpur Division,
 H.P. WD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99000.00
 EARNEST MONEY: - ₹ ~~2600.00~~
 TIME LIMIT: - One Month

NAME OF Restoration of Rain damages on various roads under Boh Section under HP.PWD Darini Sub- Division.

SUB-HEAD :- Hiring of Excavator cum loader for removal of slips.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks etc, completely as per instructions of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer in-Charge. The rate is inclusive of octrol, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99000.00
TOTAL :-						99000.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99000.00
 EARNEST MONEY: - ₹ 2000.00
 TIME LIMIT: One Month

NAME OF Restoration of Rain damages on various roads under Rait Section under HP.PWD Shahpur Sub- Division.

SUB-HEAD :- Hiring of Excavator cum loader for removal of slips.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Hiring of Excavator cum loader required for removal of slips, clearing road such opening of drains and catchpits etc. In all kind of earths, boulder, rocks work done etc. completely as per inspection of engineer-in-charge and minimum 25 (Twenty-five) cubic per hours output for slips / removal activates. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees One Thousand one hundred only	Per Hour	99000.00
TOTAL :-						99000.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

137
 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 92481.00
 EARNEST MONEY: - ₹ 1000.00
 TIME LIMIT: Two Months

NAME OF WORK :- Construction of Health sub center at Bhaled in Sub Tehsil Darini at In Distt: Kangra Himachal Pradesh.

SUB-HEAD :- Providing and fixing Cub board, Providing and laying Painting ,and W.S & S.I etc.(Balance work).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and fixing Fly wood lining with but jointing and nails(frame work and cove fillwts to bbe measured and paid for separately 6 mm (six millimetre) within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge.Rate inclusive toll tax, GST and any other taxes imposed by the government.	14.19	70.00	Rupees Seventy Only	Per square metre	993.00
2	Providing and fixing coloured anodized aluminum tower bolts (barrel type) anodized transparent or dyed to required shade and colour with screws etcetra complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In- Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government. (250x10mm (Two hundred fifty into ten millimetre) size).	34.00	75.50	Rupees Seventy Five And Paise Fifty Only	Each	2567.00
3	Providing and fixing coloured / anodized aluminum handle anodized transparent or dyed to required shade or colour with necessary screws etcetera complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.(100mm (one hundred millimetre) size)	34.00	65.00	Rupees Sixty Five Only	Each	2210.00
4	Providing and fixing coloured / anodized aluminum sliding door bolt, anodized transparent or dyed to required colour and shade with bolts and nuts, screws etcetra complete. The rate is inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.Rate is inclusive of toll tax, GST and any other taxes imposed by the government.(250x16mm (two hundred fifty into sixteen millimeter) size)	17.00	80.00	Rupees Eighty Only	Each	1360.00
5	Providing and fixing 100mm (One hundred millimetre) bright finished brass floor door stopper with rubber cushion screws etcetra to suit shutter thickness complete including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	17.00	70.00	Rupees Seventy Only	Each	1190.00
6	Providing and fixing oxidized M.S.spring hinges with necessary screws etcetra including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	4.00	150.00	Rupees One Hundred Fifty Only	Each	600.00

No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
7	Providing and fixing 25mm (Twelve millimetre) diameter stainless steel curtain rod and brackets plugs etcetra complete including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	24.65	550.00	Rupees Five Hundred Fifty Only	Per running metre	13558.00
8	Providing and fixing on wall face 100mm (One hundred millimetres) diametres P.V.C. rain water pipes of working pressure 4.6kg (four / six kilogramme) per square centimetre of finolex / Reliance / vectus/ prince pipe for rain water pipe fixed with approved adhesive including filling the joints complete within all leads, lifts of materials and other incidentals, and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	19.50	325.00	Rupees Three Hundred Twenty Five Only	Per running metre	6338.00
9	Providing and fixing on wall face 100 mm (One hundred millimetre) diametre plain bend Providing and fixing on wall face PVC (D-plast) accessories for rain water pipes of Supreme/Finolex/Prince /Relpipe (reliance)/ vectus including filling the joints with approved adhesive complete as per PWD specification, approved drawing and design including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer- in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	9.00	150.00	Rupees One Hundred Fifty Only	Each	1350.00
10	Providing and fixing M.S. channels in doors, windows clerestory windows frames manufactured from M.S. channel section 75x40x4mm (Seventy five into Forty into four millimetre) with M.S. flat 75x4mm (Seventy Five into Four millimetre) combination as per specifications design, drawing including hinges, jambs, beads if required threshold of M.S. angles 50x25mm (Fifty into Twenty five millimetre) welded or rigidly fixed by mechanical means lugs, with split ends tails to each jambs including steel butts hinges 2.5mm (Two decimal five millimetre) thick with a provision of locking arrangements, shock observers as specified and applying a coat of approved steel primer after pretreatment of the surfaces as directed by the Engineer-in-Charge. The rate is inclusive for carriage of material with in all leads, lifts and other incidentals including sale tax, toll tax, GST or all type of other taxes imposed by the Government.	102.42	107.00	Rupees One Hundred Seven Only	Per Killogram	10959.00
11	Applying priming costs) on new steel and other metal surfaces with enamel paint of Asian/ Nerolac to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	94.65	45.00	Rupees Forty Five Only	Per square metre	4259.00
12	Painting two coats(excluding priming costs) on new steel and other metal surfaces with enamel paint of Asian/ Nerolac to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	94.65	75.00	Rupees Seventy Five Only	Per square metre	7099.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
13	Applying priming costs) on new wood and other wood surfaces with enamel paint of Asian/ Nerolac to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	68.61	50.00	Rupees Fifty Only	Per square metre	3431.00
14	Painting two coats(excluding priming costs) on new wood and other wood surfaces with enamel paint of Asian/ Nerolac to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	68.61	85.00	Rupees Eighty Five Only	Per square metre	5832.00
15	Providing under layer for plinth protection of 75 mm (seventy-five millimetre) thick (unconsolidated)bed dry brick/stone aggregated 40 mm (forty millimetre) nominal size with rammed and consolidated and grouted with fine sand including preparation of ground complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	19.99	250.00	Rupees Two Hundred Fifty Only	Per square metre	4998.00
16	Providing plinth protection 50mm (fifty millimetre) thick in cement concrete 1:3:6 (1 cement: 3 sand: 6 Graded) stone aggregated 20 mm (twenty millimetre) nominal size complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	19.99	350.00	Rupees Three Hundred Fifty Only	Per square metre	6997.00
17	Providing and fixing orisa Pan No 20090 of size 53x41 cm (fifty three into forty one centimeter) vitreous china water closet squatting pan (Indian Type W.C. Pan) of Cera/hindware/ Jaguar of star white/ snow white shade with low level PVC cistern (earth work, bed concrete, foot rest PVC cistern and trap to be measured and paid for separately) including entire carriage of material within all leads, lifts and other incidentals as per direction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	1.00	1850.00	Rupees One Thousand Eight Hundred Fifty Only	Each	1850.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
18	Providing and fixing vitreous China wash down water closet (European type W.C. pan) of Constellation No. S No. 20087(S-10) size 57x35x39cm (Fifty seven into thirty five into thirty nine centimetre) with PVC Cistern (Sleek plus) and fixed with jet pressure of Hindware /Cera/ Jaquar of star white / snow white shade with intergal P or S trap including jointing the trap with soil pipe in cement mortar 1:1 (One cement isto one sand) (seat cover and jet spray to be measured and paid for separately) and further as per Architectural drawing ,design and specifications including entire carriage of material within all leads, lifts and other incidentals as per direction of Engineer-In-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	2.00	4050.00	Rupees Four Thousand Fifty Only	Each	8100.00
19	Providing and fixing plastic seal (solid) and cover of Hindware/ Jaguar/ Cera for wash down water closet with C.P. brass hinges ad rubber buffers (solid type) while plastic seal and cover complete within all leads. lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	2.00	650.00	Rupees Six Hundred Fifty Only	Each	1300.00
20	Providing and fixing 100mm (One hundred millimetres) nominal size diameter CP grating of ESS/JAL/Kingston for nahni trap of approved shade complete, within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government	6.00	95.00	Rupees Ninety Five Only	Each	570.00
21	Providing and fixing 100mm (One hundred millimetre) size 'P' or 'S' trap for water closet (squatting pan) including jointing the trap with the pan and soil pipe in cement mortar 1:1 (one cement isto one sand) including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	1.00	150.00	Rupees One Hundred Fifty Only	Each	150.00
22	Providing and fixing vitreous China wash basin 55x40cm (Fifty five into forty centimetre) Delta No.10010 of HINDWARE/CERA/JAQUAR of star white/ snow white shade with single hole for pillar tap with C.I. or M.S. brackets painted white including cutting holes and making good the same but excluding fittings complete including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	3.00	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Each	6750.00
TOTAL :-						92461.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

135
Executive Engineer,
Shahpur Division,
HPRWD Shahpur

SCHEDULE OF QUANTITY

72


ESTIMATED COST :- ₹ 65120.00
EARNEST MONEY :- ₹ 1310.00
TIME LIMIT :- One Month

NAME OF WORK :- C/o Shed at Dadbaru ward No.3 in G.P. Prai Tehsil Shahpur Distt Kangra (H.P). (Deposit Work)

SUB-HEAD :- Providing and laying painting and grill etc.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint in beams, joists, channels, angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like, complete as per specification, approved drawing, design, as per the entire satisfaction and direction of the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	450.06	105.00	Rupees One Hundred Five Only	Per Kilogram	47256.00
2	Finishing walls with Apex weather proof exterior emulsion paint of Asian / Dulux / Berger / Nerolac Suraksha paints of approved shade having VOC less than 50 gm/litre (Fifty gram per litre) and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @ 1.43 litre/ 10 sqm (One point forty three litre per ten square metre) Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm (Zero point Nine zero litre per ten square metre) complete as per Architectural drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	70.13	85.00	Rupees Eighty Five Only	Per Square metre	5961.00
3	Painting two or more coats (excluding priming coat) on new steel and other metal surfaces with enamel paint brushing of Asian paint/ Nerolac/Berger of approved shade to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matter enamel paint other than white within all leads, lifts of materials and other incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	38.44	62.50	Rupees Sixty Two And Paise Fifty Only	Per Square metre	2403.00

4	Providing and placing water tank make P.V.C. SINTEX three layer having capacity of 500 (Five hundred) liters each tank with necessary fittings including over flow pipe scour pipe etcetera and pads required for in let and out let ball valve with cover and locking arrangements complete in all respect within all leads, lifts of materials and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.00	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Each	9500.00
TOTAL :-						65120.00
Quoted Rate in Figure (%)			(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)			(Amount to be quoted by the contractor in words)			


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

13

262

ESTIMATED COST :- ₹ 99200.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- Two Months

NAME OF WORK :- Repair and Restoration of various roads under Shahpur Sub -Division.
SUB-HEAD :- Hiring of rock breaker on Shahpur Chakban Lapiyana Road KM 0/00 to 20/00.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Hiring of Rock Breaker having 2 to 4 tonne hammer capacity for removal of boulder slips, rock cutting for drains, removal of boulders from catchpits, opening of blocked drains due to boulder etc. and other similar road works requiring breaking of rock and boulders on road in various reached up to any height, depth and disposal of material up to 20.00 meters lead in all kind and classification of soil including rocky portion as per direction and entire satisfactions of Engineer-in-charge. The rock Breaker should work minimum 8.00 hours daily. Any loss to the property or any accident etc. happened during the course of hiring period /execution of work, shall be the absolute responsibility of the Rock Breaker owner which shall have to be provided by the owner. The repair, spare and watch and ward of Rock Breaker will also be born by the Contractor/Owner. The daily log book will be maintained at site which should be duly certified by the Engineer -in -charge . The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	32.00	3100.00	#NAME?	Per Hour	99200.00
TOTAL :-						99200.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹

84561.00

EARNEST MONEY :- ₹

1700.00

TIME LIMIT :-

One Month

NAME OF WORK :- C/o Shed at Dadbaru ward No.3 in G.P. Prai Tehsil Shahpur Distt Kangra (H.P). (Deposit Work)

SUB-HEAD :- Providing and laying Tile flooring and plaster work etc.

S. No.	Description of items	Quantity		RATES		Unit	Amount
		3	4	In fig	In words	6	7
1	Providing and laying Size of (600x 600mm) (Six hundred into Six hundred millimetre) Double charged/Ultra charged vetrified tiles of Restile/Nitco /Rak/Kajaria / Orient -Bell/AGL/Simpolo /Johnson/Somany/ Orient & Bell as per approved shade and design of the office in flooring (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero decimal zero eight percentage) and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm (twenty millimetres) thick cement mortar 1:4 (one cement isto four coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (three decimal three kilogram per squaremetre) including grouting the joints with white cement and matching pigments etc., complete as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	18.00	1358.20		Rupees One Thousand Three Hundred Fifty Eight And Paise Twenty Only	Per Squire metre	24448.00
2	Providing and laying 300X450 mm (three hundred into four hundred fifty millimetre) white glazed tile of Premimum quality of Nitco/ Kajaria/ /Johnson/ AGL/ Somany/ Orient Bell in Dado/Skirting over 12mm (twelve millimetre) thick cement mortar 1:3 (one cement isto three sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete within all leads, lifts of materials and other incidentals. as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	40.05	980.00		Rupees Nine Hundred Eighty Only	Per Squire metre	39249.00
3	15mm (Fifteen millimetres) thick cement plaster in single coat on rough side of brick/concrete/stone walls for interior plastering upto all floor levels including arises internal rounded angles, chamfers and or rounded angles not exceeding 80mm (Eighty millimetres) in girth and finished even and smooth with cement mortar 1:6 (One cement isto six sand) within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	70.13	245.00		Rupees Two Hundred Forty Five Only	Per Squire metre	17182.00

Qty	10	Providing and applying white cement based putty of Birla / JK average thickness 1 mm (one millimetre) over the plastered wall surface to prepare the surface even and smooth complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST and any other taxes imposed by the Government.	70.13	52.50	Rupees Fifty Two And Paise Fifty Only	Per Squire metre	3682.00
TOTAL :-							84561.00
Quoted Rate in Figure (%)			(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)			(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HAPWD Shahpur

(15)

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98803.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of Mini Secretariat Building at Shahpur Tehsil Shahpur Distt Kangra (H.P).
SUB-HEAD :- C/o U-Shape drain at Rd.0/067 to 088-0/088

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying mechanically mixed and vibrated plain cement in open foundations for all type of structure using plain cement concrete grade M- 10 (M- Ten) nominal mix (1:3:6) (One cement isto Three sand isto Six graded crushed stone aggregate 20mm (Twenty millimetres) nominal size) in or under water and curing complete including pumping of bailing out water, dewatering removal of slush as required at side which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in drains as per drawing and MORD technical Specification section 800,900 and 1200 as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax or any type of taxes imposed by the Government.	14.10	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	75858.00
2	Providing and fixing 20 mm (Twenty millimetre) thick factory made cement concrete Edge block of M:30 grade made by block making machine with strong vibratory compaction, of approved size and design & shape, laid in required color and pattern over and including fixing with the 1:3 finished with neat cement slurry, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	35.30	650.00	Rupees Six Hundred Fifty Only	Per running metre	22945.00
TOTAL :-						98803.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

16

SCHEDULE OF QUANTITY

211

ESTIMATED COST: - ₹ 93061.00
 EARNEST MONEY :- ₹ 1900.00
 TIME LIMIT : Two Months

NAME OF WORK :- Special repair of Vetnary Hospital Gohju in Tehsil Shahpur at Distt. Kangra Himachal Pradesh.
SUB-HEAD :- C/o Piller for boundary wall .

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Second class brick work using common burnt clay building bricks in cement mortar 1:4 (one cement isto four sand) in super structure upto all floor levels as per PWD specification, drawing and design and curing complete including scaffolding and cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government. Government.	13.39	6950.00	Rupees Six Thousand Nine Hundred Fifty Only	Per square metre	93061.00
TOTAL :-						93061.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HP&WD Shahpur

SCHEDULE OF QUANTITY

17

ESTIMATED COST :- ₹ 98795.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- Two Months

NAME OF WORK :- Restoration of rain damages Shahpur Kiari Gandhrrop road Km 0/00 to 2/400 in Tehsil Shahpur Distt Kangra (H.P).
SUB-HEAD :- C/o Breast wall at Km 1/712 to 1/718

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drain and Parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 and as per direction of the Engineer- In – Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and lift including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layer not executing 150 mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth any quantam of water including cleaning of slush which may arise out during dewatering complete as per direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	6.60	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2310.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in all type of structure as per drawing and MORD technical specification section 800, 900 ,1200 and 1600 for nominal mix 1: 4: 8 (one cement isto four sand isto eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depths including the cost of form work in retaining walls, breast walls etcetera as per the direction of Engineer-in-Charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	19.10	4850.00	Rupees Four Thousand Eight Hundred Fifty Only	Per cubic metre	92635.00

3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope I(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	11.00	350.00	Rupees Three Hundred Fifty Only	Each	3850.00
TOTAL :-						98795.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

18

ESTIMATED ₹ 98513.00
EARNEST ₹ 2000.00
TIME LIMIT Two Months

NAME OF WORK :- Construction of Community Bhawan at Ghad Mata Gram Panchayat Nerti (Deposit Work).

SUB-HEAD :- Construction of ground floor.(Balance work).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation in foundation, trenches etc. in earth work in all classification of soil such as pick work, jumper work, pick jumper work, blasting work, jumper blasting work, soft and hard blasting and saturated soil, de-watering, including wedging out rocks where blasting work is prohibited, chiseling or any other mixed variety of soil, including shoring, shuttering and pumping out water upto any depth or any quantam of water including slush which may be arise during de-watering removal of slush and stacking the serviceable and un-serviceable material clear from the edge of excavation as direction of Engineer-In-Charge and retuning the stacked soil in 15cm (Fifteen centimeter) layers, when required into plinths, sides of foundation etc; consolidating each deposited layer by ramming, watering and then disposing of all excavated earth as directed by the Engineer-in-Charge, within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rates inclusive of octroi, royalty, Malkhana, toll taxes, GST and any other taxes imposed by the Government.	10.07	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3525.00
2	Providing and laying in position machine batched and machine mixed cement concrete work of grade M-20 (M- twenty) design mix to obtain the compressive strength of 20N/mm 2 (twenty newton per Square millimetre) for reinforced cement concrete work, using cement with cement content not less than @ 320 kg/cum. (three hundred thirty six kilogram per cubic metre) or as per approved design mix for all work upto plinth level to give a smooth surfaces mechanically mixed and vibrated including curing complete and pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	5.40	7050.00	Rupees Seven Thousand Fifty Only	Per cubic metre	38070.00
3	Providing and laying in position machine batched and machine mixed cement concrete work of grade M-20 (M- twenty) design mix to obtain the compressive strength of 20N/mm 2 (twenty newton per Square millimetre) for reinforced cement concrete work, using cement with cement content not less than @ 320 kg/cum. (three hundred thirty six kilogram per cubic metre) or as per approved design mix for all work above plinth level to give a smooth surfaces mechanically mixed and vibrated including curing complete and pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.05	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	7508.00

	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
	2	3	4	5	6	7
4	Providing and laying tor steel of TataTISCO, SAIL reinforcement for reinforced cement concrete work including bending, binding and placing in position complete in all respects as per approved drawing, design, and specification in all floor levels including the cost of binding wire and dewatering if arisen during placement of reinforcement as per PWD specification and approved, drawing design including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	520.10	95.00	Rupees Ninety Five Only	Per Killogram	49410.00
TOTAL :-						98513.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99642.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of Mini Secretariat Building at Shahpur Tehsil Shahpur Distt Kangra (H.P).
SUB-HEAD :- C/o water tank and Stand.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	3.50	6350.00	Rupees Six Thousand Three Hundred Fifty Only	Per cubic metre	22225.00
2	Supplying fitting and placing HYSD bar reinforcement in super-structures complete as per drawings and MORTH technical specifications clause 1600 and 2200, including cutting bending, binding, Straightening and placing in position complete in all respect including the cost of binding, wire upto all heights and depths and as per direction and entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The rate is including Royalty, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government.	455.30	98.00	Rupees Ninety Eight Only	Per Killograme	44619.00
3	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint in beams joists channels, angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like, complete as per specification, approved drawing, design, as per the entire satisfaction and direction of the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	305.10	107.50	Rupees One Hundred Seven And Paise Fifty Only	Per Killograme	32798.00
TOTAL :-						99642.00
Quoted Rate in Figure (%)		0	(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)		0	(Amount to be quoted by the contractor in words)			

B-1
 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

(20)

245

ESTIMATED COST: - ₹ 99100.00
 EARNEST MONEY: - ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of Link road Palwala to Lanjot in G.P. Durgella KM 0/00 to 0/900 in Tehsil Shahpur Distt. Kangra (H.P). (Under S.C.S.P)

SUB-HEAD :- Providing and laying G-II & G-III at RD 0/480 to 0/543 .

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading by mechanical means to required slope and compacted with three wheel 80-100 (eighty -one hundred) kN static roller to meet requirement of Table 300.2 complete as per MORD technical Specification section 400 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals.. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	40.20	91.30	Rupees Ninety One And Paise Thirty Only	Per cubic metre	3670.00
2	Providing, laying, spreading and compacting by mechanical means crushed stone aggregate size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II (75mm (seventy five millimetres) consolidated thickness) to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.20 cum (zero point two zero cubic metres) per ten square metres and binding material at the rate of 0.06 cum (zero point zero six cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications section 400 and as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads, lifts and other incidental The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government.	26.70	2150.00	Rupees Two Thousand One Hundred Fifty Only	Per cubic metre	57405.00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
3	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam' specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government.	16.90	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	38025.00
TOTAL :-						99100.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

13-1
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

(21)

(214)

ESTIMATED ₹ 99483.00
EARNST ₹ 2000.00
TIME LIMIT Two Months

NAME OF WORK :- Construction of Community Bhawan at Ghad Mata Gram Panchayat Nerti (Deposit Work).
SUB-HEAD :- Construction of ground floor.)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation in foundation, trenches etc. in earth work in all classification of soil such as pick work, jumper work, pick jumper work, blasting work, jumper blasting work, soft and hard blasting and saturated soil, de-watering, including wedging out rocks where blasting work is prohibited, chiseling or any other mixed variety of soil, including shoring, shuttering and pumping out water upto any depth or any quantam of water including slush which may be arise during de-watering removal of slush and stacking the serviceable and un-serviceable material clear from the edge of excavation as direction of Engineer-in-Charge and retuning the stacked soil in 15cm (Fifteen centimeter) layers, when required into plinths, sides of foundation etc; consolidating each deposited layer by ramming, watering and then disposing of all excavated earth as directed by the Engineer-in-Charge, within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rates inclusive of octroi, royalty, Malkhana, toll taxes, GST and any other taxes imposed by the Government.	10.07	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3525.00
2	Providing and laying cement concrete 1:4:8 (One cement isto Four sand isto Eight graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size and down gauge) mechanically mixed and curing complete excluding cost of forms work in foundation and plinth within all leads, lifts of materials and other incidentals as per approved specification, drawing, design and as directed by the Engineer-in-Charge. The rate is including Royalty, Malkhana, Octroi, Toll Tax, Sale Tax, GST or any other taxes imposed by the Government.	5.42	4850.50	Rupees Four Thousand Eight Hundred Fifty And Paise Fifty Only	Per cubic metre	26290.00
3	Providing and laying in position machine batched and machine mixed cement concrete work of grade M-20 (M- twenty) design mix to obtain the compressive strength of 20N/mm 2 (twenty newton per Square millimetre) for reinforced cement concrete work, using cement with cement content not less than @ 320 kg/cum. (three hundred thirty six kilogram per cubic metre) or as per approved design mix for all work upto plinth level to give a smooth surfaces mechanically mixed and vibrated including curing complete and pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.10	7050.00	Rupees Seven Thousand Fifty Only	Per cubic metre	14805.00

1	2	Quantity	RATES		Unit	Amount
			In fig	In words		
3	4	5	6	7		
4	Providing and laying for steel of TataTISCO, SAIL reinforcement for reinforced cement concrete work including bending, binding and placing in position complete in all respects as per approved drawing, design, and specification in all floor levels including the cost of binding wire and dewatering if arisen during placement of reinforcement as per PWD specification and approved, drawing design including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	577.50	95.00	Rupees Ninety Five Only	Per Killogram	54863.00
TOTAL :-						99483.00
Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure				
Quated Rate in Words (%)		(Amount to be quoted by the contractor in				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

22

ESTIMATED COST :- ₹ 95708.00
EARNEST MONEY :- ₹ 1950.00
TIME LIMIT : Two Months

NAME OF WORK :- Construction of Mini Secretariat Building at Shahpur Tehsil Shahpur Distt Kangra (H.P).
SUB-HEAD :- C/o U-Shape drain at Rd.0/089 to 0/114.60

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying mechanically mixed and vibrated plain cement in open foundations for all type of structure using plain cement concrete grade M- 10 (M- Ten) nominal mix. (1:3:6) (One cement isto Three sand isto Six graded crushed stone aggregate 20mm (Twenty millimetres) nominal size) in or under water and curing complete including pumping of bailing out water, dewatering removal of slush as required at side which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in drains as per drawing and MORD technical Specification section 800,900 and 1200 as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax or any type of taxes imposed by the Government.	17.10	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	91998.00
2	Excavation in foundation and trenches in all heights and depths and in all kinds of soil including saturated soils comprising of pick work, jumper work, pick jumper work, blasting work both in soft and hard rock, chiseling / wedging out of rock (Where blasting is prohibited) or any other mixed variety of soil including shoring, strutting, de-watering and pumping or bailing out water (surface and sub soil water) up to any heights / depths or any quantum of water including slush which may arise during de-watering, removal of slush and stacking the serviceable and un-serviceable materials clear from the edges of excavation and then returning the stacked soil in 15cm (fifteen centimeters) layers where required into plinth and side of foundation etcetera, consolidating each deposited layer by ramming & watering and then disposing of all surplus un-serviceable excavated earth as directed within all leads and lifts by head-load, mechanical transportation or by any other mode of transportation with all cost of labours, machineries and disposed materials to be neatly dressed and leveled as per specifications approved drawing, design, as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	10.60	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3710.00
TOTAL :-						95708.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 74355.00
 EARNEST MONEY: - ₹ 1500.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of Link road Palwala to Lanjot in G.P. Durgella KM 0/00 to 0/900 in Tehsil Shahpur Distt. Kangra (H.P). (Under S.C.S.P)

SUB-HEAD :- Construction of V-Shape Drain at RD 0/448 to 0/462 (RHS)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	45.00	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	15750.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	10.30	5350.00	Rupees Five Thousand Three Hundred Fifty Only	Per cubic metre	55105.00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope I(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	10.00	350.00	Rupees Three Hundred Fifty Only	Each	3500.00
TOTAL :-						74355.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer.
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

244

ESTIMATED COST: - ₹ 97597.00
 EARNEST MONEY: - ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of Link road Palwala to Lanjot in G.P. Durgella KM 0/00 to 0/900 in Tehsil Shahpur Distt. Kangra (H.P). (Under S.C.S.P)

SUB-HEAD :- Providing and laying G-II & G-III at RD 0/545 to 0/608 .

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading by mechanical means to required slope and compacted with three wheel 80-100 (eighty -one hundred) kN static roller to meet requirement of Table 300.2 complete as per MORD technical Specification section 400 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals.. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	41.10	91.30	Rupees Ninety One And Paise Thirty Only	Per cubic metre	3752.00
2	Providing, laying, spreading and compacting by mechanical means crushed stone aggregate size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II (75mm (seventy five millimetres) consolidated thickness) to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.20 cum (zero point two zero cubic metres) per ten square metres and binding material at the rate of 0.06 cum (zero point zero six cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications section 400 and as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads, lifts and other incidental The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government.	26.80	2150.00	Rupees Two Thousand One Hundred Fifty Only	Per cubic metre	57620.00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
3	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government.	16.10	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	36225.00
TOTAL :-						97597.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer.
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 94897.00
 EARNEST MONEY :- ₹ 1900.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of Community Bhawan at Ghad Mata Gram Panchayat Nerti (Deposit Work).

SUB-HEAD :- Construction of slab in 1st floor.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying in position machine batched and machine mixed cement concrete work of grade M-20 (M- twenty) design mix to obtain the compressive strength of 20N/mm 2 (twenty newton per Square millimetre) for reinforced cement concrete work, using cement with cement content not less than @ 320 kg/cum. (three hundred thirty six kilogram per cubic metre) or as per approved design mix for all work above plinth level to give a smooth surfaces mechanically mixed and vibrated including curing complete and pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.10	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	15015.00
2	Providing and laying in position machine batched and machine mixed cement concrete work of grade M-25 (M- twenty) design mix to obtain the compressive strength of 20N/mm 2 (twenty newton per Square millimetre) for reinforced cement concrete work, using cement with cement content not less than @ 360 kg/cum. (three hundred thirty six kilogram per cubic metre) or as per approved design mix for all work above plinth level to give a smooth surfaces mechanically mixed and vibrated including curing complete and pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	5.25	7250.00	Rupees Seven Thousand Two Hundred Fifty Only	Per cubic metre	38063.00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
3	Providing and laying tor steel of TataTISCO, SAIL reinforcement for reinforced cement concrete work including bending, binding and placing in position complete in all respects as per approved drawing, design, and specification in all floor levels including the cost of binding wire and dewatering if arrisen during placement of reinforcement as per PWD specification and approved, drawing design including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	440.20	95.00	Rupees Ninety Five Only	Per Killogram	41819.00
TOTAL :-						94897.00
Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

26

ESTIMATED COST :- ₹

99678.00

EARNEST MONEY :- ₹

2000.00

TIME LIMIT :-

Two Months

NAME OF WORK :- Construction of Mini Secretariat Building at Shahpur Tehsil Shahpur Distt Kangra (H.P).
SUB-HEAD :- C/o Rain water surface of water tank.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and Laying mechanically mixed and vibrated plain cement concrete, as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	4.15	4850.00	Rupees Four Thousand Eight Hundred Fifty Only	Per cubic metre	20128.00
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in super structure as per drawing and M.O.R.D., technical specification section 800, 900 and 1400 using R.C.C. grade M-25 (twenty five) design mix with cement contents not less than 400 kg (four hundred kilogram) per cubic metre with 20mm (twenty millimetre) nominal size graded crushed stone aggregate and curing complete including cost of form work but excluding the cost of reinforcement for reinforced concrete work in deck slab and to the entire satisfaction and as per the direction of Engineer-in-Charge including carriage of material within all leads , lifts and other incidentals .The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. Inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	6.24	7250.00	Rupees Seven Thousand Two Hundred Fifty Only	Per cubic metre	45240.00
3	Supplying fitting and placing HYSD bar reinforcement in super-structures complete as per drawings and MORTH technical specifications clause 1600 and 2200, including cutting bending, binding, Straightening and placing in position complete in all respect including the cost of binding, wire upto all heights and depths and as per direction and entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The rate is including Royalty, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government.	350.10	98.00	Rupees Ninety Eight Only	Per Killograme	34310.00
TOTAL :-						99678.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

27

248

ESTIMATED COST :- ₹ 75240.00
 EARNEST MONEY :- ₹ 1550.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of Link road Palwala to Lanjot in G.P. Durgella KM 0/00 to 0/900 in Tehsil Shahpur Distt. Kangra (H.P.). (Under S.C.S.P)

SUB-HEAD :- Construction of V-Shape Drain at RD 0/432 to 0/446 (RHS)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	46.00	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	16100.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	10.40	5350.00	Rupees Five Thousand Three Hundred Fifty Only	Per cubic metre	55640.00

No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	10.00	350.00	Rupees Three Hundred Fifty Only	Each	3500.00
TOTAL :-						75240.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer.
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99708.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT :- One Month

NAME OF WORK :- Construction of Link Road NH 154 to Dhanotu via Bad Basti lin 0/000 to 3/670 In District Kangra (HP) under RIDF-XXX (NABARD)

SUB-HEAD :- Providing board and Painting and writing lettering, figures etcetra.)

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Painting two coats (excluding priming coat) on previously steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning the surface to remove all dirt, dust and other foreign matter with enamel paint other than white including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	45.00	36.10	Rupees Thirty Six And Paise Ten Only	Per square metre	1625.00
2	Providing and erecting direction and place identification retro-reflective sign boards, as per IRC-67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting width, 2 mm (two millimeters) thick with area not exceeding 0.90 sqm (zero point nine zero) supported on mild steel iron post 75 mm x 75 mm x 6 mm, (seventy five into seventy five into six millimeters), 2 Nos. (two numbers) firmly fixed to the ground by mean of properly designed foundation with M-15 grade (M-fifteen grade) cement concrete 450x450x600mm (four hundred fifty into four hundred fifty into six hundred millimetre), 600mm (six hundred millimetre) below ground level as per approved drawings and technical specification section 1700, including painting angle iron post with primes and two coats of Epoxy paint as per specification and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	10500.00	Rupees Ten Thousand Five Hundred Only	Each	10500.00
3	Writing letters or figures on any surfaces with synthetic enamel paint (other than white) stops, comas, hyphens and the like not to be measured and paid separately, Block letters, Indian letters / figures etc. including carriage of materials within all leads, lifts and other Incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	33050.00	2.65	Rupees Two And Paise Sixty Five Only	Per letter per centimetre height	87583.00
TOTAL :-						99708.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

29

235

R/D

SCHEDULE OF QUANTITY

Name of work :- Construction of Link road from Rajol to Della Bhatti Km 0/000 to 3/000. (SHE Construction of Edge wall & Embankment between km 1/705 to 1/720 Rojol side)							Estimated cost Rs.	97,449.00
							Earnest Money Rs.	1,950.00
							Time Limits	Two Months
S. No.	Description of Item	Quantity	Rate		Unit	Amount		
			In Figures	In Word				
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.67	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3385.00		
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	16.42	4300.00	Rupees Four Thousand Three Hundred Only	Per cubic metre	70606.00		
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in- charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	6.00	350.00	Rupees Three Hundred Fifty Only	Each	2100.00		
4	Back filling with granular material behind abutments, wing walls, return walls and retaning walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.06	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4301.00		
5	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	12.82	239.10	Rupees Two Hundred Thirty Nine And Paise Ten Only	Per cubic metre	3065.00		

6	Construction of granular sub-base by providing well graded materials, spreading in uniform layers with tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller 80-100 (Eighty-hundred) kN static roller to achieve the desired density, complete as per MORD Technical Specification Clause 401 for grading-I material, as per the entire satisfaction and directions of Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.55	1636.50	Rupees One Thousand Six Hundred Thirty Six And Paise Fifty Only	Per cubic metre	13992.00
	Total					97449.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shajapur Division,
 HP PWD Shajapur.

(30)

(238)

DNIT						
NAME OF WORK:- DIGITAL SURVEY OF GOVT. DEGREE COLLEGE RIRKMAR .					ESTIMATED COST:-	75,000.00
					EARNEST MONEY:-	1,500.00
					TIME LIMIT	ONE MONTHS
SUB HEAD : PREPARATION OF DETAILED PROJECT REPORT & DIGITAL SURVEY						
SR. NO.	DESCRIPTION OF ITEMS	NO. / QTY. / JOB	UNIT	ESTIMATED RATE (IN RS.)	ESTIMATED RATE IN WORDS	TOTAL AMOUNT INCLUSIVE OF ALL TAXES IN RS.
1	2	3	4	5	6	7
1	PREPARATION OF DIGITAL SURVEY CONTOUR PLAN WITH DRAWING COMPLETE IN ALL RESPECT IN MANUSCRIPT FROM AND SUBMISSION OF THE SAME TO HIGHER OFFICE FOR APPROVAL. IF ANY CORRECTION/AMENDMENT HAS DESIRED BY THE HEAD OFFICE. THE SAME MAY BE CORRECTED AS DESIRED AND DIRECTED BY THE ENGINEER-IN-CHARGE COMPLETE IN ALL RESPECT . AFTER APPROVAL, THE SAME SHOULD BE SUBMITTED IN TWO NO. SET OF FAIR DRAWING AGAIN IF ANY CORRECTION/AMENDMENT AS DESIRED BY HEAD OFFICES.	1.00	JOB	75,000.00	SEVENTY FIVE THOUSAND ONLY	75,000.000
					TOTAL	75,000.00
Quoted Rate in Figure (%)			(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)			(Amount to be quoted by the contractor in words)			

EXECUTIVE ENGINEER
SHAHPUR DIVISION
HPPWD SHAHPUR

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98625.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- Two Months

NAME OF WORK :- C/o Pargod to Kalru road km 0/000 to 4/000.
SUB-HEAD :- Construction of Retaining wall in wire crate at KM 2/080 to 2/096.35

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.92	350.00	Rupees Three Hundred Fifty Only	Per Cubic metre	3822.00
2	Providing and laying of boulder apron or gabion walls laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone bounders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	29.77	3184.50	Rupees Three Thousand One Hundred Eighty Four And Paise Fifty Only	Per Cubic metre	94803.00
TOTAL :-						98625.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

32

219

ESTIMATED COST: ₹ 98995.00
 EARNEST MONEY ₹ 2000.00
 TIME LIMIT: Two Months

NAME OF WORK :- Construction of Stairs of Akhada at Chhinj Mela ground Manai (SDP/2022/371) (Deposit work)
SUB-HEAD :- Construction of Stairs steps.

S No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.98	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1393.00
2	Providing and laying cement concrete 1:4:8 (One Cement isto Four Sand isto eight) graded stone aggregate 40mm (Forty millimetre) nominal size for haunching of pipes of the 150 mm (One hundred fifty millimetre) internal diameters, necessary form work and curing complete within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	17.35	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	82413.00
3	Providing 40mm (Forty millimetre) thick Cement concrete flooring 1:2:4 (one cement isto two sand isto four aggregate) graded/crushed stone aggregate 20 mm (twenty millimetre) nominal size mechanically mixed including curing complete as per PWD specification, laid in one layer finished with a floating coat of neat cement. The rate is inclusive of cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	70.45	215.60	Rupees Two Hundred Fifteen And Paise Sixty Only	Per square metre	15189.00
TOTAL :-						98995.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

(33)

ESTIMATED COST: - ₹ 97832.00
EARNEST MONEY: - ₹ 2000.00
TIME LIMIT: - Two Months

NAME OF WORK :- C/o Pargod to Kalru road km 0/000 to 4/000.
SUB-HEAD :- Construction of Retaining wall in wire crate at KM 1/367 to 1/373.30

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including cartage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.84	350.00	Rupees Three Hundred Fifty Only	Per Cubic metre	3794.00
2	Providing and laying of boulder apron or gabion walls laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone bounders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including cartage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	29.53	3184.50	Rupees Three Thousand One Hundred Eighty Four And Paise Fifty Only	Per Cubic metre	94038.00
TOTAL :-						97832.00
Quoted Rate in Figure (%)		{Amount to be quoted by the contractor in Figure }				
Quoted Rate in Words (%)		{Amount to be quoted by the contractor in words}				

Executive Engineer,
Shahpur Division,
H.P.W.D. Shahpur

SCHEDULE OF QUANTITY

34

ESTIMATED COST: ₹
EARNEST MONEY ₹
TIME LIMIT

97918.00
2000.00
Two Months

NAME OF WORK :- Construction of Staircase at Chhinj Mela ground Manai (SDP/2022/371) (Deposit work)

SUB-HEAD :- Construction of Stairs steps (Balance work).

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			in fig	in words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.95	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1383.00
2	Providing and laying cement concrete 1:4:8 (One Cement isto Four Sand isto eight) graded stone aggregate 40mm (Forty millimetre) nominal size for haunching of pipes of the 150 mm (One hundred fifty millimetre) internal diameters, necessary form work and curing complete within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	17.35	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	82413.00
3	Providing 40mm (Forty millimetre) thick Cement concrete flooring 1:2:4 (one cement isto two sand isto four aggregate) graded/crushed stone aggregate 20 mm (twenty millimeter) nominal size mechanically mixed including curing complete as per PWD specification, laid in one layer finished with a floating coat of neat cement. The rate is inclusive of cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	65.50	215.60	Rupees Two Hundred Fifteen And Paise Sixty Only	Per square metre	14122.00
TOTAL :-						97918.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

35

272

ESTIMATED COST: - ₹ 98018.00
EARNEST MONEY: - ₹ 2000.00
TIME LIMIT: - Two Months

NAME OF WORK :- Special repair of Vetnary Hospital Gohju in Tehsil Shahpur at Distt. Kangra Himachal Pradesh.
SUB-HEAD :- C/o Cow shed .

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying cement concrete 1:4:8 (One cement isto Four sand isto Eight graded broken/crushed stone aggregate 40mm (Forty milimetres) nominal size and down gauge) mechanically mixed and curing complete excluding cost of forms work up to plinth level within all leads, lifts of materials and other incidentals as per approved specification, drawing, design and as directed by the Engineer-in-Charge. The rate is including Royalty, Malkhana, Octroi, Toll Tax, Sale Tax, GST or any other taxes imposed by the Government.	4.50	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	21375.00
2	Providing and laying cement concrete work of grade M20 mix design to obtain the minimum compressive strength 20N/mm2 (twenty newton per square millileter) with cement contents not less than 330 kg/ cum with mechanically mixed and vibrated curing complete excluding cost of form work and reinforcement for reinforced concrete work in foundation footing, base of columns, and the like mass cooncrete as per approved specification, drawing and design including entire carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	6.75	7050.00	Rupees Seven Thousand Fifty Only	Per cubic metre	47588.00
3	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws. 35mm (thirty five millimetre) thick Second class DEODAR wood within all leads, lifts of materials and other incidentals as per approved specification, drawing, design and as directed by the Engineer-in-Charge. The rate is including Royalty, Malkhana, Octroi, Toll Tax, Sale Tax, GST or any other taxes imposed by the Government.	4.41	3350.00	Rupees Three Thousand Three Hundred Fifty Only	Per square metre	14774.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
4	Providing and fixing 25mm (twenty five millimeters) thick Kota stone of 55X55cm (Fifty five into Fifty five centimetre) size of rough side same flooring of approved shade as per detail slab in flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	12.00	1190.10	Rupees One Thousand One Hundred Ninety And Paise Ten Only	Per square metre	14281.00
TOTAL :-						98018.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99214.00
 EARNEST MONEY :- ₹ 1900.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of Health sub center at Bhaled in Sub Tehsil Darini at in Distt. Kangra Himachal Pradesh.
SUB-HEAD :- Providing and Laying Painting and distempering etc.(Balance work).

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Applying Birta white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters and sand papered smooth to give final matt finish to the surface complete including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	533.00	70.00	Rupees Seventy Only	Per square metre	37310.00
2	Distempering (two coats) with acrylic oil bound washable distemper with Nerolac/ Asian paints of approved brand and manufacture and of required shade on ceiling/sloping roof surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth. Priming coat with distemper primer within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge.	533.00	75.50	Rupees Seventy Five And Paise Fifty Only	Per square metre	40242.00
3	Providing and fixing 19mm (Nineteen millimetre) thick water proof terminate resistant commercial board Century/Alpro or equivalent in shutters for SDB/cup boards with 6 mm (six millimetre) thick hard wood edging all round and PGI sheet lining in side i/c fixing with nickel plated piano hinges with screws etc complete) within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	14.19	950.00	Rupees Nine Hundred Fifty Only	Per square metre	13481.00
4	Providing and fixing 19mm (Nineteen millimetre) thick water proof terminate resistant commercial board Century/Alpro or equivalent in shelves for SDB/cup boards with 6 mm (six millimetre) thick hard wood edging all round and PGI sheet lining in side i/c fixing with nickel plated piano hinges with screws etc complete) within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	9.09	900.00	Rupees Nine Hundred Only	Per square metre	8181.00
TOTAL :-						99214.00
Quoted Rate in Figure (%)			(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)			(Amount to be quoted by the contractor in words)			

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

37

SCHEDULE OF QUANTITY

Sr no- 252

ESTIMATED COST:- ₹ 90692.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- C/o Chattri Pehad Road Km 0/00 to 3/780

SUB-HEAD :- C/O B/wall At Rd 3/610 to 3/615 and V-Shape Drain from Rd 3/608 to 3/620 (Portion Kholi khad road Km 3/00 to 3/780)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	14.25	350.00	Rupees Three hundred Fifty only	Per cubic metre	4988.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	16.38	4250.00	Rupees Four Thousand two hundred Fifty only	Per cubic metre	69615.00

3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	10.00	350.00	Rupees Three hundred Fifty only	Each	3500.00
4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	2.34	5380.00	Rupees Five Thousand three hundred eighty only	Per cubic metre	12589.00
TOTAL :-						90692.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPWD Shahpur

DRAFT SCHEDULE OF QUANTITY

38

ESTIMATED ₹ 89305.00
EARNEST ₹ 1800.00
TIME LIMIT Two Months

58 no - 278

NAME OF WORK :- in C/o Link road from NH-154 to Hiet College at Shahpur in Khasra No.1 (Deposit work).

SUB-HEAD :- c P/L PCC 1:4:8 side locking in CC 1:2:4 and 80 MM thick cement concrete interlocking paver blocks from KM 1/208 to 1/220

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.63	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	17243.00
2	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	1.88	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per cubic metre	11562.00
3	Providing and laying 80 mm thick Interlocking M-40 grade Concrete paver block pavement conforming to ISI 15658:2006 having thickness 60mm(sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	48.40	1250.00	Rupees One Thousand Two Hundred Fifty Only	Each	60500.00
TOTAL :-						89305.00

Draft schedule of quantity approved for
₹ 89,305/- only

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

139

ESTIMATED COST :- ₹ 99000.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- A/R & M/O various roads under Shahpur Sub Division HP.PWD Shahpur.

SUB-HEAD :- Hiring of JCB / excavator cum loader on various roads under Road section .

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Hiring of J.C.B./Excavator cum loader (J.C.B.) for removal of slips including trimming and edge cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil due to non availability of departmental machinery as per direction and entire satisfaction of engineering-in- Charge. The J.C.B./Excavator cum loader should work minimum 8.00 (eight) hours daily and excavated at least 30.00(thirty) cubic metre quantity per hour . Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fule and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. No deviation shall be allowed in any case.	90.00 Hours	1100.00	Rupees One Thousand One Hundred Only	Per hours	99000.00
TOTAL :-						99000.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99000.00
 EARNEST MONEY: - ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- A/R & M/O on Various roads under Draman section under HP,PWD Sub Division Shahpur.

SUB-HEAD :- Hiring of JCB / excavator cum loader for removal of slips.)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Hiring of J.C.B./Excavator cum loader (J.C.B.) for removal of slips including trimming and edge cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil due to non availability of departmental machinery as per direction and entire satisfaction of engineering-in- Charge. The J.C.B./Excavator cum loader should work minimum 8.00 (eight) hours daily and excavated at least 30.00(thirty) cubic metre quantity per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. No deviation shall be allowed in any case.	90.00 Hours	1100.00	Rupees One Thousand One Hundred Only	Per hours	99000.00
TOTAL :-						99000.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

(1.1)

80 no - 267

ESTIMATED COST :- ₹ 97763.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Restoration of Rain Damages on Salhi to Konal road Km 0/0 to 2/250.

SUB-HEAD :- Providing and laying wearing at RD 0/300 to 0/478.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size (75mm (seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, wateridg and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government..	43.45 Cubic metres	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	97763.00
TOTAL :-						97763.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

135
Executive Engineer,
Shahpur Division,
HARIDWAR

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99000.00
 EARNEST MONEY: - ₹ 2000.00
 TIME LIMIT: - One Month

NAME OF Restoration of Rain damages on various roads under Darini Section under HP.PWD Darini Sub- Division.
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Hiring of Excavator cum loader required for removal of slips, clearing road such opening of drains and catchpits etc. In all kind of earths, boulder, rocks etc. completely as per inspections of engineer-in-charge and minimum 25 (Twenty-five) cubic per hours output for slips / removal activates. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99000.00
TOTAL :-						99000.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HP.PWD Shahpur

SCHEDULE OF QUANTITY

Sr no - 257.

ESTIMATED COST:- ₹ 91375.00
EARNEST MONEY :- ₹ 1850.00
TIME LIMIT :- Two Months

NAME OF WORK :- Landslide Disaster Related Mitigation work on Salhi to Khari- Behl road Km. 0/00 to 9/570.

SUB-HEAD :- C/o Edge wall with pusta at Rd 4/208 to 4/215.20 and 3/190 to 3/193.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8.91	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3119.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	15.57	5350.00	Rupees Five Thousand Three Hundred Fifty Only	Per cubic metre	83300.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.83	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4956.00
TOTAL :-						91375.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

(44)

S 8 No-258

ESTIMATED COST: ₹ 98950.00
EARNEST MONEY ₹ 2000.00
TIME LIMIT Two Months

NAME OF WORK :- Construction of Stairs at Chhinj Mela Batwala G.P Manhe.(VKV/2022/2152) (Deposit work)
SUB-HEAD :- Construction of Stairs steps.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.85	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1348.00
2	Providing and laying cement concrete 1:4:8 (One Cement isto Four Sand isto eight) graded stone aggregate 40mm (Forty millimetre) nominal size for haunching of pipes of the 150 mm (One hundred fifty millimetre) internal diameters, necessary form work and curing complete within all leads, lifts off materials and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	17.35	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	82413.00
3	Providing 40mm (Forty millimetre) thick Cement concrete flooring 1:2:4 (one cement isto two snad isto four aggregate) graded/crushed stone aggregate 20 mm (twenty millimeter) nominal size mechanically mixed including curing complete as per PWD specification, laid in one layer finished with a floating coat of neat cement. The rate is inclusive of cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	70.45	215.60	Rupees Two Hundred Fifteen And Paise Sixty Only	Per square metre	15189.00
TOTAL :-						98950.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QTY

4E

S.no-268

ESTIMATED COST :- ₹
EARNEST MONEY :- ₹
TIME LIMIT :

99338.00
2000.00
Two Months

NAME OF SUB-HEAD : Restoration of Rain Damages on Salli to Kanol Road km 0/00 to 2/500 Providing and laying G-II at various RDs						
S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 63mm to 45mm (Sixty three millimeter to fourty five millimeter) Grading-II size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the Interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octrol, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	44.15	2250.00	RupeesTwo thousand two hundred fifty only	Per cubic metre	99338.00
TOTAL :-						99338.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor In Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor In words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QTY

48

S.No-270

ESTIMATED COST:- ₹ 99225.00
 EARNEST MONEY:- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF : A/R & M/O link road salil to Lahari km 0/00 to 1/750						
SUB-HEAD : Providing and laying G-II at RD 1/545 to 1/680 (Under MMSRR)						
S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 63mm to 45mm (Sixty three millimeter to forty five millimeter) Grading-II size [75mm (seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	44.10	2250.00	Rupees Two thousand two hundred fifty only	Per cubic metre	99225.00
TOTAL :-						99225.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

JST
 Executive Engineer,
 Shahpur Division,
 H.B. Shahpur

SCHEDULE OF QUANTITY

Name of Work: - Contingencies against various deposit head under Shahpur Division					Estimated Cost	99757.00
					Earnest Money	2000.00
(SH: - Providing and installation of HP Desktop, Printer and UPS in HPPWD Sub Division Office Shahpur)					Time	One Month
Sr. No.	Description of item	Qty.	Unit	Rate		Amount
				In figure	In words	
1	2	3	4	5	6	7
1	Providing and Installation of HP Desktop Core i5 13th Generation 8GB RAM, 512GB SSD, Windows 11, MS Office, 20" Screen with keyboard and mouse, Logitech Web camera and desktop speaker with USB 2.0 having One year Antivirus protection & One year warranty on all including all taxes.	1.00	Each	72093.00	(Rupees Seventy Two Thousand and Ninty three)	72093.00
2	Providing and Installation of HP Printer Laser Jet Single Function, Pro 1108 including all taxes.	1.00	Each	16554.00	(Rupees Sixteen thousand Five Hundred Fifty Four)	16554.00
3	Providing and Installation of UPS 1KVA of make Luminious, Intex, Zebronic or its equivalent including all taxes.	2.00	Each	5555.00	(Rupees Five thousand Five Hundred Fifty Five only)	11110.00
Total:-						99,757.00
Quoted Rate in Figure (%)				(Amount to be quoted by the contractor in Figure)		
Quoted Rate in Words (%)				(Amount to be quoted by the contractor in words)		


 Executive Engineer
 Shahpur Division
 HPPWD Shahpur

SCHEDULE OF QUANTITY

48

279

ESTIMATED COST: - ₹ 98841.00
EARNEST MONEY: - ₹ 2000.00
TIME LIMIT: Two Months

NAME OF WORK :- Stock storage under HP.PWD Sub Division Gaggal.

SUB-HEAD :- Providing and laying brick work above plinth.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Steel work welded in built up sections of TATA/SAIL joists channels, angles, tees with connection plates or angles, cleat as in trusses, trussed purlins main and cross beams, hips jack rafters, purlins connected to common rafters and the like in building including cutting, fixing, lifting, hoisting and; placing in position complete and applying a coat of red lead paint, within all leads, lifts of materials and other incidentals. as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	849.50 Kilo gram	105.00	Rupees One Hundred Five Only	Per kilogram	89198.00
2	Second class brick work using common burnt clay building bricks in super-structure upto all floor level in cement mortar 1:4 (One cement isto four sand) and curing complete, within all leads, lifts of materials and other incidentals, as per approved specification, drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.33 Cubic metres	7250.00	Rupees Seven Thousand Two Hundred Fifty Only	Per cubic metre	9643.00
TOTAL :-						98841.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

1351
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

(277)

ESTIMATED COST: - ₹ 99817.00
EARNEST MONEY: - ₹ 2000.00
TIME LIMIT: - Two Months

NAME OF WORK :- Stock storage under HP.PWD Sub Division Gaggal.
SUB-HEAD :- Construction of Foundation etc. for Gate.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation in foundation, trenches etc. in earth work in all classification of soil such as pick work, jumper work, pick jumper work, blasting work, jumper blasting work, soft and hard blasting and saturated soil, de-watering, including wedging out rocks where blasting work is prohibited, chiseling or any other mixed variety of soil, including shoring, shuttering and pumping out water upto any depth or any quantity of water including slush which may be arise during de-watering removal of slush and stacking the serviceable and un-serviceable material clear from the edge of excavation as direction of Engineer-in-Charge and returning the stacked soil in 15cm (Fifteen centimeter) layers, when required into plinths, sides of foundation etc; consolidating each deposited layer by ramming, watering and then disposing of all excavated earth as directed by the Engineer-in-Charge, within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rates inclusive of octroi, royalty, Malkhana, toll taxes, GST and any other taxes imposed by the Government.	5.02 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1757.00
2	Providing and laying cement concrete 1:4:8 (One cement isto Four sand isto Eight graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size and down gauge) mechanically mixed and curing complete excluding cost of forms work in foundation and plinth within all leads, lifts of materials and other incidentals as per approved specification, drawing, design and as directed by the Engineer-in-Charge. The rate is including Royalty, Malkhana, Octroi, Toll Tax, Sale Tax, GST or any other taxes imposed by the Government.	0.49 Cubic metres	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	2328.00
3	Providing form work with steel plates of 3.15mm (Three decimal one five millimetres) thick, welded with angle iron in frames of 30x30x5mm (Thirty into Thirty into Five millimetres), so as to give a fair finish including centring, shuttering strutting and propping etc, with wooden battens and ballies for all heights/depths of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in Foundation footings, bases of columns and mass concrete within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	15.84 Square metres	275.45	Rupees Two Hundred Seventy Five And Paise Forty Five Only	Per square metre	4363.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
4	Providing form work with steel plates of 3-15mm (Three decimal one five millimetres) thick, welded with angle iron in frames of 30x30x5mm (Thirty into Thirty into Five millimetres), so as to give a fair finish including centring, shuttering strutting and propping etc. with wooden battens and ballies for all heights/depths of propping and centring below supporting floor to ceiling and removal of the same for in-situ reinforced concrete and plain concrete work in beams cantilevers girders and lintels sides and soffits of beams, beam haunchings, cantilevers, bressumers and lintels upto all depths within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.73 Square metres	360.10	Rupees Three Hundred Sixty And Paise Ten Only	Per square metre	623.00
5	Providing and laying in position machine batched and machine mixed cement concrete work of grade M-20 (M-twenty) - design mix to obtain the compressive strength of 20N/mm ² (twenty newton per Square millimetre) for reinforced cement concrete work, using cement with cement content not less than @ 320 kg/cum. (three hundred twenty kilogram per cubic metre) or as per approved design mix for all work upto plinth level to give a smooth surfaces mechanically mixed and vibrated including curing complete and pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	0.65 Cubic metres	6550.50	Rupees Six Thousand Five Hundred Fifty And Paise Fifty Only	Per cubic metre	4258.00
6	Providing Tor steel reinforcement of Sail / Tisco / Tata for reinforced cement concrete work including bending, binding, straighting, cutting and placing in position complete including cost of binding wires complete for all floors within all leads, lifts of materials and other incidentals as per approved specification, drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	400.25 Kilo gram	95.00	Rupees Ninety Five Only	Per kilograme	38024.00
7	Providing and fixing mild steel round holding down bolts with nuts and washer plates complete, within all leads, lifts of materials and other incidentals as per approved specification, drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	130.43 Kilo gram	125.00	Rupees One Hundred Twenty Five Only	Per kilograme	16304.00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
8	Steel work in built up tubular, round, square or rectangular hollow tubes trusses etc, including cutting, fixing, lifting, hoisting and, placing in position complete and applying a coat of red lead paint; within all leads, lifts of materials and other incidentals, as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	299.30 Kilo gram	107.45	Rupees One Hundred Seven And Paise Forty Five Only	Per kilograme	32160.00
TOTAL :-						99817.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

13/12

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

50

Sr no-275

ESTIMATED COST: ₹ 88539.00
EARNEST MONEY ₹ 1800.00
TIME LIMIT Two Months

NAME OF WORK :- C/o Link road from NH-154 to Hiet College at Shahpur in Khasra No.1 (Deposit work).
SUB-HEAD :- P/L PCC 1:4:8 side locking in CC-1:2:4 and 80 MM thick cement concrete Interlocking paver blocks from KM 1/194 to 1/206

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty milimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octrol, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.60	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	17100.00
2	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octrol, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	1.86	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per cubic metre	11439.00
3	Providing and laying 80 mm thick Interlocking M-40 grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of Interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octrol, royalty, GST, toll tax, or other taxes imposed by the Government.	48.00	1250.00	Rupees One Thousand Two Hundred Fifty Only	Each	60000.00
TOTAL :-						88539.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

P3-1
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QTY

52

Sr no - 269

ESTIMATED COST :- ₹ 99225.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF : A/R & M/O link road salli to Lahari km 0/00 to 1/750						
SUB-HEAD : Providing and laying G-II at RD 1/400 to 1/540 (under MMSRDV)						
S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 63mm to 45mm (Sixty three millimeter to forty five millimeter) Grading-II size (75mm (seventy five millimeters) compacted thickness) to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	44.10	2250.00	Rupees Two thousand two hundred fifty only	Per cubic metre	99225.00
TOTAL :-						99225.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
H.P.W.D. Shahpur

SCHEDULE OF QUANTITY

52

S.No - 273

ESTIMATED COST :- ₹ 89634.00
EARNEST MONEY :- ₹ 1800.00
TIME LIMIT : Two Months

NAME OF WORK :- C/o Link road from NH-154 to Hiet College at Shahpur in Khasra No.1 (Deposit work),

SUB-HEAD :- P/L PCC 1:4:8 side locking in CC 1:2:4 and 80 MM thick cement concrete interlocking paver blocks from KM 1/150 to 1/162.50.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.66	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	17385.00
2	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	1.89	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per cubic metre	11624.00
3	Providing and laying 80 mm thick Interlocking M-40 grade Concrete paver block pavement conforming to ISI 15658:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	48.50	1250.00	Rupees One Thousand Two Hundred Fifty Only	Each	60625.00
TOTAL :-						89634.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

54

Sr no - 279

ESTIMATED ₹ 90254.00
EARNEST ₹ 1950.00
TIME LIMIT Two Months

NAME OF WORK :- C/o Link road from NH-154 to Hiet College at Shahpur in Khasra No.1 (Deposit work).

SUB-HEAD :- P/L PCC 1:4:8 side locking in CC 1:2:4 and 80 MM thick cement concrete interlocking paver blocks from KM 1/165 to 1/177.50

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty milimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other Incidentals. The rate is Including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.66	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	17385.00
2	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	1.94	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per cubic metre	11931.00
3	Providing and laying 80 mm thick Interlocking M-40 grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	48.75	1250.00	Rupees One Thousand Two Hundred Fifty Only	Each	60938.00
TOTAL :-						90254.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in				

P. S. J.
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

94

SCHEDULE OF QUANTITY

Estimated cost:- Rs. 99200.00
Earnest Money:- Rs.2000.00
Time Allowed:- One Month

Name of Work: - R/O R/D On various Roads under Boh Section.
Sub Head:- Hiring of Poclain for removal of slips.

Sr. No.	Sub-Head/ Items of Work.	Quantity	Rates		Unit	Amount
			In Figures	In Words		
1.	Hiring of Poclain with Bucket/breaker (140 HP) for excavation/cutting removal of debris & dressing of road as per desired level, clearing the entire debris generated during the excavation work including all leads and lift with a maximum bukect capacity of 1 cum capacity of 45.00 per hourn minimum six hour per day including pay of operator, POL charges maintenance of any minor or major accidental and other damages to private and Govt. property is the whole responsibility of the contractor. the work shall be excuted as per the direction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges..	31.00	3200.00	(Rupees Three Thousand Two Hundred only)	Per Hour	99200.00
					Total:-	99200.00
	Quated Rate in Figure (%)	Amount to be Quoted by contractor in Figure				
	Quated Rate in Words (%)	Amount to be Quoted by contractor in Words				

31

Executive Engineer
Shahpur Division,
HPPWD, Shahpur.

SCHEDULE OF QUANTITY

Estimated cost:- Rs. 99200.00
Earnest Money:- Rs.2000.00
Time Allowed:- One Month

Name of Work:- R/O R/D On various Roads under Darini Sub Division
Sub Head:- Hiring of Poclain for removal of slips.

Sr. No.	Sub-Head/ Items of Work.	Quantity	Rates		Unit	Amount
			In Figures	In Words		
1.	Hiring of Poclain with Bucket/breaker (140 HP) for excavation/cutting removal of debris & dressing of road as per desired level, clearing the entire debris generated during the excavation work including all leads and lift with a maximum bukect capacity of 1 cum capacity of 45.00 per hourn minimum six hour per day including pay of operator, POL charges maintenance of any minor or major accidental and other damages to private and Govt. property is the whole responsibility of the contractor. the work shall be excuted as per the direction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges..	31.00	3200.00	(Rupees Three Thousand Two Hundred only)	Per Hour	99200.00
					Total:-	99200.00
	Quated Rate in Figure (%)		Amount to be Quoted by contractor in Figure			
	Quated Rate in Words (%)		Amount to be Quoted by contractor in Words			

Executive Engineer
Shahpur Division,
HPPWD, Shahpur

SCHEDULE OF QUANTITY

56

ESTIMATED COST :- ₹ 73236.00
 EARNEST MONEY :- ₹ 1500.00
 TIME LIMIT :- Two - Months

NAME OF WORK :- C/o Jeepable road from main road Ranjeet Singh house to Chuni Lal House ward No-03 Uperla Dibbar (VKV2024/957) Deposit Work).

SUB-HEAD :- C.C.Pavmnt at Km 0/126 to 0/150

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and balling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.67	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1985.00
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) as per drawing and technical specification. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax or any type of taxes imposed by the Government.	6.35	580.00	Rupees Five Hundred Eighty Only	Per cubic metre	3683.00

3	Construction of plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement and any other equivalent type as per Clause 1501 using M25 (Grade),(design mix) concrete having coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre), mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic meter) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished as approved, curing of concrete slabs for 14 (fourteen) days using curing compound (where specified) and water finishing lines and grade as per drawing and MORD Technical specification section 1500 and as directed by the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	9.45	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	67568.00
TOTAL :-						73236.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPBW Shahpur

SCHEDULE OF QUANTITY


ESTIMATED COST :- ₹ 73207.00
 EARNEST MONEY :- ₹ 1500.00
 TIME LIMIT : Two Months

NAME OF WORK :- C/o Jeepable road from main road Ranjeet Singh house to Chuni Lal House ward No-03 Uperla
SUB-HEAD :- C.C.Pavmrnt at Km 0/100 to 0/125

Dibbar (VKV2024/957) Deposit Work).

S. No.	Description of Items	Quantity		RATES		Unit	Amount
		3	4	In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.67	350.00		Rupees Three Hundred Fifty Only	Per cubic metre	1985.00
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) as per drawing and technical specification. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax or any type of taxes imposed by the Government.	6.30	580.00		Rupees Five Hundred Eighty Only	Per cubic metre	3654.00

3	Construction of plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement and any other equivalent type as per Clause 1501 using M25 (Grade),(design mix) concrete having coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre), mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic meter) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished as approved, curing of concrete slabs for 14 (fourteen) days using curing compound (where specified) and water finishing lines and grade as per drawing and MORD Technical specification section 1500 and as directed by the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	9.45	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	67568.00
TOTAL :-						73207.00
Quoted Rate in Figure (%)			(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)			(Amount to be quoted by the contractor in words)			


 Executive Engineer,
 Shahpur Division,
 APPWD Shahpur



SCHEDULE OF QUANTITY

88 no 282

ESTIMATED COST: - ₹ 98407.00
EARNEST MONEY: - ₹ 2000.00
TIME LIMIT: - Two Months

NAME OF WORK :- C/o Pucca path alongwith Protection wall near the House of Sh. Bhisham Singh S/o Bhuri Singh, Ward No-2, G.P. Mundla, (Under Head-VKVNY(MLALAD) (Deposit work).

SUB-HEAD :- C/o Protection wall.

S. No.	Description of Items	Quantity		RATES		Unit	Amount
		3	4	In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.70		350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3745.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	17.40		5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	93612.00

3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in- charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.00	350.00	Rupees Three Hundred Fifty Only	Each	1050.00
						TOTAL :- 98407.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

(54)
SCHEDULE OF QUANTITY

So no- 283

ESTIMATED COST:- ₹ 93168.00
EARNEST MONEY :- ₹ 1900.00
TIME LIMIT : Two Months

NAME OF WORK :- C/o Pucca path alongwith Protection wall near the House of Sh. Bhisham Singh S/o Bhuri Singh , Ward No-2, G.P. Mundla.(Under Head-VKVN(MALAD) (Deposit work).

SUB-HEAD :- C/o Protection wall and Providing and fixing M.S. Grating

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	6.10	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	32818.00
2	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in- charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	1.00	350.00	Rupees Three Hundred Fifty Only	Each	350.00
3	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) as per drawing and technical specification. as per direction of Engineer-in-Charge including carriage of materials within all leads , lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	10.80	750.00	Rupees Seven Hundred Fifty Only	Per cubic metre	8100.00

4	Providing and laying cement concrete 1:4:8 (One cement; Four sand; eight graded broken/crushed stone aggregate 40mm (forty millimetres) nominal size) mechanically mixed and curing complete excluding cost of forms work in foundation and plinth in all depth as per H.P.P.W.D specification, approved drawing, design, as per the entire satisfaction and direction of the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	5.40	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	25650.00
5	Steel work welded in built up sections in railing work including cutting hoisting and fixing in position and applying a paint in gratings framed guard bars ladders railings and similar work etc. including carriage of materials within all leads lifts and other incidentals and as per direction of the Engineer-in-charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	250.00	105.00	Rupees One Hundred Five Only	Per Kilogram	26250.00
TOTAL :-						93168.00
Quoted Rate in Figure (%)			(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)			(Amount to be quoted by the contractor in words)			


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY


ESTIMATED COST :- ₹ 99000.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- A/R & M/O Rulehar to Lam road Km 0/000 to 4/000 in Tehsil Shahpur Distt Kangra (H.P).

SUB-HEAD :- Hiring of JCB / excavator cum loader at Rd on 0/00 to 4/00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Hiring of J.C.B./Excavator cum loader (J.C.B.) for removal of slips including trimming and edge cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil due to non availability of departmental machinery as per direction and entire satisfaction of engineering-in- Charge. The J.C.B./Excavator cum loader should work minimum 8.00 (eight) hours daily and excavated at least 30.00(thirty) cubic metre quantity per hour . Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. No deviation shall be allowed in any case.	90.00 Hours	1100.00	Rupees One Thousand One Hundred Only	Per hours	99000.00
TOTAL :-						99000.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


Assistant Engineer,
H.P.P.W.D. Sub-Division,
Darini.


Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

64

S no - 274

ESTIMATED COST :- ₹ 89501.00
EARNEST MONEY :- ₹ 1800.00
TIME LIMIT :- Two Months


NAME OF WORK :- C/o Link road from NH-154 to Hiet College at Shahpur In Khasra No.1 (Deposit work).
SUB-HEAD :- P/L PCC 1:4:8 side locking In CC 1:2:4 and 80 MM thick cement concrete interlocking paver blocks from KM 1/180 to 1/192.40

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.63	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	17243.00
2	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	1.92	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per cubic metre	11808.00
3	Providing and laying 80 mm thick Interlocking M-40 grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shell be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	48.36	1250.00	Rupees One Thousand Two Hundred Fifty Only	Each	60450.00
TOTAL :-						89501.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
RPPWD Shahpur

62

SCHEDULE OF QUANTITY						
Name of Work: C/O 35.00 Metre Span Bridge Over Banoi Khad at Km 0/300 on Link road Ruhru to Narghota Km 0/00-10/500(Sh: - Investigation of Soil Bearing Capacity of Bridge)Abutment-I					Estimated Cost:-	97500.00
					Earnest Money: -	2000.00
					Time Limit :-	One Month
Sr. No	Description of work	Qty	Unit	Rate		AMOUNT Rs. P
				Figure	Words	
1	Investigation Bearing capacity of soil at Bridge Site at different locations(ie. Left side Abutment of minimum 13.00 (Thirteen) meter depth of each bore and submitted the test result complete in all respect .The rate is including GST, toll tax, Sale Tax or other taxes imposed by the government.	13.000	Runnin g Metre			
Total:-						
	Quated rate in Percentage	Excess(+)	%age			
		Less(-)	%age			
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer
 Shahpur Division
 H.P.W.D. Shahpur

63

SCHEDULE OF QUANTITY						
Name of Work: C/O 35.00 Metre Span Bridge Over Banol Khad at Km 0/300 on Link road Ruhru to Narghota Km 0/00-10				Estimated	97500.00	
1/500(Sh: - Investigation of Soil Bearing Capacity of Bridge)Abutment-II				Earnest Money	2000.00	
				Time Limit :-	One Month	
Sr. No	Description of work	Qty	Unit	Rate		AMOUNT Rs. P
				Figure	Words	
1	Investigation Bearing capacity of soil at Bridge Site at different locations(ie. Left side Abutment of minimum 13.00 (Thirteen) meter depth of each bore and submitted the test result complete in all respect .The rate is including GST, toll tax, Sale Tax or other taxes imposed by the government.	13.000	Runnin g Metre			
Total:-						
	Quated rate in Percentage	Excess(+)	%age			
		Less(-)	%age			
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer
 Shahpur Division
 HPKWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99273.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT :- Two Months

NAME OF WORK :- Annual repair and maintenance of various roads under Under HP.PWD. Sub Division Shahpur.

SUB-HEAD :- Painting and writing lettering, figures and kilometre stone etcetra under Harchakin Section,)

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Painting two coats (excluding priming coat) on previously steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning the surface to remove all dirt,dust and other foreign matter with enamel paint other than white including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	44.00 Squire metre	36.10	Rupees Thirty Six And Paise Ten Only	Per square metre	1588.00
2	Painting two or more coats of Nerolac/Asian paint/ Berger (excluding priming coat) on previously concrete based surface with enamel paint white to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering and stoping , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	45.00 Squire metre	86.10	Rupees Eighty Six And Paise Ten Only	Per square metre	3875.00
3	Writing letters or figures on any surfaces with synthetic enamel paint (other than white) stops, comas, hyphens and the like not to be measured and paid separately ,Block letters, Indian letters / figures etc. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	35400.00 Per letter per centimetre hight	2.65	Rupees Two And Paise Sixty Five Only	Per letter per centimetre hight	93810.00
TOTAL :-						99273.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Sd/- Engineer
Shahpur Sub Division
H.P P.W.D. Shahpur

Executive Engineer,
Shahpur Division,
H.P.W.D. Shahpur