

**Himachal Pradesh
Public works Department
Notice inviting Tender**

Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Gohar Division, H.P.PWD Gohar for the following works from the approved and eligible contractors enlisted in H.P.PWD so as to reach in his office on or before **29-11-2025 up to 11.00 A.M.** and will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The D.N.I.T. tender documents can be had from this office against cash payment (Non-refundable) up to 5.00 P.M. on **28-11-2025**. The applications for issue of tender forms will be received **up to 2.00 P.M. on 27-11-2025**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account/F.D. Rs. in any of the Post Office/Nationalized Banks in Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany the request for issue of tender form for each work. Conditional tenders and the tenders received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tenders without assigning any reason. It is further added that the rates be quoted both in words and figures for proper checking to avoid any complications. If the date of opening will be holiday, the tenders will be opened on the next working day at the same time.

Sr. No.	Name of road/work	Estimated Cost	Earnest Money	Time limit
1	R/O Restoration of rain Damages on Dhaban Baggi Diaragi Jai Devi road km 0/00 to 9/00 (SH:- Unlined surface drain, surface dressing, earth filling, Trimming of grass & Removal of slips at various RDs) Under SDF/2025/3341	98,279	2000	Two Month
2	R/O Restoration of rain Damages on Dhaban Tamroh Chauntra road km 0/00 to 5/500 (SH:- Unlined surface drain, surface dressing, earth filling, Trimming of grass & Removal of slips at various RDs) Under SDF/2025/327	77971	1600	Two Month
3	R/O Restoration of rain Damages on Segli Palahota road km 0/00 to 3/00 (SH:- Unlined surface drain, surface dressing, earth filling, Trimming of grass & Removal of slips at various RDs) Under SDF/2025/330	80786	1700	Two Month
4	RRD on Aproach road BSL Colony to Sundernagar Jaidevi to Rohangaloo road via Jangam Baag road km 0/00 to 0/900 (SH:- Removal of balance slip on various RDs)	98939	2000	Two Month
5	RRD on Jaidevi to Siyanji road km. 0/000 to 5/000 (SH:- Removal of balance slip on various RDs)	99756	2000	Two Month

6	RRD on Hafwana to Panyas road km. 0/00 to 17/500 (SH:- Removal of balance slips on various RDs)	96731	2000	Two Month
7	C/o Kukradhar to Babag road km 0/00 to 1/00 (SH:- Formation cutting at RD 0/00 to 0/120) Deposit work	70583	1200	Two Month
8	SDF/2025/702, Repair of Bridal Path Kunkradhar to Chevadi in GP Sainj (SH:- Formation cutting at KM 0/120 to 0/270) Deposit work	66679	1400	Two Month
9	SDF/2025/346 R/O Got Khad Biju road km 0/00 to 2/00 (SH:- C/o wire crate R/wall at RD 3/654.50 to 3/664)	94,049	1900	Two Month
10	SDF/2025/346 R/O Got Khad Biju road km 0/00 to 2/00 (SH:- Hirring of JCB for removal of slips/debris, dressing of berms c/o unlined surface drain etc. at various RDs)	61600	1300	Two Month
11	RRD on Shimla Mandi via Tattapani road km. 115/00 to 135/00 (SH:- Unlined surface drain, Maintenance of earthen shoulder, and Removal of slips at various RDs between km. 120/00 to 123/00)	99042	2000	Two Months
12	RRD on Shimla Mandi via Tattapani road km. 145/00 to 172/00(SH:- Providing and fixing of informatior sign board of size 450 x 600 mm rectangular) OFC Deposit	99000	2000	Two Months
13	RRD on Dhanotu Rohangaloo road km. 0/00 to 32/400(SH:- Providing and fixing of informatory sign board of size 450 x 600 mm rectangular) OFC Deposit	99000	2000	Two Months
14	RRD on Shaheed Tej Singh Jatta Ra Nallah to Harizan Basti Salon Kafflon road km. 0/00 to 5/500(SH:- Removal of slip, C/o unlined surface drain, surface dressing) Under SDF/2025/337	96,338	2000	Two Months
16	RRD on Sikibain to Sarogi road via Chhiba Killing Dahal upto Dahal road km. 0/00 to 4/00 (SH:- C/o Unlined surface dressing, earth filling and removal of slips at various RDs)	99530	2000	Two Months
17	RRD on Bassa Kuther nehra road km. 0/00 to 4/00 (SH:- C/o PCC W/wall at 3/130 to 3/135.50	99,365	2000	Two Months
18	RRD on various roads under Sub-Division Dhanotu HPPWD Dhanotu (SH:- Hiring of Tipper for carriage of different material in various road under Baggi Section)	96,100	2000	Two Months
19	RRD on various road in Baggi section under Dhanotu Sub-Divison (SH:- Hiring of JCB for removal of slips/debris, dressing of berms in various road under Baggi section)	99,000	2000	Two Months
20	SDF/2025/329-Restoration of rain Damages on Dhanotu Rohangaloo road km. 0/00 to 32/400 (SH:- Restoration of rain cuts, and Removal of slip between km. 13/00 to 18/00)	81,518	1700	Two Months
21	SDF/2025/329-Restoration of rain Damages on Dhanotu Rohangaloo road km. 0/00 to 32/400 (SH:- Restoration of rain cuts, and Removal of slip between km. 18/00 to 22/00)	81,518	1700	Two Months

22	RRD on Gopalpur Khadbh road km. 0/00 to 4/00 (SH:- Removal of slips at various RDs under jaidevi section sub-division Dhanotu)	99000	2000	Two Months
----	---	-------	------	------------

Certified that tender of above works are being called for emergent nature in exigency of public interest.

GENERAL CONDITIONS:-

1. The Contractors are required to submit the valid Enlistment/GST registration and latest ITR alongwith application form.
2. The Contractors should quote the percentage rates in the tenders both in figures and words.
3. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
4. An undertaking will have to be given by the contractor that he has not more than two works in hand at the time of opening of this tender.
5. Contractors will have to submit appropriate Earnest Money in the shape of F.D.R along with the application form for getting issued the tender forms. Applications with out EMD shall be summarily rejected.
6. As per Govt. Notification No.PBW(B)A(3)1/2020-I dated 07-10-2021 the tenders above 5% of estimated cost will be summarily rejected. The tender offered below 30 % will also be accepted as per the office letter No. Engineer-in- Chief office letter No. PW-CTR/32-20/Genl Inst. CPWD-2020-37996-38096 dated 13.03.2023 and further ex- post-facto approval has been granted by the Principal Secretary (PW) to the Govt. of H.P. letter No. PBW (B) A(3)1/2020-I dated 10.05.2023. Beside this the additional performance security will have to borne by the bidders as per the said notifications.
7. Conditional and incomplete tenders shall be rejected.
8. The Executive Engineer reserves the right to accept or reject the tender without any reason.

Executive Engineer,
Gohar Division (B&R),
HPPWD Gohar.

Dated - 20/11/2023

No. PW-GHR-Tender/NIT/2025 : -6789-98

Copy along with Tender inviting Notice forwarded for information:-

1. The Deputy Commissioner, Mandi H.P.
2. The Engineer-in-Chief HP.PWD.Shimla.
1. The Superintending Engineer 1stCircle, HP.PWD Mandi.
2. **The Executive Engineer (IT Cell) O/O Engineer-in-Chief, HPPWD Nirman Bhawan, Nigam Vihar, Shimla-2 for uploading the NIT on departmental website please.**
3. The Sub- Divisional Officer (Civil) Chachiot at Gohar.
4. The Block Development Officer Gohar.
5. The Assistant Engineer HPPWD Sub- Division Gohar/Dhanotu.
6. Various contractors.
7. Notice Board/DB/AB.

B.S. Saini
Executive Engineer,
Gohar Division (B&R),
HPPWD, Gohar.

BILL OF QUANTITY

Name of work :- R/O Restoration of rain Damages on Baggi Diaragi Jai Devi road km 0/00 to 9/00 (SH:-
Unlined surface drain, Surface dressing, earth filling, Trimming of grass & Removal of slip at various Rd's)
Under SDIF/2025/334

Estimated cost Rs. - 98,279/-

Earnest Money cost Rs.2,000/-

Time - Two Month

SR. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 300 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge.	45.41	per Cubic metre	181.35		
2	Construction of unlined surface drains of average cross-sectional area 0.20sqm (zero point two zero square metre) in ordinary rock to specified lines, grades, levels and dimensions. excavated material to be used in embankment with a lift upto any metre and lead of any metere as per Technical Specification Clause 307 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	1230.00	per Running metre	22.20		
3	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in any lift and lead upto 1000 m as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge.	388.84	Per Cubic meter	105.20		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- R/O Restoration of rain Damages on Dhaban Tamroh Chauntra road km 0/00 to 5/500(SH:- Unlined surface drain, Surface dressing, earth filling, Trimming of grass & Removal of slip at various Rd's) Under SDF/2025/327					Estimated cost Rs. - 77,971/- Earnest Money cost Rs.1600/- Time - Two Month	
SR. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 300 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge.	84.84	per Cubic metre	181.35		
2	Construction of unlined surface drains of average cross-sectional area 0.20sqm (zero point two zero square metre) in ordinary rock to specified lines, grades, levels and dimensions, excavated material to be used in embankment with a lift upto any metre and lead of any metere as per Technical Specification Clause 307 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	1875.00	per Running metre	22.20		
3	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in any lift and lead upto 1000 m as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge.	199.24	Per Cubic meter	105.20		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar


BILL OF QUANTITY

Name of work :- R/O Restoration of rain Damages on Segli Palahota road km 0/00 to 3/00(SH:- Unlined surface drain, Surface dressing, earth filling, Trimming of grass & Removal of slip at various Rd's) Under SDF/2025/330					Estimated cost Rs. - 80,786/- Earnest Money cost Rs.1700/- Time - Two Month	
SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 300 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge.	75.94	per Cubic metre	181.35		
2	Cutting of branches of trees shrubs and trimming of grass and weeds cutting of branches of trees and shrubs from the road way or with in R.O.W including disposal of wood and leaves to suitable location as per technical specification Clause 1914 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	2610.00	per square metre	5.90		
3	Construction of unlined surface drains of average cross-sectional area 0.20sqm (zero point two zero square metre) in ordinary rock to specified lines, grades, levels and dimensions, excavated material to be used in embankment with a lift upto any metre and lead of any metere as per Technical Specification Clause 307 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	2325.00	per Running metre	22.20		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- RRD on Approach road BSL Colony to Sundernagar Jaidevi to Rohangaloo road via Jangam Baag road km 0/00 to 0/900 (SH:- Removal of balance slip on various RDs)					Estimated cost Rs. 98,939/-	
					Earnest Money cost Rs. 2,000/-	
					Time - Two Month	
SR. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in any lift and lead upto 1000 m as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge.	946.78	Per Cubic meter	104.50		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					


 Executive Engineer
 Gohar Division (B&R)
 HP PWD Gohar

BILL OF QUANTITY

Name of work :- RRD on Jaidevi to Siyanji road km 0/00 to 5/00 (SH:- Removal of balance slip on various RDs)					Estimated cost Rs. 99,756/-	
					Earnest Money cost Rs. 2,000/-	
					Time - Two Month	
SR. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in any lift and lead upto 1000 m as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge.	954.60	Per Cubic meter	104.50		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					


 Executive Engineer
 Gahar Division (B&R)
 HP PWD Gahar



BILL OF QUANTITY

Name of work :- RRD on Hafwana to Panyas road km 0/00 to 17/500 (SH:- Removal of balance slip on various RDs)					Estimated cost Rs. 96,731/-	
					Earnest Money cost Rs. 2,000/-	
					Time - Two Month	
SR. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in any lift and lead upto 1000 m as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge.	925.66	Per Cubic meter	104.50		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					


 Executive Engineer
 Gohar Division (B&R)
 HP PWD Gohar


BILL OF QUANTITY

Name of work :-Construction of Kukradhar to Babag road km 0/00 to 1/00 (SH:- Formation cutting at RD 0/00 to 0/120) Deposit work					Estimated cost Rs. - 70,583/- Earnest Money cost Rs. 1200/- Time - Two Month	
SR. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Excavation in soil in hill area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper blasting work both in soft and hard rock with chiseling / wedging out side of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where required setting out to the required line grades , side slopes trimming bottom and level as shown on drawings as directed by the Engineer-in charge at site according to technical clause 1603.1 and 1603.2 sorting useful / un-useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in roads ways , embankments for grades improvements and leveling to the require grade and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries , materials , tools equipment's and safety measures and incidentals necessary to complete the work by all means (if any required) recovery for 3.84 cubic metre @ Rs. 300.00 per cubic metre amount Rs.1152/- shall be done on prorata basis for the quantity of cutting in earth work effected . Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor , which shall have to be duly compensated by him in all respect including all leads and lifts and materials and as per direction of Engineer in charge .	500.20	Per Cubic meter	141.11		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY

Line of work :-SDF/2023/702, Repair of Bridal Path Kunkradhar to Chevadi in GP Sainj (SH:- Formation cutting at KM 0/120 to 0/270) Deposit work						Estimated cost Rs. - 66,679/-	Earnest Money cost Rs. 1400/-	Time - Two Month
SR. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words		
1	Excavation in soil in hill area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper blasting work both in soft and hard rock with chiseling / wedging out side of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where required setting out to the required line grades , side slopes trimming bottom and level as shown on drawings as directed by the Engineer-in charge at site according to technical clause 1603.1 and 1603.2 sorting useful / un-useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in roads ways , embankments for grades improvements and leveling to the require grade and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour , machineries , materials , tools equipment's and safety measures and incidentals necessary to complete the work by all means (if any required) recovery for 4.62 cubic metre @ Rs. 300.00 per cubic metre amount Rs.1386/- shall be done on prorata basis for the quantity of cutting in earth work effected . Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect including all leads and lifts and materials and as per direction of Engineer in charge .	462.76	Per Cubic meter	144.09				
	Total:-							
	Percentage rate Quoted in figure							
	Percentage rate Quoted in words							


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- SDF/2025/346 R/O Got Khad Biju road km 0/00 to 2/00 (SH:- Construction of wire Crate R/Walla RD 3/654.50 to 3/664)					Estimated cost Rs. - 94,049/- Earnest Money cost Rs.1900/- Time - Two Month	
SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter dia) G.I wire conforming to IS 280 and IS 4826 in 150 mm x 150 mm mesh (woven diagonally) including 10% of laps laid with boulders apron weighing not less than 25 kg (twenty five kilo gram) each as per drawing including all leads ,lifts of material and technical specification clause 1301. wire crate provided by the department within all leads ,lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge complete in all respect.	55.30	Per Cubic meter	1700.70		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					


 Executive Engineer
 Gohar Division (B&R)
 HP PWD Gohar

BILL OF QUANTITY

<p>Name of work :- SDF/2025/346 R/O Got Khad Biju road km 0/00 to 2/00 (SH:- Hirring of JCB for removal of slips/debris , dressing of berms c/o unlined surface drain etc. at various RDs) .</p>					Estimated cost Rs. - 61,600/-	
					Earnest Money cost Rs.1300/-	
					Time - Two Month	
Sr. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of slips/ debris in all kind of soil and saturated soil, dressing of road surface, filling of depressions and disposing of all excavated slips / earth or un-serviseable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	56.00	Per Hour	1100.00		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					


 Executive Engineer
 Gohar Division (B&R)
 HP PWD Gohar

(161)

BILL OF QUANTITY

Name of work :- RRD on Shimla Mandi via Tattapani road km 115/00 to 135/00 (SH:- Unlined surface drain, Maintenance of earthen shoulder, and Removal of slips at various Rd's between km 120/00 to 123/00)					Estimated cost Rs. - 99,042/- Earnest Money cost Rs.2,000/- Time - Two Month	
SR. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Construction of unlined surface drains of average cross-sectional area 0.20sqm (zero point two zero square metre) in ordinary rock to specified lines, grades, levels and dimensions, excavated material to be used in embankment with a lift upto any metre and lead of any metere as per Technical Specification Clause 307 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	1170.00	per Running metre	22.20		
2	Maintenance of earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals .	1406.00	per square metre	15.10		
3	Maintenance of earthen shoulder (Filling with fresh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	1406.00	per square metre	30.20		
4	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in any lift and lead upto 1000 m as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge .	89.13	Per Cubic meter	105.20		
		Total:-				
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

(162)

B/Sarv
 Executive Engineer
 Gohar Division (B&R)
 HP PWD Gohar

BILL OF QUANTITY


Name of work :- RRD on Shimla Mandi via Tattapani road km 145/00 to 172/000 (SH:- Providing and fixing of informative sign board of size 450 x 600 mm rectangular) OFC Deposit					Estimated cost Rs. -99,000/-
					Earnest Money cost Rs. 2,000/-
					Time - Two Month
SR. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P
1	Providing and fixing of 0.27 sqm (zero point twenty seven square metre) in rectangular of retro-reflectored cautionary, mandatory and informative sign board as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm (one point five millimetre) thick supported on a mild steel angle iron post 50 mm x 50 mm x 5 mm (fifty into fifty into five millimetre) firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 250 mm x 250 mm x 300 mm, 600 mm (two hundred fifty into two hundred fifty into three hundred x six hundred) millimetre below ground level as per drawings and Technical Specification Clause 801 as per direction of entire satisfaction on Engineer-in-Charge.	18.00	Per Running Metre	5500.00	
	Total:-				
	Percentage rate Quoted in figure				
	Percentage rate Quoted in words				


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

177

BILL OF QUANTITY


Name of work :- RRD on Dhanotu Rohangaloo road km 0/00 to 32/400 (SH:- Providing and fixing of informative sign board of size 450 x 600 mm rectangular) OFC Deposit					Estimated cost Rs. -99,000/-	
					Earnest Money cost Rs. 2,000/-	
					Time - Two Month	
SR. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Providing and fixing of 0.27 sqm (zero point twenty seven square metre) in rectangular of retro-reflectorised cautionary, mandatory and informative sign board as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm (one point five millimetre) thick supported on a mild steel angle iron post 50 mm x 50 mm x 5 mm (fifty into fifty into five millimetre) firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 250 mm x 250 mm x 300 mm, 600 mm (two hundred fifty into two hundred fifty into thre hundred x six hundred) millimetre below ground level as per drawings and Technical Specification Clause 801 as per direction of entire satisfaction on Engineer-in-Charge.	18.00	Per Running Metre	5500.00		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- RRD on Shaheed Tej Singh Jatta Ra Nallah to Harizan Basti Salon Kafflon road km 0/00 to 5/500 (SH:- Removal of slip, C/o Unlined surface drain, Surface dressing) Under SDF/2025/337					Estimated cost Rs. - 96,338/-	
					Earnest Money cost Rs.2,000/-	
					Time - Two Month	
SR. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Restoration of rain cuts with soil, morum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 300 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge .	335.63	per Cubic metre	181.35		
2	Construction of unlined surface drains of average cross-sectional area 0.20sqm (zero point two zero square metre) in ordinary rock to specified lines, grades, levels and dimensions. excavated material to be used in embankment with a lift upto any metre and lead of any metere as per Technical Specification Clause 307 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	1150.00	per Running metre	22.20		
4	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in any lift and lead upto 1000 m as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge .	94.50	Per Cubic meter	105.20		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

(101)


 Executive Engineer
 Gohar Division (B&R)
 HP PWD Gohar

BILL OF QUANTITY

Name of work :- RRD on Sikibain to sarogi road via Chhiba Killing Dahal upto Dahal road km 0/00 to 4/00 (SH:- C/o Unlined surface drain, Surface dressing, earth filling and removal of slips at various RDs)					Estimated cost Rs. - 99,530/- Earnest Money cost Rs.2,000/- Time - Two Month	
SR. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Construction of unlined surface drains of average cross-sectional area 0.20sqm (zero point two zero square metre) in ordinary rock to specified lines, grades, levels and dimensions. excavated material to be used in embankment with a lift upto any metre and lead of any metere as per Technical Specification Clause 307 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	510.00	per Running metre	22.20		
2	Maintenance of earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals .	1335.00	per square metre	15.10		
3	Maintenance of earthen shoulder (Filling with fresh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals .	1285.00	per square metre	30.20		
4	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in any lift and lead upto 1000 m as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge .	277.97	Per Cubic meter	105.20		
Total:- Percentage rate Quoted in figure Percentage rate Quoted in words						

BILL OF QUANTITY

Scope of work :- RRD on Bassa Kuther Nehra road km 0/000 to 4/00 (SH:- Construction of PCC W/Wall at RD 130 to 3/135.50)

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Estimated cost Rs. - 99,367/-
					Earnest Money cost Rs.2,000/-
					Time - Two Month
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	7.53	Per Cubic meter	230.00	
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals <u>as per direction of Engineer-in-Charge completer in all respect.</u>	21.03	Per Cubic meter	4350.20	
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads ,lifts and carriage of materials and other incidentals <u>as per direction of Engineer-in-Charge completer in all respect.</u>	3.68	Per Cubic meter	1050.60	
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer-in-Charge complete in all respect.	6.00	Each	380.70	
	Total:-				
	Percentage rate Quoted in figure				
	Percentage rate Quoted in words				

BILL OF QUANTITY

Name of work :- RRD on various roads under Sub Division Dhanotu HPPWD Dhanotu (SH:- Hiring of Tipper for carriage of different material in various road under Baggi Section)

Estimated cost Rs. - 96,100/-


Earnest Money cost Rs. 2,000/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of Tipper for carriage/ disposal of debris to dumping site of work with lift to suitable place with in all leads and lifts to the entire satisfaction of the Engineer-in Charge . The Tipper should work minimum 9.00 AM to 5.00 PM daily any loss to the public/ private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the Tipper owner which shall have to be fully compensated by him in all cases the fuel and Tipper driver and lodging & boarding of operational staff will be provided by the Tipper owner the repair and spare including watch and ward of Tipper also borne by the contractor /owner. The daily log book will be maintained at site which should be dully verified by the Engineer-in charge.	31.00	Days	3100.00		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

Terms and conditions:-

- 1 The daily logbook will be maintained at site which should be daily verified by the Engineer-in-Charge
- 2 During working hours any type of accident or loss of private/Govt. property the owner is responsible.
- 3 Driver and POL will be provided by the owner.


 Executive Engineer
 Gehar Division
 H.P.P.W.D. Gehar


 108

BILL OF QUANTITY

Name of work :- RRD on various road in Baggi section under Dhanotu Sub - Division (SH:- Hirring of JCB for removal of slips/debris , dressing of berms in various road under Baggi section) .						Estimated cost Rs. - 99,000/-
						Earnest Money cost Rs.2,000/-
						Time - Two Month
Sr. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of slips/ debris in all kind of soil and saturated soil, dressing of road surface, filling of depressions and disposing of all excavated slips / earth or un-serviseable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	90.00	Per Hour	1100.00		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

Terms and conditions:-

- 1 The daily logbook will be maintained at site which should be daily verified by the Engineer-in-Charge
- 2 During working hours any type of accident or loss of private/Govt. property the owner is responsible.
- 3 Driver and FOL will be provided by the owner.


 Executive Engineer
 Gohar Division
 R.P.P.W.D. Gohar

(107)

BILL OF QUANTITY

Name of work :- SDF/2025/329- Restoration of rain Damages on Dhanotu Rohangaloo road km 0/00 to 32/400 (SH:- Restoration of rain cuts, and Removal of slip between km 13/00 to 18/00)					Estimated cost Rs. - 81,518/-	
					Earnest Money cost Rs.1700/-	
					Time - Two Month	
SR. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 300 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge.	239.85	per Cubic metre	181.35		
2	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge.	3000.00	per Running metre	4.70		
3	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in any lift and lead upto 1000 m as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge.	227.39	Per Cubic meter	105.20		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					


 Executive Engineer
 Gohar Division (B&R)
 HP PWD Gohar

BILL OF QUANTITY

Name of work :- SDF/2025/329- Restoration of rain Damages on Dhanotu Rohangaloo road km 0/00 to 32/400 (SH:- Restoration of rain cuts, and Removal of slip between km 18/00 to 22/00)					Estimated cost Rs. - 81,518/- Earnest Money cost Rs.1700/- Time - Two Month	
SR. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 300 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge.	239.85	per Cubic metre	181.35		
2	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge.	3000.00	per Running metre	4.70		
3	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in any lift and lead upto 1000 m as per technical specification 3023.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge.	227.39	Per Cubic meter	105.20		
		Total:-				
Percentage rate Quoted in figure						
Percentage rate Quoted in words						