

Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

"NOTICE INVITING TENDERS"

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD, Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **22-11-2025** up to 11.00 AM. and the same shall be opened on the same day at **11.30 A.M.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on 21-11-2025 up to **4.00 P.M** and the application for issue of tender form shall be received on 21-11-2025 up to **1.00 PM**.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	A/R & M/O Hamirpur Sujampur Thural Maranda road km. 30/00 to 59/775 (SH:- P/F Dul Directional retro reflective cat eyes studs in km. 55/750 to 56/240)	98400/-	2000/-	One Month	350/-
2	A/R & M/O Hamirpur Sujampur Thural Maranda road km. 30/00 to 59/775 (SH:- P/F Dul Directional retro reflective cat eyes studs in km. 55/250 to 55/730)	96000/-	1900/-	One Month	350/-
3	Restoration of rain damages on Hamirpur Sujampur Thural Maranda road km. 30/00 to 59/775 (SH:- P/L crate work in km. 44/230 to 44/237)	96711/-	1900/-	Three Month	350/-
4	Restoration of rain damages on Tikkar Balbhurian road km. 0/00 to 4/00 (SH:- P/L crate work in km. 3/610 to 3/622.50)	97810/-	2000/-	Three Month	350/-
5	C/O Ambulance road from Deor Basti road to Kala house Mundhi (SH:- P/L Soling & wearing at RD. 0/166 to 0/254) (DC Deposit) SDP/2024/491	99286/-	2000/-	Three Month	350/-
6	C/O Link road from Ghartholi to Rajehar Ghaogehar Lasenu, Palashan & Patehlim (SH:- C/O 900mm dia hume pipe cause way at RD 0/240) (DC Deposit) SDP/2023/956	199443/-	4000/-	Three Month	350/-
7	A/R & M/O on Hamirpur Sujampur Thural Maranda road km. 45/500 to 59/775 (SH:- Painting & writing of boards at various RDs)	96750/-	1900/-	One Month	350/-

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm has to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.

Executive Engineer
Bhawarna Division
HPPWD Bhawarna

On behalf of Governor of Himachal Pradesh


Dated:- 13/11/2025

No. PWD/BWD/TA/NIT/2025-26/

Copy is forwarded to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Superintending Engineer, 5th Circle, HPPWD., Palampur.
3. All the Assistant Engineers under this Division.
4. The Computer Cell office of the Engineer-in-Chief, HPPWD. Shimla for uploading the NIT on the departmental website.
5. The Drawing /Accounts Branch in this office.
6. Notice Board.


Executive Engineer,
Bhawarna Division,
HPPWD. Bhawarna.



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

CERTIFICATE

Certified that tender of works are being called of an emergent nature and for larger public interest so there is exigencies/ emergency in calling these tenders without press vide this office letter No. PWD/BWD/TA/NIT/2025-26-9887-9C dated: 13-11-2025.


Executive Engineer,
Bhawarna Division,
HPPWD. Bhawarna.

Schedule of Quantity

1

Work of work:- A/R & M/O Hamirpur Sujapur Thural Maranda road Km 30/00 to 59/775


Estimate Cost :- Rs. 98,400/-

Earnest Money :- Rs. 2000/-

Time Limit :- One Month

H:- P/F Dual Directional retro reflective cat eyes studs in Km 55/750 to 56/240)

No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		Rs.
1	Providing and fixing dual Directional retro reflective cat eyes studs made from high quality ABS plastic stud of size 90x100mm (Ninety into one hundred millimetre) at 4 (four) meter center to center (C/C) provided with fixing to roads by hammering made of gree lite complete as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	246.00	400.00	Rupees Four Hundred Only	Each	98400.00
					Total:-	98400.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

2

ne of work:- A/R & M/O Hamirpur Sujanpur Thural Maranda road Km 30/00 to 59/775


Estimate Cost :- Rs. 96,000/-

Earnest Money :- Rs. 1900/-

Time Limit :- One Month

SH:- P/F Dual Directional retro reflective cat eyes studs in Km 55/250 to 55/730)

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		Rs.
1	Providing and fixing dual Directional retro reflective cat eyes studs made from high quality ABS plastic stud of size 90x100mm (Ninety into one hundred millimetre) at 4 (four) meter center to center (C/C) provided with fixing to roads by hammering made of gree lite complete as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	240.00	400.00	Rupees Four Hundred Only	Each	96000.00
Total:-						96000.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawarna / Division
 HP PWD Bhawarna

Schedule of Quantity

3


Of Work :- Restoration of rain damages on Hamirpur Sujampur Thural Maranda road Km 30/0 to 59/775 (SH:- P/I Crate
k in Km 44/230 to 44/237).

Estimate Cost :- Rs. 96,711/-

Earnest Money :- Rs. 1900/-

Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	6.13	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	1533.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone bounders weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	32.82	2900.00	Rupees Two Thousand Nine Hundred Only	Per Cubic metre	95178.00
Total :-						96711.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

4


Name of Work :- Restoration of rain damages on Tikker Balbhurian road Km 0/00 to 4/00 (SH:- P/I Crate work in Km 3/610 to 3/622.50).

Estimate Cost :- Rs. 97,810/-

Earnest Money :- Rs. 2000/-

Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		Rs.
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	19.69	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	4923.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone bounders weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	32.03	2900.00	Rupees Two Thousand Nine Hundred Only	Per Cubic metre	92887.00
Total :-						97810.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

5


ne of Work:-Construction of Ambulance road from Deor Basti Road to Kala House Mundhi. (SH:- P/L Soling & Wearing at RD 6 to 0/254) (DC Deposit)

Estimated Cost :- Rs. 99,286/-

Earnest Money :- Rs. 2000/-

Time Limit :- Two Months

No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	28.16	2000.00	Rupees Two Thousand Only	Per Cubic metre	56320.00
	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five milimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	20.46	2100.00	Rupees Two Thousand One Hundred Only	Per Cubic metre	42966.00
Total :-						99286.00
Quoted rates percentage in figures						
Quoted rates percentage in words						



 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work:- C/o link road from Ghartholi to Rajehar Gharhgar Lasenu, Palashan & Patehlim. (SH:- C/o 900mm dia Hume pipe casue way at RD Estimated Cost :- Rs. 1,99,443/-
0/240 (DC Deposit) . Earnest Money :- Rs. 4000/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	7.57	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	1893.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	7.77	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	38462.00
	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub-structure for all type of structure complete of plain cement concrete nominal mix 1: 2 ½ :5 (One cement : two point five sand : five graded crushed/ broken stone aggregate 20mm (Twenty millimetre) nominal size) on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths in abutments etcetera and the like including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and as per direction of Engineer-in-Charge Including carriage of material within all leads and lifts and other incidental . The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.94	5500.00	Rupees Five Thousand Five Hundred Only	Per Cubic metre	54670.00
	Providing and laying (to level or slope) 900mm dia (Nine hundred millimetre) diameter reinforced cement concrete non pressure pipes IS Class NP-2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications section 1100 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	15.00	3900.00	Rupees Three Thousand Nine Hundred Only	Per Running metre	58500.00

5	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.48	4300.00	Rupees Four Thousand Three Hundred Only	Per Cubic metre	23564.00
6	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.34	700.00	Rupees Seven Hundred Only	Per Cubic metre	4438.00
7	Providing, laying, Soling 90 to 45mm (Ninety to forty five milimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clasue 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.58	2000.00	Rupees Two Thousand Only	Per Cubic metre	3160.00
8	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 20mm (Twenty millimeter) nominal size in open foundation as per drawing and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203, including the cost of form work, curing complete and hauling of materials in all kinds of leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.38	6200.00	Rupees Six Thousand Two Hundred Only	Per Cubic metre	14756.00
Total :-						199443.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

7


ne of Work :- A/R &M/O on Hamiprur Sujapur Thural Maranda road Km 45/500 to 59/775 (SH:- Painting & writing of boards at various Rd's)

Estimate Cost :- Rs. 96,750/-

Earnest Money :- Rs. 1900/-

Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		Rs.
1	Painting one coat (excluding priming coat) on previously painted steel and other metal surfaces with enamel paint of Asian/ Nerolac to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	62.00	60.00	Rupees Sixty Only	Per Square Metre	3720.00
2	Writing letters or figures on any surface with black japan paint (stops,comas,hyphens and the like not to be measured and paid separately) as per the direction of Engineer-in-Charge.					
	Block letters/figures	21500.00	2.25	Rupees Two And Paise Twenty Five Only	Per letter per centimeter height	48375.00
	Indian(letters/figures)	21500.00	2.25	Rupees Two And Paise Twenty Five Only	Per letter per centimeter height	48375.00
Total :-						96750.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna