HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PWD/DEH/CB/Tender/2025.26- 8212-33 Dated 21/11/25
To

The Executive Engineer (IT Cell)
HPPWD Nirman Bhawan Nigam Bihar
HPPWD Shimla

Subject:- **Tender Notice**

Sir,

Enclosing Kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on Department website as per notification of Principal Secretary (PW) to the Govt. of HP vide No ; PWD/(B) A(3) 1/2024 dated 03.01.2024 as the works mentioned in the inviting tender are urgent in nature and public interest

Executive Engineer,
Dehra Division HP.PWD.,
Dehra.

Copy to the F.C-cum- Secretary (PW) to the Govt. of Himachal Pradesh Shimla - 2 for favour of information please.

Copy to the Engineer-in-Chief HPPWD Shimla for information please.

Copy to the Chief Engineer (KZ) HPPWD Dharamshala for favour of information please.

Copy to the Superintending Engineer 9th Circle HPPWD Nurpur for favour of information please.

Copy to Notice Board

Copy to All the head of Branches

Copy to All the Contractors working under Dehra Division

Executive Engineer,
Dehra Division HPPWD.,
Dehra.

H. P. P.W.D. TENDER

Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Dehra Division HPPWD., Dehra on behalf of the Governor of HP for the following works from the approved and eligible contractors (C&D Class) enlisted in HPPWD.

TENDER SCHEULE:

1. Date and time of receipt of application for tender form: 02.12.2025 upto 1.00 PM
2. Date and time of issue of tender form: 02.12.2025 upto 5.00 PM
3. Date and time of receipt of tenders: 03.12.2025 upto 11.00 AM
4. Date and time of opening of tenders: 03.12.2025 at 11.30 AM

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dehra Division HPPWD Dehra must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
1	Restoration of Rain Damages on Jawalamukhi Dehra Raja ka Talab Talab Road in km 22/00 to 29/00 (SH:- Providing & erecting's" metal beam crash beam Crash barrier at Various Rds in Km 22/00 to 25/00) Under PDNA	Rs499148	Rs.10000/-	Three month.	Rs.350/-
2	Restoration of Rain Damages on Bankhandi to Kherian Road Km 0/0 to4/00 (SH- C/O Hume Pipe culverts at Rd 0/830 along with walls & Causeway from Rd 2/490 to2/509 Edge wall from Rd 0/695 to 0/743 LHS) Under PDNA	Rs496946	Rs.10000/-	One month.	Rs.350/-
3	Restoration Of Rain Damages on Jwala Mukhi Dehra Jawali Raja Ka Talab Road Km 22/00 to 39/180 (SH :- Demolition & Re – Construction of Rain shelter kherian at Rd 22/055 & Bilaspur (Bhater) at Rd 34/465 (under PDNA	Rs254325	Rs.6000/-	One month.	Rs.350/-
4	Restoration of Rain Damages on Bankhandi to Haripur Road km 0/0 to 8/00 (SHC/O R/Wall from Rd 6/981 to 6/992 RHS)	Rs495453	Rs.10000/-	One month.	Rs.350/-
5	Restoration of rain Damages on Jawalmukhi Dehra Jawali Raja ka Talab Road in km 22/00 to 29/00 SH :- Providing & erecting's" metal beam crash beam Crash barrier at Various Rds in Km 25/00 to 29/00) Under PDNA	Rs.488972	Rs.10000/-	One month.	Rs.350/-
6	Restoration of Rain Damages on Gopipur to Chamukha Road in km 0/0 to 6/00 ((SH:- Providing & erecting's" metal beam crash beam Crash barrier at Various Rds in Km 3/300 to to 4/410) Under PDNA	Rs.499316	Rs.10000/-	One month.	Rs.350/-
7	Restoration of Rain Damages on Gopipur to Chamukha Road in km 0/0 to 6/00 ((SH:- Providing & erecting's" metal beam crash beam Crash barrier at Various Rds in Km 2/700 to to 2/830) Under PDNA	Rs.499316	Rs.10000/-	One month.	Rs.350/-
8	Restoration of Rain Damages on on Kaloha Pragpur NehranPukhar Dhaliara Dada Siba Road km 9/00 to 22/200 (SH:- Providing and laying 80mmthcik Interlocking Paver Block at Rd 18/210 to 18/248)	Rs429410	Rs.10000/-	Three month.	Rs.350/-

1.	The contractors/firms should possess the following documents(Photocopy to be attached with the application): Copy of Registration/Latest renewal of enlistment.
(i)	PAN (Permanent Account No.)
(ii)	Registration under GST No.
(iii)	EPF(Employee Provident Fund Account No.)
(iv)	The proof ownership/hire/lease, buying of required machinery for micro surfacing works.
(v)	
2	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.
3	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).
4	The offer of the tender shall remain valid upto 30 days after the opening.

Executive Engineer
HPPWD Division Dehra
Distt Kangra H.P.
on behalf of Governor of Himachal Pradesh
HIM LOK SAMPARK

(334)

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,99,148.00
Earnest Money :- Rs. 10,000.00
Time Limit :- Three Months.

Name of work:- Restoration of rain damages on J/Mukhi Dehra Jawali Raja Ka Talab Road in Km 22/000 to 29/000 (SH:- Providing & erecting "W" metal beam crash barrier at various RD's in Km. 22/00 to 25/00). Under PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	***Earth work in excavation in foundation for all types of structures such*** as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	8.04 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	2,332.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-15 (M-Fifteen) Nominal mix 1:2½:5 (one cement isto two and half sand isto five graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water, including pumping or bailing out water/ dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, in sub structure etcetera including cost of form work and curing complete as per MORD technical specification clauses 802, 804, 805, 806, 807, 1202 & 1204 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Toll tax, Sale tax or any other taxes imposed by the Government.	8.58 Cubic metre	5200.00	Rupees Five Thousand Two Hundred Only	Per Cubic metre	44,616.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing an erecting a "W" metal beam crash barrier comprting of 2mm (Two milimetre) tack comuged et metal beam rail, 70cm (Seventy continetre) above rod ground level, fixed on ISIC series channel vertical post, 150x75x5mm (One hundred fifty into seventy five into ve milanatre) spacelt 2m (Two mets) centre to centre, 1.8m (One point eight metraj high, 1 tin [One point one metrs) below graundiroad level, all steel parts and Innerts to be golvanised by nat dip process, all fittings to confirm to S:1367 and 15:1554, metal beam rail to be fand on the vertical post with a spacer of channel section150x25x5mm, (One hundred titty into savenly five into live milimetre) 330mm (Three hundred eaty milimetre) long complete as per clause 810 Engineer-in charge, including camage of matenais ethio all leads, lifts and other incidentals. The rate is including Octro, Reyality, Makara, GST, tot tax or ary sther tres imposed by the Government	133.00 Running metre	3400.00	Rupees Three Thousand Four Hundred Only	Per Running metre	4,52,200.00
	Total					4,99,148.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage BLOQ quantity checked & approved for Rs 499148/-

Executive Engineer,
Dehra Division ,
HPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,96,946.00
Earnest Money :- Rs. 10,000.00
Time Limit :- Three Months.

Name of work:- Restoration of rain damages on Bankhandi to Kherian road Km 0/0 to 4/000 (SH:- Construction of Hume Pipe culverts at RD 0/830 alongwith wing walls & Causeway from RD 2/490 to 2/509, Edge wall from RD 0/695 to 0/743 LHS). Under PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	54.80 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	15,892.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	34.55 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	1,39,928.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	36.01 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	1,78,250.00
4	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-15 (M-Fifteen) Nominal mix 1:2½:5 (one cement isto two and half sand isto five graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water, including pumping or bailing out water/ dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, in Abutments and toe walls, Parapets etcetera including cost of form work and curing complete as per MORD technical specification clauses 802, 804, 805, 806, 807, 1202 & 1204 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Toll tax, Sale tax or any other taxes imposed by the Government.	14.39 Cubic metre	5200.00	Rupees Five Thousand Two Hundred Only	Per Cubic metre	74,828.00
5	Providing and laying (to level or slope) 900mm (Nine Hundred millimeter) diameter ISI marked reinforced cement concrete Light duty non pressure pipes I.S class NP-3 as per design for culverts on type 'A' (concrete cradle) bedding of M-15 (M-fifteen) grade cement concrete in single row including providing and fixing collar with cement mortar 1:2 (one cement isto two sand) but excluding the cost of excavation, protection works, back filling, concrete and masonary work in head walls and parapets etcetera as per drawing and MORD Technical specification as clause 1106 complete and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, GST, Toll tax, sale tax or any other taxes imposed by the Government	7.50 Running metre	3500.00	Rupees Three Thousand Five Hundred Only	Per Running metre	26,250.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
6	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub structure Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in Bed block and Dirt wall etcetera, including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete for all heights/depths and any quantum of water complete including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, Toll tax or any other taxes imposed by the Government.	10.31 Cubic metre	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic metre	59,798.00
7	Providing 100mm (One Hundred millimeter) dia PVC pipe Weep Holes in brick masonry/stone masonry/plain /reinforced concrete abutments, wing wall/ return wall, retaining walls and breast walls etcetra, extending through the full width of the structure with slope of IV:20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 & 1200 and as per the directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, toll tax or any other taxes imposed by the Government.	8.00 Numbers	250.00	Rupees Two Hundred Fifty Only	Each	2,000.00
	Total					**4,96,946.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage Bill & quantity checked & approved for Rs 496946/—

Executive Engineer,
Dehra Division,
UPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 2,54,325.00
Earnest Money :-Rs. 6,000.00
Time Limit :- Two Months.

Name of work:- Restoration of rain damages on J/Mukhi Dehra Jawali Raja Ka Talab road Km 22/0 to 39/180 (SH:- Demolition & Re-Construction of Rain Shelter Kherian at RD 22/055 & Bilaspur (Bhated) at RD 34/465). (Under PDNA).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal ofunserviceable material within 50 metres lead complete and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Octroi, Royality, Malkhana, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	5.04 Cubic metre	1465.35	Rupees One Thousand Four Hundred Sixty Five And Paise Thirty Five Only	Per Cubic metre	7,385.00
2	Demolishing stone rubble masonry manually/ by mechanical means in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead complete and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Octroi, Royality, Malkhana, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	37.66 Cubic metre	1011.75	Rupees One Thousand Eleven And Paise Seventy Five Only	Per Cubic metre	38,103.00
3	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains of soil such as pick work, jumper work, pick jumper work, blasting work, jumper blasting work, soft and hard blasting and saturated soil, de-watering, including wedging out rocks where blasting work is prohibited, chiseling or any other mixed variety of soil, including shoring, strutting or bailing out water upto any depth or any height quantum of water including de-watering removal of slush and stacking the serviceable and un-serviceable material clear from the edge of excavation as per direction of Engineer-in-Charge and returning the stacked soil in 15cm (Fifteen centimeter) layers, when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming, watering and then disposing of all excavated earth including carriage of material within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-Incharge. The rate is inclusive of octroi, royality, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	2.48 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	719.00
4	Providing and laying cement concrete 1:4:8 (One cement isto four sand isto eight graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete excluding cost of forms work in foundation and plinth within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of Octroi, Royality, Malkhana, Toll tax, Sale tax, GST and any other taxes imposed by the Government.	2.69 Cubic metre	4955.20	Rupees Four Thousand Nine Hundred Fifty Five And Paise Twenty Only	Per Cubic metre	13,329.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
5	Providing form work with steel plates 3.15mm (Three point one five millimeters) thick, welded with angle iron in frame 30x30x5mm (Thirty into Thirty into Five millimeters) so as to give a fair finish including centering, shuttering strutting and propping etc, with wooden battens and ballies, height of propping and centering in all heights. below supporting floor to ceiling and removal of the same for in situ reinforced concrete and plain concrete work in Suspended floors, roofs, landings, balconies, shelves and access platform and the like floor, etc. up to any thickness, up to all floor level and as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Toll Tax Sales tax or any other taxes imposed by the Government.	9.12 Square metre	486.30	Rupees Four Hundred Eighty Six And Paise Thirty Only	Per Square metre	4,435.00
6	Providing and laying in position machine batched and machine mixed cement concrete work of grade M-25 (M-Twenty five) design mix to obtain the minimum compressive strength of 25N/mm2 (Twenty five niewton per square millimetre) with cement contents not less than @ 360 kg/cum (at the rate Three hundred sixty kilogram per cubic metre) or as per approved design mix. All works above plinth level upto all floor level to give a smooth surfaces machanically mixed and vibrated including curing complete and pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability etcetera including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royality, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	3.01 Cubic metre	6934.90	Rupees Six Thousand Nine Hundred Thirty Four And Paise Ninety Only	Per Cubic metre	20,874.00
7	Supplying and stacking of hard stone (for stone pitching) 22.5cm (Twenty two point five centimatre) thick at site including watering ramming, consolidation and dressing complete as per specification and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	0.76 Cubic metre	969.80	Rupees Nine Hundred Sixty Nine And Paise Eighty Only	Per Cubic metre	737.00
8	Providing and laying 40mm (forty millimeter) thick cement concrete flooring 1:2:4 (One cement isto two sand isto four graded stone. aggregate 20mm (Twenty millimetre) nominal size) laid one layer finished with a floating coat of neat cement. including preparation of surface grading complete and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Octroi, Royality, Malkhana, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	24.00 Square metre	378.95	Rupees Three Hundred Seventy Eight And Paise Ninety Five Only	Per Square metre	9,095.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
9	Providing and applying 15mm (fifteen millimeters) thick cement plaster with cement mortar 1:6 (one cement isto six sand) in single coat on rough side of brick/concrete/ stone walls for interior plastering upto all floor level including arises, internal rounded angles, chamfers and/or rounded angles in all girth and finished even and smooth complete as per HPPWD specifications and as per direction by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Royality, Malkhana, Octroi, GST, Toll Tax Sales tax or any other taxes imposed by the Government.	41.32 Square metre	196.45	Rupees One Hundred Ninety Six And Paise Forty Five Only	Per Square metre	8,117.00
10	Steel work of Tata/Sail, riveted, bolted or welded in built up sections, framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Octroi, Royality, Malkhana, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	750.00 Kilogram me	107.45	Rupees One Hundred Seven And Paise Forty Five Only	Per Kilogram me	80,588.00
11	Providing and fixing 0.60mm (zero point six zero millimetre) thick ISI marked Z-120 (Z-one hundred twenty) prepainted steel sheet of TATA/Sail/Relience/Jindal in roofing over steel trusses with hot dip metalic zinc coated sheet with top coat of regular modified polyster (RMP) Organic coating of 20 (TWENTY) microns over 5 (five) microns of primer back coat of polyster of 5 (five) microns over 5 (five) primer coating including finishing with prepainted, iron J or L hoks, bolts and nuts 6mm (six millimeter) diametre with prepainted limpet and rubber washer filled with required colour and laid completely with all accessories or required as per direction of Engineer-In-charge including carriage of materials with in all lead and lift and other incidental as per the direction of Engineer-in-Charge. The rate including Royality, Malkhana, Octroi, GST, Toll Tax Sales tax or any other taxes imposed by the Government.	40.03 Square metre	1086.00	Rupees One Thousand Eighty Six Only	Per Square metre	43,473.00
12	Providing and fixing ridges or hips 60cm (Sixty centimetre) over all with 0.60 (zero point six zero millimetre) thick prepainted steel sheet of TATA/Sail in roofing with hot dip metalic zinc coated sheet with top coat of regular modified polyster (RMP) organic coating of 20 (Twenty) microns over 5 (five) microns of primer back coat of polyster of 5 (five) microns over 5 (five) primer coating including finishing with prepainted iron J or L hoks, bolts and nuts 6mm (six millimeter) diametre with prepainted limpet and rubber washer complete with all accessories or required as per direction of Engineer-in-Charge including carriage of materials with in all lead and lift and other incidental. The rate including Royality, Malkhana, Octroi, GST, Toll Tax Sales tax or any other taxes imposed by the Government.	4.90 Running metre	721.90	Rupees Seven Hundred Twenty One And Paise Ninety Only	Per Running metre	3,537.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
13	Providing and fixing **M.S. black plain sheet 2.00mm** (Two point zero zero millimeter) thick in facia/eaves boards/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per HPPWD specifications and as direction by the Engineer-in-Charge, (base members of steel work shell be measured and paid for separately), including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Octroi, GST, Toll Tax Sales tax or any other taxes imposed by the Government.	9.33 Square metre	1692.40	Rupees One Thousand Six Hundred Ninety Two And Paise Forty Only	Per Square metre	15,790.00
14	Painting steel work with Deluxe Multi Surface Paint to give an even shade Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.80 ltr/10 sqm of approved brand and manufacture completed and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	40.00 Square metre	89.90	Rupees Eighty Nine And Paise Ninety Only	Per Square metre	3,596.00
15	Finishing walls with weather proof exterior emulsion paint of Asian/Dulux /Berger/Nerolac Suraksha paints of approved shade having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	41.32 Square metre	110.05	Rupees One Hundred Ten And Paise Five Only	Per Square metre	4,547.00
	TOTAL					**2,54,325.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage BUG 94 on qty checked & PPPW for Rs 254325/-

Executive Engineer,
Dehra Division ,
HPPWD Dehra.

336

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,95,453.00
Earnest Money :-Rs. 10,000.00
Time Limit :- Three Months.

Name of work:- Restoration of rain damages on Bankhandi to Haripur road Km 0/00 to 8/000 (SH:- Construction of Retaining wall from RD 6/981 to 6/992 RHS).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation **in foundation for all types** of road structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown in the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification section 300 & 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, toll tax or any other taxes imposed by the Government.	55.77 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	16,173.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in open foundation for all type of structure and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900 and 1200 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, toll tax or any other taxes imposed by the Government.	111.61 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	4,52,021.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	30.00 Numbers	250.00	Rupees Two Hundred Fifty Only	Each	7,500.00
4	Back filling with granular material behind abutment Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200 & 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, toll tax or any other taxes imposed by the Government.	16.50 Cubic metre	750.00	Rupees Seven Hundred Fifty Only	Per Cubic metre	12,375.00
5	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-15 (M-Fifteen) Nominal mix 1:2½:5 (one cement isto two and half sand isto five graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water, including pumping or bailing out water/ dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, in Parapets etcetera including cost of form work and curing complete as per MORD technical specification clauses 802, 804, 805, 806, 807, 1202 & 1204 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Toll tax, Sale tax or any other taxes imposed by the Government.	1.42 Cubic metre	5200.00	Rupees Five Thousand Two Hundred Only	Per Cubic metre	7,384.00
	Total					4,95,453.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage Bid & quantity checked & approved to Rs 495453/-

Executive Engineer,
Dehra Division,
PPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. **4,88,972.00**
Earnest Money :- Rs. **10,000.00**
Time Limit :- Three Months.

Name of work:- Restoration of rain damages on J/Mukhi Dehra Jawali Raja Ka Talab Road in Km 22/000 to 29/000 (SH:- Providing "W" metal beam crash barrier in Km. 25/00 to 29/000 at various RD's).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	***Earth work in excavation in foundation for all types of structures such*** as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	10.87 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	3,152.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-15 (M-Fifteen) Nominal mix 1.2½:5 (one cement isto two and half sand isto five graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water, including pumping or bailing out water/ dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, in sub structure etcetera including cost of form work and curing complete as per MORD technical specification clauses 802, 804, 805, 806, 807, 1202 & 1204 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Toll tax, Sale tax or any other taxes imposed by the Government.	11.60 Cubic metre	5200.00	Rupees Five Thousand Two Hundred Only	Per Cubic metre	60,320.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing an erecting a "W" metal beam crash barrier comprting of 2mm (Two milimetre) tack comuged et metal beam rail, 70cm (Seventy continetre) above rod ground level, fixed on ISIC series channel vertical post, 150x75x5mm (One hundred fifty into seventy five into ve milanatre) spacelt 2m (Two mets) centre to centre, 1.8m (One point eight metraj high, 1 tin [One point one metrs) below graundiroad level, all steel parts and Innerts to be golvanised by nat dip process, all fittings to confirm to S:1367 and 15:1554, metal beam rail to be fand on the vertical post with a spacer of channel section150x25x5mm, (One hundred titty into savenly five into live milimetre) 330mm (Three hundred eaty milimetre) long complete as per clause 810 Engineer-in charge, including camage of matenais ethio all leads, lifts and other incidentals. The rate is including Octro, Reyality, Makara, GST, tot tax or ary sther tres imposed by the Government	115.00 Running metre	3700.00	Rupees Three Thousand Seven Hundred Only	Per Running metre	4,25,500.00
	Total					**4,88,972.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage BLL of quantity check & approved Rs 488972/—

Executive Engineer,
Dehra Division ,
HPPWD Dehra.

336

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,99,316.00
Earnest Money :- Rs. 10,000.00
Time Limit :- Three Months.

Name of work:- Restoration of rain damages on Gopipur to Chamukha Road in Km 0/00 to 6/00 (SH:- Providing & erecting "W" metal beam crash barrier at various RD's in Km. 3/300 to 4/410). Under PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	***Earth work in excavation in foundation for all types of structures such*** as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	10.44 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	3,028.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-15 (M-Fifteen) Nominal mix 1:2½:5 (one cement isto two and half sand isto five graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water, including pumping or bailing out water/ dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, in sub structure etcetera including cost of form work and curing complete as per MORD technical specification clauses 802, 804, 805, 806, 807, 1202 & 1204 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Toll tax, Sale tax or any other taxes imposed by the Government.	10.44 Cubic metre	5200.00	Rupees Five Thousand Two Hundred Only	Per Cubic metre	54,288.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing an erecting a "W" metal beam crash barrier comprting of 2mm (Two milimetre) tack comuged et metal beam rail, 70cm (Seventy continetre) above rod ground level, fixed on ISIC series channel vertical post, 150x75x5mm (One hundred fifty into seventy five into ve milanatre) spacelt 2m (Two mets) centre to centre, 1.8m (One point eight metraj high, 1 tin [One point one metrs) below graundiroad level, all steel parts and Innerts to be golvanised by nat dip process, all fittings to confirm to S:1367 and 15:1554, metal beam rail to be fand on the vertical post with a spacer of channel section150x25x5mm, (One hundred titty into savenly five into live milimetre) 330mm (Three hundred eaty milimetre) long complete as per clause 810 Engineer-in charge, including camage of matenais ethio all leads, lifts and other incidentals. The rate is including Octro, Reyality, Makara, GST, tot tax or ary sther tres imposed by the Government	130.00 Running metre	3400.00	Rupees Three Thousand Four Hundred Only	Per Running metre	4,42,000.00
	Total					**4,99,316.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage Bill & quantity checked & Approved for Rs 499316/-

Executive Engineer,
Dehra Division ,
HPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. **4,99,316.00**
Earnest Money :- Rs. **10,000.00**
Time Limit :- Three Months.

Name of work:- Restoration of rain damages on Gopipur to Chamukha Road in Km 0/00 to 6/00 (SH:- Providing & erecting "W" metal beam crash barrier at various RD's in Km. 2/700 to 2/830). Under PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	***Earth work in excavation in foundation for all types of structures such*** as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	10.44 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	3,028.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-15 (M-Fifteen) Nominal mix 1:2½:5 (one cement isto two and half sand isto five graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water, including pumping or bailing out water/ dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, in sub structure etcetera including cost of form work and curing complete as per MORD technical specification clauses 802, 804, 805, 806, 807, 1202 & 1204 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Toll tax, Sale tax or any other taxes imposed by the Government.	10.44 Cubic metre	5200.00	Rupees Five Thousand Two Hundred Only	Per Cubic metre	54,288.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing an erecting a "W" metal beam crash barrier comprting of 2mm (Two milimetre) tack comuged et metal beam rail, 70cm (Seventy continetre) above rod ground level, fixed on ISIC series channel vertical post, 150x75x5mm (One hundred fifty into seventy five into ve milanatre) spacelt 2m (Two mets) centre to centre, 1.8m (One point eight metraj high, 1 tin [One point one metrs) below graundiroad level, all steel parts and Innerts to be golvanised by nat dip process, all fittings to confirm to S:1367 and 15:1554, metal beam rail to be fand on the vertical post with a spacer of channel section150x25x5mm, (One hundred titty into savenly five into live milimetre) 330mm (Three hundred eaty milimetre) long complete as per clause 810 Engineer-in charge, including camage of matenais ethio all leads, lifts and other incidentals. The rate is including Octro, Reyality, Makara, GST, tot tax or ary sther tres imposed by the Government	130.00 Running metre	3400.00	Rupees Three Thousand Four Hundred Only	Per Running metre	4;42,000.00
	Total					**4,99,316.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage BLUG quantity checked & approved for Rs 499316/-

Executive Engineer,
Dehra Division ,
HPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs 429410.00
Earnest Money :-Rs. 9000.00
Time Limit :- Three Month.

Name of work:- **Restoration of Rain Damages on Kaloha Pragpur Nehranpukhar Dhaliara Dadasiba Road km. 9/00 to 22/200 (SH:- Providing and Laying 80mm thick Interlocking Paver Block at RD.18/170 to 18/208)**

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	26.60 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	7,714.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	26.60 Cubic meter	4050.00	Rupees Four Thousand Fifty Only	Per Cubic meter	1,07,730.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure and the like in solid causeway and Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government	6.75 Cubic meter	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic meter	39,150.00
4	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 80 mm of M-30 grade with approved color design and pattern in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, toll tax, sale tax ,GST or any other taxes imposed by the Government.	243.20 Square meter	1130.00	Rupees One Thousand One Hundred Thirty Only	Square meter	2,74,816.00
	Total					4,29,410.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage Bill Quantity checked & approved to Rs 429410/-

Executive Engineer,
Dehra Division,
HPPWD Dehra