

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.: PW/ESDD/CONT/2025-26/-

5962-71

Dated: 10-11-2025

To

The Executive Engineer (IT Cell),
Nigam Vihar, Shimla-2.

Subject: Publishing of Short Term Tender Notice.

Jai Hind

Enclosed please find herewith the Tender Notice of works as given in the Notice Inviting Tender along with Schedule of Quantities for uploading on departmental website as per Notification Pr. SEC(PW) to the Govt. of HP letter No. PBW(B)A9(3)1/2020 dated Shimla-26th July 2021.

It is certified that the works mentioned in the Notice Inviting Tenders are urgent in nature and in public Interest.

DA/NIT,SQs


Executive Engineer
Electrical Division
HP PWD Palampur

Copy forwarded to the following for information and necessary action please:

1. The Superintending Engineer, 2nd Electrical Circle, HP PWD Dharamshala.
2. All the Assistant Engineers Working under this Division.
3. Drawing Branch of this office.
4. The Notice board in this office.


Executive Engineer
Electrical Division
HP PWD Palampur

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"Notice Inviting Tenders"**

Sealed percentage rate tenders on form 7&8 are hereby invited by the Executive Engineer, Electrical Division, HP PWD Palampur on behalf of the Governor of H.P. for the following work from the approved and eligible contractors enlisted in HP.PWD, (Elect.) whose registration stood renewed as per revised rules and also registered under the H.P. General Sales Tax Act, 1968 so as to reach in his office on or before **21-11-2025** up to 11.00 AM, and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on **20-11-2025** up to 4.00 P.M. and the application for issue of tender form shall be received on **20-11-2025** up to 12.00 noon.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time Limit	Form No.	Cost of Form
1	Repair and maintenance of E.I of various Non Residential building under ESD Dharamshala Distt. Kangra (H.P)(SH:- Replacement of burnt and unrepairable E.I in Rest House Dharamshala	90,842/-	1900/-	Three Months	Three Months	350/-
2	R/M of E.I in Vidhan Sabha Complex at Tapovan Dharamshala Distt. Kangra (H.P)(SH:-Replacement of AMF Controller , time relay etc of 100 KVA DG set installed in Vidhan Shaba Complex Tapovan at Dharamshala Distt. Kangra (H.P)	61,138/-	1300/-	Three Months	Three Months	350/-
3	Repair and maintenance of E.I of various non residential building under ESD Dharamshala Distt. Kangra (H.P)(SH:- Providing and fixing Air Conditioning system VVIP set therein).	96,690/-	2000/-	Three Months	Three Months	350/-
4	Repair and maintenance of E.I Circuit House building under ESD Dharamshala Distt. Kangra (H.P).(SH:-Annual repair and maintenance of A.C 1.0 Ton/2.0 Ton capacity split type under ESD Dharamshala for the year 2025-26.).	72,800/-	1500/-	Three Months	Three Months	350/-
5	Repair and maintenance of E.I in various Govt. N/R building under ESD Dharamshala Distt. Kangra (H.P).(SH:-Annual repair and maintenance of A.C 1.0 Ton/2.0 Ton capacity split type under ESD Dharamshala for the year 2025-26.).Dharamshala section-II).	67,000/-	1400/-	Three Months	Three Months	350/-
6	R/M of E.I in various Govt. N/R building under ESD Dharamshala , Distt. Kangra (H.P)(SH:-Providing and fixing CCTV for Biometric machine surveillance , shifting of video conferencing system and tower speaker set in the meeting hall of Chief Engineer (KZ)HPPWD Dharamshala).	76,770/-	1600	Three months	Three months	350/-
7	Construction of Shree Mata Chamunda Mata Temple in Tehsil Dharamshala Distt. Kangra (H.P)(Providing steel conduit &PVC conduit and GI box therein).	97,748/-	2000/-	Three months	Three months	350/-
8	Repair and maintenance of Electrical Installation (E.I)to main boys hostel at Dr. RPGMC Kangra at Tanda for the year 2025-2026.	96,766/-	2000/-	Three months	Three months	350/-
9	Construction additional VIP Room (G,F),3Nos. rooms and street light at Jaisinghpur in Distt. Kangra (H.P)(SH:-Providing E.I)(Balance work therein).	98,952/-	2000/-	Fifteen Days	Fifteen Days	350/-
10	Repair and day to day maintenance of electrical installtion (E.I) to 1st year MBBS Girls Hostel at Dr. RPGMC Tanda.	98,883/-	2000/-	Six month	Six month	350/-
11	Construction of Hall for Har Har Mahadev Mahila mandal at upper Bagoda Teh. Palampur,Distt. Kangra (H.P.) (SH:- Providing E.I. therein)	71,944/-	1500/-	One year	One year	350/-
12	Annual Repair and maintenance of A.C 1.5 Ton capacity (various type and various make) in various Govt. Buildings under Electrical Sub Division Nurpur for the year 2025-26 (Fatehpur Section).	99,400/-	2000/-	One year	One year	350/-
13	Annual repair and maintenance of portable Fire Extinguishers installed in various hostel of 500 bedded Hospital in Dr. RPGMC Kangra at Tanda .(SH:-Refilling of portable fire extinguishers of different capacity and type of 1st year MBBS	65,920/-	1400/-	One month	One month	350/-

	girls hostel Ravi hostels and library building of 500 bedded in Dr. RPGMC Tanda).					
14	Annual repair and maintenance of portable Fire Extinguishers installed in various hostel of 500 bedded Hospital in Dr. RPGMC Kangra at Tanda. (BH -Refilling of portable fire extinguishers of different capacity and type of , intern hostel , main boys & girls hostel , Satluj and 1st year MBBS boys hostel of 500 bedded in Dr. RPGMC Tanda).	80,240/-	1600/-	One month	One month	355/-
15	Replacement of safety device and E I in Vet Hospital Chowki Khalet in Tehsil Palampur Distt. Kangra (H P).	95,616/-	2000/-	One month	One month	355/-

HIM SUCHNA AYAM JAN SAMPARK VIBHAG

This is certified that the above works are required to be carried out immediately being emergent nature of work in Public Interest. The Tender documents shall be issued only to those contractor/firm who fulfill the following criteria/documents with the application.

Conditions:

1. The contractor should have the EPF registration certificate should be attached with application.
2. The GST registration certificate.
3. The contractor should produce a copy of latest enlistment/renewal.
4. The latest ITR filed should be attached with application.
5. The bidders enlisted in a particular class shall be eligible to tender for his own class or one step below.
6. The bidder should attach authorization and work done certificate with application for Specialized Jobs.
7. In case of Holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
8. Ambiguous/telephonic/conditional tenders or tenders fax/email/whatsapp shall not be considered and will be summarily be rejected.
9. The FDR duly pledged should be attached separately with each tender.
10. Only two number tender forms will be issued to the eligible contractor.
11. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected.
12. The Executive Engineer, Electrical Division, HP PWD Palampur reserves the right to reject any tender without assigning any reasons.


Executive Engineer
Electrical Division
HP PWD Palampur

On behalf of Governor of Himachal Pradesh

SCHEDULE OF QUANTITY

Name of Work :- Repair and maintenance of E.I of various Non residential building under ESD Dharamshala Distt Kangra (H.P) (SH : Replacement of burnt and unrepairable E.I. in Rest house Dharamshala).

job No ①

**ESTIMATED COST: Rs.90,842/-only.
EARNEST MONEY: Rs.1900/-only
TIME ALLOWED: Three Months**

SR. NO.	DESCRIPTION	QTY.	RATES		UNIT	AMOUNT
			FIGURES	WORDS		
1.00	Supplying and fixing following modular switch/socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. (Make:- Anchor/ Schneider/ Legrand/L&T)					
1.01	S.P. 5/ 6 Amps one way Modular switch.	~~9~~	93	Rupees Ninety Three Only	Each	~~837~~
1.02	S.P. 15/ 16 Amps one way Modular switch.	~~6~~	164	Rupees One Hundred Sixty Four Only	Each	~~984~~
1.03	5 pin, 5/ 6 Amps Modular socket outlet.	~~6~~	136	Rupees One Hundred Thirty Six Only	Each	~~816~~
1.04	6 pin, 15/16 Amps Modular socket outlet.	~~7~~	231	Rupees Two Hundred Thirty One Only	Each	~~1617~~
2.00	Supplying and fixing following size/modules, G.I box alongwith modular base & cover for modular switches in recess etc.as required. (Make:- Anchor/ Schneider/ Legrand/L&T)					
2.01	6 Module (200mmX75mm)	~~6~~	425	Rupees Four Hundred Twenty Five Only	Each	~~2550~~
2.02	8 Module (250mmX75mm)	~~6~~	462	Rupees Four Hundred Sixty Two Only	Each	~~2772~~

3.00	Supplying and fixing 6 amps to 32 amps rating, 240/415 volts, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
3.01	6 Amp Single pole	~~3~~	239	Rupees Two Hundred Thirty Nine Only	Each	~~717~~
3.02	16/25 Amp Single pole	~~3~~	239	Rupees Two Hundred Thirty Nine Only	Each	~~717~~
4.00	Supplying and fixing following rating, double pole, 240 V, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
4.01	40 Amps. (Make:- Anchor/ Schneider/ Legrand/L&T)	~~2~~	426	Rupees Four Hundred Twenty Six Only	Each	~~852~~
4.02	63 Amps. (Make:- Anchor/ Schneider/ Legrand/L&T)	~~2~~	530	Rupees Five Hundred Thirty Only	Each	~~1060~~
5.00	Providing and installation of stationary storage type Electric water heater ((Geyser) of various sizes by means of Expansion-bolts with nuts and washers, including embedding of expansion-bolts in the wall, providing and fixing of Non-return valve, Dead weight safety valve, 2 No C.P. connection rods 18" long, making good the damages, electrical connections, safety valve connections, testing and commissioning etc. as required:-					
5.01	35 Liter capacity water heater (Cat-A) Makes: Usha/Bajaj/Racold	~~1~~	14083	Rupees Fourteen Thousand Eighty Three Only	Each	~~14083~~
6.00	Providing and installation exhaust fan of following sizes in the existing opening, including making the hole to suit the size of the above fan, making good the damages, connections, testing and commissioning etc. as required.					

6.01	Exhaust Fan, Light duty, (Domestic) 300 mm sweep Makes: Bajaj/Usha/Crompton	2 ✓	2567	Rupees Two Thousand Five Hundred Sixty Seven Only	Each	5134 ✓
7.00	Providing and fixing LED tube fixture (including the cost of Batten/channel and LED Lamp) suitable for surface application with the use of the latest technology 18 watt (1800 Lumen) 6000K and it should be compatible with specification i.e. Power Factor $\geq$ 0.9, Harmonic Distortion $\leq$ 10% and efficacy $\geq$ 100 Lumens per watt, CRI rating > 80 suitable for input voltage: AC 220-240 V, 50 Hz, complete with all accessories, connections, testing and commissioning etc. as required. Makes: Havells/ Bajaj/ Philips /Wipro.	3 ✓	867	Rupees Eight Hundred Sixty Seven Only	Each	2601 ✓
8.00	Supplying and fixing LED lamps of Following watt with polycarbonate diffuser on the existing light point as required complete in all respect.					
8.01	LED Lamp 12 watt	12 ✓	187	Rupees One Hundred Eighty Seven Only	Each	2244 ✓
9.00	Providing skilled Electrician-II and unskilled Team-mate for cleaning of LED Luminaires, Switches and sockets, ceiling fans, exhaust fans, mirror lights, Fancy wall brackets and reconnection of electrical panels, insulation testing & earth testing etc. as required complete in all respects.	1 ✓	9248	Rupees Nine Thousand Two Hundred Forty Eight Only	Per Job	9248 ✓
10.00	Supplying and fixing metal box of 180mm X 100mm X 60mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in FRLS on including providing and fixing 6 pin 15/16 amps socket outlet and 15/16 amps piano type switch, connection, painting etc. as required.	9 ✓	406	Rupees Four Hundred Six Only	Each	3654 ✓

11.00	Supplying and fixing of LED Post Top fixtures of 35 watt and are made of Spun alum. Top and cast alum. base provided with UV stabilized P.C. diffuser. Power LED's mounted on metal clad PCB's then mounted on extruded/cast aluminium Heat Sinks complete with all accessories, including connections, testing and commissioning etc. as required complete in all respects. Makes: (Wipro/ Twinkle/ Bajaj/ Panasonic).	2	7899	Rupees Seven Thousand Eight Hundred Ninety Nine Only	Each	15798
12.00	Earthing with G.I. earth plate 600 mmx600 mmx 6 mm thick, including accessories and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt) as required.	2	7899	Rupees Seven Thousand Eight Hundred Ninety Nine Only	Per set	15798
13.00	Supplying and laying 6 SWG G.I. wire at 0.50 mtr. below ground level for earth electrode conductor, including soldering etc. as required.	180	52	Rupees Fifty Two Only	Per Metre	9360
	Total					90842

Schedule of Quantity checked & Approved As 90842/-

Executive Engineer
Electrical Division
HP PWD Palampur

[Signature]

SCHEDULE OF QUANTITY

Name of Work :- R/M of E.I in VIDHAN SABHA Complex at Tapovan
Dharamshala Distt Kangra (H.P) (SH : Replacement of AMF
Controller, Time relay etc. of 100 KVA D.G. Set installed in VIDHAN
SABHA Complex Tapovan at Dharamshala Distt Kangra (H.P.)

job No
2

ESTIMATED COST: Rs.61,138/-only.
EARNEST MONEY: Rs.1300/-only
TIME ALLOWED: Three Months

SR. NO.	DESCRIPTION	QTY.	RATES		UNIT	AMOUNT
			FIGURES	WORDS		
1	Providing and fixing AMF Controller (1 No), sensor LOP (1 No) Sensor Water (1 No), Time relay (1 No) with wiring and calibration etc. as required complete in all respects in the existing Panel of 100 KVA DG Set	1	61138.00	Rupees Sixty One Thousand One Hundred Thirty Eight Only	Per Job	61138
Total						61138

Schedule of Quantity checked & approved by

As 61138-100

Executive Engineer
Electrical Division
HP PWD Palampur

[Signature]

SCHEDULE OF QUANTITY

Name of Work :-Repair and maintenance of E.I of various Non residential building under ESD Dharamshala Distt Kangra (H.P) (SH:- Providing and fixing Air Conditioning System VVIP set therein).		Job No 2		ESTIMATED COST: Rs.96,690/-only. EARNEST MONEY: Rs.2000/-only TIME ALLOWED: Three Months		
SR. NO.	DESCRIPTION	QTY.	RATES		UNIT	AMOUNT
			FIGURES	WORDS		
1.00	Supplying, installation, testing and commissioning of Following Ton (Hot & Cold) 3 star Inverter Split type Air-Conditioning unit with R32 Refrigerent, Power supply 1 Phase 50 Hz, 230 V of following make confirming to I.S.I.-1391 PART-1992 with ammendment No. 1 (expect power consumption norms) fitted with hermatically shielded air-compressor, making connections , testing etc. as required complete in all respects.					
1.02	A.C. Unit 1.8/ 2.0 Ton capacity (Split Inverter)	1	71585	Rupees Seventy One Thousand Five Hundred Eighty Five Only	Each	71585
1.03	Makes:- Daikin/ O-General /Mitsubishi/ Toshiba					
2.00	Providing & fixing of M.S. Outdoor heavy duty stand powder coated suitable suitable to hang Following type AC with six nos. anchor bolts (The make of outdoor units and compressor shall be same) as required complete in all respects.					
2.01	MS Outdoor Stand for Split AC 1.8 / 2.0 TR	1	750	Rupees Seven Hundred Fifty Only	Each	750
3.00	Supplying, Installation, testing & Commissioning of the insulated refrigerant piping Size of (6.4-12.7) mm and (9.5-15.9) mm for all the Outdoor Units as per specifications with insulation of thick 19 mm Nitrlie rubber through out the running length of the refrigerant piping. Nitrlie Rubber of Density 50+20% (Class O) kg/m3 to interconnect Indoor & Outdoor Units for each circuit etc. as required complete in all respects.					

3.01	Ref. Copper Piping for AC 2.0 TR	5	1056	Rupees One Thousand Fifty Six Only	Per Meter	5280
4.00	Supplying and fixing of PVC hard drain piping with fitting, valves & insulation with 10mm for indoor Application Closed Cell nitrile rubber 60+/-10kg/m ³ with the accessories in surface/recess including cutting the wall and making good the same etc. as required complete in all respect.	10	135	Rupees One Hundred Thirty Five Only	Per Meter	1350
5.00	Supplying and fixing of cable tray DLP trunking size 105mmx50mm for covering of copper pipe along with the accessories etc. as required complete in all respects.	10	1480	Rupees One Thousand Four Hundred Eighty Only	Per Meter	14800
6.00	Providing and laying of Communication Shielded cabling between ODU & IDU and between ODU & central controller in flexible PVC Conduit etc. as required complete in all respects.					
6.01	Control cabling from indoor to outdoor unit Split AC	15	195	Rupees One Hundred Ninety Five Only	Per metre	2925
	Total					96690

Schedule of Quantity checked & approved for Rs 96690/- only

Executive Engineer
Electrical Division
HP PWD Palampur

[Signature]

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
Name of Work :-Repair and Maintenance of E.I in Circuit House building Dharamshala under ESD Dharamshala Distt. Kangra (H.P.) (SH:-Annual repair and Maintenance of A.C 1.0 Ton/ 1.5 Ton/ 2Ton capacity Split type under ESD Dharamshala for the year 2025-26.)			ESTIMATED COST: Rs.72,800/-only. EARNEST MONEY: Rs.1500/-only TIME ALLOWED: One Year			
SR. NO.	DESCRIPTION	QTY.	RATES		UNIT	AMOUNT
			FIGURES	WORDS		
1.00	Annual Repair and Maintenance (Routine & preventive) of various makes' types and different capacity Split AC's with four numbers mandatory services and all emergency break down services as and when required from time to time as per the best satisfaction of Engineer-in-Charge. The firm shall maintain the register of servicing record with the department.					
1.01	The A.M.C will include the following:-					
1.02	Maintenance of voltage stabilizer and other accessories extra copper pipe with insulation wire, PVC drain pipe, Capacitor, Thermostat, Relay, blower motor indoor unit, outdoor unit fan motor, fan blade, Timers, PCB, temperature sensors, Evaporators, Condensers, Driers, Capillary, Control box, Refilling of Gas when required and replacement of compressor, servicing, cleaning the filter and Four Nos of service time to time as per satisfaction of Engineer-in - charge.					
1.03	All defective components shall be replaced with compatible working parts and defective parts shall be company's/ firm/ contractor's property.					
1.04	Split type Air Conditioner 1 Ton/ 1.5 Ton	4	4400	Rupees Four Thousand Four Hundred Only	Each	17600
1.05	Split type Air Conditioner 1.8 Ton/ 2 Ton/ 2.5 Ton	12	4500	Rupees Four Thousand Six Hundred Only	Each	55200
Total						72800

Schedule of Quantity checked & Approved As In

72800/-only

Executive Engineer
 Electrical Division
 HP PWD Palampur

Bm

SCHEDULE OF QUANTITY

Name of Work :- Repair and Maintenance of E.I in various Govt N/R buildings under ESD Dharamshala Distt. Kangra (H.P.) (SH:-Annual repair and Maintenance of A.C 1.0 Ton/ 1.5 Ton/ 2Ton capacity Split type under ESD Dharamshala for the year 2025-26.) (Dharamshala Section-II)
--

job No

ESTIMATED COST: Rs.67,000/-only.
EARNEST MONEY: Rs.1400/-only
TIME ALLOWED: One Year

SR. NO.	DESCRIPTION	QTY.	RATES		UNIT	AMOUNT
			FIGURES	WORDS		
1.00	Annual Repair and Maintenance (Routine & preventive) of various makes/ types and different capacity Split AC's with four numbers mandatory services and all emergency break down services as and when required from time to time as per the best satisfaction of Engineer-in-Charge. The firm shall maintain the register of servicing record with the department					
1.01	The AMC will include the following:-					
1.02	Maintenance of voltage stabilizer and other accessories extra copper pipe with insulation wire, PVC drain pipe, Capacitor, Thermostat, Relay, blower motor indoor unit, outdoor unit fan motor, fan blade, Timers, PCB, temperature sensors, Evaporators, Condensers, Driers, Capillary, Control box, Refilling of Gas when required and replacement of compressor servicing, cleaning the filter and Four Nos of service time to time as per satisfaction of Engineer-in - charge.					
1.03	All defective components shall be replaced with compatible working parts and defective parts shall be company's/ firm/ contractor's property.					
1.04	Split type Air Conditioner 1 Ton/ 1.5 Ton	10	4400	Rupees Forty Four Thousand Only	Each	44000
1.05	Split type Air Conditioner 1.8 Ton/ 2 Ton/ 2.5 Ton	5	4600	Rupees Forty Six Thousand Only	Each	23000
	Total					67000

Schedule	Quantity	checked	Approved for
14	1		

Executive Engineer
Electrical Division
HP PWD Palampur

~~Executive Engineer~~
Electrical Division
HP PWD Palampur

SCHEDULE OF QUANTITY

Name of Work :-R/M of E.I. in various Govt. N/R buildings under ESD Dharamshala, District Kangra (H.P.) (Providing and fixing CCTV for Biometric machine surveillance, Shifting of Video Conferencing system and Tower speaker set in the meeting hall of Chief Engineer (KZ) HPPWD Dharamshala).			job No 6		ESTIMATED COST: Rs.76,770/-only. EARNEST MONEY: Rs.1600/-only TIME ALLOWED: Three Months	
SR. NO.	DESCRIPTION	QTY.	RATES		UNIT	AMOUNT
			FIGURES	WORDS		
1.00	Supplying, installation, testing and commissioning of Tower Speaker set (1 set = 2 speaker) with Wireless Mic. The speaker is a 2.0 tower speaker system with a total RMS power output of 60 watts (30W + 30W) and a frequency response of 40Hz-20KHz. Key features include Bluetooth, USB, SD/MMC card, and AUX input connectivity, an FM radio tuner, a 3.5mm AUX input, an LED display, a remote control, and dual wireless microphones for karaoke. The system supports MP3 file formats from USB/SD cards and has a maximum supported memory size of 32GB. General Specifications Output Power (RMS): 60W (30W + 30W), Frequency Response: 40Hz-20KHz, S/N Ratio: ≥70Db, Separation: ≥45dB Connectivity & Storage, Wireless: Bluetooth, Wired: 3.5mm AUX Input, USB/SD Card Support: Supports MP3 file format up to 32GB memory size, Media Inputs: USB, SD/MMC card, AUX Features, Channel: 2.0 channel Tower Speaker, Display: LED Display, Control: Fully functional remote control, Microphones: Dual wireless microphones with separate volume and echo controls, Radio: Built-in FM Radio with an antenna for better reception, Additional: Karaoke functionality with dual microphone input jacks, Design: Contemporary design with a wooden enclosure etc. as required complete in all respects. Makes: Zebtronics/ JBL/ Sony or any other equivalent make.	1	31750	Rupees Thirty One Thousand Seven Hundred Fifty Only	Per set	31750

2.00	Supplying, installation, testing and commissioning of Network Dual lens camera resolution 2MP+2MP (4MP), Access, manage and control your cameras, Store alarm or continuous video recording in the SSD card, Get real time text or image alert notification on your phone, Two way talking system with SSD Card 128GB. Makes:- True view/ Care cam pro/ ezviz or any other equivalent make.	3	6190	Rupees Six Thousand One Hundred Ninety Only	Each	18570
3.00	Supplying and laying Cat6 UTP cable solid bare copper conductor, Comply with Cat6 specifications, 4-pair unshielded twisted pair (UTP) cable, Pairs are braided in aluminum foil with drain wire, 23 AWG solid copper conductor. Makes: D-link/Molex/ Beldon	90	55	Rupees Fifty Five Only	Per Metre	4950
4.00	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required. Makes: Diplast/Polyplast/Anchor/BEC.	75	90	Rupees Ninety Only	Per Metre	6750
5.00	Shifting and fixing (Removing and Reinstallation) of Video conferencing System from old building to New building (The Chamber of Chief Engineer (KZ) Dharamshala) including the following component A. LOGITECH MEETUP (video bar) Ultra HD image sensor, all-in-one design. B. EPOS (MIC) EXPAND 30+, Bluetooth speaker with USB type C. LG Commercial 4K UHD Smart TV 65UT801C, Backlight Direct, 4K UHD, Resolution 3,840 x 2,160 (4K UHD), Screen Size 65", Refresh Rate 60 Hz Native. D. USB Extended cable. E. HDMI Cable, etc. as required Complete in all respect.	1	14750	Rupees Fourteen Thousand Seven Hundred Fifty Only	Per job	14750
Total						76770

Schedule of Quantity checked & Approved for

PS 769770-104

Executive Engineer
Electrical Division
HP PWD Palampur

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
Name of Work :-Construction of Shree Chamunda Mata Temple in Tehsil Dharamshala District Kangra (H.P.) (Providing Steel conduit & PVC conduit and GI Box therein).			job No 12		ESTIMATED COST: Rs.97,748/-only. EARNEST MONEY: Rs.2000/-only TIME ALLOWED: Three Months	
SR. NO.	DESCRIPTION	QTY.	RATES		UNIT	AMOUNT
			FIGURES	WORDS		
1.00	Supplying and fixing of following sizes of steel conduit along with the accessories in surface / recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as required:-					
1.01	25 mm. dia	145	202	Rupees Two Hundred Two Only	Per metre	29290
2.00	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.					
2.01	S/D 3 X 1.5 sq. mm	70	100	Rupees One Hundred Only	Per metre	7000
2.02	S/D 6 X 1.5 sq. mm	20	193	Rupees One Hundred Ninety Three Only	Per metre	3860
3.00	Supplying and fixing following size/modules,G.I box alongwith modular base & cover for modular switches in recess etc.as required.					
3.01	6 Module	4	266	Rupees Two Hundred Sixty Six Only	Each	1064
3.02	12 Module	12	313	Rupees Three Hundred Thirteen Only	Each	3756
4.00	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.					
4.01	25mm PVC Conduit	450	87	Rupees Eighty Seven Only	Per metre	39150

5.00	Supplying and fixing of following way triple pole and neutral, sheet steel MCB distribution board, 415 volts, on surface / recess, with provision to mount 4 pole MCCB incomer, 2 module sub-incomer and SP MCBs as outgoing, complete with tinned copper bus-bar, wire-set, neutral link, earth bar, din-bar, detachable gland plate, cable, identification labels interconnections, phosphatized and powder painted, including earthing etc. as required.					
5.01	Double door 2+12 way (MCCB+6+36) module.	1	13628	Rupees Thirteen Thousand Six Hundred Twenty Eight Only	Each	13628
	Total					97748

Schedule of Quantity checked & Approved for
ps 97748-teny

Signature
 Executive Engineer
 Electrical Division
 HP PWD Palampur

SCHEDULE OF QUANTITY

NAME OF WORK :- Repair & Maintenance of Electrical Installation (E.I.) to Main Boys Hostel at Dr. RPGMC Kangra at Tanda for the year 2025-26.		8		ESTIMATED COST:-96,766/-only. EARNEST MONEY: Rs.2000/-only TIME ALLOWED: -one Year		
SR. NO.	DESCRIPTION	job No	RATES	WORDS	UNIT	AMOUNT
1	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.					
1.1	2x4sq.mm	40	311.00	Rupree three hundred eleven only	Per Meter	12440
	Make:- Finolex/Anchor/Plaza					
2	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.					
2.1	3x1.5 Sq. mm.	60	100.00	Rupree one hundred only	Per Meter	6000
	Make:- Finolex/Anchor/Plaza					
3	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required.					
3.1	5/6 amps Piano type switch	40	42.00	Rupree forty two only	Each	1680
3.2	15/16 Amps. Piano type switch	35	116.00	Rupree one hundred sixteen only	Each	4060
3.3	5/6 amps Piano type socket	35	57.00	Rupree fifty seven only	Each	1995.00
3.4	15/16 amp Piano type socket	35	123.00	Rupree one hundred twenty three only	Each	4305
	Makes:- Anchor-Romal&T/Schneider					

4	Supplying and fixing LED retrofit lamp suitable for B-22 holder base fittings with polycarbonate diffuser and aluminium heat sink as required complete in all respects.					
4.1	9 Watt LED Lamp	40	157.00	Ruppee one hundred fifty seven only	Each	6280
	Makes:- Havells/Panasonic/Osram					
5	Supplying and fixing 6 amps to 32 amps rating, 240/415 volts, 10 KA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
5.1	Single pole	12	239.00	Ruppee two hundred thirty nine only	Each	2868
	Makes:- Anchor-Uno/L&T/Schneider					
6	Supplying and fixing following rating, double pole, 240 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
6.1	63 Amps	5	530.00	Ruppee five hundred thirty only	Each	2650
	Makes:- Anchor-Uno/L&T/Schneider					
7	Supplying and fixing Batten Holder as required complete in all respects.					
7.1	Batten Holder	25	80.00	Ruppee eighty only	Each	2000
	Makes:- Havells/L&T/Bajaj					

5	Providing and fixing decorative LED mirror light having high quality design suitable for LED tube up to 10Watt (1000 lumen) 6500K and it should be compatible with specifications i.e. power factor ≥ 0.9 , harmonic distortion $\leq 10\%$ and efficacy ≥ 100 lumens per watt, CRI > 80 , suitable for input voltage AC 220-240V, 50/60 Hz, complete with all accessories, connections, testing and commissioning etc. as required.					
S.1	10 Watt LED Mirror Light, 2 ft.	25	426.00	Rupree four hundred twenty six only	Each	10650
	Makes: Havells/Bajaj/Osram					
9	Providing and fixing of LED batten having minimum efficacy of 100 lm/W, P.F. >0.95 with THD $<10\%$, CCT 6500 K, CRI 80, Surge Protection range 2 kV. The LED with useful life of 50000 Hrs at L70 with five years warranty. The Input voltage shall be 150V to 270V, 50/60 HZ along with all accessories, including connections, testing etc. as required complete in all respects.					
9.1	LED Batten 20 Watt	45	606.00	Rupree six hundred six only	Each	27270
	Makes:- Wipro/Havells/Bajaj					
10	Providing and Fixing of IP20 LED fixture of 18 watt +/- 1 W LED Surface Mounted Downlighter Round Shape with minimum system lumen efficacy of 100 lm/W with Polycarbonate housing, pressure die cast heat sink and P.F. >0.95 with THD $<10\%$, CRI 80. The LED shall be tested with LM80-08 standard with Useful life of 50000 Hrs at L70. The LEDs used in the luminaire shall have CCT of ANSI Bin 5700 K with CRI of minimum 80. The Input voltage range shall be 150V to 270V, 50/60 HZ complete with all accessories, including connections, testing and commissioning etc. as required complete in all respects.					

10.1	LED surface Mounting Round Downlighter	8	1,821.00	Rupee one thousand eight hundred twenty one only	Each	14568
	Makes:- Wipro/Havells/Panasonic					
	Total:-					96766

Schedule of Quantity checked & approved for Rs 96,766/- only

[Signature]
Executive Engineer
Electrical Division
HPPWD Palampur

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
NAME OF WORK :- C/O Additional VIP Room (G.F.) ,3 nos. Rooms and street light at Jaisinghpur in Tehsil Jaisinghpur in Distt. Kangra HP(SH:- Providing E I (Balance Work therein)		Ⓟ		ESTIMATED COST:-98,952/-only. EARNEST MONEY: Rs.2000/-only TIME ALLOWED: 15Days		
SR. NO.	DESCRIPTION	job No	RATES	WORDS	UNIT	AMOUNT
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required.					
	Group B	8	1650	Ruppee one thousand six hundred fifty only	Per point.	13200
	Havells/KEI/Phinolex make					
2	Supplying and fixing of following way, single pole and neutral sheet steel MCB distribution board, 240 volts, on surface / recess, complete with tinned copper bus- bar, neutral link, earth bar, din-bar, interconnections, powder painted, including earthing etc. as required.-(But without MCB/RCCB/isolator)					
	Double door-12 way	2	2055	Ruppee two thousand fifty five only	Each	4110
	L&T/Legrand/Schneider make					
3	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed steel conduit as required					
	2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	20	332	Ruppee three hundred thirty two only	P/Mtr.	6640
	2 X 10 sq. mm + 1 X 6 sq. mm earth wire	22	696	Ruppee six hundred ninety six only	P/Mtr.	15312.00

	2 X 4.0 sq. mm + 1 X 4.0 sq. mm earth wire	45	395	Rupree three hundred ninety five only	P/Mtr.	17775
	2 X 6.0 sq. mm + 1 X 6.0 sq. mm earth wire	25	564	Rupree five hundred sixty four only	P/Mtr.	14100.00
	Havells/KEI/Phinolex make					
4	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel PVC conduit as required					
	3x2.5 sq mm	80	151	Rupree one hundred fifty one only	P/Mtr.	12080
	Havells/KEI/Phinolex make					
5	Providing & Laying of one number aluminium conductor, PVC insulated and PVC sheathed armoured/ XLPE power cable, 1.1 KV grade of following sizes on wall surface as required.					
	Armoured cable 6 sq. mm (Twin Core)	45	208	Rupree two hundred eight only	P/Mtr.	9360
	Armoured cable 6 sq. mm (Twin Core)	25	255	Rupree two hundred fifty five only	P/Mtr.	6375
	Total:-					98952

Schedule of Quantity checked & Approved

For Rs 98,952/- only

Executive Engineer
Electrical Division
HPPWD Balampur

[Signature]

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
NAME OF WORK :- Repair and day to day maintenance of electrical installation (E.I) to 1st year MBBS Girls Hostel at Dr. RPGMC Tanda.				ESTIMATED COST:-98,883/-only. EARNEST MONEY: Rs.2000/-only TIME ALLOWED: -Six Months		
SR. NO.	DESCRIPTION	Job No	RATES	WORDS	UNIT	AMOUNT
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.					
1.1	3x1.5 Sq. mm.	25 ✓	100.00	Rupree one hundred only	Per Meter	2500 ✓
1.2	S/D 3 X 4 sq. mm	25 ✓	220.00	Rupree two hundred twenty only	Per Meter	5500 ✓
	Make:- KEI/Anchor/Plaza					
2	Supplying and fixing following modular switch/socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.					
2.1	5/10 Amps. Modular switch	30 ✓	93.00	Rupree ninety three only	Each	2790 ✓
2.2	15/16 Amps. Modular switch	25 ✓	164.00	Rupree one hundred sixty four only	Each	4100.00 ✓
2.3	5/6 amp modular socket outlet	30 ✓	136.00	Rupree one hundred thirty six only	Each	4080 ✓
2.4	15/16 amp modular socket outlet	25 ✓	231.00	Rupree two hundred thirty one only	Each	5775 ✓
	Makes:- Anchor-Romall&T/Schneider					
3	Providing and installation exhaust fan of following sizes in the existing opening, including making the hole to suit the size of the above fan, making good the damages, connections, testing and commissioning etc. as required.					

Exhaust Fan, Light duty, (Domestic)	4	2567.00	Rupree two thousand five hundred sixty seven only	Each	10268
Makes:- Usha/Havells/Bajaj					
4 Supplying and fixing LED retrofit lamp suitable for B-22 holder base fittings with polycarbonate diffuser and aluminium heat sink as required complete in all respects.					
9 Watt LED Lamp	40	157.00	Rupree one hundred fifty seven only	Each	6280
Makes: Havells/Panasonic/Osram					
5 Supplying and fixing 6 amps to 32 amps rating, 240/415 volts, 10 KA "C" curve, miniature circuit breaker suitable for inductive load of following poles in the miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
Single pole	12	239.00	Rupree two hundred thirty nine only	Each	2868
Makes:- Anchor-Uno/L&T/Schneider					
6 Supplying and fixing following rating, double pole, 240 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
63 Amps	5	530.00	Rupree five hundred thirty only	Each	2650
Makes:- Anchor-Uno/L&T/Schneider					

7	Providing and fixing of LED batten having minimum efficacy of 100 lm/W, P.F.>0.95 with THD<10%, CCT 6500 K, CRI 80, Surge Protection range 2 kV. The LED with useful life of 50000 Hrs. at L70 with five years warranty. The input voltage shall be 150V to 270V, 50/60 HZ along with all accessories, including connections, testing etc. as required complete in all respects.						
	LED Batten 20 Watt	45 ✓	606.00	Rupee six hundred six only	Each	27270 ✓	
	Makes:- Wipro/Havells/Bajaj						
8	Supplying and fixing Batten Holder as required complete in all respects.						
	Batten Holder	18 ✓	80.00	Rupee eighty only	Each	1440 ✓	
	Makes: Havells/L & T/Bajaj						
9	Providing and fixing decorative LED mirror light having high quality design suitable for LED tube up to 10Watt (1000 lumen) 6500K and it should be compatible with specifications i.e. power factor ≥ 0.9, harmonic distortion ≤ 10% and efficacy ≥ 100 lumens per watt, CRI > 80, suitable for input voltage AC 220-240V, 50/60 Hz, complete with all accessories, connections, testing and commissioning etc. as required.						
	10 Watt LED Mirror Light, 2 ft.	12 ✓	426.00	Rupee four hundred twenty six only	Each	5112 ✓	
	Makes: Bajaj/Havells/Osram						
10	Providing & fixing following size service wire 10 Sq mm as required complete in all respect and to the best satisfaction of Engineer-in-charge.	150 ✓	55.00	Rupee fifty five only	Per Mtr.	8250 ✓	
11	Providing & fixing of geyser element 100 ltr. Water heater etc as required complete in all respects and to the best satisfaction of Engineer-in-charge..	2 ✓	5500	Rupee five thousand five hundred only	each	11000 ✓	
	Total:-					99883	

Schedule of Quantity checked & Approved by

999883-100

Executive Engineer
Electrical Division
HP PWD Palampur

(Signature)

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
NAME OF WORK :- Construction of Hall for Har Har Mahadev Mahila mandal at upper Bagoda Teh. Palampur, Distt. Kangra (H.P.) (SH:-Providing E.I. therein)		11		ESTIMATED COST:-71,944/-only. EARNEST MONEY: Rs.1500/-only TIME ALLOWED: ~~one~~ Year		
SR. NO.	DESCRIPTION	job No	RATES	WORDS	UNIT	AMOUNT
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable in surface / recessed heavy class PVC conduit having wall thickness minimum 2 mm with piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with 1.5 sq. mm. FRLS PVC insulated copper conductor single core cable etc as required					
	Group C.	13	1238	Rupree one thousand two hundred thirty eight only	Per point.	16094
	SCI/KEI/Finolex make					
2	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed heavy class PVC conduit having wall thickness 2.0mm as required					
	2 X 4 sq. mm + 1 X 4 sq. mm earth wire	25	311	Rupree three hundred eleven only	P/Mtr.	7775
	2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	10	249	Rupree two hundred forty nine only	P/Mtr.	2490
	2x6Sqmm+ 1 X 6 sq. mm earth wire	1	432	Rupree four hundred thirty two only	P/Mtr.	432.00
	SCI/KEI/Finolex make					

3	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel PVC conduit as required						
	3 X 2.5 sq. mm	15	151	Rupee one hundred fifty one only	P/Mtr.	2265.00	
	SCI/KEI/Finolex make						
4	Supplying and fixing suitable size G I box with modular plate and cover in front on surface or in recess including providing and fixing 6 pin 15/16 amps modular socket outlet and 15/16 amps, modular switch, connections etc. as required.	3	621	Rupee six hundred twenty one only	Each.	1863	
	Make :- Schenider/L&T/Legrand						
5	Providing, Installation, testing and commissioning of BLDC ceiling fan (5 star rating), including wiring the down rods of standard length (up to 30 cm) with 16/0.20 mm twin twisted flexible, cotton braided, copper cable, including providing and fixing phenolic laminated sheet cover on the fan box and earthing etc. as required:						
	Ceiling Fan 1200 mm sweep, Category-A	2	4323	Rupee four thousand three hundred twenty three only	Each	8646	
	Makes :- Ceiling Fan 1200 mm sweep, Category-A usha Technix Plus 5 Star, Crompton, Bajaj						
6	Providing and installation of LED fixture 18 W +/- 1 W LED Square Surface Mounted Downlighter Round Shape with minimum system lumen efficacy of 85 lm/W with and P. F > 0.95 with THD <20%, CCT 6000 K, CRI 80, The LED with useful life of 50000 Hrs at L70. The input voltage range shall be 150V to 270V						
	LED Surface mounting round downlighter 18 watt	7	1821	Rupee one thousand eight hundred twenty one only	Each	12747	

	Makes :- Panasonic (Cat No :- PDL M36188/Philips/ Wipro)					
7	Providing and installation of exhaust fan of following sizes in the existing opening, including making the hole to suit the size of the above fan, making good the damages, connections, testing and commissioning etc. as required:-					
	Exhaust Fan, Light duty, (Domestic) 300 mm sweep (Usha,Bajaj,Crompton make)	1	2567	Rupree two thousand five hundred sixty seven only	Each	2567
8	Providing and installation of IP65 LED Bulk Head 10 W +/- 1 W LED with system with efficacy 100 lm/W with Aluminium housing and P. F > 0.95 with THD <10%, CCT 5700 K, CRI 70, Surge protection 4 Kv. The LED with useful life of 50000 Hrs at L70. The input voltage range shall be 150V to 270V .	3	1420	Rupree one thousand four hundred twenty only	Each	4260
	Makes :-Wipro (Cat. No.:-LW07-141-XXX-57-G1) Philips/Bajaj .					
9	Supplying and fixing of following way, single pole and neutral sheet steel MCB distribution board, 240 volts, on surface / recess, complete with tinned copper bus- bar, neutral link, earth bar, din-bar, interconnections, powder painted, including earthing etc. as required:-(But without MCB/RCCB/isolator)					
	Double door-12 way	1	2055	Rupree two thousand fifty five only	Each	2055
	L&T/Legrand/Schneider make					
10	Supplying and fixing of 6 amps. to 32 amps. rating, 240/415 volts, 10 kA 'C' curves, miniature circuit breaker suitable for inductive load of following poles in the existing miniature circuit breaker suitable load of following poles in the existing MCB DB complete with connections testing and commissioning etc. as required:-					

	6 Amp Single pole. Cat-A.	1	239	Rupree two hundred thirty nine only	Each	239
	16 Amp Single pole. Cat-A.	3	239	Rupree two hundred thirty nine only	Each	717
	L&T/Legrand/Schneider make					
11	Supplying and fixing following rating, double pole, 240 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
	40 Amps. Cat-A.	1	426	Rupree four thousand twenty six only		426
	L&T/Legrand/Schneider make					
12	Supplying and fixing following rating, double pole (single phase & neutral) 240 volts, residual current circuit breaker (RCCB), having a sensitivity current up to 300 miliampers in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
	40 Amps. Cat-A.	1	2272	Rupree two thousand two hundred seventy two only	Each	2272
	L&T/Legrand/Schneider make					
13	Earthing with G I earth plate 600mmx600mmx3mm thick including accessories and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. etc. (with charcoal or coke and salt) complete as required.	1	6021	Rupree six thousand twenty one only	Per set	6021
14	Supplying and laying 6 SWG G.I. wire at 0.50 metre below ground level for conductor earth electrode, including connection/ termination with GI thimble etc. as required.	25	43	Rupree forty three only	Per Mtr	1075
	Total:					71944

Schedule of Quantity checked & Approved By 719944-10mg

Executive Engineer
Electrical Division
HP PWD Palampur
Am

SCHEDULE OF QUANTITY

NAME OF WORK :- Annual Repair and maintenance of A.C
1.5 Ton capacity (various type and various make) in
various Govt. Buildings under Electrical Sub Division
Nurpur for the year 2025-26 (Fatehpur Section).

ESTIMATED COST : 99,400/-only.
EARNEST MONEY: Rs.2000/-only
TIME ALLOWED: One Year

SR. NO.	DESCRIPTION	Job No		WORDS	UNIT	AMOUNT
		RATES				
1	SPLIT TYPE 1.5 Ton AC UNIT:-Annual repair and maintenance of various make and different capacity Air Conditioner unit (Split Type) i/c cost of all type spare parts, four times general services, refilling of F-22 gas and service due on time to time as per rules, cost of rewinding of moter, compressors, stablizer including the replacement of compressor if beyond repair as per the instructions and directions of the Engineer-In-Charge.	19 ✓	4300	Rupree four thousand three hundred only	each	81700 ✓
2	SPLIT TYPE 2 Ton AC UNIT:-Annual repair and maintenance of various make and different capacity Air Conditioner unit (Split Type) i/c cost of all type spare parts, four times general services, refilling of F-22 gas and service due on time to time as per rules, cost of rewinding of moter, compressors, stablizer including the replacement of compressor if beyond repair as per the instructions and directions of the Engineer-In-Charge.	3 ✓	4500	Rupree four thousand five hundred only	each	13500 ✓
3	WINDOW TYPE AC UNIT:-Annual repair and maintenance of various make and different capacity Air Conditioner unit (Window Type) i/c cost of all type spare parts, four times general services, refilling of F-22 gas and service due on time to time as per rules, cost of rewinding of moter, compressors, stablizer including the replacement of compressor if beyond repair as per the instructions and directions of the Engineer-In-Charge.	1 ✓	4200	Rupree four thousand two hundred only	each	4200 ✓
Total:-						99400 ✓

Executive Engineer
Electrical Division
HPPWD Palampur

Signature

Back
Schedule of Quantity checked & Approved for
Pg 99400 only

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
NAME OF WORK :- Annual repair and maintenance of portable Fire Extinguishers installed in various hostel of 500 bedded Hospital in Dr. RPGMC Kangra at Tanda .(SH:-Refilling of portable fire extinguishers of different capacity and type of 1st year MBBS girls hostel Ravi hostels and library building of 500 bedded in Dr. RPGMC Tanda).			(13)	ESTIMATED COST:65,920/-only. EARNEST MONEY:Rs. 1400/-only TIME ALLOWED: -one month		
SR. NO.	DESCRIPTION	job No		WORDS	UNIT	AMOUNT
			RATES			
1	Refilling of portable fire extinguishers , CO2 type 4.5 kg. capacity complete in all respects.	22 ✓	1450.00	Ruppee one thousand four hundred fifty only	Nos.	31900 ✓
2	Refilling of portable fire extinguishers ,water CO2 gas cartridge type capacity 9 liters , complete in all respects.	22 ✓	750.00	Ruppee seven hundred fifty only	Nos.	16500 ✓
3	Refilling of portable fire extinguishers ABC type (filled with 50 map powder)9kg. Capacity complete in all respects.	8 ✓	2190	Ruppee two thousand one hundred ninety only	Nos.	17520 ✓
Total:-						65920.00 ✓

Schedule of Quantity checked & approved As per 65920/-only


 Executive Engineer
 Electrical Division
 HPPWD Palampur



SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
NAME OF WORK :- Annual repair and maintenance of portable Fire Extinguishers installed in various hostel of 500 bedded Hospital in Dr. RPGMC Kangra at Tanda .(SH:-Refilling of portable fire extinguishers of different capacity and type of , intern hostel , main boys & girls hostel , Satluj and 1st year MBBS boys hostel of 500 bedded in Dr. RPGMC Tanda).				ESTIMATED COST:80,240/-only. EARNEST MONEY:Rs.1600/-only TIME ALLOWED: -one month		
SR. NO.	DESCRIPTION	job No		WORDS	UNIT	AMOUNT
			RATES			
1	Refilling of portable fire extinguishers , CO2 type 4.5 kg. capacity complete in all respects.	34 ✓	1450.00	Rupree one thousand four hundred fifty only	Nos.	49300 ✓
2	Refilling of portable fire extinguishers ,water CO2 gas cartridge type capacity 9 liters , complete in all respects.	20 ✓	750.00	Rupree seven hundred fifty only	Nos.	15000 ✓
3	Refilling of portable fire extinguishers ,water types (S/P) capacity 9 liters . Complete in all respects.	8 ✓	800	Rupree eighty hundred only	Nos.	6400 ✓
4	Refilling of portable fire extinguishers ,ABC type (Filled with 50 maza powder)6 kg. Capacity complete in all respects.	6 ✓	1,590.00	Rupree one thousand five hundred ninety only	Nos.	9540.00 ✓
Total:						80240 ✓

Schedule of Quantity

Checked & Approved

Pg 809240-1000

Executive Engineer
Electrical Division
HPPWD Palampur

[Signature]

SCHEDULE OF QUANTITY

NAME OF WORK :- Replacement of safety Devices and E.I in Vet.
Hospital Chowki Khalet in Tehsil Palampur Dist. Kangra HP

Job No (15)

ESTIMATED COST: Rs. 95,616/-only.
EARNEST MONEY: Rs.2000/-only
TIME ALLOWED: One Month

SR. NO.	DESCRIPTION	QTY.	RATES		UNIT	AMOUNT
			FIGURES	WORDS		
1	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm.FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel conduit including dismantling as required.					
	Group C.	5	766	Rupees Seven Hundred Sixty Six Only	Per point.	3830
	KEI/Finolex/Anchor make					
2	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor. single core cable in surface/ recessed steel conduit as required					
i	4 X 6 sq. mm + 2 X 6 sq. mm earth wire	45	1061	Rupees One Thousand Sixty One Only	P/Mtr.	47745
	KEI/Finolex/Anchor make					
3	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel PVC conduit as required					
i	3 X 2.5 sq. mm	15	151	Rupees One Hundred Fifty One Only	P/Mtr.	2265
ii	2 x 4 sq.mm	16	153	Rupees One Hundred Fifty Three Only	P/Mtr.	2448
	KEI/Finolex /Anchor make					
4	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/isolator)	1	1425	Rupees One Thousand Four Hundred Twenty Five Only	Each	1425

	4 way, Double door							
	L&T/Legrand/Schneider make							
5	Supplying and fixing of 6 amps to 32 amps. rating, 240/415 volts, 10 kA 'C' curves, miniature circuit breaker suitable for inductive load of following poles in the existing miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections testing and commissioning etc. as required:-							
i	6 Amp Single pole. Cat-A.	2	239	Rupees Two Hundred Thirty Nine Only	Each	478		
ii	16 Amp Single pole. Cat-A.	1	239	Rupees Two Hundred Thirty Nine Only	Each	239		
	L&T/Legrand/Schneider make							
6	Supplying and fixing following rating, four pole, 415 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.							
i	63 Amps. Cat-A.	1	976	Rupees Nine Hundred Seventy Six Only	Each	976		
	L&T/Legrand/Schneider make							
7	Providing & Laying of one number aluminium conductor, PVC insulated and PVC sheathed armoured/ XLPE power cable, 1.1 KV grade of following sizes on wall surface as required.	85	426	Rupees Four Hundred Twenty Six Only	P/Mtr.	36210		
	Armoured cable 25 sq. mm (3.5 core)							
	Make :- KEL, Grandlay, Finolex							
	Total					95616		

Schedule of Quantity checked & approved for
P.S 9596161000

M.K.
 Executive Engineer
 Electrical Division
 HPPWD Palampur

B
am