HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PWI/CB/2nd C/Tender case/2025-26 5643-72 Dated: 22/11/25

To

The Executive Engineer,
HP.PWD. Nirman Bhawan, Nigam Vihar,
Shimla.

Subject:- Publication of tender Notice on departmental site.

Sir,

In this context, it is submitted that the tender notice is being enclosed herewith for up loading on Department web-site as per Notification of the Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A-(3)1/2024 dated Shimla-2 the 03.01.2024 as the work mentioned in the tender notice are urgent in nature and in public intrest.

DA/As above.

Executive Engineer,
Indora Division, HPPWD,
Indora.

Copy forwarded for information to following for information please:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur.
2. All the Assistant Engineers working under this Division.
3. Various Contractors.
4. Notice Board.

DA/As above.

Executive Engineer,
Indora Division, HPPWD, Indora
Telephone No. 01893-242336
e-mail- eepwd-indora-hp@gov.in

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed item rate tenders on the form 6 & 8 are hereby invited by the the Executive Engineer, Indora Division HPPWD., Indora on behalf of the worthy Governor of Himachal Pradesh for the following works from the approved and eligible contractors enlisted in HP.PWD. The application for purchase of tender form should be reached in this office on dated **28.11.2025** up to 1.00 PM and tender form will be issued from this office against cash payment (Nonrefundable) up to 4.00 PM on same day. The tender will be opened on **29.11.2025 at 11.00 PM** in presence of the contractor or their authorized representatives who may like to be present.

The Earnest Money in shape of National Saving Certificate/ time deposit account/saving account in any nationalized bank in HP duly pledged in favour of the Executive Engineer, Indora division, HPPWD., Indora will be received along with application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders will be kept open for 90 days from the date of opening of tender. The Executive Engineer, Indora Division, HP.PWD. Indora reserves the right to reject any or all tenders without assigning any reason. The contractor should append their Enlistment/ Renewed Certificate/ Sale Registration Number with the application for issue of tender form. If any of the mentioned above date happens to be holiday the same should be processed on next working day.

Sr. No.	Name of work.	Estimated cost (Rs.)	Earnest money (Rs.)	Time limit	Cost of form (Rs.)	Eligible class of Contractor.
1.	Restoration of Rain damages on Mokhtli to Jhikla Surajpur road Km. 0/0 to 1/500 (SH:- C/O PCC E/ Wall at RD. 0/984 to 0/997 (RHS).	97216	2000	Two Months	350	Class- D
2.	Restoration of Rain damages on Mokhtli to Jhikla Surajpur road Km. 0/0 to 1/500 (SH:- C/O PCC E/ Wall at 0/997 to 1/010 (RHS).	97551	2000	Two Months	350	Class- D
3.	Restoration of Rain damages on Mohtli Indora AL-I Km. 0/0 to 10/0 (SH:- Repair of Pot holes between Km. 1/800 to 2/600).	97975	2000	Two Months	350	Class- D
4.	Restoration of Rain damages on Mohtli Indora AL-I Km. 0/0 to 10/0 (SH:- Repair of Pot holes between Km. 1/00 to 1/800).	98352	2000	Two Months	350	Class- D
5.	Restoration of Rain damages on Birari Di Hatti to Branda road Km. 0/0 to 4/0 (SH:- C/O C.C. Pavement at RD. 2/600 to 2/623.50).	99932	2000	Two Months	350	Class- D
6.	Restoration of Rain damages on BCKD road Km. 65/0 to 95/560 (SH:- Maintenance of Earthen Shoulders/ Berms Both sides between Km. 74/0 to 75/0).	98834	2000	Two Months	350	Class- D
7.	Restoration of Rain damages on Mohtli Indora AL-I Km. 0/0 to 10/0 (SH:- Repair of Pot holes between Km. 2/600 to 3/400).	99239	2000	Two Months	350	Class- D
8.	Restoration of Rain damages on Birari Di Hatti to Branda road Km. 0/0 to 4/0 (SH:- C/O C.C. Pavement at RD. 2/623.50 to 2/647).	99932	2000	Two Months	350	Class- D
9.	Restoration of Rain damages on BCKD road Km. 65/0 to 95/560 (SH:- Hiring of Excavator-Cum-Loader (JCB).	98010	2000	Two Months	350	Class- D
10.	Restoration of Rain damages on Mohtli Indora AL-I Km. 0/0 to 10/0 (SH:- Repair of Pot holes between Km. 3/400 to 4/00).	99358	2000	Two Months	350	Class- D

TERMS AND CONDITIONS:-

1. The contractor/Firm shall have his GST No. & copy of the same be attached with the application.
2. The intending Contractors/firm should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender for The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender form. In this regard, the contractor has submitted an affidavit that he is not having more than two work
5. The intending contractors are required to see the site of the work before submitting the tender.
6. The offer of the tender shall remain valid upto 75 days after the opening of tender.
7. The Executive Engineer reserves the right to reject/accept any or all tenders without assigning any reasons.

Executive Engineer,
Indora Division, HPPWD.,
Indora.

Copy to the following for inforamion and necessary action:-

1. The Superintending Engineer, 9th Circle, HP.PWD. Nurpur.
2. All Assistant Engineer working under this office.
3. Notice Board.

Executive Engineer,
Indora Division, HPPWD,
Indora.

(1) (195)

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages on Mohtli to Jhikla Surajpur road km 0/00 to 1/500. (SH:- Construction of PCC E/wall at RD 0/984 to 0/997 (R.H.S).

Estimated Cost :-Rs. 97216/-
Earnest Money:- Rs. 2000/-
Time Limit :- Two Months

Sr.No.	Description of Items	Quantity	Units	Rate in fig.	words	Amount
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 50m compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .The rate is including octri , Royality , Malkana , Toll Tax , Sale Tax ,GST or any other taxes imposed by the Government.	8.32	Per Cubic Meter	413.60	Rupees Tfour hundred thirteen and paise Six zero only.	3441.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure plain cement concrete nominal mix 1:4:8 (One cement : four sand : eight graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in Retaining walls, Breast walls and the like etcetera including pumping or bailing out matter , cleaning of slush at site which many rise at the time of laying concrete and the cost of form work as per drawing and M.O.R.D technical specification section clause 802,803,1202 and 1203 as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octri , Royality , Malkana , Toll Tax , Sale Tax ,GST or any other taxes imposed by the Government.	22.49	Per Cubic Meter	4050.40	Rupees Four thousand and rupees fifty only.	91093.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 complete as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.00	Each	335.20	Rupees three hundred thirty five and paise two zero only.	2682.00
		Total:-				**97216.00**

DNIT Checked and approved for Rs. 97216/-only.
(Rs. Ninety Seven thousand two hundred Sixteen)

Executive Engineer
Indora Division
HPPWD Indora

HPPWD Indora

(2) (196)

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages on Mohtli to Jhikla Surajpur road km 0/00 to 1/500. (SH:- Construction of PCC E/wall at RD 0/997 to 1/010 (R.H.S).

Estimated Cost :-Rs. 97551/-
Earnest Money:- Rs. 2000/-
Time Limit :- Two Months

Sr.No.	Description of Items	Quantity	Units	Rate in fig.	words	Amount
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305.1 section 300 as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 50m compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .The rate is including octri , Royality , Malkana , Toll Tax , Sale Tax ,GST or any other taxes imposed by the Government.	8.32	Per Cubic Meter	413.60	Rupees Tfour hundred thirteen and paise Six zero only.	3441.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure plain cement concrete nominal mix 1:4:8 (One cement : four sand : eight graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in Retaining walls, Breast walls and the like etcetera including pumping or bailing out matter , cleaning of slush at site which many rise at the time of laying concrete and the cost of form work as per drawing and M.O.R.D technical specification section clause 802,803,1202 and 1203 as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octri , Royality , Malkana , Toll Tax , Sale Tax ,GST or any other taxes imposed by the Government.	22.49	Per Cubic Meter	4050.40	Rupees Four thousand and rupees fifty only.	91093.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 complete as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.00	Each	335.20	Rupees three hundred thirty five and paise two zero only.	3017.00
		Total:-				**97551.00**

DNIT Checked and approved for Rs. 97551/-only.
(Rs. Ninety Seven thousand five hundred fifty one)

Executive Engineer
Indora Division
HPPWD Indora

(3)

(197)

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages on Mohtli Indora AL-I road km 0/00 to 10/00 (SH:- Repair of Pot holes between km 1/800 to 2/800)

Estimated Cost :-Rs. 97795/-
Earnest Money:- Rs 2000/-
Time Limit :- Two Months

Sr.No.	Description of Items	Quantity	Units	Rate in fig.	words	Amount
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading –III, 53mm to 22mm (sixty three millimetres to forty five millimetres)size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer – in-Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.10	Per Cubic Meter	1710.20	Rupees One thousand Seven hundred Ten and paise two zero only.	5302.00
2	Repair to pot holes and removal of loose materials, triming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelledor towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	270.50	Per Square Meter	342.60	Rupees Three hundred forty two and paise Six zero only.	92673.00
		Total:-				97975.00

DNIT Checked and approved for Rs. 97975/- only.
(Rs. Ninety Seven thousand Nine hundred Seventy Five)

Executive Engineer
Indora Division
HPPWD Indora

(4) (178)

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages on Mohtli Indora AL-I road km 0/00 to 10/00 (SH:- Repair of Pot holes between km 1/00 to 1/800)

Estimated Cost :-Rs. 98352/-
Earnest Money:- Rs 2000/-
Time Limit :- Two Months

Sr.No	Description of Items	Quantity	Units	Rate in fig.	words	Amount
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading –III, 53mm to 22mm (sixty three millimetres to forty five millimetres)size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer – in-Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.14	Per Cubic Meter	1710.20	Rupees One thousand Seven hundred Ten and paise two zero only.	5370.00
2	Repair to pot holes and removal of loose materials, triming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelledor towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	271.40	Per Square Meter	342.60	Rupees Three hundred forty two and paise Six zero only.	92982.00
		Total:-				98352.00

DMIT Checked and appoved for Rs. 98352/- Only.
(Rs. Ninety Eight thousand three hundred fifty two)

Executive Engineer
Indora Division
HPPWD Indora

(6) (201) (5) (199)

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages Bihari Di Hatti to Baranda road km 0/00 to 4/00. (SH:- C/O C.C Pavement at RD 2/600 to 2/623.50)

Estimated Cost :-Rs. 99932/-
Earnest Money:- Rs 2000/-
Time Limit :- Two Monts

Sr. No.	Description of Items	Quantity	Units	Rate in fig.	words	Amount
1	Providing and laying mechanically mixed and vibrated conccreate for plain/reinforced concrete in open foundation for all types of structure complete of plain cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slash as required at site which may arise at the time of laying under water complete for all heights/ depths in including the cost of form work as per drawing and M.O.R.D technical specification clause 802,803,1202 and 1203 as per the direction of Engineer-in-charge including carriage of materils within all leads and lifts and other incidential.The rate is including octri , Royality , Malkana , Toll Tax , Sale Tax ,GST or any other taxes imposed by the Government.	16.45	Per Cubic Meter	6074.90	Rupees Six thousand Seventy four and paise Nine zero only.	99932.00
		Total:-				99932.00

AMIT Checked and cepprved for Rs. 99932/-only (Rs. Ninety Nine thousand Nine hundred thirty two)

Executive Engineer
Indora Division
HPPWD Indora

(6)

(201)

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages on Bharwain Chintpurni Khatiar Damtal road km 65/00 to 95/560. (SH:- Maintenance of Earthen shoulder/ berms both sides between km 74/00 to 75/00)				Estimated Cost :-Rs. 98834/- Earnest Money:- Rs 2000/- Time Limit :- One Month		
Sr. No.	Description of Items	Quantity	Units	Rate in fig.	words	Amount
1	Making up loss of materials/Irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a any leads of 1000m as per technical specification clause 1903 as per direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octoroi, royality, malakana, toll tax, sale tax, GST or other taxes imposed by the Government.	1793.00	Per Square Meter	55.12	Rupees Fifty five and paise One two only.	98834.00
		Total:-				98834.00

DNIT Checked and approved for Rs. 98834/- only.
(Rs. Ninety Eight thousand Eight hundred thirty Four)

Executive Engineer
Indora Division
HPPWD Indora

(7)

(202)

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages on Mohtli Indora AL-I road km 0/00 to 10/00 (SH:- Repair of Pot holes between km 2/600 to 3/400)

Estimated Cost :-Rs. 99239/-
Earnest Money:- Rs 2000/-
Time Limit :- Two Months

Sr.No.	Description of Items	Quantity	Units	Rate in fig.	words	Amount
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22mm (sixty three millimetres to forty five millimetres)size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer – in-Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.19	Per Cubic Meter	1710.20	Rupees One thousand Seven hundred Ten and paise two zero only.	5456.00
2	Repair to pot holes and removal of loose materials, triming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelledor towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	273.74	Per Square Meter	342.60	Rupees Three hundred forty two and paise Six zero only.	93783.00
		Total:-				**99239.00**

DNIT Checked and approved for Rs. 99239/- only.
(Rs. Ninety Nine thousand two hundred thirty Nine)

Executive Engineer
Indora Division
HPPWD Indora

(8)

(200)

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages Bihari Di Hatti to Baranda road km 0/00 to 4/00. (SH:- C/O C.C Pavement at RD 2/623.50 to 2/647)

Estimated Cost :-Rs. 99932/-
Earnest Money:- Rs 2000/-
Time Limit :- Two Monts

Sr. No.	Description of Items	Quantity	Units	Rate in fig.	words	Amount
1	Providing and laying mechanically mixed and vibrated conccreate for plain/reinforced concrete in open foundation for all types of structure complete of plain cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slash as required at site which may arise at the time of laying under water complete for all heights/ depths in including the cost of form work as per drawing and M.O.R.D technical specification clause 802,803,1202 and 1203 as per the direction of Engineer-in-charge including carriage of materils within all leads and lifts and other incidential.The rate is including octri , Royality , Malkana , Toll Tax , Sale Tax ,GST or any other taxes imposed by the Government.	16.45	Per Cubic Meter	6074.90	Rupees Six thousand Seventy four and paise Nine zero only.	99932.00
		Total:-				**99932.00**

DNIT Checked and approved for Rs. 99932/- only.
(Rs. Ninety Nine thousand Nine hundred Thirty two)

Executive Engineer
Indora Division
HPPWD Indora

9

204

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on B.C.K.D road km 65/0 to 95/560.	Estimated cost Rs.:-	98010.00
	Earnest Money Rs.:-	2000.00
(SH:- Hiring of excavator cum loader. (J.C.B)	Time limit:-	One onth

Sr. No	Description of items	Quantity	Rate		Amount
			In words	In figures	
1	2	3	4	5	6
1	Deployment of excavator cum loader (JCB) for removal of slips,trees and such like activities repair of berms, earthern shoulders and katcha drain on hiring basis in all kind of classification of soil complete in all respect as per direction of Engineer-in-charge. The cost of lubricant, diesel oil, operator, maintenance cost etc. will be borne by the contractor.	81.00 Hours	1210.00	Rupees One Thousand Two Hundred Ten only	98010.00
	Total:-				98010.00

DNIT Checked and approved for Rs. 98010/-
(Rs. Ninety Eight thousand and rupees ten)

Terms and Conditions:-

1 Hire charges should be quoted for per hour per working day for six hour.

2 Hire charges should be including of all expenses i.e. fuel, lubricant and on account of establishment for major /minor repair, loading and deployment of all equipment required.

3 Hire charges should be payable after signing of contract agreement and entire satisfaction as per direction of the Engineer-in-Charge and transportation expenses shall be payable by the Government.

4 Charges also include insurance of machinery and driver and establishment and the department shall not be responsible for fatal/non fatal accident.

5 The minimum quantity to be execution cubical contents shall be measured as per HPPWD specification.

6 No deviation shall be allowed in any case.

Executive Engineer
Indora Division
HPPWD Indora

(10)

(203)

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages on Mohtli Indora AL-I road km 0/00 to 10/00 (SH:- Repair of Pot holes between km 3/400 to 4/00)

Estimated Cost :-Rs. 99358/-
Earnest Money:- Rs 2000/-
Time Limit :- Two Months

Sr.No.	Description of Items	Quantity	Units	Rate in fig.	words	Amount
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading –III, 53mm to 22mm (sixty three millimetres to forty five millimetres)size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer – in-Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.26	Per Cubic Meter	1710.20	Rupees One thousand Seven hundred Ten and paise two zero only.	5575.00
2	Repair to pot holes and removal of loose materials, triming of sides cleaning of surface by providing and applying tack coat with paving bitumen of VG-10 (Viscosity Grade - ten) grade conforming to IS:73 (IS: Seventy three) to be applied by heating in oil fired and self propelledor towed bitumen boiler and spraying the material uniformly with pressure sprayer at a rate of 0.30 (zero point thirty) per square meter including providing , laying and rolling of open graded premix carpet of 20mm (Twenty millimeter) compacted thickness, composed of type-A 13.2mm (Thirteen decimal two millimeter) to 5.6mm (Five decimal six millimeter) aggregate at the rate 0.27cum.per 10 sqm. (Zero point two seven cubic meter) per ten square meter premixed with bitumen binder VG-10(viscosity grade-ten) at the rate 14.6 kg. (fourteen point six kilogramme) per ten square meter of road surface and providing and laying of premix seal coat type-B for sealing the voids in a bituminous surface laid to the specified level, grade and cross fall using 0.06(zero point zero six) cubic meter of fine aggregate per ten square meter premixed with VG-10(viscosity grade -ten) 6.8 Kg.(Six decimal eight kilogramme) as per MORD technical specification clause-1904.2 and as per the direction of entire satisfaction of Engineer-in-charge including the cost of labour, machinery and aggregate/sand including carriage of materials with in all leads and lifts and other incidental. The rates including octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	273.74	Per Square Meter	342.60	Rupees Three hundred forty two and paise Six zero only.	93783.00
		Total:-				**99358.00**

DMIT Checked and approved for Rs. 99358/-only.
(Rs Ninety Nine thousand Three hundred Fifty Eight)

Executive Engineer
Indora Division
HPPWD Indora