



OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh Works Department
Jaisinghpur 176095 Phone No. 01894-228030
Email ee-jaipwd-hp@gov.in

"CERTIFICATE"

Certified that the tenders are being called in exigency of works of public interest vide
this office letter No. PWD/JSD/TA/NIT/ 2025-26- 6831-40 dated 18-11-2025.


Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur.



OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh Works Department Jaisinghpur 176095
Phone No. 01894-228030
Email ee-jaisinghpur-hp@gov.in

"NOTICE INVITING TENDERS"

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **24.11.2025 up to 11:00 A.M.** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **22.11.2025 up to 4:00 PM** and the application for issue of tender form shall be received on **22.11.2025 up to 11:30 AM**. The applications for issue of tender forms should accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD., Division Jaisinghpur.


The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for **75 days**:-

Sr. No.	Name of Work	Estimated Cost (Rs.)	EMD	Time limit	Cost of tender form
1	Restoration of rain damages on Bhuna to Ashapuri road Km 0/00 to 12/100 (SH:- Removal of Boulders, stones and landslide from Rd 5/730 to 5/745)	99982.00	2000.00	One Month	350/-
2	C/O Ambulance road from House of Balak Ram to Nichli Khoul ward No.3 Gher Bhuna (SH:-C/O R/wall from RD 0/00 to 0/028) Deposit VKV/2025/597	494759.00	9900.00	Two Month	350/-
3	Restoration of rain damages on Bhuna to Ashapuri road Km 0/00 to 12/100 (SH:- Removal of Boulders, stones and landslide from Rd 5/760 to 5/770)	99978.00	2000.00	One Month	350/-
4	C/O link road from Biara to Batthan Km 0/00 to 3/500 (SH:- P/L CC Pavement from Km 1/00 to 1/055) (Depsoit VKV)	196863.00	2000.00	Two month	350/-
5	Restoration of rain Damages on Dharamshala Dadh Holta Chadhiar Sandhole Road Km 45/00 to 56/000 (SH:-C/Oimprovement of curve between RD 54/270 to 54/315,54/495 to 54/525, 54/675 to 54/750) PDNA	394089.00	7900.00	Two Month	350/-
6	Restoration of rain Damages on Dharamshala Dadh Holta Chadhiar Sandhole Road Km 45/00 to 56/000 (SH:-C/O pusta above existing Breast wall for protection of house at Rd 53/810 to 53/840) PDNA	249219.00	5000.00	Two Month	350/-
7	Restoration of rain damages on various roads under Balakrupi Sub Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Balakrupi Section)	99990.00	2000.00	One Month	350/-
8	C/O road near Petrol Pump Mohal Andretta (SH:-C/O U-Shape drain along with Grating and providing and laying CC pavement from RD 0/0 to 0/035) Deposit VKV/2025/600	244436.00	5000.00	Two Month	350/-
9	Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Balakrupi Section)	99880.00	2000.00	One Month	350/-
10	Balance work of Shahidi Gate at Saliana Near Molichak on Banuri Saliana road at Km 2/500 (SH:- P/F Granite, ACP cladding and painting worm) Deposit VKV/2024/851	246458.00	5000.00	Two Month	350/-
11	Restoration of rain damages on Karori Killi Duhak road Balh road Km 0/00 to 5/00 (SH:-C/O R/wall at RD 2/855 to 2/856.5)	99912.00	2000.00	One Month	350/-
12	Restoration of rain damages on various roads Panchrukhi Sub Division (SH:- Removal of slips between various RDS Jalag Section)	99131.00	2000.00	One Month	350/-
13	Restoration of rain damages on Karori Killi Duhak road Balh road Km 0/00 to 5/00 (SH:-C/O R/wall at RD 2/862.50 to 858)	99962.00	2000.00	One Month	350/-
14	Restoration of rain Damages on Bhawarna to Jhunga Devi road Km 15/500 to 26/250 (SH:- P/L patch work between Km 23/00 to 26/133.5) Under PDNA	494899.00	9900.00	One Month	350/-

15	Restoration of rain Damages on Damages on Dharamshala Dadh Holta Chadhiar sandhole Road Km 45/00 to 56/000 (SH:- P/L patch work between Km 45/00 to 46/00)	98825.00	2000.00	One Month	350/-
16	Restoration of rain damages on various roads Panchrukhi Sub Division (SH:- Removal of slips between various RDS Jalag Section)	99042.00	2000.00	One Month	350/-
17	Restoration of rain Damages on Jalari curve to Village Jalari road Km 0/00 to 1/000 (SH:-P/L V-shape drain at Rd 0/667 to 0/700, 0/759 to 0/930 and Hume pipe culvert at RD 0/615 and 0/759) Under PDNA	374945.00	7500.00	Two Month	350/-
18	Restoration of rain Damages on Damages on Dharamshala Dadh Holta Chadhiar Sandhole Road Km 45/00 to 56/000 (SH:-Removal of slips between RD 54/240 to 54/261 Near GPS Khajurnu)	99400.00	2000.00	One Month	350/-

Terms & Conditions:-

1. The contractors will have to produce a copy of enlistment / renewal of valid class at time of application / tender form.
2. The contractors will have to produce a copy of GST, EPF and PAN.
3. The contractors are directed to insert the rate / percentage both in figures and words.
4. The tenders forms will not be issued to those contractors who have not completed their previous works / commitments or whose performance is not found satisfactory.
5. The Executive Engineer reserves the right to reject / cancel any or all the tenders without assigning any reason.



Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

On behalf of Governor of Himachal Pradesh)

Dated:


18-11-2025

No.PWD/JSPR/CB/Tenders/2025-26-

6831-40

Copy to the following for information and necessary action:-

1. The Chief Engineer (K.Z.) HP.PWD., Dharamshala.
2. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
3. The Executive Engineer (IT) O/O E-in-C, HP.PWD., Shimla.
- 4-6. All the Assistant Engineer under this Division.
- 7-8. The Drawings / Accounts Branch in this office.
9. N.I.T. Register.
10. Notice Board.



Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

①

Estimated cost Rs.	99982.00
Earnest Money Rs.	2000.00

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-C/O Ambulance road from House of balak Ram to Nichli Khouli ward No.3 Gher
Bhuana (SH:-C/O R/wall from RD 0/00 to 0/028) Deposit VKV/2025/597

Name of work :-C/O Ambulance road from House of balak Ram to Nichli Khouli ward No.3 Gher Bhuana (SH:-C/O R/wall from RD 0/00 to 0/028) Deposit VKV/2025/597						
S. N.	Description of Item	Quantity	Estimated cost Rs.		494759.00	
			Earnest Money Rs.		9900.00	
			Time Limits		Two Month	
			In Figures	Rate In Word	Unit Amount	
1	Earthwork in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm (thirty centimetre) in depth, 1.5 m (one point five metre in width as well as 10 sqm (ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty metre) and lift upto 1.5 m, (one point five metre) as directed by Engineer-incharge within all leads, lifts and other incidentals, as per approved drawing, design, specifications and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkhana, toll taxes, GST and any other taxes imposed by the Government.	37.68	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre 8478.00	
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	122.93	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per cubic Metre 473281.00	

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Bhuana to Ashapuri road Km 0/00 to 12/100 (SH:- Removal of Boulders, stones and landslide from Rd 5/760 to 5/770)

Name of work :-Restoration of rain damages on Bhuana to Ashapuri road Km 0/00 to 12/100 (SH:- Removal of Boulders, stones and landslide from Rd 5/760 to 5/770)							Estimated cost Rs.	99978.00
							Earnest Money Rs.	2000.00
							Time Limits	One Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount		
			In Figures	In Word				
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock,soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 12.08 (twelve cubic decimal zero eight) cubic metre at the rate of Rs. 300/- (Rupees Three Hundred) per cubic metre shall be effected from the contractors running bill on pro-rata basis as per actual quantity executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	241.55	413.90	Rupees Four Hundred Thirteen And Paise Ninety Only	Per cubic metre	99978.00		

Signature
Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-C/O link road from Biara to Baithan Km 0/00 to 3/500 (SH:- P/L CC Pavement from Km 1/00 to 1/055) (Depsoit)✓✓✓✓

Estimated cost Rs. 196863.00
Earnest Money Rs. 4000.00
Time Limits Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	4.46	2050.00	Ruppes Two Thousand Fifty Only	Per Cubic Metre	9143.00
2	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishing and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty millimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	28.88	6500.00	Ruppes Six Thousand Five Hundred Only	Per Cubic Metre	187720.00
Total						196863.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						

Amr
Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

(5)

SCHEDULE OF QUANTITY

Name of work :Restoration of rain Damages on Dharamshala Dadh Holta Chadhiar sandhole Road Km 45/00 to 56/000 (SH:-C/Oimprovement of curve between RD 54/270 to 54/315,54/495 to 54/525, 54/675 to 54/750) **PDNA**

SCHEDULE OF QUANTITY									
Name of work :Restoration of rain Damages on Dharamshala Dadh Holta Chadhiar sandhole Road Km 45/00 to 56/000 (SH:-C/Oimprovement of curve between RD 54/270 to 54/315,54/495 to 54/525, 54/675 to 54/750) PDNA							Estimated cost Rs.		394089.00
S. N.							Earnest Money Rs.		7900.00
							Time Limits		Two Month
Description of Item		Quantity	Rate		Unit	Amount			
			In Figures	In Word					
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock,soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 44.09 (forty four cubic decimal zero nine) cubic metre at the rate of Rs. 300/- (Rupees Three Hundred) per cubic metre shall be effected from the contractors running bill on pro-rata basis as per actual quantity executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	881.73	446.95	Rupees Four Hundred Forty Six And Paise Ninety Five Only	Per cubic metre	394089.00			
Quoted Rate (in Figures) Percentage		Excess (+)			%	394089.00			
		Less (-)			%				
G.Total in Figures									
G.Total in Words									


Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain Damages on Dharamshala Dadh Holta Chadhiar sandhole Road Km 45/00 to 56/000 (SH:-C/O pusta above existing Breast wall for protection of house at Rd 53/810 to 53/840) PDNA

S. N.	Description of Item	Quantity	Estimated cost Rs.		Unit	Amount
			Earnest Money Rs.	Time Limits		
		In Figures	In Word	Rate		
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /cartage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.24	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre	729.00

2	Providing and laying mechanically mixed and vibrated plain cement concrete for all type of structure complete in grade M-10 (M-ten) with crushed stone aggregate 40mm (Forty millimetre) nominal size with cement contents not less than 230 kg (Two hundred thirty Kilogram) per cubic meter and curing complete for 14 (fourteen) days including the cost of form work in open foundation including pumping or bailing out water, dewatering, removal of slush which may arise at the time of laying concrete in all heights/depths complete as per drawings and MORTH technical specification section 1500, 1700 and 2100 and as directed by the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	50.20	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per cubic Metre	248490.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	249219.00
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Amal
 Executive Engineer,
 Jaisinghpur Division,
 HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Balakrupi Section)

Name of work :-Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Balakrupi Section)							Estimated cost Rs.	99990.00
							Earnest Money Rs.	2000.00
							Time Limits	One Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount		
			In Figures	In Word				
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.Note:- The hire charges of plant machinery on per hour basis	90.90	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99990.00		

Prm
 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur


8

SCHEDULE OF QUANTITY

Name of work :-C/O road near Petrol Pump Mohal andretta (SH:-C/O U-Shape drain along with Grating and providing and laying CC pavement from RD 0/0 to 0/035) Deposit VKV/2025/600

S. N.	Description of Item	Quantity	Estimated cost Rs.		Earnest Money Rs.		Time Limits	
			In Figures	Rate In Word	Unit	Amount	Two Month	Two Month
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock,soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	15.40	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre	3465.00		
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including carriage of materials within directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty,	10.800	1200.00	Rupees One Thousand Two Hundred Only	Per cubic metre	12960.00		

3	Providing and laying mechanically mixed and vibrated plain cement concrete for all type of structure complete in grade M-10 (M-ten) with crushed stone aggregate 40mm (Forty millimetre) nominal size with cement contents not less than 230 kg (Two hundred thirty Kilogram) per cubic meter and curing complete for 14 (fourteen) days including the cost of form work in open foundation including pumping or bailing out water, dewatering, removal of slush which may arise at the time of laying concrete in all heights/depths complete as per drawings and MORTH technical specification section 1500, 1700 and 2100 and as directed by the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.96	4850.00	Rupees Four Thousand Eight Hundred Fifty Only	Per cubic Metre	38606.00
4	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishing and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty millimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	16.20	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per Cubic Metre	99630.00
5	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	945.00	95.00	Rupees Ninety Five Only	Per Kilogram	89775.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	244436.00
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on various roads under Balakrupi Sub-Division (SH:- Hiring of JCB /Excavator for removal of slips and boulder of various road under Balakrupi Section)

S. N.	Description of Item	Quantity	Estimated cost Rs.		Unit	Amount
			Earnest Money Rs.	Time Limits		
						One Month
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinery will be provided by the owner. The repair and spare watch and ward of machinery also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. Note:- The hire charges of plant machinery on per hour basis	90.80	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99880.00
	Total					99880.00
	Quoted Rate (in Figures) Percentage	Excess (+) Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Balance work of Shahidi Gate at Saliara Near Moichak on Banuri Saliara road at Km 2/500 (SH:- P/F Granite, ACP cladding and painting work) Deposit VKV/2024/851

Name of work :-Balance work of Shahidi Gate at Saliana Near Molichak on Banuri Saliana road at Km 2/500 (SH:- P/F Granite, ACP cladding and painting work) Deposit VKY/2024/851							Estimated cost Rs.	246458.00
							Earnest Money Rs.	5000.00
							Time Limits	Two Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount		
			In Figures	In Word				
1	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm (forty millimetre) nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.85	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per Cubic Metre	7863.00		
2	Providing and laying polished granite stone flooring in required design and patterns, in liner as well as cu rivliner portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm thick base of cement mortar 1:4 (one cement:four cement) The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	20.04	4500.00	Rupees Four Thousand Five Hundred Only	Per Square Metre	90180.00		
3	Providing and fixing aluminium coated sheet exterior grade wooden shade with aluminium section in inner area strcture adhesive tape adhesive glue to make edges and joints smooth and water proof fixing with necessary screws etcetera complete and as per direction of Engineer-In-charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	28.08	5000.00	Rupees Five Thousand Only	Per Square Metre	140400.00		

4	Painting steel work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr. (zero point nine zero liter /10 (ten) Per Square Metre. Over an under coat of primer applied @ 0.80 ltr (zero point eight)/ 10 (ten) Per Square Metre. of approved brand and manufacture including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	76.33	105.00	Rupees One Hundred Five Only	Per Square Metre	8015.00
	Total					246458.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur


SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Karori Killi Duhak road balh road Km 0/00 to 5/00
(SH:-C/O R/wall at RD 2/855 to 2/856.5)

Estimated cost Rs.	99912.00
Earnest Money Rs.	2000.00
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock,soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.40	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre	990.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	24.72	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per cubic Metre	95172.00


3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	15.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	3750.00
		Excess (+)			%	99912.00
	Quoted Rate (in Figures) Percentage	Less (-)			%	
	G.Total in Figures					
	G.Total in Words					



Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on various roads Panchrukhi Sub Division (SH:-Removal of slips between various RDS Jalag Section)				Estimated cost Rs.		99131.00
				Earnest Money Rs.		2000.00
				Time Limits		TwoMonth
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000 metre as per technical specification 302.3.5 and 1611 (One hours hiring will be justified after removal of 25 cubic metre quantity of disposed material) as per drawing as per the direction of Engineer-in-Charge within all lifts and other lifts and other incidentals. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	885.10	112.00	Rupees One Hundred Twelve Only	Per cubic Metre.	99131.00
	Total					99131.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					



Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur


SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Karori Killi Duhak road balh road Km 0/00 to 5/00
(SH:-C/O R/wall at RD 2/862.50 to 858)

Estimated cost Rs.	99962.00
Earnest Money Rs.	2000.00
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.40	225.00	Rupees Two Hundred Twenty Five Only	Per cubic metre	990.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	24.72	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per cubic Metre	95172.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	15.20	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	3800.00
		Excess (+)			%	99962.00
	Quoted Rate (in Figures) Percentage	Less (-)			%	
	G.Total in Figures					
	G.Total in Words					




Executive Engineer,
Jaisinghpur Division,
H.P.W.D Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Bhawarna to Jhunga Devi road Km 15/500 to 26/250
(SH:- P/L patch work between Km 23/00 to 26/133.5) Under PDNA

Estimated cost Rs.	494899.00
Earnest Money Rs.	5000.00
Time Limits	One Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Repairing of pot holes and removal of loose material trimming of sides by providing with Bitumen Vg-10(ten) tack coat at the rate of 0.30 kg. (zero point thirty kilograms) per Square metre,Open grades premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm (thirteen decimal two millimeter) to 5.6mm (five decimal six millimeter) aggregate @ 0.27 cum (zero decimal twenty seven cubic metres) mixed with using penetration grade bitumen VG-10(ten) @ 14.60 kg (fourteen point sixty kilogram) per ten square of road surface required line grade and level and seal coat sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per M.O.R.D. technical specification clause 510 premixed with 6.8 kg (six point eight) kilogram bitumen vg-10 (ten) 0.06 (zero point zero six) cubic metre of fine aggregate per 10 Sqm. (Ten square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten capacity) and as per directions of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	1477.31	335.00	Rupees Three Hundred Thirty Five Only	Per Square Metre	494899.00
	Total					494899.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					



 Executive Engineer,
 Jaisinghpur Division,
 HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Damages on Dharamshala Dadh Holta Chadhiar sandhole Road Km 45/00 to 56/000 (SH:- P/L patch work between Km 45/00 to 46/00) ~~Under PDNA~~

Estimated cost Rs.	98825.00
Earnest Money Rs.	2000.00
Time Limits	One Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Reparing of pot holes and removal of loose material trimming of sides by providing with Bitumen Vg-10(ten) tack coat at the rate of 0.30 kg. (zero point thirty kilograms) per Square metre,Open grades premix carpet of 20mm (twenty millimeter) thickness composed of 13.2mm (thirteen decimal two millimeter) to 5.6mm (five decimal six millimeter) aggregate @ 0.27 cum (zero decimal twenty seven cubic metres) mixed with using penetration grade bitumen VG-10(ten) @ 14.60 kg (fourteen point sixty kilogram) per ten square of road surface required line grade and level and seal coat sealing the voids in a bituminous surface laid to specified level grade and cross fall using type-B as per M.O.R.D. technical specification clause 510 premixed with 6.8 kg (six point eight) kilogram bitumen vg-10 (ten) 0.06 (zero point zero six) cubic metre of fine aggregate per 10 Sqm. (Ten square metre) heated in mini hot mix plant and laying manually of mixed material and rolling with power road roller 8-10 (eight to ten capacity) and as per directions of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation all leads, lifts and other incidental complete in all respect.The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	295.00	335.00	Rupees Three Hundred Thirty Five Only	Per Square Metre	98825.00
	Total					98825.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					



Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on various roads Panchrukhi Sub Division (SH:-Removal of slips between various RDS Jalag Section)

Estimated cost Rs.	99042.00
Earnest Money Rs.	2000.00
Time Limits	TwoMonth

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000 metre as per technical specification 302.3.5 and 1611 (One hours hiring will be justified after removal of 25 cubic metre quantity of disposed material) as per drawing as per the direction of Engineer-in-Charge within all lifts and other lifts and other incidentals. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	884.30	112.00	Rupees One Hundred Twelve Only	Per cubic Metre.	99042.00
	Total					99042.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY


Name of work :-Restoration of rain Damages on Jalari curve to Village Jalari road Km 0/00 to 1/000
(SH:-P/L V-shape drain at Rd 0/667 to 0/700, 0/759 to 0/930 and Hume pipe culvert at RD 0/615 and 0/759) Under PDNA

Estimated cost Rs.	374945.00
Earnest Money Rs.	7500.00
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	158.29	225.00	Rupees Two Hundred Twenty Five Only	Per Cubic Metre	35615.00

2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	32.04	4850.00	Rupees Four Thousand Eight Hundred Fifty Only	Per cubic metre	155394.00
3	Providing and laying mechanically mixed and vibrated concrete for plain/ cement concrete in sub structure for all type of structure complete using plain cement concrete grade M-15 (M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilograme) per cubic metre in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800, 900 and 1200, and as per the direction of Engineer-in-Charge including carriage of material within all leads , lifts and other incidentals .The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	19.98	5400.00	Rupees Five Thousand Four Hundred Only	Per cubic metre	107892.00

4	Providing and laying flooring laid over cement concrete bedding complete using cement concrete block grade M-15 (M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilogram) per cubic metre in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in flooring laid over bedding as per drawings and M.O.R.D. technical specification clause 1303 and curing complete including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidentals. The rate is including octroi, royalty, GST, or other taxes imposed by the Government.	4.46	6400.00	Rupees Six Thousand Four Hundred Only	Per cubic metre	28544.00
5	Providing and laying (to level or slope) 900mm dia (nine hundred millimeter) diameter reinforced cement concrete pipes IS Class NP-2 for culverts in single row including fixing collar with cement mortar 1:2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, bedding concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications clause 1101 and as per direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate including of octroi,royalty,Malkana, toll tax , or other taxes imposed by the Government.	12.50	3800.00	Rupees Three Thousand Eight Hundred Only	Per Running metres	47500.00
	Total					374945.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur


SCHEDULE OF QUANTITY

18

Name of work : Restoration of rain Damages on Damages on Dharamshala Dadh Holta Chadhiar sandhole Road Km 45/00 to 56/000 (SH:-Removal of slips between RD 54/240 to 54/261 Near GPS Khajurnu)

Estimated cost Rs.	99400.00
Earnest Money Rs.	2000.00
Time Limits	TwoMonth

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000 metre as per technical specification 302.3.5 and 1611 (One hours hiring will be justified after removal of 25 cubic metre quantity of disposed material) as per drawing as per the direction of Engineer-in-Charge within all lifts and other lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	887.50	112.00	Rupees One Hundred Twelve Only	Per cubic Metre.	99400.00
	Total					99400.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					



Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur